



BLUE BOOK

Additional Mold Base Processing & Mold Parts Edition VOL.1

Futaba Standard

Plastic Mold Component



A proposal for reducing man-hours while ensuring quick delivery in mold des

We are able to fulfill a wide variety of your requirements for


Mold base

An extensive product lineup is available in various sizes and types. We fulfill customer requests with short delivery times by changing standard mold base specifications.

Additional machining

In order to meet diversified customer requirements, we offer a broad menu of additional machining and parts installation.

In m
bro
in m



Design, production and manufacturing for “mold bases and parts” !!

Mold parts

In response to a wide range of needs, we offer a wide menu of mold parts which can be installed on mold bases.



We provide customers with total solutions:

MOLDZUKAN® → P.3

The software that helps customers to speed up the total process from the design to ordering to shorten their lead time!


Easy operation enables users to select mold bases and instruct us additional machining and parts installation.



Insert blocks & plates → P.259

Customers can order by specifying the material and size from the options that meet a broad range of applications. We deliver high-precision finished plates with short delivery times!

The chamfer size can also be specified. We boast superior accuracy in any of dimensions, squareness and surface roughness.



System for molding resin pressure/temperature inside molds (Mold Marshalling System) → P.458

Visualize the inside of the mold

A measuring system that realizes quality improvement and cost reduction of injection molding. This system can be used for various purposes such as setting of optimal molding conditions, automatic selection of defective products, evaluation of molds, etc.



Mold base

An “BLUE BOOK Plastic Mold Components” catalog for mold bases is also available. Contact your nearest Futaba sales office to get your copy.




Table of Contents

MOLDZUKAN®	3	Mold Parts	
Additional Processing		Mold Parts General Table of Contents	253
Additional Processing Overview	11	Insert Blocks & Plates.....	259
Specification Change/Addition	21	Guide and Positioning Parts	267
Parts Installation	85	Mold Opening Control Parts.....	305
Machining.....	191	Ejector Space Parts.....	323
Additional Plate Processing	243	Locating Rings, Sprue Bushings, Runner & Gate Parts....	349
Product Data/Technical Data	423	Screws & Coil Springs Parts	391
Customer Guide.....	457	Heat Insulator Sheets.....	407
Index	463		



Safety Precautions

- Check the weight of the mold base and plates and take necessary safety measures before performing operations. The weight of the merchandize is indicated on the address label placed on the top surface of the carton. When transporting or moving heavy goods, only qualified personnel who have completed the required skill training courses such as those for “crane operations”, “slinging operation” and “forklift operations” should operate suspension equipment, and perform slinging and forklift operations in accordance with the Industrial Safety and Health Act.
- When disassembling or assembling mold bases and cavity retainer sets, etc., care must be taken not to get your hand or finger caught between the parting surfaces. Also, adequate precautions should be taken to prevent mold bases or cavity retainer sets from falling off from the parting line, resulting in an injury or accident.
- Some merchandizes may have sharp edges depending on the contents of order (specifications and structure). Please use extreme care when handling these merchandizes.

How to use catalogs


This catalog contains additional processing specifications of mold bases and mold components along with their respective codes. Please use this catalog combined with BLUE BOOK Plastic Mold Components VOL.1 as illustrated below as an aid while designing plastic molds.

※ Note that specifications and prices of mold parts shown in the BLUE BOOK Plastic Mold Components VOL.1 have been changed to those shown in this catalog. Please select mold parts from this catalog.


Specify additional processings of mold base



BLUE BOOK
Additional Mold Base Processing &
Mold Parts Edition Vol.1




Select mold parts



Select standard mold bases



BLUE BOOK
Plastic Mold Components VOL.1



MOLDZUKAN[®]

MOLDZUKAN[®] Overview 4

MOLDZUKAN[®] 6

Flow to Order 8

Q & A Here we answer to some frequently asked questions.... 10

MOLDZUKAN® Overview

Software that provides comprehensive supports during process from design to ordering

MOLDZUKAN® helps users to increase design efficiency, speed up the procurement of mold bases and parts and shorten the delivery time of mold products.

Easy selection! Easy operation!

Mold parts, installation & machining Select a variety of processing options freely!

More user-friendly
user interface

New function
User library

CAD data output!

Output the data
designed in CAD format!

Multilingual Support!

Offers a language
selection of English, Korean
and Japanese!

Purchase & inquiry

To purchase or inquire further about **MOLDZUKAN®**, please contact **your nearest Futaba sales office or branch office** listed at the end of this catalog, or **Machinery & Tooling Marketing & Sales Group** shown below.

Machinery & Tooling Marketing & Sales Group

Chosei Machinery & Tooling Technology Center, 1080 Yabutsuka, Chosei-mura, Chosei-gun, Chiba 299-4395, Japan TEL: +81-475-30-0809 FAX: +81-475-30-0818

Technical inquiry

Machinery & Tooling Technology Group

Chosei Machinery & Tooling Technology Center, 1080 Yabutsuka, Chosei-mura, Chosei-gun, Chiba 299-4395, Japan TEL: +81-475-32-6062 FAX: +81-475-32-3244

Export Control

If you export **MOLDZUKAN®** overseas, the export might be regulated under the Foreign Exchange and Foreign Trade Act, depending on the use of the software (is or is likely to be used or diverted for developing weapons). Before exporting **MOLDZUKAN®**, you should make sure whether or not the export is subject to regulations in accordance with the act and take necessary procedures such as obtaining a license, etc.

Realizing increased design efficiency, simplified ordering and shortened procurement period

MOLDZUKAN® saves users the efforts of outputting procurement drawings and making phone calls and allows them to place orders quickly and paperless.

Also, Futaba has built a system that automates the process from procurement of materials to the processing of them each time an order is placed, thereby delivering mold bases in a short period of time.

Benefit 3

Shortened procurement period of mold bases


Benefit 2

Simplified ordering

Allows users to concentrate on cavity & core production!!

Benefit 1

Increased efficiency of mold conceptual design



Comparison of mold production periods

Mold conceptual design, mold base procurement, mold parts procurement and business support software

MOLDZUKAN®

Contributes to shortening mold lead time by increasing efficiency of mold conceptual design and speeding up mold base procurement


Standard price

Category	Specifications	Price
3D Mode Version	Can be used by switching between 3D and 2D modes.	39,800 yen
2D Mode Version	For exclusive use in 2D mode.	4,980 yen

Operating environment

OS	Microsoft Windows XP (32bit) Microsoft Windows Vista (32bit, 64bit) Microsoft Windows 7 (32bit, 64bit) ※ OS must support Japanese.
CPU	Core2Duo 2.0GHz or more is recommended.
Required memory capacity	2.0GB or more is recommended.
Required hard disk space	250MB or more is recommended.
Others	① Microsoft .NET Framework 3.5 SP1 must be installed. ② The Microsoft Visual C++ 2008 Redistributable must be installed.

MOLDZUKAN® 2D Mode Version




Main functions

Category	Function	3D Mode Version	2D Mode Version
Data generation	Generating data of standard mold bases, parts and plates	○	○
Edit	Undo	○	○
	Redo	○	○
	Setting work area	○	—
	Opening channel (Boolean operation)	○	—
	Switching between 3D & 2D	○	—
Display	Switching direction of projection	○	—
	Multi-view	○	—
	Perspective view	○	—
	Zooming(full, zoom-in, zoom-out)	○	○
	Un-hiding/hiding channels	○	—
Measurement	Opening/closing of fixed sides	○	—
	Length of line segment edge	○	○
	Diameter of circle and circular arc edge	○	○
	Angle of line segment edge	○	—
	Shortest distance between bodies	○	—
	Shortest distance between plates	○	—
	Shortest distance between lines and edges	○	○
	Distance between parallel lines and parallel edges	○	○
	Shortest distance between channels	○	○
	Interference check	○	—

Category	Function	3D Mode Version	2D Mode Version
Data output	Outputting CAD data (3D)	IGES STL	—
	Outputting CAD data (2D)	DXF	DXF
	Outputting parts list (CSV format)	○	○
	Outputting added machining specification list (CSV format)	○	○
Print	Printing drawing area	○	○
	Hard copy of drawing area	○	○
Ordering	Prepare order/quotation request	○	○
Registration	User library	○	○
Setting	Setting CAD data layer	○	○
	Setting color for models	○	—
	Displaying product name for tree title	○	○
	Un-hiding/hiding of reference plate signs	○	○
	Un-hiding/hiding compass	○	○
	Un-hiding/hiding ruler	○	○
	Online update function	○	○
	Using large fonts for tree	○	○
	Translucent view	○	—
Help	Adjust transparency	○	—
	Catalog (Blue book, Red book)	○	○
	Manual (Function/Operation)	○	○

MoldZUKAN® 3D Mode Version




◆ The software is subject to updates without notice. For latest information on the operating environment and prices, contact your nearest Futaba sales office.

Flow to Order


Select Futaba standard parts for mold

- ◆ Select a mold base from product size.
- ◆ Select a catalog code by following on-screen directions.
- ◆ Order data can be reused.

On the [right tree] → [Mold Base tab], select a mold base series.



Specify the specifications of the mold base and then click [OK] button.



Output as CAD data


- ◆ The data can be retrieved into your CAD software.

- On the [left tree] → [Configuration tab] → [Additional machining], the specified additional machining code will be displayed.
- The 2D drawing or 3D model is displayed with temperature control channel reflected.


3D Edition	Output 3D CAD data	Output 2D CAD data
	IGES • STL	DXF

2D Edition	Output 2D CAD data
	DXF


2D model




3D model



2D Drawing





3D Model



Enter each parameter and click [OK] button.

On the [right tree] → [Additional machining tab], double-click [MH2xx water/oil/heater channel (at two places)]. A dialog box opens.



- ◆ Select the additional machining by following on-screen directions.
- ◆ Reflect the machining specifications on the mold base drawn.
- ◆ This function helps reduce mold design errors.

Q & A Here we answer to some frequently asked questions

Q How do I update to the latest version?

A With online update function via the Internet, you can easily update to the latest version of software.

Q I'm currently using the 2D Mode Version. Can I change it to the 3D Mode Version?

A Yes. Please purchase the 3D Mode Version of the software.

Q Is MOLDZUKAN® available only in Japanese?

A On the Environment Setting menu, you can switch the language to the English, Korean or Chinese.

Q Can I use MOLDZUKAN® on a trial basis?

A We offer the trial version of the software. Please feel free to contact your nearest sales office.

Q Is MOLDZUKAN® CAD software?

A No. You cannot create shapes freely with the software like you do with CAD software. However, you can create shapes by selecting our catalog codes on an interactive basis. The created shapes can be output as CAD data. The data can also be retrieved into your CAD software in IGES, DXF or other format.

Q Can I reuse the product specification data created by MOLDZUKAN®?

A Yes. You can retrieve the data you want to edit into MOLDZUKAN® to modify or add machining to it.

Additional Processing Overview

- Additional Processing Overview 12
- Additional Processing Overview — Specification Change/Addition..... 14
- Additional Processing Overview — Parts Installation 16
- Additional Processing Overview — Machining 18

Additional Processing Overview

What is additional processing?

This is a term we use to describe a number of common processes additionally made to standard mold bases, the specifications of which are set in place with simple codes assigned to them so that customers can order required alternation or modification of standard mold bases easily with the codes. Additional processing includes machining of water channels, heater holes and other temperature control channels, as well as installation of puller bolts, ejector guide pins and other parts. Minor changes of standard mold bases due to the changes in specifications of molds or molding machines can also be specified by using the codes.

Category	1st digit of catalog No.	Major specifications
Specification change/addition	C E S	Plate thickness change Plate material change Part length change Part pitch change
Parts Installation	P	Puller bolt installation Ejector guide installation Locating ring installation Coil Spring Installation
Machining	M	Water channel, oil channel heater hole machining Pocket milling Eye bolt threaded hole machining Ejector rod hole machining

How to order

Please order "additional processing specifications" by specifying mold base item name and additional processing specifications using codes as shown in the order example below. Write the additional specifications by beginning a new line for each specification.


【Order example】

Mold base model ——— MDCDA2025354060XVBJOH210

Additional processing specifications {

- MKKB2/PL — B — A85 — B140 — C75 — D130 — R8 — RD — Z25 — X55 — Y55
- MKKMD/PL — B — B56 — Z15 — X140 — Y97 — M60
- MHH2AKP — U — D8.0 — Z250 — RC1/8 — P90 — H15 — ZHC — E20 — G20
- MFK2AC — T — M12 — H15
- PLRC — D100 — G70 — T20 — Z5 — S022 — X100 — Y125 — MNZ/E60/J12

The rest is omitted



Price

We will be pleased to provide you with a preliminary price quotation. Please request a quotation from our sales office.

Delivery date

Delivery dates will vary depending on the contents and volume of "Additional Processing Specifications".

Please inquire with our sales office.

Specifications not listed in this catalog

"Additional processing specifications" are commonly used specifications that are set in place with codes assigned to them. We also accept orders for products of specifications not shown in our catalog. Please advise us on your application requirements with a drawing, etc. or consult our sales office.

Using MOLDZUKAN®


MOLDZUKAN® is software that supports selection of additional processing specifications and issuance of purchase orders. MOLDZUKAN® allows customers to more easily select additional processing specifications and issue purchase orders. For details, refer to page 3.


Liability note

"Additional processing specifications" are provided to show customers how to order additional processings. When designing molds, various conditions such as strength and accuracy need to be taken into account. Therefore, we shall not be responsible or liable for any loss or damage of any kind incurred as a result of, or in connection with your use of additional processing specifications or selection of mold bases.

Mold base plate name

The name of the plates in the mold base overall view charts as well as in the text herein are shown with abbreviated form of the names as listed below:

Reference diagram	Plate abbreviated name	Plate name
 Plate T Plate R Plate A Plate S Plate B Plate U Plate C Plate E Plate F Plate L	Plate T	Top clamping plate
	Plate R	Runner plate
	Plate A	Cavity plate (fixed half)
	Plate S	Stripper plate
	Plate B	Cavity plate (moving half)
	Plate U	Backing plate
	Plate C	Spacer block
	Plate E	Ejector retainer plate
	Plate F	Ejector base plate
	Plate L	Bottom clamping plate



Additional Processing Overview — Specification Change/Addition

The basic specifications of standard mold bases can be changed, added or deleted as shown below:

Specification Change/Addition on Plates



Change Dimension and/or Installation Method of Clamping Plates	22	Surface Grind	31
Change Plates Thickness	24	Mold Base for Insert Molding	32
Change Width of Spacer Blocks and Ejector Plates	28	Change Nominal Base Size	34
Change Plate Materials	29	Omit Standard Plates	36
Change Tolerance of Plate Thickness	30	Added Plates	38

Specification Change/Addition on Parts


Change Parts Diameter	40	Change Return Pin Collars Thickness to 8 mm	66
Change Precision Guide Pins and Guide Bushings	42	Added Machining Return Pin Holes on S-Plate	67
Change Type and Length of Guide Pins	44	Added Return Pin Holes and/or Chang Return Pin Holes Diameter	68
Change Installation of Guide Bushings and/or Added Guide Bushings Specification	48	Change Return Pin with Thread Holes	70
Added Clearance Holes for Guide Pin	54	Change Position of Parts	72
Change Specification of Guide Pin Holes	55	Change Position and the Number of Assembly Screws	74
Install Guide Pins	56	Added Assembly Screws	76
Change Type and Length of Support Pins	58	Specifications of Thread Holes for Assembly Screws	78
Add/Omit Support Pin Collars	60	Change Puller Bolt Specification of H Series	80
Change Clearance Holes for Support Pin	62	Omit Standard Parts and Holes	82
Change Length of Return Pins, Assembly Screws, Puller Bolts	64		



"Additional processing specifications" are provided to show customers how to order additional processing. When designing molds, various conditions such as strength and accuracy need to be taken into account. Therefore, we shall not be responsible or liable for any loss or damage of any kind incurred as a result of, or in connection with your use of additional processing specifications or selection of mold bases.



Additional Processing Overview — Parts Installation



Locating Ring Addition

Added Locating Rings — Overview	86
Added Locating Rings — ①	88
Added Locating Rings — ②	90

Sprue Bushing Addition

Added Sprue Bushings — Overview	92
Added Sprue Bushings — Bolts Type	94
Added Sprue Bushings — Shoulder Type	96

Taper Guide pin Addition

Added Taper Guide Pin Sets — Overview	98
Added Taper Guide Pin Sets M-TLCS, M-TLDS	104
Added Taper Guide Pin Sets M-TLGS, M-TLHS	106
Added Taper Guide Pin Set M-TLBS	108

Ejector Guide Pin Addition

Added Guide Pins and Bushings — Overview	110
Added Ejector Guide Pin M-EGA	120
Added Ejector Guide Pin M-EGB	122
Added Ejector Guide Pin M-EGC	124
Added Ejector Guide Pin M-EGBM	126
Added Ejector Guide Pin M-EGCM	128
Added Ejector Guide Pin M-GPHF and M-GPA	130
Added Ejector Guide Pins and Bushings — Standard Position	132

Base Spacer Addition


Added Base Spacer	188
-------------------------	-----

Support Pillar Addition

Added Support Pillars — Overview	142
Added Support Pillar	144

Mold Opening Prevention Plate Addition

Added Mold Opening Prevention Plate — Overview	182
Added Mold Opening Prevention Plate (at one place)	184
Added Mold Opening Prevention Plate (at two or four places)	186



Puller Bolt Addition

■ Added Puller Bolts — Overview.....	148
■ Added Puller Bolts — B1.....	154
■ Added Puller Bolts — B2.....	156
■ Added Puller Bolts — B3.....	158
■ Added Puller Bolts — B4.....	160
■ Added Puller Bolts — B5.....	162
■ Added Puller Bolts — AH1.....	164
■ Added Puller Bolts — A1.....	166
■ Added Puller Bolts — AH2/A2.....	168
■ Added Puller Bolts — Standard Position.....	170

Tension Link Addition

■ Added Tension Links — Overview.....	172
■ Added Tension Link M-HLA.....	176
■ Added Tension Link M-HLB.....	178

Spring Addition

■ Added Springs — Overview.....	134
■ Added Springs — ①.....	136
■ Added Springs — ②.....	138

PL Puller Addition

■ Added PL Pullers.....	180
-------------------------	-----

Addition of Stop Pin or Stop Ring

■ Added Stop Pins or Stop Rings.....	140
--------------------------------------	-----

Ejector Rod Addition

■ Added Ejector Rods.....	146
---------------------------	-----



Eye Bolt Addition


■ Added Eye Bolts.....	231
------------------------	-----



"Additional processing specifications" are provided to show customers how to order additional processing. When designing molds, various conditions such as strength and accuracy need to be taken into account. Therefore, we shall not be responsible or liable for any loss or damage of any kind incurred as a result of, or in connection with your use of additional processing specifications or selection of mold bases.

Additional Processing Overview — Machining





Channels for Water, Oil and Heater

Channels for Water, Oil and Heater — Overview.....	192	Channels for water & Oil — Circulation Type.....	198
Channels for Water, Oil and Heater — 1 Hole	194	Channels for Water, Oil and Heater — Entrance Counterbore Hole.....	200
Channels for Water, Oil and Heater — 2 Holes	196	Channels for Water, Oil and Heater — One Side Pipe Thread Holes	202

Rough Pockets Machining

Rough Pockets Machining — Overview	204	Rough Pockets Machining — Through Groove.....	214
Rough Pockets Machining — Rectangular with Rounded Corners (Inside Corner R)	206	Rough Pockets Machining — Slide Core Groove	216
Rough Pockets Machining — Rectangular with Rounded Corners (Outside Corner R)	208	Rough Pockets Machining — Blind Groove (Inside Corner R)	218
Rough Pockets Machining — Circular Pocket.....	210	Rough Pockets Machining — Blind Groove (Outside Corner R)	220
Pocket Gas Cutting — Rectangular & Circular Pocket.....	212		

Threaded Holes for Eyebolt (Side Surface Threaded Holes)

Added Threaded Holes for Eyebolt (Side Surface Threaded Holes) — Overview	222	Added Threaded Holes for Eyebolt (Side Surface Threaded Holes) — Chamfering	230
Added Threaded Holes for Eyebolt (Side Surface Threaded Holes) — 1 Holes.....	224	Added Eye Bolts	231
Added Threaded Holes for Eyebolt (Side Surface Threaded Holes) — 2 Holes or 4 Holes	226	Omit Threaded Holes for Standard Eyebolt.....	232
Added Threaded Holes for Eyebolt (Side Surface Threaded Holes) — For C-Plate.....	228	Added Side Surface Threaded Holes with Counterbore.....	234

Ejector Rod Hole Addition or Omission

Added or Omitted Ejector Rod Holes	236
--	-----

Clamp Slot Addition (For Clamping Plate)

Added Clamp Slot (For Clamping Plate)	238
---	-----

Addition of Clamping Hole or U Ditch for Clamping

Added Clamping Holes or U Ditch for Clamping	240
--	-----

Clamp Slot Addition (For A-Plate or B-Plate)

Added Clamp Slot (For A-Plate or B-Plate)	241
---	-----

 "Additional processing specifications" are provided to show customers how to order additional processing. When designing molds, various conditions such as strength and accuracy need to be taken into account. Therefore, we shall not be responsible or liable for any loss or damage of any kind incurred as a result of, or in connection with your use of additional processing specifications or selection of mold bases.

Specification Change/Addition

Specification Change/Addition on Plats

Change Dimension and/or Installation Method of Clamping Plates...	22	Surface Grind	31
Change Plates Thickness.....	24	Mold Base for Insert Molding.....	32
Change Width of Spacer Blocks and Ejector Plates.....	28	Change Nominal Base Size.....	34
Change Plate Materials.....	29	Omit Standard Plates.....	36
Change Tolerance of Plate Thickness.....	30	Added Plates	38

Specification Change/Addition on Parts

Change Precision Guide Pins and Guide Bushings	42	Change Return Pin Collars Thickness to 8 mm	66
Change Type and Length of Guide Pins	44	Added Machining Return Pin Holes on S-Plate.....	67
Change Installation of Guide Bushing and/or Added Guide Bushings Specification.....	48	Added Return Pin Holes and/or Change Return Pin Holes Diameter	68
Added Clearance Holes for Guide Pin	54	Change Return Pin with Thread Holes.....	70
Change Specification of Guide Pins Holes.....	55	Change Position of Parts	72
Install Guide Pins	56	Change Position and the Number of Assembly Screws	74
Change Type and Length of Support Pins.....	58	Added Assembly Screws	76
Add/Omit Support Pin Collars	60	Specifications of Thread Holes for Assembly Screws	78
Change Clearance Holes for Support Pin.....	62	Change Puller Bolt Specification of H Series.....	80
Change Length of Return Pins, Assembly Screws, Puller Bolts.....	64	Omit Standard Parts and Holes	82



“Additional processing specifications” are provided to show customers how to order additional processing. When designing molds, various conditions such as strength and accuracy need to be taken into account. Therefore, we shall not be responsible or liable for any loss or damage of any kind incurred as a result of, or in connection with your use of additional processing specifications or selection of mold bases.

Change Dimension and/or Installation Method of Clamping Plates










Change the dimensions and/or installation method of clamping plates.



When changing the dimensions of clamping plates, take into account the strength, etc.

Application Mold Bases

Specification Change/Addition
Change Dimension and/or Installation Method of Clamping Plates

No protrusion (clamping and mold plates are same dimension)		2-direction protrusion	
Catalog No. CIS1 	Catalog No. CIS2 	Catalog No. CIS3 	
3-direction protrusion		4-direction protrusion	
Catalog No. CIS4 	Catalog No. CIS5 	Catalog No. CIS8 	
Catalog No. CIS6 	Catalog No. CIS7 	Plate code of clamping plate 	

Catalog No.	Plate code	A (width)	B (length)	T (thickness)	X *1	Y *1
CIS1~CIS8	T (Plate T) L (Plate L)	Select from the Plate General Catalog Red Book. (Product of sizes other than shown in the plate catalog will be made to order)			In 1 mm steps	In 1 mm steps

※ If any plate thickness change of **Catalog No.** CIT is specified, re-specify it by using **Catalog No.** CIS.
Mixed use of CIS and CIT is not allowed.

*1. Specify X dimension and Y dimension as follows:

Protrusion spec.	Catalog No.	X	Y	Remarks
No protrusion	CIS1	No need to specify	No need to specify	
2-direction protrusion	CIS2	Need to specify	No need to specify	No need to specify if amount of protrusion X on right and left is the same.
	CIS3	No need to specify	Need to specify	No need to specify if amount of protrusion Y on top and bottom is the same.
3-direction protrusion	CIS4	Need to specify	Need to specify	
	CIS5	Specify X0	Need to specify	
	CIS6	Need to specify	Specify Y0	
	CIS7	Need to specify	Need to specify	
4-direction	CIS8	Need to specify	Need to specify	No need to specify if protrusion X on right and left is the same, and protrusion Y on top and bottom is the same.

How to order

	Catalog No.	Plate code	A	B	T	X	Y
Plate T change	CIS4	T	A300	B350	T25	X25	Y30
Plate L change	CIS8	L	A250	B280	T20	X30	Y20

※ Changing clamping plate thickness results in changes in length of installation parts as described below:

Part name	Applicable series	Handling of dimensions
Assembly screw	S series	Increase or decrease the screw length by the amount of increase or decrease in clamping plate thickness. (However, the last digit must be rounded down to the nearest unit of 5 mm)
	D·E series	
	F·G series	
	H series	
Support pin	D·E series	Specify the length of the support pins in the mold base item name.
	F·G series	
	H series	
Puller bolt	H series	① Specify the length of puller bolt M-PBA in the mold base item name.
		② For length of puller bolt M-PBC, see P.80

Regarding mold base item name

When changing dimension and installation method of clamping plates, please note:

In addition to the above mentioned instruction codes, please specify the **mold base item name** with codes as described below:

For standard mold bases item name, specify the width of clamping plate and orientation of the guide with S, X, Y or Z. When changing the dimension and installation method of clamping plates, specify the code of the mold base item name with S (when installing guide pins in the cavity plate (moving half)) or Y (when installing guide pins in the cavity plate (fixed half)). For F G series, specify S as the code.

※ If the nominal dimension is 1113, 1313 or 1315, then:

Specify the code of the mold base item name with X (when installing guide pins in the cavity plate (moving half)) or Z (when installing guide pins in the cavity plate (fixed half)). For F G series, specify X as the code.

Change Plates Thickness — ①


Change the plate thickness to the values other than the standard plate thickness.

Changing Dimension and Installation Method of clamping Plate → P.22



When changing plate thickness, take into account the strength, etc.

Application Mold bases, cavity retainer sets, cavity retainer sets for die cast



Catalog No.	Plate code	T (plate thickness)
CIT	T (Plate T)	① Select from the standard sizes shown in Plate General Catalog Red Book. ② Product of sizes other than shown in the plate general catalog will be made to order.
	R (Plate R)	
	A (Plate A)	
	S (Plate S)	
	B (Plate B)	
	U (Plate U)	
	C (Plate C)	
	E (Plate E)	
	F (Plate F)	
	L (Plate L)	

※ If any clamping plate dimension and installation method change of **Catalog No.** CIS is specified, Plate T and Plate L cannot be specified.
Mixed use of CIS and CIT is not allowed.



How to order

Catalog No.

CIT

Plate code

U

T

T50

Regarding mold base item name

※ When changing thickness of Plate A, B or C, please note:

In addition to the instruction codes on the left page, please specify the mold base item name with codes as described below:

Mold base item name: MDC Type Nominal dimension Plate A thickness Plate B thickness Plate C thickness Other spec.

Specify the thickness of Plate A, B or C with 2-digit numbers.

If the thickness is over 100, indicate the number in 2 digits (e.g. 100 → 10, 220 → 22)

Instruction example

If changing the specifications of a mold base to SA Type, nominal dimension 1520, Plate A thickness 90, Plate C thickness 100, specify the mold base item name as follows:

Mold base item name MDC SA 1520 90 30 10 S V M J

Additional processing instruction code CIT — A — T90

Additional processing instruction code CIT — C — T100

Note: Changing thickness of Plate A, B or C requires specifying both the mold base item name and additional processing instruction codes.

※ When changing the thickness of Plate U:

In addition to the instruction codes shown on the left page, specify the mold base item name as follows:

For the standard mold base item name, specify the Plate U dimension with V or W code. When changing the thickness of the U dimension, specify V as the code of the model base item name.

Length of supplied parts

Changing plate thickness results in changes in part length as described below:

Part name	Handling of dimensions
Return pin	Increase or decrease the return pin length by the amount of increase or decrease in plate thickness.
Assembly Screw bolt	Increase or decrease the screw length by the amount of increase or decrease in plate thickness.
Guide bushing	The length is determined by the setting shown in page 26.
Guide pin	The length is determined by the setting shown below.
Support pin	Specify the length of support pins in the mold base item name.


Setting of Guide Pin Length

Guide pin diameter	Thickness of Plate A or Plate B (Thickness of plates in which to install guide bushing)		Guide pin length	
	Mold base Plastic main mold	Die cast main mold		
12	20 ≤ Thickness ≤ 60	—	Determined based on our setting standards. Mold base, cavity retainer sets ↓ See page 439	For the thickness other than listed on the left, specify the length of the guide pin. Details on how to specify: ↓ P.44
16	20 ≤ Thickness ≤ 80	40 ≤ Thickness ≤ 60		
20	20 ≤ Thickness ≤ 100	50 ≤ Thickness ≤ 80		
25	25 ≤ Thickness ≤ 120	60 ≤ Thickness ≤ 100		
30	30 ≤ Thickness ≤ 130	70 ≤ Thickness ≤ 140	Cavity retainer sets for die cast ↓ See the Blue Book Dimension Diagram	
35	40 ≤ Thickness ≤ 150	100 ≤ Thickness ≤ 150		
40	40 ≤ Thickness ≤ 150	110 ≤ Thickness ≤ 160		
50	50 ≤ Thickness ≤ 250	—		
60	100 ≤ Thickness ≤ 250	—		
70		—		


Change Plates Thickness — ②

Depending on the thickness, install guide bushings in Plate A and Plate B as illustrated below:


Application Mold bases, cavity retainer sets, cavity retainer sets for die cast





Guide bushing specification of Plate A guide pins




Guide bushing specification of Plate B guide pins



Guide bushing specification of D, E and H series Plate A support pins



Guide bushing specification of F and G series Plate A and Plate B support pins



Thickness of Plate A & B (Thickness of plates in which to install guide bushings) and guide bushing specifications

D	GBA spec.	GBB spec.					Remarks
	Thickness of Plate A or B	Thickness of Plate A or B	L *1	D1	D2	M	
12	20 ≤ Thickness ≤ 60	60 < Thickness	30	14 ~ 17	14	M4	
16	20 ≤ Thickness ≤ 80	80 < Thickness	50	18 ~ 24	18	M5	
20	20 ≤ Thickness ≤ 100	100 < Thickness	70	24 ~ 29	22	M6	
25	25 ≤ Thickness ≤ 120	120 < Thickness	80	29 ~ 34	27	M8	
30	30 ≤ Thickness ≤ 150	150 < Thickness	100	34 ~ 41	32		
35	40 ≤ Thickness ≤ 150			39 ~ 47	37		
40	40 ≤ Thickness ≤ 160	160 < Thickness		45 ~ 54	42		
50	50 ≤ Thickness ≤ 160			54 ~ 69	M10		
60	100 ≤ Thickness ≤ 200	200 < Thickness	130	65 ~ 79		When thickness is 140, 170 or 190, GBB specification is used.	
70				75 ~ 89			

*1. Guide bushing length = L-1

※ The above table shows installation specification of guide bushings, thickness of which can be specified in 10 mm steps (When D is 12, 16, 20 or 25 and plate thickness is 25 or 35, and when D is 30 and plate thickness is 35, GBA specification is used.)

※ If different type of guide bushings are used, settings other than the above may be used. → P.44

※ Installation methods other than those shown on the left page → P.48

Guide bushing specifications for Plate S and Plate R

For Plate S and Plate R, M-GBB is installed as shown in the charts on the left page.

Guide bushing length = plate thickness - 1

D	Thickness of Plate S and Plate R													
	10	15	20	25	30	35	40	45	50	60	70	80	90	100
12	○	○	○	○	○	○								
16		○	○	○	○	○	○	○	○					
20		○	○	○	○	○	○	○	○	○	○			
25		○	○	○	○	○	○	○	○	○	○	○		
30			○	○	○	○	○	○	○	○	○	○	○	○
35			○	○	○	○	○		○	○	○	○	○	○
40				○	○	○	○		○	○	○	○	○	○
50					○		○		○	○	○	○	○	○
60										○	○			
70											○			

※ For plate thickness dimensions other than the above, guide bushing needs to be custom-made.

※ If different type of guide bushings are used, settings other than the above may be used. → P.44


※ Installation methods other than those shown on the left page → P.48

Support pin specifications change according to the change in the thickness of the 3-plate type Plate T

Changing Plate T thickness requires change in head thickness of support pin as follows:

As the Plate T becomes thinner, the support force of the pin decreases. Therefore, when changing the plate thickness, take into account the strength, etc.

D	Standard Plate T thickness			Change in Plate T thickness			L1	
	T	H	L1	T	H			
12	25	6	24	T < 20	5		※ When T < Standard Plate T thickness, L1 = T-1	
				20 ≤ T	6			
16	25	8	24	T < 20	6			
				20 ≤ T	8			
20	30	10	29	T < 25	6		※ When Standard Plate T thickness < T, L1 = L1 dimensions shown in the left table	
				25 ≤ T	10			
25	35	12	34	T < 30	8			
				30 ≤ T	12			
30	45	14	44	T < 40	8			
				40 ≤ T	14			
35	50	16	49	T < 45	8			
				45 ≤ T	16			
40	60	18	59	T < 55	10			
				55 ≤ T	18			



Change Width of Spacer Blocks and Ejector Plates

Change the width dimensions of spacer blocks and ejector plates.



When changing the width dimensions of spacer blocks and ejector plates, consider the following:


- ① When changing the width dimensions of spacer blocks and ejector plates, take into account the strength, etc.
- ② Changing the plate width may result in difficulties in installation of parts such as return pin, etc.
Please specify the change in pitch between parts.

Changing position of parts ➡ P.72

Changing position and the number of assembly screws ➡ P.74

Application Mold bases

Catalog No. CISCEF



【Setting conditions】

$$KW = 2 \times CW + EFW + 2 \times SW$$

Provided $SW \geq 1$

※ When $SW = 1$, because of the gap between bolt and bolt hole, plate may get closer, result in inability to secure sufficient space.
Assemble molds so that sufficient space is secured between plates.

Catalog No.	CW	EFW	Remarks
CISCEF	1 mm steps $CW \geq 20$	1 mm steps $EFW \geq 40$	If the last digit of CW dimension is 3 or 8 and the last digit of EFW dimension is 0, standard precision plate may be available for your review. E.g. CW=43 EFW=110

※ For mold base types without supplied ejector plates, specify only CW.



How to order

Catalog No.

CW

EFW

CISCEF


CW63

EFW100

Change Plate Materials

Change the materials of plate.

Application Mold bases, cavity retainer sets, cavity retainer sets for die cast



Catalog No.	Plate code	Material name
CIMA	T (Plate T) R (Plate R) A (Plate A) S (Plate S) B (Plate B) U (Plate U) C (Plate C) E (Plate E) F (Plate F) L (Plate L)	① Select from the standard sizes shown in Plate General Catalog Red Book. ② Product of other materials will be made to order.
	Additional Plate N (Plate N) O (Plate O) Q (Plate Q) V (Plate V) W (Plate W) X (Plate X) Y (Plate Y) Additional plate specification ↓ P.38	


How to order

Catalog No. — **Plate code** — < **Material name** >
 CIMA — A — < HPM1 >
 CIMA — B — < NAK55 >

Change Tolerance of Plate Thickness

Change the dimensional limit deviations of plate thickness.

Application Mold bases, cavity retainer sets, cavity retainer sets for die cast




Applicable dimensional range

L dimensional range ($W \leq L$)	Tolerance
$L \leq 300$	Specify tolerance of 0.01 or more
$300 < L \leq 600$	Specify tolerance of 0.02 or more.
$600 < L \leq 1000$	Specify tolerance of 0.03 or more.

Tolerance = Upper deviation — lower deviation

E.g. If the deviations are 30 ± 0.02 , then the tolerance is 0.04.
 If the deviations are $30 \begin{smallmatrix} 0 \\ -0.02 \end{smallmatrix}$, then the tolerance is 0.02.
 If the deviations are $30 \begin{smallmatrix} +0.03 \\ 0 \end{smallmatrix}$, then the tolerance is 0.03.

※ For grinding, rotary grinding is used. Depending on tolerance, however, surface grinding (reciprocating grinding) may be used. If surface grinding is preferred, specify it as shown on the right page.



Catalog No.	Plate code	Upper deviations	Lower deviations
CILI	T (Plate T) R (Plate R) A (Plate A) S (Plate S) B (Plate B) U (Plate U) C (Plate C) E (Plate E) F (Plate F) L (Plate L) Additional Plate N (Plate N) O (Plate O) Q (Plate Q) V (Plate V) W (Plate W) X (Plate X) Y (Plate Y) Additional plate specification ↓ P.38	In 0.005 mm steps	In 0.005 mm steps


How to order

Catalog No.	Plate code	T	Upper deviations	/	Lower deviations	>
CILI	A	T	+0.15	/	+0.05	>
CILI	B	T	-0.01	/	-0.03	>
CILI	C	T	+0.1	/	-0.1	>

Surface Grind


Change the plate surface grinding method to surface grinding (reciprocating grinding).

Application Mold bases, cavity retainer sets, cavity retainer sets for die cast



Surface grinding applicable dimensional range

L dimensional range ($W \leq L$)	Tolerance
$L \leq 300$	Specify tolerance of 0.01 or more.
$300 < L \leq 600$	Specify tolerance of 0.02 or more.
$600 < L \leq 1000$	Specify tolerance of 0.03 or more.
Tolerance = Upper deviation – lower deviation E.g. If the deviations are 30 ± 0.02 , then the tolerance is 0.04. If the deviations are $30 \begin{smallmatrix} 0 \\ -0.02 \end{smallmatrix}$, then the tolerance is 0.02. If the deviations are $30 \begin{smallmatrix} +0.03 \\ 0 \end{smallmatrix}$, then the tolerance is 0.03.	



Catalog No.	Plate code	Upper deviation	Lower deviation
CISG	T (Plate T)	In 0.005 mm steps F: Do not specify limit deviations. *1	In 0.005 mm steps F: Do not specify limit deviations. *1
	R (Plate R)		
	A (Plate A)		
	S (Plate S)		
	B (Plate B)		
	U (Plate U)		
	C (Plate C)		
	E (Plate E)		
	F (Plate F)		
	L (Plate L)		
	Additional Plate N (Plate N) O (Plate O) Q (Plate Q) V (Plate V) W (Plate W) X (Plate X) Y (Plate Y) Additional plate specification ↓ P.38		

*1. If limit deviations are not specified, the deviations will be set to around ± 0.2 . If you do not specify particular limit deviations tolerances, please specify F for both the upper and lower deviations.

How to order

Catalog No.	Plate code	T	Upper deviation	/	Lower deviation	>
CISG	A	T	+0.01	/	-0.01	>
CISG	B	T	F	/	F	>
CISG	F	T	+0.02	/	0	>

Mold Base for Insert Molding


Use this as mold base specifications for insert molding.

We deliver one fixed half and two moving halves of a mold base in sets after machining datum plane.

The order quantity of the mold base will be one. If you order two or more mold bases, we carry out machining work by the unit of one fixed half and two moving halves for the respective mold bases.

Application Mold bases

Catalog No. SIMB



Catalog No.

SIMB

How to order


Catalog No.

SIMB


When installing additional plates, categorize plates the fixed half and moving halves as shown below:

Additional plate specification → P.38

In the case of S series:



In the case of 3-plate type (The chart below shows the D·E series as an example, but other series have the same configuration)




Change Nominal Base Size


Change B dimension (length direction) and A dimension (width direction) of mold plate external dimensions to extended or reduced dimension.

Application Mold bases, cavity retainer sets, cavity retainer sets for die cast

Catalog No. CSET



Basic mold base



Extended sized mold base

Constraint conditions on setting of A and B dimensions

Dimension	Constraint condition
A dimension	① $110 \leq A \leq 700$ ② $A \leq A0 + 200$ ③ When reducing the size, the shortest distance of the head diameter must be 10 or more. If no ejector plate is installed, then $A \geq A0/2$
B dimension	① If $A \times 3 \leq 1400$, then $B0 - 50 \leq B \leq A \times 3$ ② If $1400 \leq A \times$, then $B0 - 50 \leq B \leq 1400$

How to set each dimension

If you specify A and B dimensions, we set each dimension as shown in the table below. Please review each dimension for mold design strength etc. and separately specify changes in dimensions and specifications.

Item	Setting method
Width of clamping plate (TW)	$TW = TW0 + (A - A0)$
Width of spacer block (CW)	$CW = CW0$
Width of ejector plate (EFW)	$EFW = EFW0 + (A - A0)$
Thickness of plates	The same dimensions as those of basic mold base
Pitch of respective parts	When extending the size, the pitch of respective parts is calculated by adding the extended dimension $(A - A0)$, $(B - B0)$. When reducing the size, it is calculated by subtracting the reduced dimension.
Diameter and quantity of respective parts	The same diameter and quantity as those of basic mold base.
Tapped hole diameter for eye bolts	The same tapped hole diameter as that of basic mold base.



Specification of tapped holes for eye bolts:

Size extended mold base gets heavier than basic mold base. Specify appropriate tapped holes for eye bolts.

Diameter and quantity of parts and thickness of plates:

The diameter and quantity of parts and thickness of plates are the same as those of basic mold base. Please review each dimension for mold design strength etc. and separately specify changes in dimensions and specifications.

Catalog No.	B	Name of basic item	A
CSET	In 10 mm steps	Name of item as the basis for extension and reduction (Specify type and nominal dimension)	In 10 mm steps

※ For mold base order item name, specify the name of item of size to be made. Specify the nominal dimensions of the item name with the first 2 digits of A and B dimensions.


E.g. If A dimension is 320 and B dimension is 430, then the nominal dimension of the item name will be 3243.

How to order

Catalog No.	B	Basic item	A
CSET	B650	MDCSC3060	A320
CSET	B230	MDCSC2525	A250

※ For mold base order item name, specify the item of nominal dimensions to be made → MDCSC3265507080S-MN


The drawing below shows an example of extending the size of SC type 6075 by 30 mm in the length direction and by 20 mm in the width direction.



Omit Standard Plates

Omit standard plates of a mold base.

Application Mold bases, cavity retainer sets, cavity retainer sets for die cast



Catalog No.	Plate codes		※ Be sure to specify the thickness of Plate A, B and C in the mold base item name. We set the length of parts by using the thickness values specified. ※ If omitting any plates with guide bushings attached, the guide bushing will also be eliminated together with the plate.
ESI	T (Plate T)	U (Plate U)	
	R (Plate R)	C (Plate C)	
	A (Plate A)	E (Plate E)	
	S (Plate S)	F (Plate F)	
	B (Plate B)	L (Plate L)	

Cases where the omission of Plate S can be specified

- ※ The omission of Plate S can be specified only when the mold base is of SE, SF, DE, DF, EE, EF, FE, FF, GE or GF type. For other types, Plate S cannot be omitted.
- ※ The guide pins get shorter by the amount of thickness of Plate S.
- ※ A clearance hole for a support pin should be machined to the plate with which the support pin does not interfere with Plate S eliminated.

How to order

Catalog No.



ESI

Plate code


T

The charts below show the configurations of mold bases when specifying the omission of respective plates. These are typical examples. The similar configurations will be applied to other types as well.





Omit Plate T







Omit Plate R




Omit Plate A




Omit Plate B




Omit Plate S



Omit Plate U




Omit Plate C




※ The guide pins get shorter by the amount of thickness of Plate S.


Omit Plate E



Omit Plate F



Omit Plate L




Added Plates


Add plates to standard mold bases.

Application Mold bases


Specification
Change/Addition
Added Plates




Configuration of adding plates to S series




Configuration of adding plate to D·E series



Configuration of adding plates to F·G series



Configuration of adding plates to H series



Configuration of adding plates common to all series

- ※ Guide pins, return pins and other parts for additional plates, which are installed in each series of standard mold bases are shown in the charts.
- ※ The specification of additional plate Y is common to all series.
- ※ Additional Plate X and Plate Y are alternative options, either of which can be specified. If you want to add the both, please specify them with drawings, etc. attached.
- ※ Assembly Screw (M) for additional Plate Y are to be separately specified. Be sure to specify them.
Added assembly Screws ➔ P.76
- ※ Diameter ϕ D1 of holes machined on additional Plate N

D	12	16	20	25	30	35	40
D1	14	18	24	29	34	39	45

Plate addition determination table by mold base type

○ : Mold base type for which additional plate can be specified

Type	Plate codes of additional plates							Type	Plate codes of additional plates						
	Plate N	Plate O	Plate Q	Plate V	Plate W	Plate X	Plate Y		Plate N	Plate O	Plate Q	Plate V	Plate W	Plate X	Plate Y
SA	○				○	○	○	FA	○	○			○	○	○
SB	○		○	○	○	○	○	FB	○	○	○	○	○	○	○
SC	○					○	○	FC	○	○				○	○
SD	○		○	○		○	○	FD	○	○	○	○		○	○
SE	○		○	○	○	○		FE	○	○	○	○	○	○	
SF	○		○	○		○		FF	○	○	○	○		○	
DA	○	○			○	○	○	GA	○				○	○	○
DB	○	○	○	○	○	○	○	GB	○		○	○	○	○	○
DC	○	○				○	○	GC	○					○	○
DD	○	○	○	○		○	○	GD	○		○	○		○	○
DE	○	○	○	○	○	○		GE	○		○	○	○	○	
DF	○	○	○	○		○		GF	○		○	○		○	
EA	○				○	○	○	HA	○	○			○	○	○
EB	○		○	○	○	○	○	HB	○	○	○	○	○	○	○
EC	○					○	○	HC	○	○				○	○
ED	○		○	○		○	○	HD	○	○	○	○		○	○
EE	○		○	○	○	○		※ Additional plate X and Plate Y are alternative options, either of which can be specified. If you want to specify the both, please specify them with drawings, etc. attached.							
EF	○		○	○		○									

Catalog No.	Plate code of additional plates	T (thickness of additional plate)	Length of installation parts
SADDP	N (Additional Plate N)	Select from Plate General Catalog Red Book. (Product of thickness other than shown in the plate general catalog will be made to order.)	① Guide pins, guide bushings, return pins and assembly screws get longer by the amount of thickness of added plates. ② Please specify the length of support pin and puller bolts.
	O (Additional Plate O)		
	Q (Additional Plate Q)		
	V (Additional Plate V)		
	W (Additional Plate W)		
	X (Additional Plate X)		
	Y (Additional Plate Y)		

 How to order

 Catalog No. — — — —

Change Parts Diameter



Change the diameter of guide pins, support pins, return pins, and assembly screws and related hole dimensions.



When changing diameter of parts, consider the following:

- ① When changing diameter of parts, take into account the strength, etc.
- ② Changing diameter of a part may result in interference with other parts.
Consider the positions, etc.

Application Mold bases, cavity retainer sets, cavity retainer sets for die cast



※ Changing diameter of guide pins and support pins also requires changes in diameter of guide bushings that will fit them.

Part name	Catalog No.	Part classification code	D or M
Guide pins and guide bushings	CPD	GP	12 16 20 25 30 35 40 50 60 70
Support pins and guide bushings		SP	12 16 20 25 30 35 40
Return pins		RP	10 12 15 20 25 30
Fixed side assembly screws		TCS	M8 M10 M12 M14 M16 M20 M24
Moving side assembly screws		LCS	M8 M10 M12 M14 M16 M20 M24
Ejector plate assembly screws		ECS	M5 M6 M8 M10 M12 M14 M16

How to order

	Catalog No.	Part classification	D or M
Change the diameter of guide pins and guide bushings	CPD	GP	D25
Change the diameter of support pins and guide bushings	CPD	SP	D40
Change the diameter of return pins	CPD	RP	D12
Change the diameter of fixed side assembly screws	CPD	TCS	M16
Change the diameter of movable side assembly screws	CPD	LCS	M12
Change the diameter of ejector plate assembly screws	CPD	ECS	M8

Regarding use of MOLDZUKAN®

When entering specification changes of standard installation parts (guide pins and support pins, etc.) by using MOLDZUKAN®, you need to follow a certain entry sequence defined according to the contents of changes as shown below. If entered in incorrect sequence, MOLDZUKAN® may not function properly.

● Entry sequence of standard installation parts specification changes

Special form of guide
↓
Part diameter change
↓
Precision guide pin and guide bushing installation
↓
Guide pin type and length change
↓
Support pin type and length change
↓
Guide bushing installation specification change and addition
↓
Enter each item only if there is any change in the item.
If no change, then skip the item and move to the next one.
After entering the above items, you can enter other items in any sequence.

Change Precision Guide Pins and Guide Bushings





Install precision guide pins and precision guide bushings in standard mold bases.



If installing precision guide pins and guide bushings, please specify the details by following the steps below:



- ① For plates in which precision guide pins and precision guide bushing are installed, surface grinding will be used.
The limit deviations of plate thickness are required.
Please specify them.
How to specify surface grinding → P.31
 - ② To maintain the accuracy of holes in plates, we also recommend rough machining of pockets and slide core grooves, etc.
How to specify machining of pockets and slide core grooves → P.204 - 221
 - ③ As the clearance between the guide pin and guide bushing is small, we recommend to provide an air vent.
- Precaution for use of precision guide pins and guide bushings → P.272**

Application Mold bases S series, D and E series, cavity retainer sets

		Precision guide bushing M-GBHF	Precision guide bushing M-GBSF
Precision guide bushing	Precision guide pin		
		■ Nominal diameter 12 16 20 25 ■ Part details ➡ P.288	■ Nominal diameter 12 16 20 25 ■ Part details ➡ P.289
Precision guide pin M-GPH		Combination code GPP1 ■ Nominal diameter of parts that can be combined: 12	
■ Nominal diameter 12  ■ Part details ➡ P.278			
Precision guide pin M-GPHF		Combination code GPP2 ■ Nominal diameter of parts that can be combined: 12 16 20 25	
■ Nominal diameter 12 16 20 25  ■ Part details ➡ P.279			

※ The length of guide bushing is the same as that before change. Depending on the type of guide bushing, however, appropriate length may not be available. Refer to "Guide Bushing Installation Specification Change and Addition" in ➡ P.48 for review.

Guide pin specifications



Precision guide pin M-GPH	Precision guide pin M-GPHF
Corresponds to Combination code GPP1	Corresponds to Combination code GPP2
	

Guide bushing installation specifications for D and E series

When installing precision guide bushing in the D and E series, differentiate the use of guide bushings to install in various plates as shown below.

When installing precision guide bushing in Plate A:


Install straight type precision bushing in Plate A with specifications as shown below.



D	A	L
12 16	20 25 30 35 40	L=A-1
20	20 25 30 35 40 50	
25	25 30 35 40 50	

D	A	L
12 16	A > 40	L=39
20	A > 50	L=49
25	A > 50	L=49

When installing precision guide bushing in Plate B:




Install shoulder type precision guide bushing in Plate B. Depending on thickness of the plate, however, appropriate length may not be available.

Optional specifications (specify only when necessary)

Option code

Specifications

AC



Provide an air vent in the plate adjacent to the guide bushing. The shape of the air vent will be either A or B depending on the position of the guide pin.

■ How to specify:
Specify AC

Catalog No.	Combination code	Guide pin specifications		Optional specification
		L	SL	
CGPGBS	GPP1	Select from page 278	Select from page 278	AC
	GPP2	In 5 mm steps See page 279	In 1 mm steps See page 279	

※ Even when the guide pin is longer than the mold plate, the clearance hole of the guide pin will not be machined.
Added Clearance Holes for Guide Pin → P.54

How to order

Catalog No.	Combination code	L	SL	Optional specification
CGPGBS	GPP1	L60	SL24	AC
CGPGBS	GPP2	L120	SL39	AC

Regarding use of MOLDZUKAN®

When entering specification changes of standard installation parts (guide pins and support pins, etc.) by using MOLDZUKAN®, you need to follow a certain entry sequence defined according to the contents of changes.

If entered in incorrect sequence, MOLDZUKAN® may not function properly.

MOLDZUKAN® operation procedure details → P.41

Change Type and Length of Guide Pins — ①

Change guide pins and guide bushings for standard mold base to difference types of guide pins and guide bushings.
Change the length of guide pins for standard mold bases.





Application Mold bases, cavity retainer sets, cavity retainer sets for die cast

Specification Change/Addition Change Type and Length of Guide Pins — ①	Guide bushing		Guide pin			
	■ No oil groove ■ Nominal diameter: 12 16 20 25 30 35 40 50 60 70 ■ Part details → P.286		■ With oil groove ■ Nominal diameter: 12 16 20 25 30 35 40 50 ■ Part details → P.290		■ Self lubricating, copper alloy type ■ Nominal diameter: 16 20 25 30 35 40 50 ■ Part details → P.292	
	Guide bushing M-GBA	Guide bushing M-GBB	Guide bushing M-GBGF	Guide bushing M-GBRF	Guide bushing M-GBGDF	Guide bushing M-GBRDF
Guide pin M-GPA ■ With oil groove ■ Nominal diameter: 12 16 20 25 30 35 40 50 60 70 ■ Part details → P.274	Combination code GPH0 ※ This is a combination for standard mold base. ※ If not specified, this combination will be used.					
Guide pin M-GPH ■ No oil groove ■ Nominal diameter: 12 ■ Part details → P.278			Combination code GPH1 ■ Nominal diameter of parts that can be combined: 12			
Guide pin M-GPHF ■ No oil groove ■ Nominal diameter: 12 16 20 25 30 35 40 50 ■ Part details → P.279			Combination code GPH2 ■ Nominal diameter of parts that can be combined: 12 16 20 25 30 35 40 50		Combination code GPH3 ■ Nominal diameter of parts that can be combined: 16 20 25 30 35 40 50	
Guide pin M-GPHFS ■ With spiral oil groove ■ Nominal diameter: 12 16 20 25 30 35 40 50 ■ Part details → P.280	Combination code GPH4 ■ Nominal diameter of parts that can be combined: 12 16 20 25 30 35 40 50					

※ The length of guide bushing is the same as that before change. Depending on the type of guide bushing, however, appropriate length may not be available. Refer to "Guide Bushing Installation Specification Change and Addition" in → P.48 for review.

※ The combinations of guide pins and guide bushings shown in the above charts are standard combinations. The combinations in the blank columns cannot be specified with additional processing codes. If specifying them, please provide drawings, etc.

Guide pin specification

Guide pin M-GPA		Guide pin M-GPH	
Fits	Combination code GPH0	Fits	Combination code GPH1
			
Guide pin M-GPHFS		Guide pin M-GPHF	
Fits	Combination code GPH4	Fits	Combination code GPH2、GPH3
			

Catalog No.	Combination code	Guide pin specification		
		L	SL	S
CGPGB1	GPH0 *1	Select from P.274	Select from P.274	—
	GPH1	Select from P.278	Select from P.278	
	GPH2 GPH3	In 5 mm steps See page 279	In 1 mm steps See page 279	
	GPH4	In 5 mm steps See page 280	In 1 mm steps See page 280	In 1 mm steps See page 280

*1. If the SL dimension of Combination code **GPH0** is not specified, we will set the dimension.
Specify the SL dimension only when necessary.

※ For Combination code **GPH1 – GPH4**, the specification of SL dimension cannot be omitted.

※ Even when the guide pin is longer than the retainer plate, the clearance hole of the guide pin will not be machined.

Machining Clearance Holes for Guide Pins → P.54

How to order

Catalog No.	Combination code	L	SL	S
CGPGB1	GPH0	L97	SL29	
CGPGB1	GPH2	L60	SL24	
CGPGB1	GPH4	L120	SL39	S60

Regarding use of MOLDZUKAN®

When entering specification changes of standard installation parts (guide pins and support pins, etc.) by using MOLDZUKAN®, you need to follow a certain entry sequence defined according to the contents of changes.

If entered in incorrect sequence, MOLDZUKAN® may not function properly.

MOLDZUKAN® operation procedure details → P.41

Change Type and Length of Guide Pins — ②

Change the guide pins and guide bushings for standard mold bases to different types of straight guide pins and guide bushings.

Application Mold bases, cavity retainer sets, cavity retainer sets for die cast

Guide bushing / Guide pin	Guide bushing		Guide bushing		Guide bushing	
	Guide bushing M-GBA	Guide bushing M-GBB	Guide bushing M-GBGF	Guide bushing M-GBRF	Guide bushing M-GBGDF	Guide bushing M-GBRDF
Guide pin M-GPSF	■ No oil groove ■ Nominal diameter: 12 16 20 25 30 35 40 50 60 70 ■ Part details → P.286		■ With oil groove ■ Nominal diameter: 12 16 20 25 30 35 40 50 ■ Part details → P.290		■ Self lubricating, copper alloy type ■ Nominal diameter: 16 20 25 30 35 40 50 ■ Part details → P.292	
Guide pin M-GPSFR	■ No oil groove ■ Nominal diameter: 25 30 35 40 50 ■ Part details → P.282		Combination code GPS1 ■ Nominal diameter of parts that can be combined: 25 30 35 40 50		Combination code GPS2 ■ Nominal diameter of parts that can be combined: 25 30 35 40 50	
Guide pin M-GPSFS	Combination code GPS3 ■ Nominal diameter of parts that can be combined: 25 30 35 40 50					
Guide pin M-GPSFS	Combination code GPS4 ■ With spiral oil groove ■ Nominal diameter: 25 30 35 40 50 ■ Part details → P.284					

※ The length of guide bushing is the same as that before change. Depending on the type of guide bushing, however, appropriate length may not be available. Refer to "Change Installation of Guide Bushings and/or Added Guide Bushing Specification" in → P.48 for review.


※ The combinations of guide pins and guide bushing shown in the above charts are standard combinations. The combinations in the blank columns cannot be specified with additional processing codes. If specifying them, please provide drawings, etc.

Guide pin specification


Guide pin M-GPSF	Guide pin M-GPSFR	Guide pin M-GPSFS
Fits Combination code GPS1, GPS2	Fits Combination code GPS3	Fits Combination code GPS4

Guide pin installation specification


Installation code SZ




Installation code SS



Installation code YZ



Installation code YS



Guide pin dia.		25	30	35	40	50
Z		$Z \leq 120$	$Z \leq 130$	$Z \leq 150$	$Z \leq 200$	
M		M12			M16	
BZ		13			17	
BL	Combination code	SZ	BL=Plate B thickness -Z-BZ+20			BL=Plate B thickness -Z-BZ+26
		SS	BL=Plate U thickness -BZ+20			BL=Plate U thickness -BZ+26
		YZ	BL=Plate A thickness -Z-BZ+20			BL=Plate A thickness -Z-BZ+26
		YS	BL=Plate T thickness -BZ+20			BL=Plate T thickness -BZ+26
Round down the last digit of calculation result, 0-4 to 0 and 5-9 to 5						
Z1		$Z1 \geq 5$ This formula is not a guarantee of strength.				
Installation code		YS is not applied to mold bases of 3 plate types and with additional Plate N.				

Catalog No.	Combination code	Installation code	Z	Guide pin specification				Optional Specification
				L	SL	Q(# of grooves)	S	
CGPGB2	GPS1 GPS2	SZ SS YZ YS	In 1 mm steps	In 5 mm steps See page 282	In 1 mm steps See page 282	—	—	DKC ^{*1}
	GPS3		No need to specify for SS and YS	In 5 mm steps See page 283	In 1 mm steps See page 283	In 1 line steps See page 283	—	
	GPS4			In 5 mm steps See page 284	In 1 mm steps See page 284	—	In 1 mm steps See page 284	

*1. The dimensional limit deviations of press fit section of the guide pin will be in between +0.005 to 0.

※ Even when the guide pin is longer than the mold plate, the clearance hole for the guide pin will not be machined.

Added Clearance Holes for Guide Pins ➡ P.54

How to order

Catalog No.	Combination code	Installation code	Z	L	SL	Q	S	Optional spec.
CGPGB2	GPS1	SZ	Z50	L150	SL39			
CGPGB2	GPS3	SZ	Z70	L180	SL59	Q3		
CGPGB2	GPS4	YZ	Z60	L160	SL59		S80	DKC

Regarding use of MOLDZUKAN®

When entering specification changes of standard installation parts (guide pins and support pins, etc.) by using MOLDZUKAN®, you need to follow a certain entry sequence defined according to the contents of changes.

If entered in incorrect sequence, MOLDZUKAN® may not function properly.

MOLDZUKAN® operation procedure details ➡ P.41







Change Installation of Guide Bushings and/or Added Guide Bushings Specification – Overview









Change the installation specifications of guide bushings that fit the guide pins and support pins for standard mold bases.

This additional processing specification allows users to order 3 types of change or addition to the standard mold base installation specifications:

- ① Changes in length of guide bushings of standard installation specifications
- ② Changes in guide bushing installation specifications of standard mold bases
- ③ Installation of guide bushings in the plates with no guide bushing installed in the standard mold bases.

The charts below show examples of changing guide bushing installation specifications of standard mold bases.

Before ordering the changes in guide bushing installation specifications	After ordering the changes in guide bushing installation specifications	Examples of orders for changes in guide bushing installation specifications
 Plate A	 Plate A	When changing the length of a guide bushing for Plate A: [Order example] CPHGBN – GP – A – GBT1 – L59 Details on how to order: Shoulder type ➡ P.50 Straight type ➡ P.52
 Plate A	 Plate A	When changing a guide bushing for Plate A from shoulder type to straight type and move it closer to the one end: [Order example] CPHGBN – GP – A – GB19 – L69 – Z18 Details on how to order: Shoulder type ➡ P.50 Straight type ➡ P.52
 Plate S	 Plate S	When changing a guide bushing for Plate S from the straight type to the shoulder type and move it closer to the one end: [Order example] CPHGBN – GP – S – GBT2 – L29 Details on how to order: Shoulder type ➡ P.50 Straight type ➡ P.52

Before ordering the changes in guide bushing installation specifications	After ordering the changes in guide bushing installation specifications	Examples of orders for changes in guide bushing installation specifications
 Plate S	 Plate S	When moving the guide bushing for Plate S closer to the one end: [Order example] CPHGBN—GP—S—GBI4—L24 Details on how to order: Shoulder type ➡ P.50 Straight type ➡ P.52
 Plate A	 Plate A	When making the counterbore machined for the guide bushing on the Plate A deeper: [Order example] CPHGBN—SP—A—GBT4—L59—Z20 Details on how to order: Shoulder type ➡ P.50 Straight type ➡ P.52
 Plate S	 Plate S	When adding a guide bushing to Plate S: [Order example] CPHGBN—SP—S—GBT2—L29 Details on how to order: Shoulder type ➡ P.50 Straight type ➡ P.52
 Additional Plate N	 Additional Plate N	When adding a guide bushing to an additional plate, Plate N. [Order example] SADDP—N—T30 (Order of adding a plate) CPHGBN—GP—N—GBI1—L29 CGPGB1—GPH0—L107—SL29 (Order of changing guide pin length) ※ An order of changing the length of guide pin is required. Details on how to order: Shoulder type ➡ P.50 Straight type ➡ P.52


Change Installation of Guide Bushings and/or Added Guide Bushings Specification – ①

Change the installation specifications of guide bushings that fit the guide pins and support pins for standard mold bases.

This additional processing specification allows users to order 3 types of change or addition to the standard mold base installation specifications:

- ① Changes in length of guide bushings of standard installation specifications
- ② Changes in guide bushing installation specifications of standard mold bases
- ③ Installation of guide bushings in the plates with no guide bushing installed in the standard mold bases.

Application Mold bases, cavity retainer sets, cavity retainer sets for die cast



[The length of guide pin in the case of adding an guide bushing]

The length of the guide pin is the same as that before adding the guide bushing. When changing the length of the guide pin, specify it separately.

Change the length of guide pins ➔ P.44



Change the type of guide pins and guide bushings ➔ P.44

	Head up*1	Head down*1	Install two guide bushings
Flushness of guide bushing	Installation code GBT1 	Installation code GBT2 	Installation code GBT5
Specify the depth of counterbore	Installation code GBT3 	Installation code GBT4 	Installation code GBT6 ※ When making either of Z or J side flush with the guide bushing, specify the depth of the side as 0.

*1. Specifying "Head up" will install the guide bushing with its head facing the top clamping plate (Plate T) while specifying "Head down" will install it with its head facing the bottom clamping plate (Plate L).

※ The length of the guide bushing can be specified, even when it is longer than the thickness of the plate, with the exception of **Installation code** GBT5, GBT6.

Guide bushing Installation specifications



D	D1	H	Z	L1 or L2 ^{*2}
12	18	5	Z ≤ 45	L1 or L2 ≤ 80
16	25	6	Z ≤ 55	L1 or L2 ≤ 120
20	30	8	Z ≤ 60	L1 or L2 ≤ 130
25	35	8	Z ≤ 65	L1 or L2 ≤ 150
30	42	10	Z ≤ 65	L1 or L2 ≤ 200
35	48	10	Z ≤ 70	L1 or L2 ≤ 200
40	55	10	Z ≤ 70	L1 or L2 ≤ 200
50	70	12	Z ≤ 70	L1 or L2 ≤ 200
60	80	15	Z ≤ 70	L1 or L2 ≤ 200
70	90	15	Z ≤ 70	L1 or L2 ≤ 200

*2. Either of L1 or L2 condition must be met.

*3. When $T \geq L1$ (Maximum value in the above table), a clearance hole of $D2=D1-(1 \sim 2)$ may be used.

※ Depending on the balance with other additional specifications, different specification may be used. In that case, we will notify you.

Catalog No.	Part classification code	Plate code ^{*4}	Guide bushing installation specification				
			Installation code	L	Z	N	J
CPHGBN	GP SP	T (Plate T) R (Plate R) A (Plate A) S (Plate S) B (Plate B) U (Plate U) L (Plate L) Additional plate N (Plate N) O (Plate O) Q (Plate Q) V (Plate V) W (Plate W) X (Plate X) Additional plate specifications ↓ P.38	GBT1 GBT2	See table below	—	—	—
			GBT3 GBT4		In 1 mm steps		
			GBT5		—	See table below	In 1 mm steps
			GBT6		In 1 mm steps		

*4. Please specify the plate codes of the plates to which to specify changes in installation specification or addition of guide bushings.

Variations in types of shoulder guide bushings

Guide bushing installed in standard mold bases	If installing these types of guide bushings, the type of the guide bushing need to be changed. → P.44		
Guide bushing M-GBA → P.286	Guide bushing M-GBHF → P.288	Guide bushing M-GBGF → P.290	Guide bushing M-GBGDF → P.292
☒ No oil groove ☒ Precision: Standard	☒ With oil groove ☒ Precision: High	☒ With oil groove ☒ Precision: Standard	☒ Self lubricating, copper alloy type ☒ Precision: Standard

How to order

Catalog No.	Part classification code	Plate code	Installation code	L	Z	N	J
CPHGBN	GP	S	GBT2	L39			
CPHGBN	SP	A	GBT6	L59	Z10	N49	J15


Change Installation of Guide Bushings and/or Added Guide Bushings Specification – ②

Change the installation specifications of guide bushings that fit the guide pins and support pins for standard mold bases.


This additional processing specification allows users to order 3 types of specification change or addition to the standard mold base installation specifications:

- ① Changes in length of guide bushings of standard installation specifications
- ② Changes in guide bushing installation specifications of standard mold bases
- ③ Installation of guide bushings in the plates with no guide bushing installed in the standard mold bases.

Application Mold bases, cavity retainer sets, cavity retainer sets for die cast




Installation code **GBI0**^{*2}



※ The hole dia. is the same as the guide pin dia.

Installation code **GBI1**




※ Applied when thickness = L+1

Move to upper side^{*1}


Move to lower side^{*1}

Flushness of guide bushing


Installation code **GBI2**
[Through-hole boring]




Installation code **GBI3**



Installation code **GBI4**
[Through-hole boring]




Installation code **GBI5**




Specify the depth of counterbore


Installation code **GBI6**
[Through-hole boring]




Installation code **GBI7**



Installation code **GBI8**
[Through-hole boring]



Installation code **GBI9**



*1. Specifying "Move to upper side" will install the guide bushing from the top clamping plate (Plate T) while specifying "Move to lower side" will install guide bushing from the bottom clamping plate (Plate L).

*2. The hole dimension of Installation code **GBI0** will be as follows:

D	DIMM.	12	16	20	25	30	35	40	50	60	70
	Deviation H6	+0.011 0		+0.013 0			+0.016 0			+0.019 0	
T		T≤60 T≤80		T≤100	T≤120	T≤130	T≤150	T≤200	T≤200	T≤200	T≤200

Guide bushing installation specifications

If selecting an installation code **GBI3**, **GBI5**, **GBI7** or **GBI9**, then the installation hole of the guide bushing will be any one of Type 1 to Type 3 shown in the following charts depending on the Plate N dimension:

Type1			Type2				Type3			
D	12	16	20	25	30	35	40	50	60	70
D1	18	25	30	35	42	48	55	70	80	90
D2※2	14	18	24	29	34	39	45	54	65	75
N	Type1	N ≧ 12	N ≧ 14	N ≧ 15	N ≧ 17	N ≧ 21	N ≧ 24	N ≧ 27	N ≧ 33	N ≧ 39
	Type2	6 ≦ N < 12	6 ≦ N < 14	6 ≦ N < 15	6 ≦ N < 17	6 ≦ N < 21	6 ≦ N < 24	6 ≦ N < 27	6 ≦ N < 33	6 ≦ N < 39
	Type3	N < 6 ※ The specifications of Type 3 are the same as those of installation code GBI2, GBI4, GBI6 and GBI8. When specifying Type 3, use installation code GBI2, GBI4, GBI6 or GBI8.								
L1	L1 ≦ 80	L1 ≦ 120	L1 ≦ 130	L1 ≦ 150	L1 ≦ 200	L1 ≦ 200	L1 ≦ 200	L1 ≦ 200	L1 ≦ 200	L1 ≦ 200
P	$P = \frac{L}{2} + Z + 0.5$									

*2. The guide bushing hole for D·E series and H series support pins is D2=D+2.

※ Depending on the balance with other additional specifications, different specification may be used. In that case, we will notify you.

Catalog No.	Part classification code	Plate code *3	Guide bushing installation specification		
			Installation code	L	Z
CPHGBN	GP SP	Additional Plates N (Plate N) O (Plate O) Q (Plate Q) V (Plate V) W (Plate W) X (Plate X) Additional plate specifications ↓ P.38	GBI0 GBI1	—	—
			GBI2 GBI3 GBI4 GBI5	See table below	In 0.5 mm steps
			GBI6 GBI7 GBI8 GBI9		

*3. Please specify the plate codes of the plates to which to specify changes in installation specification or addition of guide bushings.

Variations in types of straight guide bushings

Guide bushing installed in standard mold bases	If installing these types of guide bushings, the type of the guide bushing need to be changed. → P.44		
Guide bushing M-GBB → P.287	Guide bushing M-GBSF → P.289	Guide bushing M-GBRF → P.291	Guide bushing M-GBRDF → P.293
☒ No oil groove ☒ Precision: standard	☒ With oil groove ☒ Precision: High	☒ With oil groove ☒ Precision: standard	☒ Self lubricating, copper alloy type ☒ Precision: standard

How to order

Catalog No.	Part classification code	Plate code	Installation code	L	Z
CPHGBN	GP	A	GBI1		
CPHGBN	SP	B	GBI7	L69	Z10

Added Clearance Holes for Guide Pin


Perform additional machining of clearance holes for guide pins.

Application Mold bases (excluding F and G series)


Specification Change/Addition
Added Clearance Holes for Guide Pin

Install guide pins in the moving side

Application S series




Application D·E series, H series




Install guide pins in the fixed side

Application S series, D·E series, H series



D	12	16	20	25	30	35	40	50	60	70
D1	14	18	24	29	34	39	45	54	65	75

Optional specification (specify only when necessary)

Option code	Specification
MHD	 Machine a clearance hole for guide pin as a blind hole in the plates specified. ■ How to specify: MHD/Z [Z dimension] [E.g.] MHD/Z30

Orientation of guide	Catalog No.	Plate code ^{*1}	Optional spec.
Install the guide pins in the moving side.	MGPHN	T (Plate T) N (Additional plate N) ^{*2} R (Plate R) O (Additional plate O) ^{*2}	MHD
Install the guide pins in the fixed side.		U (Plate U) W (Additional plate W) ^{*2} C (Plate C) X (Additional plate X) ^{*2} L (Plate L)	

*1. The clearance holes for guide pins will be machined through to the plate specified with a plate code.

*2. Additional plate specifications → P.38

How to order

Catalog No. — Plate code — Optional specification


MGPHN — T

MGPHN — C — MHD/Z25


Change Specification of Guide Pin Holes

Change specifications of holes for guide pins.

- Application** Mold bases (excluding F and G series), cavity retainer sets, cavity retainer sets for die cast
This change cannot be specified for straight type guide pins.




Basic holes for guide pins installed in the standard mold bases are through-boring holes as shown in the chart below: *1




A section specification

Specification code **PLB**



Specification code **PLD**



- *1. If the nominal dimension for a mold base is 5555 to 7080 and the thickness of the plate is over 200, the specifications of holes for guide pins need to be specified.
*2. The ϕD and $\phi D+(0.2\sim 1)$ holes are not concentric to each other.
※ Please specify the length of press fit section of the guide pin.
Specify length of press fit section of guide pin ➔ P.44
※ If the thickness of the plate in which the guide pins are installed exceeds Z dimension, the specifications of the holes for guide pins need to be specified.

D	12	16	20	25	30	35	40	50	60	70
Z	$Z \leq 60$	$Z \leq 80$	$Z \leq 100$	$Z \leq 120$	$Z \leq 130$	$Z \leq 150$	$Z \leq 200$	$Z \leq 200$	$Z \leq 200$	$Z \leq 200$

Catalog No.	Specification code	Z
CGPH	PLB PLD	In 1 mm steps

How to order

Catalog No.	Specification code	Z
CGPH	PLB	Z50
CGPH	PLD	Z60

Install Guide Pins


Installing guide pins from Plate U

Install guide pins from Plate U.

◀Application▶ Mold bases S series, D·E series and H series (excluding the types without Plate U)


Install guide pins from Plate U

Catalog No. **SGPU1**




Install guide pins from Plate U and install moving side assembly screws through to Plate U

Catalog No. **SGPU2**




Install guide pins from Plate U and install moving side assembly screws through to Plate U. Then, install guide bushings in Plate B

Catalog No. **SGPU3**



Install guide pins from Plate U and install moving side assembly screws through to Plate U. Install straight guide bushings in Plate B.

Catalog No. **SGPU4**



※ The guide pin gets longer by the amount of thickness of Plate U (the length of press fit section will be set by Futaba).

Change the length of guide pins ➡ P.44

※ For guide bushing installation specifications, depending on the thickness of Plate B, appropriate length of guide bushing may not be available. Refer to "Change Installation of Guide Bushings and/or added Guide Bushings Specification" (➡ P.48) to review guide bushing installation method.

※ For Catalog No. **SGPU1**, counterbore holes for guide pins may be left in Plate B.

Catalog No.

SGPU1
SGPU2
SGPU3
SGPU4

How to order





Catalog No.

SGPU1

Installing guide pins from Plate T

Install guide pins from Plate T.

Application Mold bases S series

Install guide pins from Plate T	Install guide pins from Plate T and guide bushings in Plate A
Catalog No. SGPT1 	Catalog No. SGPT2 
Install guide pins from Plate T and straight type guide bushings in Plate A	When installing additional plate, Plate N
Catalog No. SGPT3 	 ※ Boring holes are machined in the additional Plate N. ※ Installing guide bushings in the additional Plate N ➡ P.48

※ The guide pin gets longer by the amount of thickness of Plate T (the length of press fit section will be set by Futaba). Change the length of guide pins ➡ P.44
 ※ For guide bushing installation specifications, depending on the thickness of Plate A, appropriate length of guide bushing may not be available.
 Refer to "Change Installation of Guide Bushings and/or added Guide Bushings Specification" in (➡ P.48) to review guide bushing installation.

Catalog No.	Fixed side assembly screw ^{*1}
SGPT1 SGPT2 SGPT3	Fixed side assembly screw not installed ESPH/TCS

*1. Specify this option when fixed side fastening bolts are unnecessary.
Both the holes for bolts and screws will be eliminated.

How to order

Catalog No. — Fixed side assembly screw

SGPT1

SGPT2 — ESPH/TCS

Regarding use of MOLDZUKAN®

When entering specification changes of standard installation parts (guide pins and support pins, etc.) by using MOLDZUKAN®, you need to follow a certain entry sequence defined according to the contents of changes.

If entered in incorrect sequence, MOLDZUKAN® may not function properly.

MOLDZUKAN® operation procedure details ➡ P.41

Change Type and Length of Support Pins

Change the support pins and guide bushings for standard mold bases to different types of support pins and guide bushings.

Change the length of support pins for standard mold bases.

Application Mold bases (excluding S series)

Specification Change/Addition Change Type and Length of Support Pins	Guide bushing		Support pin			
	- No oil groove - Nominal diameter: 12 16 20 25 30 35 40	- With oil groove - Nominal diameter: 12 16 20 25 30 35 40	- Self lubricating, copper alloy type - Nominal diameter: 16 20 25 30 35 40			
	Part details → P.286	Part details → P.290	Part details → P.292			
	Guide bushing M-GBA	Guide bushing M-GBB	Guide bushing M-GBGF	Guide bushing M-GBRF	Guide bushing M-GBGDF	Guide bushing M-GBRDF
Support pin M-SPN	Combination code SPH0					
- With oil groove - Nominal diameter 12 16 20 25 30 35 40	※ This is a combination for standard mold base. ※ If not specified, this combination will be used					
Part details → P.294						
Support pin M-SPHF			Combination code SPH1		Combination code SPH2	
- No oil groove - Nominal diameter 12 16 20 25 30 35 40			Nominal diameter of parts that can be combined: 12 16 20 25 30 35 40		Nominal diameter of parts that can be combined: 16 20 25 30 35 40	
Part details → P.295						
Support pin M-SPHFS	Combination code SPH3					
- With spiral oil groove - Nominal diameter 12 16 20 25 30 35 40	Nominal diameter of parts that can be combined: 12 16 20 25 30 35 40					
Part details → P.296						



- ※ The length of guide bushing is the same as that before change. Depending on the type of guide bushing, however, appropriate length may not be available. Refer to "Change Installation of Guide Bushings and/or added Guide Bushings Specification" in → P.48 for review.
- ※ The combinations of guide pins and guide bushings shown in the above charts are standard combinations. The combinations in the blank columns cannot be specified with additional processing codes. If specifying them, please provide drawings, etc.




Check

Calculating support pin deflection → P.445

Support pin specifications

Support pin M-SPN	Support pin M-SPHF
Corresponds to Combination code SPH0	Corresponds to Combination code SPH1,SPH2
	

Support pin M-SPHFS
Corresponds to Combination code SPH3


The H dimensions for **Combination code** SPH1 to SPH3 is available in two levels:

D	12	16	20	25	30	35	40
H	6	8	10	12	14	16	18
	5	6	6	8	8	8	10

Catalog No.	Combination code	Support pin specification			
		L	SL	H	S
CSPGB	SPH0	Select from page 294	—	—	—
	SPH1 SPH2	In 5 mm steps See page 295	In 1 mm steps See page 295	Select from the above table	
	SPH3	In 5 mm steps See page 296	In 1 mm steps See page 296		In 1 mm steps See page 296

How to order

Catalog No.	Combination code	L	SL	H	S
CSPGB	SPH0	L150			
CSPGB	SPH1	L150	SL24	H8	
CSPGB	SPH3	L250	SL34	H12	S180

Regarding use of MOLDZUKAN®

When entering specification changes of standard installation parts (guide pins and support pins, etc.) by using MOLDZUKAN®, you need to follow a certain entry sequence defined according to the contents of changes.

If entered in incorrect sequence, MOLDZUKAN® may not function properly.

MOLDZUKAN® operation procedure details ➡ P.41


Change Support Pin Collars (Type M-SPD)

Installing support pin collar M-SPD

Change the support pin collar to M-SPD. This will help reduce mold opening amount by 5 mm.

Support pin collar M-SPD ➔ P.297

Application Mold bases D and E series



Catalog No.

CPSPD



How to order


Catalog No.

CPSPD


Installing H series support pin collars

Install support pin collars for H series mold bases.


Application Mold bases H series



Type of support pin collars



Code: SPC



Code: SPD

Catalog No.	Types of support pin collars
CPHSP	SPC SPD



How to order

Catalog No.

CPHSP

Type of support pin collars


SPC

Deleting support pin collars

Change the standard specification to the one that does not install support pin collars.

※ If not installing support pin collars, no stopper of the cavity plate (fixed half) (Plate A) is provided. Therefore, adequate precaution should be taken to prevent the fixed side retainer plate from failing off the mold base when transporting or disassembling it.

Application Mold bases D and E series



Catalog No.	Part code
ESP	SPC



How to order

Catalog No.


Part code

ESP


SPC

Support pin collar specifications

For D·E and H series mold bases, the diameter of the clearance holes for support pins is determined according to whether or not the support pin collar is installed.



With a support pin collar




Without a support pin collar

Support pin	D	12	16	20	25	30	35	40
With support pin collar	D1	18	22	28	33	40	45	50
Without support pin collar	D2	14	18	24	29	34	39	45

Change Clearance Holes for Support Pin


The plates in which to machine clearance holes for support pins are determined according to the length of the support pins. Machine clearance holes for support pins in the specified plates that are not configured to have clearance holes by the standard specifications.

Application Mold base D·E series, F·G series and H series



 represents the clearance holes support pins

Optional specification (specify only when necessary)

Option code	Specification
MHD	 Machine clearance holes for support pins as a blind hole in the plates specified. How to specify: MHD/Z Z dimension [e.g.] MHD/Z30

Catalog No.	Plate code*1	Optional spec.
CIHSPN	S (Plate S) Q (Additional Plate Q)*2 B (Plate B) V (Additional Plate V)*2 U (Plate U) W (Additional Plate W)*2 C (Plate C) X (Additional Plate X)*2 L (Plate L)	MHD
No clearance hole for support pin: ALN		

*1. Clearance holes for support pins are machined through to the plate of which plate code is specified.

*2. Additional plate specifications → P.38

How to order


Catalog No. — **Plate code** — **Option code**

CIHSPN — L — MHD/Z45
 CIHSPN — C — MHD/Z45


Standard setting for support pin clearance holes

The plates in which to machine clearance holes for support pins are determined based on the following conditions:


Please order additional machining work of adding or eliminating support pin clearance holes shown on the left page only when your application does not fall under the conditions.



D·E series




F·G series




H series

Support pin	12	16	20	25	30	35	40
H	12.5	20.5	25	29.5	34	36	38

※ When the distance from a support pin to the next plate is $L0 < 3$, a through hole will be machined in the next plate as well.



※ For D·E series and H series, even when the support pin is short, a clearance hole for the support pin will be machined in Plate S, Plate B, additional Plate Q, and additional Plate V.



※ The plates between Plate U and Plate L will be machined depending on the length of the support pin.

Change Length of Return Pins, Assembly Screws, Puller Bolts



Change the length of return pins, assembly screws and puller bolts.

The machining of holes in plates is the same as that of standard specifications. Only the length of the part needs to be specified. For puller bolts, however, clearance holes will be machined according to the length of the bolts.


Application Mold bases

Specification
Change/Addition


Change Length of Return Pins, Assembly Screws, Puller Bolts




Part code RPN



Part code RPL




Part code RPM



Part code TCS

Part code LCS

Part code ECS



Part code PBA

※ The changing puller bolt length process applies to H series mold bases.

Part name	Part code	Handling of part length
Return pins (in 1 mm steps)	RPN	Return pin M-RPN (head thick 4 mm) → Select from P.338 Return pin M-RP8N (head thick 8 mm) → Select from P.338 When the desired length of return pins is not listed herein, specify it in 1 mm steps.
Return pins (in 0.1 mm steps)	RPL	Return pin M-RPL (head thick 4 mm) → Select from P.340 Return pin M-RP8L (head thick 8 mm) → Select from P.340
Return pins (in 0.01 mm steps)	RPM	Return pin M-RPM (head thick 4 mm) → Select from P.340 Return pin M-RP8M (head thick 8 mm) → Select from P.340
Assembly screws	TCS LCS ECS	Specify the length in 5 mm steps.
Puller bolts	PBA	Puller bolt M-PBA → Select P.313
Guide pins	—	Specifying the length of guide pins → P.44
Guide bushings	—	Specifying the length of guide bushings → P.48
Support pins	—	Specifying the length of support pins → P.58

Part name	Catalog No.	Part code	L
Return pins (in 1 mm steps)	CPL	RPN	See above table
Return pins (in 0.1 mm steps)		RPL	
Return pins (0.01 mm steps)		RPM	
Fixed side assembly screws		TCS	
Moving side assembly screws		LCS	
Ejector plate assembly screws		ECS	
Puller bolts		PBA	

※ Some parts may be delivered not assembled in the mold base if the assembly is difficult because of their length.

How to order


	Catalog No.	Part code	L
Change the length of return pins (in 1 mm steps)	CPL	RPN	L150
Change the length of return pins (in 0.1 mm steps)	CPL	RPL	L120.2
Change the length of return pins (in 0.01 mm steps)	CPL	RPM	L109.99
Change the length of fixed side assembly screws	CPL	TCS	L30
Change the length of puller bolts	CPL	PBA	L200

Change Return Pin Collars Thickness to 8 mm


Standard mold bases include 4 mm thick head type return pins. Change the pins to 8 mm thick head type return pins.

Depending on the ejector plate specifications of the mold base, the depth of the counterbore for the ejector plate will be as follows:

Application Mold bases



Counterbore type



Spacer type

Catalog No.

CPHRP8

 **How to order**

 **Catalog No.**


CPHRP8

Added Machining Return Pin Holes on S-Plate

Perform additional machining of return pin holes in Plate S.

Application Mold bases (applies to SB, SD, DB, DD, EB, ED, FB, FD, GB, GD, HB and HD types)

Catalog No. SRPS



When installing additional Plate Q or Plate V:

If installing either of Plate Q or Plate V, ordering with this code is not allowed.

How to order for addition of return pin holes to Plate S when installing Plate Q or Plate V → P.68

Return pin hole specifications

Select desired return pin specifications for Plate S and Plate B from the following 3 types:

How to order hole diameter not shown in the chart below → P.68

Specification code	BH	DH	FH
A section specification			

Catalog No.	Specification code	D H7		F	
SRPS	BH DH FH	10	+0.015 0	35	If plate thickness ≤ F, then F = plate thickness
		12	+0.018 0	50	
		15	0	60	
		20		80	
		25	+0.021 0	100	
		30		120	

※ The return pin gets longer by the amount of thickness of Plate S.

※ F dimensions shown in this table are minimum values. F dimensions may be set to values larger than them.

How to order

Catalog No. — **Specification code**


SRPS — BH

Added Return Pin Holes and/or Change Return Pin Holes Diameter

Change the return pin hole specifications.

- ① Perform additional machining of return pin holes in Plate S, additional Plate Q and additional Plate V.
- ② Change the diameter of the return pin holes and provide more clearance than our standard "H7 tolerance" to the hole.

Application Mold bases (excluding the types without ejector plates)




Specifications of standard mold base and return pin holes for additional plates are as follows:

Plate name	Hole diameter
Plate B Plate E	H7 hole
Plate U Additional Plate W	Return pin dia. +1
Plate S Additional plate Q Additional Plate V	No return pin hole machined

Return pin hole specifications

When changing the diameter of return pin holes, select from the specifications below:



When $\alpha : H7, \alpha \leq 0.2$

When $\alpha \geq 0.5$

α	Machining method
H7 hole	Boring hole
0.1	
0.2	
0.5	
1	Drill hole
2	

D H7	F
10	35
12	50
15	60
20	80
25	100
30	120

※ Also, when $\alpha=0.1, \alpha=0.2$, the same F dimension as that of H7 hole will be applied.

※ F dimensions shown in this table are minimum values. F dimensions may be set to values larger than them.

Catalog No.	Code of the plate for which return pin hole diameter is to be changed and the diameter ^{*1}						
	Plate Q / α ^{*2}	Plate S / α ^{*2}	Plate V / α ^{*2}	Plate B / α	Plate U / α	Plate W / α	Plate E / α
CIHRPN	Q/H7	S/H7	V/H7	B/H7	U/H7	W/H7	E/H7
	Q/0.1	S/0.1	V/0.1	B/0.1	U/0.1	W/0.1	E/0.1
	Q/0.2	S/0.2	V/0.2	B/0.2	U/0.2	W/0.2	E/0.2
	Q/0.5	S/0.5	V/0.5	B/0.5	U/0.5	W/0.5	E/0.5
	Q/1	S/1	V/1	B/1	U/1	W/1	E/1
	Q/2	S/2	V/2	B/2	U/2	W/2	E/2

- *1. Specify all the plates for which to change the return pin hole diameter. If the desired diameter is the same as that of the standard mold base, no need to specify it.
- *2. There is no hole in Plate S, additional Plate Q and additional Plate V. If the diameter of return pin holes for these plates is specified, return pin holes will be machined in the plates.
The return pin gets longer by the amount of thickness of the added plates.
How to order the addition of return pin hole to Plate S only (when not installing Plate Q, and Plate V) → P.67
- ※ How to order spring holes for Plate B, Plate U and additional Plate W → P.134



How to order



Catalog No.	Plate Q / α	Plate S / α	Plate V / α	Plate B / α	Plate U / α	Plate W / α	Plate E / α
CIHRPN	—	— S/H7	—	B/1	—	—	E/0.5
CIHRPN	Q/1	— S/0.5	—	B/H7	—	—	—

Change Return Pin with Thread Holes

Installing return pin with a thread hole — ①

Machine a thread hole in the end of each return pin.

◀Application▶ Mold bases (excluding the types without ejector plates)



Return pin dia.	Catalog No.	M (thread dia.)	N (# of pins) ^{*1}
10	CPRPT	M4 M5	2 4
12		M4 M5 M6	
15		M5 M6 M8	
20		M6 M8 M10	
25		M8 M10 M12	
30			

*1. If specifying N2, a threaded hole is machined in the end of two out of 4 pins. Please install these pins at the appropriate locations. If specifying N4, threaded holes will be machined in all the four pins.

Threaded portion details	M	E
	M4	10
	M5	12.5
	M6	15
	M8	16
	M10	20
	M12	24

How to order


Catalog No. — M — N

CPRPT — M6 — N4


Installing return pin with a thread hole — ②

Machine a threaded hole in the end of each return pin and secure the return pins and plates with bolts.


◀Application▶ Mold bases (applies to SB, SD, DB, DD, EB, ED, FB, FD, GB, GD, HB and HD types)



Counterbore for bolts — Plate S



Counterbore for bolts — additional Plate Q




Counterbore for bolts — additional Plate V

※ Specify the code of plates in which to machine the counterbores for bolts.

※ Return pin holes must be machined through to the plate adjacent to the plate in which to machine counterbore holes (the plate beneath the counterbores). If there is no return pin holes on the adjacent plate, then ordering for additional machining is necessary.

Adding return pins → P.68

※ The all the four return pins will be secured with bolts. Securing two pins only cannot be specified.

Threaded portion details	M	Thickness of plate in which to machine counterbore	Z	F	E	C	L
	M4	Thickness ≥ 10	5.5	9.5	10	1	L=Thickness *1 -Z+F+C *2 *1. Plate in which to machine counterbores *2. Compensation values
	M5	Thickness ≥ 15	7.5	11	12.5	1.5	
	M6		8.5	12	15		
	M8	Thickness ≥ 20	11	14	16	2	
	M10	Thickness ≥ 25	13.5	16	20	2.5	
	M12		15.5	23	24		

Return pin dia.	Catalog No.	M (thread dia.)	Code of plate in which to machine counterbore	Optional specification (Specify only when necessary)
10	MRPTZ	M4 M5	S (Plate S), Q (Additional Plate Q), V (Additional Plate V)	EPAT ※ Return pins, bolts and spring washers are not supplied. Machining of holes only.
12		M4 M5 M6		
15		M5 M6 M8		
20		M6 M8 M10		
25		M8 M10 M12		
30				

How to order

Catalog No. — **M** — Code of plate in which to machine counterbores — Optional spec.
 MRPTZ — **M8** — **S**

Change Position of Parts

Change pitch of guide pins, support pins, return pins and puller bolts.

Changing pitch of assembly screws → P.74





When changing the pitch of parts, consider the following:

※ Changing the pitch of parts may result in interference with other parts.

Take into account the positions, etc.



Application Mold bases, cavity retainer sets, cavity retainer sets for die cast



Part name	Catalog No.	Part classification code	A	B	With/Without offset ^{*1}
Return pins	CPP	RP	In 1 mm steps	In 1 mm steps	—
Puller bolts ^{*2}		PB			
Guide pins and guide bushings		GP			With offset: A
Support pins and guide bushings		SP			Without offset: N

*1. When specifying offset, the pin on the same datum plane as the Futaba standard (lower right) will be placed inward from the datum plane. If not using offset, care should be taken not to mishandle the fixed side and the moving side.


*2. Changing puller bolt pitch option applies to H series mold bases.



How to order


	Catalog No.	Part classification code	A	B	With or without offset
Change the pitch of return pins	CPP	RP	A60	B180	
Change the pitch of puller bolts	CPP	PB	A180	B330	
Change the pitch of guide pins and bushings	CPP	GP	A194	B234	A
Change the pitch of support pins and bushings	CPP	SP	A234	B214	N

Part classification code **RP**




Change pitch of return pins

Part classification code **PB**




Change pitch of puller bolts

Part classification code **GP**



Change pitch of guide pins

Part classification code **SP**



Change pitch of support pins

Change Position and the Number of Assembly Screws


Change the pitch and the number of assembly screws.



When changing the pitch and the number of assembly screws, consider the following:

- ① When changing the number of assembly screws, take into account the strength, etc.
- ② Changing the pitch of assembly screws may result in interference with other parts.
Consider the positional relationship.

Application Mold bases




# of bolts	Catalog No.	Part classification code	Position code	A	B	C	D	
4-bolt fastening	CPNP	TCS LCS ECS	S041	In 1 mm steps	In 1 mm steps	—	—	
6-bolt fastening			S061					In 1 mm steps
			S064					
			S065					
			S066					
8-bolt fastening			S081			In 1 mm steps		
10-bolt fastening			S101					
12-bolt fastening			S121					In 1 mm steps




How to order

Catalog No.	Part classification code	Position code	A	B	C	D
CPNP	TCS	S041	A185	B128		
CPNP	LCS	S065	A200	B230	C30	
CPNP	ECS	S121	A320	B870	C500	D170


Position code S041



Position code S061




Position code S064




※ If $A < C$, or $A > C$, order with Position code S064.
If $A = C$, order with Position code S061.


Position code S065




Position code S066




Position code S081



Position code S101



Position code S121




※ Each chart shows Part classification code TCS. The dimensions of LCS and ECS are also shown with A - D codes likewise.

Added Assembly Screws


Adding assembly screws to fasten the plates.

Application Mold bases

Specification Change/Addition
Added Assembly Screws




Catalog No. PCSMS




※ To order the addition of assembly screws, specify "the plate in which to machine counterbore holes" and "the plate in which to machine thread holes". Then, clearance holes for the bolts will be machined through all the plates in between.

Catalog No. PCSMU




Screw code TA



Blind hole

Screw code TTA



Through hole

Catalog No No.	M	Plate in which to machine counterbores			Plate in which to machine threaded holes			Position code	A *1 (X)	B *1 (Y)	C	
		Counterbore code	Plate code		Thread hole	Plate code						
PCSMS PCSMU	M4 M5 M6 M8 M10 M12 M14 M16 M20 M24	MZ	T (Plate T) R (Plate R) A (Plate A) S (Plate S) B (Plate B) U (Plate U) C (Plate C) E (Plate E) F (Plate F) L (Plate L)	- Additional plate N (Plate N) O (Plate O) Q (Plate Q) V (Plate V) W (Plate W) X (Plate X) Y (Plate Y) Additional plate specifications ↓ P.38	TA TTA Details ↓ P.78	T (Plate T) R (Plate R) A (Plate A) S (Plate S) B (Plate B) U (Plate U) C (Plate C) E (Plate E) F (Plate F) L (Plate L)	- Additional plate N (Plate N) O (Plate O) Q (Plate Q) V (Plate V) W (Plate W) X (Plate X) Y (Plate Y) Additional plate specifications ↓ P.38	S011	In 0.5 mm steps	In 0.5 mm steps	—	
								S021	In 1 mm steps	—		
								S022	—	In 1 mm steps		In 1 mm steps
								S023				
								S024				
								S041				
								S042				
								S061				
								S062				
								S064				
								S065				
								S066	In 1 mm steps			

*1. For Position code S011 only, please specify X or Y.

How to order

Catalog No.

M

Plate in which to machine counterbores

Counterbore code / Plate code

Plate in which to machine thread holes

Thread code / Plate code

PCSMS

M10

MZ/T

TA/N

PCSMU

M12

MZ/L

TTA/U

Position code

A

B

C

S041

A120

B80


S064

A160


B230

C140


Position code **S011**




Position code **S021**




Position code **S022**




Position code **S023**




Position code **S024**




Position code **S041**




Position code **S042**




Position code **S061**




Position code **S062**




Position code **S064**



Position code **S065**



Position code **S066**



※ If $A < C$ or $A > C$, order with Position code **S064**.


If $A = C$, order with Position code **S061**.

※ For positions not shown above, please order with additional specifications of assembly screws.

Specifications of Thread Holes for Assembly Screws

The thread-hole specification of the assembly screws listed in page 76 to 77 are shown below. Refer to the table below to select the through-hole and blind-hole specifications.

Blind hole specification



M	M4	M5	M6	M8	M10	M12	M14	M16	M20	M24
Z	4.5	5.5	7	9	11	13	15	17	21	25
Tn min	$Tn \geq 19$	$Tn \geq 21$	$Tn \geq 20$	$Tn \geq 20$	$Tn \geq 20$	$Tn \geq 20$	$Tn \geq 25$	$Tn \geq 35$	$Tn \geq 49$	$Tn \geq 55$

Threaded hole specification and bolt length

Threaded-hole specifications of blind holes are determined depending on Tn dimension as follows:

Tn	$Tn \geq 19$	$Tn \geq 21$	$Tn \geq 23$	$Tn \geq 24$	$Tn \geq 28$	$Tn \geq 31$	$Tn \geq 34$	$Tn \geq 37$	$Tn \geq 49$	$Tn \geq 55$
F	10	12	13	15	17	19	21	23	33	37
K max	16	18	20	21	25	28	31	34	46	52
Screw coefficient	9.5	11.5	12	14	16	18	20	22	32	36
Tn			$20 \leq Tn < 23$	$20 \leq Tn < 24$	$25 \leq Tn < 28$	$30 \leq Tn < 31$	$30 \leq Tn < 34$	$35 \leq Tn < 37$		
F			8	10	16	19	20	22		
K max			15	17	$Tn-3$	$Tn-3$	$Tn-3$	$Tn-3$		
Bolt coefficient			7	9	16	18	19	22		
Tn					$20 \leq Tn < 25$	$25 \leq Tn < 30$	$25 \leq Tn < 30$			
F					11	14	15			
K max					$Tn-3$	$Tn-3$	$Tn-3$			
Bolt coefficient					11	13	15			
Tn						$20 \leq Tn < 25$				
F						13				
K max						$Tn-2$				
Bolt coefficient						13				

$L = Tz - Z + Tc + \text{bolt coefficient}$


Tc: The total amount of thickness of intermediate plates through which the bolts pass must be added.

[Rounding of calculation results]

Round down the last digit of calculation result, 0-4 to 0 and 5-9 to 5.

L

Through hole specification



M	M4	M5	M6	M8	M10	M12	M14	M16	M20	M24
Z	4.5	5.5	7	9	11	13	15	17	21	25
Tn	$5 \leq Tn \leq 20$	$5 \leq Tn \leq 25$	$6 \leq Tn \leq 25$	$8 \leq Tn \leq 30$	$10 \leq Tn \leq 40$	$12 \leq Tn \leq 45$	$14 \leq Tn \leq 50$	$16 \leq Tn \leq 50$	$20 \leq Tn \leq 50$	$24 \leq Tn \leq 60$

Threaded hole specification and bolt length

Threaded-hole specifications of through holes are determined depending on Tn dimension as follows:



Tn	11≤Tn≤20	13≤Tn≤25	14≤Tn≤25	16≤Tn≤30	18≤Tn≤40	20≤Tn≤45	22≤Tn≤50	24≤Tn≤50	34≤Tn≤50	38≤Tn≤60
F	10	12	13	15	17	19	21	23	33	37
Bolt coefficient	9.5	11.5	12	14	16	18	20	22	32	36
Tn	Tn<11	Tn<13	Tn<14	Tn<16	Tn<18	Tn<20	Tn<22	Tn<24	Tn<34	Tn<38
	Minimum value of Tn M≤L-Tz+Z-Tc≤Tn ※ L = values calculated and rounded down as shown below									
F	F=Tn									
Bolt coefficient	F-0.5		F-1							
L	L=Tz-Z+Tc+ bolt coefficient									
	Tc: The total amount of thickness of intermediate plates through which the bolts pass must be added.									
	【Rounding of calculation results】 Round down the last digit of calculation result, 0-4 to 0 and 5-9 to 5.									

Change Puller Bolt Specification of H Series


Change the puller bolt specifications for H series mold bases.

Add counterbore holes for spring and those for adjusting stroke. Change the depth of counterbore (Z) in Plate T to adjust the mold opening stroke (S1).

Application Mold bases H series



When installing additional Plate O and N



※ Through holes of ϕE will be provided in additional plates, Plate O and Plate N.

Puller bolt installation specification of Standard mold base (H series)

Nominal dimension of mold base	T	R	D	S1	Z	H	V	F
2540 2545 2550 2740 2750	35	20	20	10	25	14	20	45
		25						
3045 3050 3055 3060 3350	45	25					30	50
		30						
3550 3555 3560 4060 4070	50	30	25		29	18	31	60
		35						

D	Z ^{*1}	P ^{*1}	E ^{*1}	G ^{*1}	
				Recommended value	Max. value ^{*2}
20	T-Z ≥ 5 ^{*3}	P ≤ 80	25 to 60 in 1 mm steps provided E ≥ D+5	34	E ≤ 37
25		P ≤ 90		41 52	E ≤ 54

*1. Specify Z, P, E or G as necessary.

P+G+5 ≤ A (This formula is not a guarantee of strength)

*2. If E dimension exceeds this value, the counterbore may interfere with guide bushing holes, etc. Change the position of the puller bolt holes, etc.

*3. This formula is not a guarantee of strength.

Relation of counterbore dia. (E) and depth (G)

E	G max
25 to 27	G ≤ 60
28 to 34	G ≤ 80
35 to 44	G ≤ 90
45 to 60	G ≤ 100

Specification	Catalog No.	P	E	G
Machine counterbore hole for spring and counterbore hole for adjusting stroke	CPPZ	In 1 mm steps See left page No need to specify if not machining them	In 1 mm steps See left page No need to specify if not machining them	In 1 mm steps See left page No need to specify if not machining them

How to order

Catalog No. — P — E — G
CPPZ — P10 — E34 — G30

Specification	Catalog No.	Z	V	F
Change the counterbore depth (Z) in Plate T	CPZL	In 1 mm steps See left page	Select from the table below Specify only when changing thickness of Plate T	Select from the table below Specify only when changing thickness of Plate T

Select puller bolt

If changing the thickness of Plate T, select a puller bolt M-PBC.

The puller bolt M-PBC that fits is determined according to the thickness of Plate T and Plate R.

T	R	Puller bolt that fits	D	H	V	F
$T \geq 35$	20 25	M-PBC20×20×45	20	14	20	45
$T \geq 45$	25 30	M-PBC20×30×50			30	50
	35	M-PBC20×30×55			35	55
$T \geq 50$	30 35	M-PBC20×35×55	25	18		31
	30 35	M-PBC25×31×60			41	65
$T \geq 60$	35 40	M-PBC25×41×65				

How to order

Catalog No. — Z — V*4 — F*4
CPZL — Z20 — V30 — F50


*4. If changing the thickness of Plate T, be sure to specify V and F.
If not, omit specifying them.

Omit Standard Parts and Holes


Omit standard parts and installation holes for standard mold bases.

Application Mold bases, cavity retainer sets, cavity retainer sets for die cast


Deletion spec.	Delete parts	Specified parts that are configured for the standard mold base will be eliminated.
	Delete installation holes	Specified installation holes that is configured for the standard mold base will be eliminated.
	Delete parts and installation holes	Specified parts and installation holes that are configured for the standard mold base will be eliminated.




Specification of installing guide pins
on the cavity plate (moving half)




Specification of installing guide pins
on the cavity plate (fixed half)



Support pin related part codes
(for D·E series, H series)



Support pin related part codes
(for F·G series)



Puller bolt related part codes for H series

Delete parts	
Part code	Description
RPN	*If the ejector plate specification is spacer type, spacer ring will also be eliminated.
SPN	*The plate in which to machine clearance holes for support pins is determined depending on the length of the pins. *Support pin collars and their accessory parts will also be eliminated. *Deleting support pin callars → P.60
Other part codes	*Specified parts will be eliminated.

Delete installation holes	
Part code	Description
GPA	*The installation holes for guide pins will be eliminated. *The installation holes for guide bushings will be provided. Guide bushings will also be installed.
SPN	*The installation holes for support pins in Plate T will be eliminated. *The installation holes for guide bushings in Plate R, Plate A, Plate S and Plate B will be provided. Guide bushings will also be installed. For support pin specifications ON and IN, installation holes in Plate R and Plate A will be also provided likewise. *The clearance holes for support pins will be eliminated.
Other part codes	*The installation holes specified with the part code will be eliminated.

Delete parts and installation holes	
Part code	Description
GPA	*The guide pins and the installation holes for guide pins will be eliminated. *The installation holes for guide bushings will be provided. Guide bushings will also be installed.
RPN	*If the ejector plate specification is spacer type, spacer ring will also be eliminated.
SPN	*The installation holes for support pins in Plate T will be eliminated. *Support pins, support pin collars and their accessory parts will also be eliminated. *The installation holes for guide bushings in Plate R, Plate A, Plate S and Plate B will be provided. Guide bushings will also be installed. For support pin specifications ON and IN, installation holes in Plate R and Plate A will be also provided likewise. *The clearance holes for support pins will be eliminated.
Other part code	*Parts and installation holes specified with the part code will be eliminated.

Catalog No.	Part codes			
ESP (Delete parts) ESH (Delete installation holes) ESPH (Delete parts and installation holes)	GPA	GPAGBA	GPQGBB	PBC
	RPN	GPBGBA	GPVGBB	PBA
	SPN	GPSGBB	SPOGBB	
	TCS	SPRGBB	SPQGBB	
	LCS	SPAGBA	SPVGBB	
	ECS	SPSGBB		
		SPBGBA		

How to order

	Catalog No.	—	Part code
Delete parts	ESP	—	RPN
Delete installation holes	ESH	—	RPN
Delete parts and installation holes	ESPH	—	RPN

Parts Installation

Locating Ring Addition

Added Locating Rings — Overview	86
Added Locating Rings — ①	88
Added Locating Rings — ②	90

Sprue Bushing Addition

Added Sprue Bushings — Overview	92
Added Sprue Bushings — Bolt Type	94
Added Sprue Bushings — Shoulder Type	96

Taper Guide Pin Set Addition

Added Taper Guide Pin Sets — Overview	98
Added Taper Guide Pin Sets M-TLCS and M-TLDS	104
Added Taper Guide Pin Sets M-TLGS and M-TLHS	106
Added Taper Guide Pin Set M-TLBS	108

Ejector Guide Pin Addition

Added Guide Pins and Bushings — Overview	110
Added Ejector Guide Pin M-EGA	120
Added Ejector Guide Pin M-EGB	122
Added Ejector Guide Pin M-EGC	124
Added Ejector Guide Pin M-EGBM	126
Added Ejector Guide Pin M-EGCM	128
Added Ejector Guide Pin M-GPHF and M-GPA	130
Added Ejector Guide Pins and Bushings — Standard Position...	132

Coil Spring Addition

Added Springs — Overview	134
Added Springs — ①	136
Added Springs — ②	138

Addition of Stop Pin or Stop Ring

Added Stop Pins or Stop Rings	140
-------------------------------------	-----

Added Support Pillars

Added Support Pillars — Overview	142
Added Support Pillars	144

Ejector Rod Addition

Added Ejector Rods	146
--------------------------	-----

Puller Bolt Addition

Added Puller Bolts — Overview	148
Added Puller Bolts — B1	154
Added Puller Bolts — B2	156
Added Puller Bolts — B3	158
Added Puller Bolts — B4	160
Added Puller Bolts — B5	162
Added Puller Bolts — AH1	164
Added Puller Bolts — A1	166
Added Puller Bolts — AH2/A2	168
Added Puller Bolts — Standard Position	170

Tension Link Addition

Added Tension Links — Overview	172
Added Tension Link M-HLA	176
Added Tension Link M-HLB	178

PL Puller Addition

Added PL Pullers	180
------------------------	-----

Mold Opening Prevention Plate Addition

Added Mold Opening Prevention Plates — Overview	182
Added Mold Opening Prevention Plate (at One Place)	184
Added Mold Opening Prevention Plates (at Two or Four Places) ...	186

Base Spacer Addition

Added Base Spacers	188
--------------------------	-----



“Additional processing specifications” are provided to show customers how to order us on additional processing. When designing molds, various conditions such as strength and accuracy need to be taken into account. Therefore, we shall not be responsible or liable for any loss or damage of any kind incurred as a result of, or in connection with your use of additional processing specifications or selection of mold bases.



Added Locating Rings — Overview

Type of Locating Rings

The following 9 types of locating rings can be installed in the mold bases:

Catalog No.	PLRA Locating ring M-LRA	Catalog No.	PLRB Locating ring M-LRB	Catalog No.	PLRC Locating ring M-LRC
	D 60		D 100 120		D 60 100 110 120 150
Catalog No.	PLRD Locating ring M-LRD	Catalog No.	PLRE Locating ring M-LRE	Catalog No.	PLRF Locating ring M-LRF
	D 60 100 110 120 150		D 100 120		D 100 120
Catalog No.	PLRG Locating ring M-LRG	Catalog No.	PLRH Locating ring M-LRH	Catalog No.	PLRJ Locating ring M-LRJ
	D 100 120		D 60		D 100 120 150

Bolt specification of Locating Rings



Threaded hole specification				
M	F	K max	Blind-hole spec	Through-hole spec
M4	10	16	$N \geq 19$	$N < 19$
M5	12	18	$N \geq 21$	$N < 21$
M6	13	20	$N \geq 23$	$N < 23$
M8	15	21	$N \geq 24$	$N < 24$

Catalog No.	D	T	Bolt length	Remarks
PLRA	60	15	$N \geq 10 \rightarrow M4 \times 20$	
PLRB	100 120	15	$10 \leq N < 13 \rightarrow M6 \times 15$ $N \geq 13 \rightarrow M6 \times 20$	
PLRC	60	10 15 20 25	$10 \leq N < 12 \rightarrow M5 \times 12$ $N \geq 12 \rightarrow M5 \times 15$	T=30 is only available when D=100 T=25 is unavailable when D=110
	100 110 120	10	$10 \leq N < 13 \rightarrow M6 \times 12$ $N \geq 13 \rightarrow M6 \times 15$	
	150	15 20 25 30	$10 \leq N < 13 \rightarrow M6 \times 15$ $N \geq 13 \rightarrow M6 \times 20$	
PLRD	60	10 15 20 25	$10 \leq N < 12 \rightarrow M5 \times 12$ $N \geq 12 \rightarrow M5 \times 15$	T=10, 30, 35 are only available when D=100.
	100 110 120	10	$10 \leq N < 13 \rightarrow M6 \times 12$ $N \geq 13 \rightarrow M6 \times 15$	
	150	15 20 25 30 35	$10 \leq N < 13 \rightarrow M6 \times 15$ $N \geq 13 \rightarrow M6 \times 20$	
PLRE	100 120	15 20	$10 \leq N < 15 \rightarrow M8 \times 15$ $N \geq 15 \rightarrow M8 \times 20$	
		35 40 45	$10 \leq N < 13 \rightarrow M6 \times 15$ $N \geq 13 \rightarrow M6 \times 20$	
PLRF	100 120	—	$10 \leq N < 13 \rightarrow M6 \times 12$ $N \geq 13 \rightarrow M6 \times 15$	
PLRG	100	—	$10 \leq N < 12 \rightarrow M5 \times 12$ $N \geq 12 \rightarrow M5 \times 15$	
	120	—	$10 \leq N < 13 \rightarrow M6 \times 15$ $N \geq 13 \rightarrow M6 \times 20$	
PLRH	60	15	$10 \leq N < 12 \rightarrow M5 \times 12$ $N \geq 12 \rightarrow M5 \times 15$	
PLRJ	100 120	15 20 25	$10 \leq N < 13 \rightarrow M6 \times 15$ $N \geq 13 \rightarrow M6 \times 20$	T=25 is only available when D=100.
	150	15 20	$10 \leq N < 15 \rightarrow M8 \times 15$ $N \geq 15 \rightarrow M8 \times 20$	

Optional specification (Specify only when necessary)	
Option code	Specification
MNZ	Machine a counterbore hole for allowing clearance around the nozzle in Plate T. ■ Applicable items Catalog No. PLRC (Excluding when D=60) Catalog No. PLRF Catalog No. PLRG (Excluding when D=100) ■ How to specify: MNZ/E [DIMM.] / J [DIMM.] ※ E, J → Specify in 1 mm steps. ※ Sprue bushing counterbore dia. $\leq E \leq$ Locating ring ID (Internal diameter) ※ Combined use with MNT is not allowed. [E.g.] MNZ/E70/J15 ※ J dimension is $J \leq \text{Plate T thickness} - 5$ This formula is not a guarantee of strength. ※ If J = T, through-holes are provided.
MNT	Machine a taper hole for allowing clearance around the nozzle in Plate T. ■ Applicable items Catalog No. PLRC (Excluding when D=60) Catalog No. PLRF Catalog No. PLRG (Excluding when D=100) ■ How to specify: MNZ/E [DIMM.] / J [DIMM.] / A [DIMM.] ※ E, J → Specify in 1 mm steps. ※ E = Sprue bushing counterbore holes ※ A = Select 30° or 45°. ※ Combined use with MNZ is not allowed. [E.g.] MNT/E41/J15/A45 ※ J dimension is $J \leq \text{Plate T thickness} - 5$. This formula is not a guarantee of strength. ※ When J = T, through hole are provided.
EPAT	Only holes for installing locating rings are provided.


Added Locating Rings — ①

Add locating rings M-LRA - M-LRE, M-LRH, M-LRJ.

For details on installation specifications, refer to page 86 and 87.

Locating rings M-LRA –M-LRE, M-LRH, M-LRJ ➔ P.352 to 357

Application Mold bases




Depth of counterbore for locating ring

- ※ $Z \leq \text{Plate T thickness} - 10$
This formula is not a guarantee of strength.
- ※ When $Z=0$, there is no counterbore.
- ※ When $Z=T$, there are through-holes in the Plate T and locating rings are installed as shown on the left.

Catalog No. **PLRA** Install M-LRA locating ring

Catalog No. **PLRH** Install M-LRH locating ring


Catalog No. **PLRC** Install M-LRC locating ring



Catalog No.	D	G	T	P	M
PLRA	60	36	15	48	M4
PLRH	60	35	15	48	M5
PLRC	60	40	10 15 20 25	50	M5
	100	70	10 15 20 25 30	85	M6
	110	80	10 15 20	95	
	120	90	10 15 20 25	105	
	150	110	15 20 25	130	

Catalog No. **PLRB** Install M-LRB locating ring

Catalog No. **PLRJ** Install M-LRJ locating ring




Catalog No.	D	G	T	P	M
PLRB	100	36	15	85	M6
	120				
PLRJ	100	35	15 20 25		
	120	40	15 20		
	150	50 *1			
				100	M8

*1. When $D=100$, $T=25$, this option cannot be specified.


Catalog No. **PLRE** Install M-LRE locating ring

Catalog No. **PLRD** Install M-LRD locating ring




Catalog No.	D	G	T	P	M
PLRE	100	40	15 20 35 40 45	85	M6
	120			105	
PLRD	60	26	10 15 20 25	50	M5
	100		10 15 20 25 30 35	85	M6
	110		15 20 25	95	
	120			105	
	150			130	M8


Bolt position code S021




Bolt position code S022



Bolt position code S042




Bolt position code S02R



K → in 1° steps
 $1^\circ \leq K \leq 89^\circ$
 $91^\circ \leq K \leq 179^\circ$

Bolt position code S04R



K → in 1° steps
 $1^\circ \leq K \leq 89^\circ$

Catalog No.	D	G	T	Z	Bolt position code		X	Y	Optional spec.
					Code	K			
PLRA PLRH PLRC PLRB PLRJ PLRE PLRD	Select from left page	Select from left page	Select from left page	In 1 mm steps	S021 ^{*2} S022 ^{*2} S02R ^{*2} S042 ^{*3} S04R ^{*3} S000 ^{*4}	Specify in 1° steps for S02R or S04R	In 1 mm steps When X=KW/2, omit X	In 1 mm steps When Y=KL/2, omit Y	MNZ MNT ^{*5} EPAT ^{*5} See page 87

*2. Catalog No. **PLRD**, bolt holes for locating rings remain at four places. Only the thread holes machined in the plate will be changed to 2 places.

*3. Can be applied to Catalog No. **PLRD**.

*4. This is a design with no thread hole for locating rings machined in the plate. Bolts are supplied.

*5. When specifying **EPAT**, no need to specify G and T dimensions.

How to order

Catalog No. — **D** — **G** — **T** — **Z** — Bolt position code — **X** — **Y**
PLRC — **D100** — **G70** — **T15** — **Z5** — **S02R/K45** — **X100** — **Y125**
— Optional spec.
— **MNZ/E70/J15**

Added Locating Rings — ②


Add locating ring M-LRF, M-LRG.

For details on installation specifications, refer to page 86 and 87.

Locating ring M-LRF → P.356 M-LRG → P.354



Application Mold bases

Catalog No. **PLRF** Add M-LRF locating ring



Catalog No.	D	V	G	P	M
PLRF	100	130	85	115	M6
	120	150	105	135	


Catalog No. **PLRG** Add M-LRG locating ring




※ M-LRG locating ring is reversible type that can be added from both its front and back sides.

Catalog No.	D	V	G	P	M
PLRG	100	60	40	50	M5
	120	100	70	85	M6


Bolt position code S021



Bolt position code S022



Bolt position code S02R



K → in 1° steps
 $1^\circ \leq K \leq 89^\circ$
 $91^\circ \leq K \leq 179^\circ$

Catalog No.	D	Bolt position code		X	Y	Optional spec.
		Code	K			
PLRF	100	S021 S022	Specify in 1° steps	In 1 mm steps	In 1 mm steps	MNZ MNT EPAT
PLRG	120	S02R S000 *1	for S02R	When $X=KW/2$, omit X	When $Y=KL/2$, omit Y	See page 87

*1. This is a design with no thread hole for locating rings machined in the plate. Bolts are supplied.

How to order

Catalog No. — D — Bolt position code — X — Y — Optional spec.
 PLRF — D100 — S02R/K30 — X150 — Y200 — MNT/E41/J15/A45


Added Sprue Bushings — Overview

Type of sprue bushings


Bolt type and shoulder type sprue bushings can be installed in mold bases.

For information on dimensions and accuracy of each part, refer to page 372 to 385.

Sprue bushings (bolt type)




How to order → P.94




Product code	D1	D	H	Material	Details
M-SBA	50	16 20	10	SK3 (no heat treatment)	P.372
M-SBC	36	13	10	SKD61 (hardness 48HRC or more)	P.372
	50	16 20			
M-SBG□	40	10 13 16 20	10	HPM1 (hardness 37-41HRC) SKD61 (hardness 48HRC or more) SKD11 modified steel (hardness 58HRC or more)	P.380
M-SBI□	50	16 20 25	15	HPM1 (hardness 37-41HRC) SKD61 (hardness 48HRC or more)	P.382
M-SAG□	40	10 13 16	10	HPM1 (hardness 37-41HRC) SKD61 (hardness 48HRC or more) SKD11 modified steel (hardness 58HRC or more)	P.378
M-SJA□	35	10 13	10	S45C HPM1 (hardness 37-41HRC) SKD61 (hardness 48HRC or more)	P.374
	50	16 20			

Sprue bushings (shoulder type)



How to order → P.96



Product code	D1	D2	D	H	Material	Details
M-SBB	40	36	16 20	25 30	SK3 (no heat treatment)	P.373
M-SBD	40	36	16 20	25 30	SKD61 (hardness 48HRC or more)	P.373
M-SBE□	30	26	10 13 16 20 25	15	HPM1 (hardness 37-41HRC) SKD61 (hardness 48HRC or more) SKD11 modified steel (hardness 58HRC or more)	P.384
M-SJC□	40	35	10 13 16 20	25 30	S45C HPM1 (hardness 37-41HRC) SKD61 (hardness 48HRC or more)	P.376

Optional specification (specify only when necessary)





Option code	Specification
EPAT	Only the holes for installing sprue bushings are provided.

Sprue bushing hole specifications

Sprue bushings can be installed in Plate T, Plate R, additional Plate O, additional Plate N and Plate A.

For the holes at the ϕ D section in the sprue bushing, either clearance hole or H7 hole specifications can be selected. For H7 specifications, there is an option whether to machine a clearance hole on the Plate T or Plate B side.

ϕ D section hole specification



ϕ D-section clearance hole spec.


ϕ D-section H7 hole spec.

ϕ D-section H7 hole spec.


D H7	10	13	16	20	25
	+0.015 0	+0.018 0		+0.021 0	
N max	35	50	60	80	100

※ If thickness of the plate exceeds N dimension, a hole of $\phi D+1$ will be machined.

Bolt specification of sprue bushings



Blind-hole specification



Through-hole specification

Threaded hole specification				
M	F	K max	Blind hole spec.	Trough hole spec.
M5	10	16	$N \geq 19$	$N < 19$
M6	10	17	$N \geq 20$	$N < 20$

Bolt specification			
Product code		N	Bolt length
M-SBA	M-SBG□	$5 \leq N < 6$	$M5 \times 8$
M-SBC	M-SAG□	$6 \leq N < 8$	$M5 \times 10$
	M-SJA□	$N \geq 8$	$M5 \times 12$
M-SBI□		$5 \leq N < 7$	$M6 \times 12$
		$N \geq 7$	$M6 \times 15$


Added Sprue Bushings — Bolt Type

Install sprue bushings. For details on installation specifications, refer to page 92 to 93.


Sprue bushing M-SBA - M-SJA □ ➔ P.372 - 383

Application Mold bases

Catalog No. **PSB1N**



Catalog No. **PSB1Z**



Sprue bushing hole specifications

Select the sprue bushing hole specification from the chart below.

Specify hole specifications of all the plates in which to machine holes for sprue bushing. Sprue bushing holes can be specified in Plate T, Plate R, additional Plate O, additional Plate N and Plate A.


Hole specifications for Plate T	Plate T hole spec. TD		Plate T hole spec. TB	
	φD-section clearance hole spec.		φD-section clearance hole spec.	
Hole specifications for Plate R, Plate N, Plate O, Plate A	Plate R hole spec. RD Plate N hole spec. ND Plate O hole spec. OD Plate A hole spec. AD	 φD-section clearance hole spec.	Plate R hole spec. RB Plate N hole spec. NB Plate O hole spec. OB Plate A hole spec. AB	 φD-section H7 hole spec
			Plate R hole spec. RR Plate N hole spec. NR Plate O hole spec. OR Plate A hole spec. AR	 φD-section H7 hole spec

※ The counterbore hole dimension **Z** for Catalog No. **PSB1Z** is taken from the plate adjacent to Plate T (beneath Plate T).


Product code	Processing code	D	DZ	P	M	Z	H
M-SBA	SBA	16 20	51	36	M5	Thickness -Z≥5 ※ This value is not a guarantee of strength.	10
M-SBC	SBC	13	37	26			
		16 20	51	36			
M-SBG□	SBG	10 13 16 20	41	30	M6		15
M-SBI□	SBI	16 20 25	51	38	M5		10
M-SAG□	SAG	10 13 16	41	30			
M-SJA□	SJA	10 13	36	25			
		16 20	51	36			

D	N max
10	35
13	50
16	60
20	80
25	100


Bolt position code S021




Bolt position code S022



Bolt position code S042




Bolt position code S02R



$K \rightarrow$ in 1° steps
 $1^\circ \leq K \leq 89^\circ$
 $91^\circ \leq K \leq 179^\circ$

Bolt position code S04R



$K \rightarrow$ in 1° steps
 $1^\circ \leq K \leq 89^\circ$

Catalog No.	Processing code	D	Z	Sprue bushing hole specification *1		Bolt position code		X	Y	Sprue bushing item name	Option spec.
						Code	K				
PSB1N PSB1Z	SBA	16 20	In 1 mm steps	Plate T hole spec.	For PSB1Z, TD is applied.	S021	Specify in 1° steps for S02R S04R S000 *2	In 1 mm steps When $X=KW/2$, omit X	In 1 mm steps When $Y=KL/2$, omit Y	Select from page 372 to 383	EPAT See page 93
	SBC	13 16 20		TD TB		S022					
	SBG	10 13 16 20		Plate R hole spec.	Plate N hole spec.	S02R					
	SBI	16 20 25		RD RB RR	ND NB NR	S042					
	SAG	10 13 16		Plate O hole spec.	Plate A hole spec.	S04R					
	SJA	10 13 16 20		OD OB OR	AD AB AR	S000					

*1. Specify hole specifications of all the plates in which to machine holes for sprue bushing.

*2. This is a design with no threaded hole for sprue bushings machined in the plate. Bolts are supplied.

How to order

Catalog No. — Processing code — D — Z — Sprue bushing hole specification — Bolt position code
 PSB1Z — SBA — D16 — Z10 — TD/ND/AB — S02R/K30
 — X — Y — Sprue bushing item name *3 — Optional spec.
 — X100 — Y125 — SBA16×50×10A

*3. Specify sprue bushing item names by omitting the preceding M-. (e.g.: M-SBA → SBA)


Added Sprue Bushings — Shoulder Type

Install sprue bushings. For details on installation specifications, refer to page 92 to 93.


Sprue bushing M-SBB - M-SJB □ ➔ P.373 - 385

Application Mold bases


Catalog No. **PSB2N**



Catalog No. **PSB2Z**



※ When Z=0, the counterbore holes will be eliminated.



Sprue bushing hole specifications


Select the sprue bushing hole specification from the chart below.

Specify hole specifications of all the plates in which to machine holes for sprue bushing. Sprue bushing holes can be specified in Plate T, Plate R, additional Plate O, additional Plate N and Plate A.

Hole specifications for Plate T	Plate T hole spec. TD 		Plate T hole spec. TB 	
	φD-section clearance hole spec		φD-section H7 hole spec	
Hole specifications for Plate R, Plate N, Plate O, Plate A	Plate R hole spec. RD Plate N hole spec. ND Plate O hole spec. OD Plate A hole spec. AD	Plate R hole spec. RB Plate N hole spec. NB Plate O hole spec. OB Plate A hole spec. AB	Plate R hole spec. RR Plate N hole spec. NR Plate O hole spec. OR Plate A hole spec. AR	
	φD-section clearance hole spec.	φD-section H7 hole spec	φD-section H7 hole spec	

※ The counterbore hole dimension Z for **Catalog No. PSB2Z** is taken from the plate adjacent to Plate T (beneath Plate T).

Product code	Processing code	D	DZ	Z	H	D	N max
M-SBB	SBB	16 20	41	Thickness -Z ≥ 5 ※ This value is not a guarantee of strength.	25 30	10	35
M-SBD	SBD	16 20	41		25 30	13	50
M-SBE □	SBE	10 13 16 20 25	31		15	16	60
M-SJC □	SJC	10 13 16 20	41		25 30	20	80
						25	100



Catalog No.	Processing code	D	Z	Sprue bushing hole specification *1		X	Y	Sprue bushing item name	Optional spec.
PSB2N	SBB	16 20	In 1 mm steps	Plate T hole spec.	For PSB2Z, TD is applied.	In 1 mm steps When X=KW/2, omit X	In 1 mm Steps When Y=KL/2, omit Y	Select from pages 373 to 385	EPAT See page 93
	SBD	16 20		TD TB					
PSB2Z	SBE	10 13 16 20 25		Plate R hole spec.	Plate N hole spec.				
				RD RB RR	ND NB NR				
	SJC	10 13 16 20		Plate O hole spec.	Plate A hole spec.				
			OD OB OR	AD AB AR					

*1. Specify hole specifications of all the plates in which to machine holes for sprue bushing.

How to order

Catalog No. — **Processing code** — **D** — **Z** — **Sprue bushing hole specification** — **X** — **Y**
PSB2Z — **SBB** — **D16** — **Z5** — **TD/ND/AD** — **X100** — **Y150**
 — **Sprue bushing item name *2** — **Optional spec.**
 — **SBB16×70×30A**






*2. Specify sprue bushing item names by omitting the preceding M-. (e.g. M-SBB → SBB)

Added Taper Guide Pin Sets — Overview ①

Type of taper guide pin sets

The following 5 types of taper guide pin sets can be installed in mold bases.

For dimension and accuracy of each part, refer to pages 298 to 300.








Taper guide pin set M-TLCS Precision type	Taper guide pin set M-TLDS Super precision type	Taper guide pin set M-TLGS Precision type	Taper guide pin set M-TLHS Super precision type	Taper guide pin set M-TLBS Precision type
				
D 16 20 25 30	D 16 20 25 30	D 16 20 25 30	D 16 20 25 30	D 13 16 20 25 32 40 50
K 1 3 5	K 1 3 5	K 1 3 5	K 1 3 5	K 10
How to order ➡ P.104	How to orde ➡ P.104	How to order ➡ P.106	How to order ➡ P.106	How to order ➡ P.108

Installation specification of taper guide pin sets





For taper guide pin set installation specifications, the specifications of bushings and pins are separately set shown below. This allows users to select optimal specifications of bushings and pins respectively.

For details on each specification, refer to pages 100 to 103.

Bushing installation specification

	Bushing code BS1	Bushing code BS2	Bushing code BS3	Bushing code BS4
[Applied item] M-TLGS M-TLHS M-TLBS				
[Applied item] M-TLCS M-TLDS				


Pin installation specification

	Pin code PN1	Pin code PN2	Pin code PN3	Pin code PN4
[Applied item] M-TLCS M-TLDS M-TLGS M-TLHS M-TLBS				


Hole diameter limit deviation specification

The limit deviation specifications of taper guide pin set installation holes are available in the following three types:


Hole code HC1





Hole code HC2




Hole code HC3




Optional specification (Specify only when necessary)

Option code	Specification
AC	 Machine an air vent on the taper guide pin set. ※ A 0.2 mm deep flat chamfer is produced on the tapered section of the pin side in parallel to the taper angle. ※ Air vents cannot be added to taper guide pin M-TLBS.
EPAT	 Only the holes for installing taper guide pin sets will be machined.

Adjustment of taper guide pin set installation



Taper guide pin sets are delivered with no adjustment made. Please measure the actual depth of the holes, and adjust the thickness of the plates, length of taper guide pin, thickness of disc spacers, etc. to properly install the taper guide pins. Taper guide pins are supplied with the mold bases but not assembled to them.



Tapered section enlarged view

When installing a taper guide pin set, there are some cases where the height of the pin and bushing need to be adjusted to fit them more tightly. Also, if the taper angle is 1° and 3°, it is necessary to consider possible seizure of the pin in the bushing. This seizure can be avoided by setting them slightly spaced from each other. If the angle is small, the deviation of B to that of A is also small, the positioning performance is not compromised.

Deviation of B to that of A

Angle	A		
	0.1	0.3	0.5
1°	0.0018	0.005	0.009
3°	0.005	0.016	0.026


※ The Values in the above table are B.

Added Taper Guide Pin Sets — Overview ②


Taper guide pin set installation specification — ①

Application This applies to installation of the taper guide pin sets “M-TLGS”, “M-TLHS”, “pin of M-TLCS”, “pin of M-TLDS”.


Bushing code BS1




Bushing code BS2



Pin code PN1



Pin code PN2



D	Z	Z2	T	M	Z1	P1		Bolt length coefficient	
						BS1, PN1	BS2, PN2	Bushing side	Pin side
16	15	20	5	M5	7	$P1 \geq 27$	$P1 \geq 32$	7	9
20	20	25	5	M6	8	$P1 \geq 33$	$P1 \geq 38$	9	11
25	25	30	5	M8	9	$P1 \geq 39$	$P1 \geq 44$	11	15
30	30	35	5	M10	11	$P1 \geq 46$	$P1 \geq 51$	13	19

※ Calculation of bolt length

For BS1, PN1, bolt length = $P1 - Z - Z1$ + bolt length coefficient


For BS2, PN2, bolt length = $P1 - Z2 - Z1 + T$ + bolt length coefficient

※ Round down the last digit of calculation result, 0-4 to 0 and 5-9 to 5.


Taper guide pin set installation specification — ②

Application This specification applies to the installation of taper guide pin set M-TLBS.


Bushing code BS1




Bushing code BS2



Pin code PN1



Pin code PN2



D	Z	Z2	T	M	Z1	P1		Bolt length coefficient	
						BS1, PN1	BS2, PN2	Bushing side	Pin side
13	16	20	4	M4	6	$P1 \geq 27$	$P1 \geq 31$	8	10
16	16	20	4	M5	7	$P1 \geq 28$	$P1 \geq 32$	8	10
20	20	25	5	M6	8	$P1 \geq 33$	$P1 \geq 38$	7	11
25	25	30	5	M6	8	$P1 \geq 38$	$P1 \geq 43$	12	14
32	30	35	5	M8	9	$P1 \geq 44$	$P1 \geq 49$	11	17
40	40	50	10	M8	9	$P1 \geq 54$	$P1 \geq 64$	15	17
50	50	60	10	M10	11	$P1 \geq 66$	$P1 \geq 76$	20	19



※ Calculation of bolt length

For BS1, PN1, bolt length = $P1 - Z - Z1$ + bolt length coefficient

For BS2, PN2, bolt length = $P1 - Z2 - Z1 + T$ + bolt length coefficient

※ Round down the last digit of calculation result, 0-4 to 0 and 5-9 to 5.


Example of use




Taper guide pin set installation specification — ③

Application This applies to installation of the taper guide pin sets, “M-TLGS”, “M-TLHS”, “pin of M-TLCS”, “pin of M-TLDS”.

Bushing code BS3



Pin code PN3



D	T									M	Z1	Bolt length coefficient	
	P1=20	P1=25	P1=30	P1=35	P1=40	P1=50	P1=60	P1=70	P1=80			Bushing side	Pin side
16	5	10	15	20	25					M5	7	7	9
20		5	10	15	20	30	40			M6	8	9	11
25			5	10	15	25	35	45	55	M8	9	11	15
30				5	10	20	30	40	50	M10	11	13	19


For the installation marked with ⊙, install taper guide pins directly without installing disc spacers.

※ Calculation of bolt length: bolt length = P2 - Z1 + T + bolt length coefficient ※ Round down the last digit of calculation result, 0-4 to 0 and 5-9 to 5.


Taper guide pin set installation specification — ④

Application This specification applies to the installation of taper guide pin set M-TLBS.

Bushing code BS3



Pin code PN3




D	T											M	Z1	Bolt length coefficient	
	P1=20	P1=25	P1=30	P1=35	P1=40	P1=50	P1=60	P1=70	P1=80	P1=90	P1=100			Bushing side	Pin side
13	4	9	14									M4	6	8	10
16	4	9	14	19	24	34						M5	7	8	10
20	⊙	5	10	15	20	30	40	50				M6	8	7	11
25		⊙	5	10	15	25	35	45				M6	8	12	14
32			⊙	5	10	20	30	40				M8	9	11	17
40					⊙	10	20	30	40			M8	9	15	17
50					⊙	10	20	30	40	50		M10	11	20	19

For the installation marked with ⊙, install taper guide pins directly without installing disc spacers.

※ Calculation of bolt length: bolt length = P2 - Z1 + T + bolt length coefficient ※ Round down the last digit of calculation result, 0-4 to 0 and 5-9 to 5.

Example of use



Added Taper Guide Pin Sets — Overview ③

Taper guide pin set installation specification — ⑤



◀Application▶ This applies to installation of the taper guide pin sets, "M-TLGS", "M-TLHS", "pin of M-TLCS", "pin of M-TLDS".

Code	D	D1	P1	T	Bolt	D	D1	P1	T	Bolt
Bushing code BS4	16	21	20	5	M5×12 ^{*1}	25	31	30	5	M8×15 ^{*1}
			25	10	M5×16 ^{*1}			35	10	M8×20 ^{*1}
			30	15	M5×15			40	15	M8×15
			35	20	M5×20			50	25	M8×25
			40	25	M5×25			60	35	M8×35
			50	35	M5×35			70	45	M8×45
Pin code PN4	20	26	25	5	M6×12 ^{*1}	30	36	80	55	M8×55
			30	10	M6×16 ^{*1}			40	10	M10×20 ^{*1}
			35	15	M6×15			50	20	M10×20
			40	20	M6×20			60	30	M10×30
			50	30	M6×30			70	40	M10×40
			60	40	M6×40			80	50	M10×50
			70	50	M6×50					



*1. The disc spacers and bolts to use are M-DSD and hexagon socket flat head bolts respectively.

Taper guide pin set installation specification — ⑥

◀Application▶ This specification applies to the installation of taper guide pin set M-TLBS.

Code	D	D1	P1	T	Bolt	D	D1	P1	T	Bolt	
Bushing code BS4 	13	18	20	4	M4 × 10 *1	32	39	40	10	M8 × 20 *1	
			25	9	M4 × 10			50	20	M8 × 20 *2	
			30	14	M4 × 15			60	30	M8 × 30 *2	
	16	21	20	4	M5 × 10 *1	40	46	50	10	M8 × 20 *1	
			25	9	M5 × 10			60	20	M8 × 25	
			30	14	M5 × 15			70	30	M8 × 35	
	Pin code PN4 	20	26	25	5	M6 × 12 *1	50	59	70	20	M10 × 25
				30	10	M6 × 10			80	30	M10 × 35
				35	15	M6 × 15			*1. The disc spacers and bolts to use are M-D SA and hexagon socket flat head bolts respectively. *2. For pins, use the bolts longer than those for bushings by 5 mm.		
25		31	30	5	M6 × 12 *1						
			35	10	M6 × 15						
			40	15	M6 × 20						


Example of use




Taper guide pin set installation specification — ⑦

Application This applies to the installation of taper guide pin sets, “bushing of M-TLCS” and “bushing of M-TLDS”.


Bushing code BS5



Bushing code BS6



Threaded hole specification.



Blind hole spec.


Through hole spec.

D	Z	Z2	T	Thread hole specification					P1		Bolt length	
				M	F	K max	Blind hole	Through hole	BS5	BS6	BS5	BS6
16	15	20	5	M5	12	18	N ≥ 21	N < 21	P1 ≥ 24	P1 ≥ 27	P1 < 27 → M5 × 12 P1 ≥ 27 → M5 × 15	P1 < 32 → M5 × 15 P1 ≥ 32 → M5 × 20
20	20	25	5	M6	13	20	N ≥ 23	N < 23	P1 ≥ 28	P1 ≥ 31	P1 < 31 → M6 × 12 P1 ≥ 31 → M6 × 15	P1 < 36 → M6 × 15 P1 ≥ 36 → M6 × 20
25	25	30	5	M8	15	21	N ≥ 24	N < 24	P1 ≥ 36	P1 ≥ 41	P1 ≥ 36 → M8 × 15	P1 ≥ 41 → M8 × 20
30	30	35	5	M10	17	25	N ≥ 28	N < 28	P1 ≥ 41	P1 ≥ 46	P1 < 46 → M10 × 15 P1 ≥ 46 → M10 × 20	P1 < 51 → M10 × 20 P1 ≥ 51 → M10 × 25


Taper guide pin set installation specification — ⑧

Application This applies to the installation of taper guide pin sets, “bushing of M-TLCS” and “bushing of M-TLDS”.

Bushing code BS7



Threaded hole specification.



Blind hole spec.



Through hole spec.

D	T									Thread hole specification					Bolt length coefficient	P2
	P1=20	P1=25	P1=30	P1=35	P1=40	P1=50	P1=60	P1=70	P1=80	M	F	K max	Blind hole	Through hole		
16	5	10	15	20	25					M5	12	18	P2≥21	P2<21	15	P2≥12
20	⊙	5	10	15	20	30	40			M6	13	20	P2≥23	P2<23	17	P2≥13
25		⊙	5	10	15	25	35	45	55	M8	15	21	P2≥24	P2<24	19	P2≥15
30			⊙	5	10	20	30	40	50	M10	17	25	P2≥28	P2<28	21	P2≥20

For the installation marked with ⊙, install taper guide pins directly without installing disc spacers.

※ Calculation of bolt length Bolt length = T + bolt length coefficient ※ Round down the last digit of calculation result, 0-4 to 0 and 5-9 to 5

Example of use



Added Taper Guide Pin Sets M-TLCS and M-TLDS

Install taper guide pin sets M-TLCS and M-TLDS.

For details on the installation specifications, refer to pages 98 to 103.

Taper guide pin sets M-TLCS → P.298, M-TLDS → P.298


Application Mold bases (excluding the types with Plate S supplied and those for insert molding)

Orientation and angle of taper guide pin sets installation

Fixed-side bushing & moving-side pin type

Catalog No. **PTLC1** Install taper guide pin set M-TLCS (precision)


Catalog No. **PTLD1** Install taper guide pin set M-TLDS (super precision)



Fixed-side pin and moving-side bushing type

Catalog No. **PTLC2** Install taper guide pin set M-TLCS (precision)

Catalog No. **PTLD2** Install taper guide pin set M-TLDS (super precision)



Bushing installation methods

Bushing code	Bushing code BS5	Bushing code BS6	Bushing code BS7
Install bushings on the fixed side			
Install bushings on the moving side			

※ Regardless of whether to install bushings on the fixed side or moving side, the bushing code is the same.

※ For details on each installation method, refer to pages 100 to 103.

※ If installing **Bushing code BS7** on the fixed side, changes to 3-plate type mold bases cannot be specified.

If installing it on the moving side, changes to the types without backing plate cannot be specified.

Pin installation method







Pin code	Pin code PN1	Pin code PN2	Pin code PN3	Pin code PN4
Install pin on the fixed side				
Install pin on the moving side				

※ Regardless of whether to install pins on the fixed side or moving side, the pin code is the same.

※ For details on each installation method, refer to pages 100 to 103.

※ If installing **Pin code PN3** on the fixed side, changes to 3-plate type mold bases cannot be specified.

If installing it on the moving side, changes to the types without backing plate cannot be specified.

Position code **S021**

Position code **S023**

Position code **S041**

Position code **S022**

Position code **S024**

Position code **S042**


If installing taper guide pin sets, advise us on the specifications by following the steps below:

- ① For Plate A and Plate B in which to install taper guide pin sets, surface grind will be used. The limit deviations of Plate A and Plate B thickness are required. Please specify them.
How to specify surface grind → P.31
- ② To maintain the accuracy of holes for taper guide pin sets, we also recommend rough machining of pockets and slide core grooves, etc.
How to specify machining of pockets and slide core grooves → P.204 - 221

Catalog No.	D	K	Bushing code	Pin code	Hole code	Position code	A	B	X	Y	Optional spec.
PTLC1	16	1	BS5	PN1	HC1	S021	In 1 mm steps	—	In 1 mm steps	In 1 mm steps	AC
PTLC2	20	3	BS6	PN2	HC2	S022	—	—	—	—	EPAT
PTLD1	25	5	BS7	PN3	HC3	S023	In 1 mm steps	In 1 mm steps	When X=KW/2, Omit X	When Y=KL/2, Omit Y	See page 99
PTLD2	30			PN4	See page 99	S024					
						S041					
						S042					



How to order

Catalog No. — **D** — **K** — **Bushing code** — **Pin code** — **Hole code** — **Position code**
PTLC1 — **D20** — **K3** — **BS5** — **PN3** — **HC1** — **S024**
 — **A** — **B** — **X** — **Y** — **Optional spec.**
 — **A160** — **B50** — **X100** — **Y125** — **AC**

Added Taper Guide Pin Sets M-TLGS and M-TLHS

Install taper guide pin sets M-TLGS, M-TLHS.

For details on the installation specifications, refer to pages 98 to 103

Taper guide pin set M-TLGS ➔ P.299, M-TLHS ➔ P.299


Application Mold bases (excluding the types with Plate S supplied and those for insert molding)

Orientation and angle of taper guide pin sets installation

Fixed-side bushing & moving-side pin type

Catalog No. **PTLG1** Install taper guide pin set M-TLGS (precision)


Catalog No. **PTLH1** Install taper guide pin set M-TLHS (super precision)



Fixed-side pin & moving-side bushing type

Catalog No. **PTLG2** Install taper guide pin set M-TLGS (precision)

Catalog No. **PTLH2** Install taper guide pin set M-TLHS (super precision)



Bushing installation methods

Bushing code	Bushing code BS1	Bushing code BS2	Bushing code BS3	Bushing code BS4
Install bushings on the fixed side				
Install bushings on the moving side				

※ Regardless of whether to install bushings on the fixed side or moving side, the bushing code is the same.

※ For details on each installation method, refer to pages 100 to 103.

※ If installing **Bushing code BS3** on the fixed side, changes to 3-plate type mold bases cannot be specified.

If installing it on the moving side, changes to the types without backing plate cannot be specified.

Pin installation method

Pin code	Pin code PN1	Pin code PN2	Pin code PN3	Pin code PN4
Install pin on the fixed side				
Install pin on the moving side				


※ Regardless of whether to install pins on the fixed side or moving side, the pin code is the same.

※ For details on each installation method, refer to pages 100 to 103.


※ If installing **Pin code PN3** on the fixed side, changes to 3-plate type mold bases cannot be specified.

If installing it on the moving side, changes to the types without backing plate cannot be specified.


Position code S021




Position code S023




Position code S041




Position code S022



Position code S024



Position code S042



If installing taper guide pin sets, advise us on the specifications by following the steps below:

- For Plate A and Plate B in which to install taper guide pin sets, surface grind will be used. The limit deviations of Plate A and Plate B thickness are required. Please specify them.
How to specify surface grind → P.31
- To maintain the accuracy of holes for taper guide pin sets, we also recommend rough machining of pockets and slide core grooves, etc.
How to specify machining of pockets and slide core grooves → P.204 - 221

Catalog No.	D	K	Bushing code	Pin code	Hole code	Position code	A	B	X	Y	Optional spec.
PTLG1	16	1	BS1	PN1	HC1	S021	In 1 mm steps	—	In 1 mm steps	In 1 mm steps	AC
PTLG2	20	3	BS2	PN2	HC2	S022	—	—	—	—	EPAT
PTLH1	25	5	BS3	PN3	HC3	S023	In 1 mm steps	In 1 mm steps	When X=KW/2, Omit X	When Y=KL/2, Omit Y	See page 99
PTLH2	30		BS4	PN4	See page 99	S024 S041 S042					

How to order

Catalog No. — **D** — **K** — **Bushing code** — **Pin code** — **Hole code** — **Position code**
 PTLH1 — D25 — K1 — BS2 — PN3 — HC2 — S024
 — **A** — **B** — **X** — **Y** — **Optional spec.**
 — A200 — B80 — X125 — Y200 — AC

Added Taper Guide Pin Set M-TLBS

Install taper guide pin set M-TLBS.

For details on the installation specification, refer to pages 98 to 103.


Taper guide pin M-TLBS ➡ P.300

Application Mold bases (excluding the types with Plate S supplied and those for insert molding)

Orientation and angle of taper guide pin sets installation


Fixed-side bushing & moving-side pin type

Catalog No. **PTLB1** Install taper guide pin set M-TLBS (precision)



Fixed-side pin & moving-side bushing type

Catalog No. **PTLB2** Install taper guide pin set M-TLBS (precision)



Bushing installation method

Bushing code	Bushing code BS1	Bushing code BS2	Bushing code BS3	Bushing code BS4
Install bushings on the fixed side				
Install bushings on the moving side				

※ Regardless of whether to install bushings on the fixed side or moving side, the bushing code is the same.

※ For details on each installation method, refer to pages 100 to 103.

※ If installing **Bushing code BS3** on the fixed side, changes to 3-plate type mold bases cannot be specified.

If installing it on the moving side, changes to the types without backing plate cannot be specified.

Pin installation method

Pin code	Pin code PN1	Pin code PN2	Pin code PN3	Pin code PN4
Install pin on the fixed side				
Install pin on the moving side				


※ Regardless of whether to install pins on the fixed side or moving side, the pin code is the same.

※ For details on each installation method, refer to pages 100 to 103.


※ If installing **Pin code PN3** on the fixed side, changes to 3-plate type mold bases cannot be specified.

If installing it on the moving side, changes to the types without backing plate cannot be specified.


Position code S021




Position code S023




Position code S041




Position code S022



Position code S024



Position code S042



If installing taper guide pin sets, advise us on the specifications by following the steps below:

- ① For Plate A and Plate B in which to install taper guide pin sets, surface grind will be used. The limit deviations of Plate A and Plate B thickness are required. Please specify them.
How to specify surface grind → P.31
- ② To maintain the accuracy of holes for taper guide pin sets, we also recommend rough machining of pockets and slide core grooves, etc.
How to specify machining of pockets and slide core grooves → P.204 - 221

Catalog No.	D	K	Bushing code	Pin code	Hole code	Position code	A	B	X	Y	Optional spec.
PTLB1	13	10	BS1 BS2 BS3 BS4	PN1 PN2 PN3 PN4	HC1 HC2 HC3	S021	In 1 mm steps	—	In 1 mm steps	In 1 mm steps	EPAT
	16					S022	—				
	20					S023	In 1 mm steps				
PTLB2	25				S024	In 1 mm steps		When X=KW/2, Omit X	When Y=KL/2, Omit Y		
	32				S041						
	40				S042						
	50			See page 99						See page 99	



How to order



















Catalog No. — **D** — **K** — **Bushing code** — **Pin code** — **Hole code** — **Position code**
PTLB1 — **D32** — **K10** — **BS1** — **PN1** — **HC1** — **S023**
 — **A** — **B** — **X** — **Y** — **Optional spec.**
 — **A200** — **B70** — **X125** — **Y150**



















Added Guide Pins and Bushings — Overview ①

Types and installation methods of guide pins and bushings — ①

Seven types of ejector guide pins and five types of ejector guide bushings can be combined to install in mold bases.

※ The combinations of guide pins and guide bushings shown in the charts below are standard combinations. The combinations in the blank columns cannot be specified with additional processing codes. If specifying them, please provide drawings, etc.

	Plain type		Self lubricating, high temp. type	Self lubricating, copper alloy type	Linear type
	Ejector guide bushing M-EBB	Ejector guide bushing M-EBBM	Ejector guide bushing M-EBC	Ejector guide bushing M-EBG	Ejector guide bushing M-EBD
	Bushing code EBB	Bushing code EBBM	Bushing code EBC	Bushing code EBG	Bushing code EBD
Ejector guide pin					
Ejector guide pin M-EGA	Catalog No. PEGA → P.120				
					
	D=10 12 16 20 25		D=10 12 16 20 25	D=16 20 25	D=10 12 16 20 25
Ejector guide pin M-EGB	Catalog No. PEGB, PEGBT → P.122				
					
	D=10 12 16 20 25		D=10 12 16 20 25	D=16 20 25	D=10 12 16 20 25
Ejector guide pin M-EGC	Catalog No. PEGC → P.124				
					
	D=20 25 30 40 50		D=20 25 30	D=20 25 30 40 50	D=20 25

Types and installation methods of guide pins and bushings — ②					
Ejector guide pin	Plain type		Self lubricating, high temp. type	Self lubricating, copper alloy type	Linear type
	Ejector guide bushing M-EBB	Ejector guide bushing M-EBBM	Ejector guide bushing M-EBC	Ejector guide bushing M-EBG	Ejector guide bushing M-EBD
	Bushing code EBB	Bushing code EBBM	Bushing code EBC	Bushing code EBG	Bushing code EBD
					
Ejector guide pin M-EGBM	Catalog No. PEGBM, PEGBMT → P.126				
		 D=10 13 16 20 25 30			 D=10 16 20 25
Ejector guide pin M-EGCM	Catalog No. PEGCM → P.128				
		 D=16 20 25 30 35 40 50			 D=16 20 25
Ejector guide pin M-GPHF ^{*1}	Catalog No. PEGPHF → P.130				
	 D=10 12 16 20 25 30		 D=10 12 16 20 25 30	 D=16 20 25 30	 D=10 12 16 20 25
Ejector guide pin M-GPA ^{*2}	Catalog No. PEGPA → P.130				
	 D=12 16 20 25 30		 D=12 16 20 25 30		
^{*1} Guide pin M-GPHF is used as ejector guide pin. When D=10, M-GPH is used. ^{*2} Guide pin M-GPA is used as ejector guide pin.					


Added Guide Pins and Bushings — Overview ②

Optional specifications for Catalog No. PEGA (specify only when necessary)

Option code

Specification


CDK

Change limit deviations of $\phi D1$ hole dimension in Plate L.

■ How to specify:

CDK

CHL



Change ejector guide pin hole H dimension and ejector guide pin length L dimension.

■ How to specify:

CHL/H [DIMM] /L [DIMM]

※ H → Specify in 1 mm steps. $10 \leq H \leq 4 \times D$


When H=plate thickness, through holes are machined.

※ L → Specify in 1 mm steps

(Product of length not listed herein needs to be custom-made.)

[E.g.] CHL/H25/L120

MLZ



Machine clearance holes for ejector guide bushing M-EBD in Plate L.

■ How to specify:

MLZ/H [DIMM] /L [DIMM] /Z [DIMM]

※ H → Specify in 1 mm steps $10 \leq H \leq 4 \times D$

When H=plate thickness, through holes will be machined

※ L → Specify in 1 mm steps

(Product of length not listed herein needs to be custom-made.)


※ Z → Specify in 1 mm steps

※ When installing additional Plate X or Plate Y, clearance holes will be machined in each plate.

[E.g.] MLZ/H20/L110/Z5






D	10	12	16	20	25
t	1		1.2		

EPAT







Only holes for installing ejector guide pins are machined.

Optional specifications for catalog No. PEGB, PEGBT, PEGBM, PEGBMT (specify only when necessary)




Option code	Specification
ECB	 Bolt holes will not be machined, nor will bolts be supplied. ■ Applicable items: Catalog No. PEGB, PEGBT, PEGBM, PEGBMT ■ How to specify: ECB
CHL	 Change ejector guide pin hole H dimension and ejector guide pin length L dimension. ■ Applicable items: Catalog No. PEGB, PEGBM ■ How to specify: CHL/H [DIMM] / L [DIMM] ※ H → Specify in 1 mm steps. $10 \leq H \leq 4 \times D$ When H=plate thickness, through holes will be machined. ※ L → In 1 mm steps (Length not listed herein is to be custom ordered) [E.g.] CHL/H23/L130
CLK	 Change the limit deviations of ejector guide pin L dimension. ■ Applicable items: Catalog No. PEGBT, PEGBMT ■ How to specify: CLK < upper deviation / lower deviation > ※ Limit deviations: in 0.01 mm steps ※ Tolerance: 0.02 mm or more Tolerance = upper deviation — lower deviation [E.g.] CLK < +0.01 / -0.01 >
MLZ	 Machine clearance holes for ejector guide bushing M-EBD in Plate L. ■ Applicable items: Catalog No. PEGB, PEGBM ■ How to specify: MLZ/H [DIMM] / L [DIMM] / Z [DIMM] ※ H → Specify in 1 mm steps. $10 \leq H \leq 4 \times D$ When H=plate thickness, through holes will be machined. ※ L → Specify in 1 mm steps. (Product of length not listed herein needs to be custom-made) ※ Z → Specify in 1 mm steps. ※ When installing additional Plate X or Plate Y, clearance holes will be machined in each plate. [E.g.] MLZ/H20/L100/Z7
EPAT	 Only holes for installing ejector guide pins are machined. ■ Applicable items: Catalog No. PEGB, PEGBT, PEGBM, PEGBMT

Added Guide Pins and Bushings — Overview ③


Optional specifications for catalog No. PEGC and PEGCM (specify only when necessary)

Option code	Specification
ECB	 Bolt holes will not be machined nor will bolts be supplied. ■ Applicable items: Catalog No. PEGC, PEGCM ■ How to specify: ECB
ENP	 Knock pin holes will not be machined, will knock pins be supplied. ■ Applicable items: Catalog No. PEGC, PEGCM ■ How to specify: ENP
CLK	 Change the limit deviations of ejector guide pin L dimension. ■ Applicable items: Catalog No. PEGC ■ How to specify: CLK < upper deviation / lower deviation > ※ Limit deviations: in 0.01 mm steps ※ Tolerance: 0.02 mm or more Tolerance = upper deviation – lower deviation [E.g.] CLK < +0.01/-0.01 >
EPAT	 Only holes for installing ejector guide pins are machined. ■ Applicable items: Catalog No. PEGC, PEGCM

Optional specifications for catalog No. PEGPHF and PEGPA (specify only when necessary)

Option code	Specification									
CHL		Change ejector guide pin hole H dimension and ejector guide pin length L dimension. ■ Applicable items: Catalog No. PEGPHF, PEGPA ■ How to specify: CHL/H [DIMM] /L [DIMM] ※ H → Specify in 1 mm steps. $10 \leq H \leq 4 \times D$ When H=plate thickness, through holes will be machined. ※ L → In 1 mm steps (Length not listed herein is to be custom ordered) [E.g.] CHL/H28/L127								
MLZ		Machine clearance holes for ejector guide bushing M-EBD in Plate L. ■ Applicable items: Catalog No. PEGPHF ■ How to specify: MLZ/H [DIMM] /L [DIMM] /Z [DIMM] ※ H → Specify in 1 mm steps. $10 \leq H \leq 4 \times D$ When H=plate thickness, through holes will be machined. ※ L → Specify in 1 mm steps. (Product of length not listed herein needs to be custom-made) ※ Z → Specify in 1 mm steps. ※ When installing additional Plate X or Plate Y, clearance holes will be machined in each plate. <table><tr><td>D</td><td>10</td><td>12~20</td><td>25</td></tr><tr><td>N</td><td>$N \geq 14$</td><td>$N \geq 19$</td><td>$N \geq 24$</td></tr></table> [E.g.] MLZ/H25/L150/Z5	D	10	12~20	25	N	$N \geq 14$	$N \geq 19$	$N \geq 24$
D	10	12~20	25							
N	$N \geq 14$	$N \geq 19$	$N \geq 24$							
EPAT		Only holes for installing ejector guide pins are machined. ■ Applicable items: Catalog No. PEGPHF, PEGPA								


Optional specifications for catalog No. PEGAS, PEGBS, PEGBTS, PEGBMS and PEGBMTS (specify only when necessary)

Option code	Specification
EPAT	 Only holes for installing ejector guide pins are machined.


Added Guide Pins and Bushings — Overview ④

Set the length of ejector guide bushings — ①

The length of ejector guide bushings is determined by the thickness of ejector plates.



Counterbore type



Spacer type

※ The range of thickness of ejector plates is the same regardless of whether the specification of the ejector plates is counterbore type or spacer type.

Ejector guide bushing M-EBB (plain type)

E	F	D=10		D=12		D=16		D=20		D=25		D=30		D=40		D=50	
		L	L1	L	L1	L	L1	L	L1	L	L1	L	L1	L	L1	L	L1
13 ≤ E < 15	13 ≤ F < 15	23	12														
	15 ≤ F	23	12	25	12	25	12	25	12	25	12						
15	15 ≤ F < 20	23	12	25	12	25	12	25	12	25	12						
	20 ≤ F	23	12	32	14	32	14	32	14	32	14	32	14				
15 < E < 20	20 ≤ F			32	14	32	14	32	14	32	14	32	14				
	20 ≤ F < 25			32	14	32	14	32	14	32	14	32	14				
20	25 ≤ F			32	14	42	19	42	19	42	19	42	19	42	19		
	25 ≤ F					42	19	42	19	42	19	42	19	42	19		
20 < E < 25	25 ≤ F < 30					42	19	42	19	42	19	42	19	42	19		
	30 ≤ F					42	19	52	24	52	24	52	24	52	24	52	24
25 < E ≤ 30	30 ≤ F							52	24	52	24	52	24	52	24	52	24

Ejector guide bushing M-EBBM (plain type)

E	F	D=10		D=13		D=16		D=20		D=25		D=30		D=35		D=40		D=50	
		L	L1	L	L1	L	L1	L	L1	L	L1	L	L1	L	L1	L	L1	L	L1
10 ≤ E < 13	13 ≤ F	22	10																
13 ≤ E < 15	13 ≤ F	25*1	13																
	15 ≤ F	25*1	13	27	13	27	13	27	13	27	13								
15 ≤ E < 20	15 ≤ F			29	15	29	15	29	15	29	15								
	20 ≤ F			29	15	29	15	29	15	34	15								
20 ≤ E < 25	15 ≤ F					34	20	34	20	34	20								
	20 ≤ F					34	20	34	20	34	20	39	20						
25 ≤ E < 30	15 ≤ F							39	25	39	25								
	20 ≤ F							39	25	39	25	44	25						
30 ≤ E ≤ 35	25 ≤ F							39	25	39	25	44	25	49	25	49	25	49	25
	15 ≤ F							44	30	44	30								
	20 ≤ F							44	30	44	30	49	30						
	25 ≤ F							44	30	49	30	54	30	54	30	54	30	54	30

*1. Can be installed even when E=15.

※ L and L1 dimensions of ejector guide bushing M-EBBM are nominal dimensions. The dimensions of the actual product are smaller than values shown in this table.

Ejector guide bushing M-EBC (self lubricating, high temperature type)

E	F	D=10		D=12		D=16		D=20		D=25		D=30	
		L	L1	L	L1	L	L1	L	L1	L	L1	L	L1
13 ≤ E < 15	13 ≤ F < 15	23	12										
	15 ≤ F	23	12	25	12	25	12	25	12	25	12		
15	15 ≤ F < 20	23	12	25	12	25	12	25	12	25	12		
	20 ≤ F	23	12	32	14	32	14	32	14	32	14	32	14
15 < E < 20	20 ≤ F			32	14	32	14	32	14	32	14	32	14
	20 ≤ F < 25			32	14	32	14	32	14	32	14	32	14
20	25 ≤ F			32	14	42	19	42	19	42	19	42	19
	25 ≤ F					42	19	42	19	42	19	42	19
20 < E ≤ 25	25 ≤ F												


Ejector guide bushing M-EBG (self lubricating copper alloy type)

E	F	D=16		D=20		D=25		D=30		D=40		D=50	
		L	L1	L	L1	L	L1	L	L1	L	L1	L	L1
13 ≤ E < 15	15 ≤ F	26	12	26	12	26	12						
15 ≤ E < 20	15 ≤ F	28	14	28	14	28	14						
	20 ≤ F	28	14	28	14	28	14	33	14				
20 ≤ E < 25	15 ≤ F	33	19	33	19	33	19						
	20 ≤ F	33	19	33	19	33	19	38	19				
25 ≤ E ≤ 30	15 ≤ F	33*2	19*2	38	24	38	24						
	20 ≤ F	33*2	19*2	38	24	38	24	43	24				
	25 ≤ F	33*2	19*2	38	24	38	24	43	24	48	24	48	24

*2. Can be applied only when E=25.

Set the length of ejector guide bushings — ②

The overall length of the ejector guide bushing M-EBD is determined by the D dimension. Therefore, when installing it in the mold bases, the length of the guide bushing M-EBD may be longer than the thickness of the ejector plates. Secure the space by installing stop pins or providing counterbore in the mounting plate.



Counterbore type

Spacer type

Ejector plate specification: counterbore type

E	F	D									
		10 (L=29)		12 (L=30)		16 (L=37)		20 (L=42)		25 (L=59)	
		H1orH2	L1	H1orH2	L1	H1orH2	L1	H1orH2	L1	H1orH2	L1
13	13	H2=3	13								
13	15	H2=1	13	H2=2	13						
15	20	H1=4	13	H1=3	13	H2=2	15				
20	25					H1=8	20	H1=3	20	H2=14	20
25	30					H1=13	20	H1=13	25	H2=4	25

Ejector plate specification: spacer type

E	F	D									
		10 (L=29)		12 (L=30)		16 (L=37)		20 (L=42)		25 (L=59)	
		H1orH2	L1	H1orH2	L1	H1orH2	L1	H1orH2	L1	H1orH2	L1
13	13	H1=1*2	13								
13	15	H1=3	13	H1=2	13						
15	20	H1=8	13	H1=7	13	H1=2	15				
20	25					H1=12	20	H1=7	20	H2=10	20
25	30					H1=17	20	H1=17	25	H1=0*1	25

※ The values written in red above are the cases where the L dimension of ejector guide bushing M-EBD is longer than the thickness of ejector plates (E+F). Secure the space by installing stop pins or providing counterbore in the mounting plate.

Installing stop pins → P.140, Adding counterbore → P.112 - 115

*1. When H1=0, the value may be slightly larger than the thickness of ejector plates. Secure the space by installing Stop pins or providing counterbore in the mounting plate.

*2. When combining with ejector guide pin M-EGA, secure space by installing stop pins or providing counterbores in the mounting plate.

※ The combinations shown above are the ejector plate combinations for standard mold bases. For combinations other than the above, calculate H1 and H2 dimensions by referring to the table below to determine the installation specifications.

D	L	E	F	L1	H1orH2
10	29	13 ≤ E ≤ 15	F ≥ 13	13	For counterbore type: H1or H2=L-L1-F
12	30	13 ≤ E ≤ 15		13	
16	37	15 ≤ E ≤ 20	F ≥ 15	15	For spacer type: H1or H2=L-L1-F-4
		20 ≤ E ≤ 25		20	
		20 ≤ E ≤ 25		20	
20	42	25 ≤ E ≤ 30		25	
		25 ≤ E ≤ 30		25	
25	59	20 ≤ E ≤ 25	F ≥ 25	20	※ F: thickness of Plate F ※ If the calculated result is a negative value, H1 dimension will be used. If it is a positive value, H2 dimension will be used.
		25 ≤ E ≤ 30	F ≥ 20	25	

Added Guide Pins and Bushings — Overview ⑤


Installation method when installing additional plates

If installing additional plates, Plate W, Plate X or Plate Y, the installation specification shown below can be used. For installation specification not listed below, specify with a drawing, etc.


The thickness of additional plate X and Plate Y must be 15 or more.

Additional plate specifications → P.38

Catalog No. PEGA





※ If the ejector guide pin does not reach Plate L, then clearance holes is not provided in the Plate L.





Catalog No. PEGB

Catalog No. PEGBM





Catalog No. PEGBT

Catalog No. PEGBMT





Catalog No. PEGC

Catalog No. PEGCM




Catalog No. PEGPHF

Catalog No. PEGPA



Bolt specification of ejector guide pins




Bolt length		
M	Z	Bolt length coefficient
M5	5.5	11
M6	7	12
M8	9	15
M10	11	19


※ Calculation of bolt length
 Bolt length = N - Z + bolt length coefficient
 Round down the last digit of calculation result, 0-4 to 0 and 5-9 to 5.

Hole specification of ejector guide pins

The pin insert holes for ejector guide pin in the mold plate will be blind holes or through holes depending on N dimension.



Blind hole



Through hole


■ Applicable item

Catalog No. PEGA, PEGB, PEGBM, PEGPHF, PEGPA


D	K max	Blind hole	Through hole
10	K=H+5	$N \geq K+3$	$H \leq N < K+3$
12	K=H+6		
13	K=H+6		
16	K=H+7		
20	K=H+8		
25	K=H+10		
30	K=H+11		

※ For H dimensions, refer to each installation specification page.

※ Shown in the charts are **Catalog No.** PEGA, but similar specifications can also be applied to other ejector guide pins.



Blind hole



Through hole

■ Applicable item

Catalog No. PEGC, PEGCM

DN	K max	Blind hole	Through hole
6	K=H+4	$N \geq K+3$	$H \leq N < K+3$
8	K=H+5		
10	K=H+5		
13	K=H+6		
16	K=H+7		

※ For H dimensions, refer to each installation specification page.

Added Ejector Guide Pin M-EGA

Install ejector guide pins M-EGA and ejector guide bushings.


For details on installation specifications, refer to pages 110 to 119.

Ejector guide pin M-EGA → P.326

Ejector guide bushing M-EBB → P.330 M-EBC → P.333 M-EBG → P.332 M-EBD → P.331


Application Mold bases (excluding the types without ejector plates)

Catalog No. PEGA




Installation of ejector guide bushing M-EBG:


If the thickness of Plate F is 15, machine the counterbores for guide pins M-EGA in the Plate L. In the case of spacer type installation method, the counterbores are not provided in Plate L.




Spacer type



Ejector guide bushing M-EBD



Counterbore type



Spacer type

※ In the cases where spacer type installation method is applied, or ejector guide bushing M-EBD is used, install as shown on the left.

D	D1 H7		P	H	D5	Z2	K max	Ejector guide bushing M-EBB · M-EBC · M-EBG ^{±1}					Ejector guide bushing M-EBD				
								D2 H7		D3	D4	Z1	D2 H7		D3	D4	Z1
10	10	+0.015 0	12	14	—	—	19	16	+0.018 0	17	21	4	19	+0.021 0	20	25	1.2
12	12	+0.018 0					20	18		19	23		21		22	27	
16	16						20	21	25	26	31		28		29	35	
20	20	+0.021 0	24	1.2	32	30	31	36	32	+0.025 0	33		39				
25	25		29		34	35	36	41	40		41		48	1.8			

*1. D=10 and 12 of ejector guide bushing M-EBG cannot be specified.







※ Thickness of Plate L ≥ 20

L dimension to C dimension

D	L dimension setting method *2	Standard range of L dimension of part
10	L=C+30	80 to 110 in 10 mm steps
12		80 to 130 in 10 mm steps
16		90 to 140 in 10 mm steps
20	L=C+40	110 to 190 in 10mm steps (180 is not available)
25		110 to 190 in 10mm steps (180 is not available)

*2. To specify L dimension: → P.112

※ M-EGA ejector guide pins other than the above need to be custom made.

Position code **S021**

Position code **S023**

Position code **S041**

Position code **S022**

Position code **S024**

Position code **S042**


Catalog No.	D	Bushing code	Position code	A	B	X	Y	Optional spec
PEGA	10	EBB (plain type)	S021	In 1 mm steps	—	In 1 mm steps	In 1 mm steps	CDK
	12	EBC (self-lubricating, high temp)	S022	—	—	—	—	CHL
	16	EBG (self-lubricating, copper alloy)	S023	In 1 mm steps	In 1 mm steps	When X=KW/2, omit X	When Y=KL/2, omit Y	MLZ
	20	EBD (linear type)	S024	In 1 mm steps	In 1 mm steps	When X=KW/2, omit X	When Y=KL/2, omit Y	EPAT
	25	Details → P.110	S041 S042	In 1 mm steps	In 1 mm steps	When X=KW/2, omit X	When Y=KL/2, omit Y	See page 112

How to order

Catalog No. — **D** — **Bushing code** — **Position code** — **A** — **B** — **X** — **Y**
PEGA — **D16** — **EBC** — **S024** — **A40** — **B250** — **X125** — **Y150**
 — **Optional spec.**
 — **CHL/H25/L120**

Added Ejector Guide Pin M-EGB

Install ejector guide pins M-EGB and ejector guide bushings.


For details on the installation specifications, refer to pages 110 to 119.

Ejector guide pin M-EGB → P.327


Ejector guide bushing M-EBB → P.330 M-EBC → P.333 M-EBG → P.332 M-EBD → P.331

Application Mold bases (excluding the types without ejector plates)

Catalog No. **PEGB**




Catalog No. **PEGBT**




Stuck-out specification

※ The Installation method of Catalog No. **PEGBT** does not provide positioning holes for ejector pins in Plate B or Plate U. Therefore, adequate precaution should be taken to avoid misalignment between centers of Plate B or U and Plate E.


Spacer type



Ejector guide bushing M-EBD



Counterbore type



Spacer type

※ In the cases where spacer type installation method is applied, or ejector guide bushing M-EBD is used, install as shown on the left.

D	D1 H7		P	H	K max	M	Ejector guide bushing M-EBB · M-EBC · M-EBG ^{*1}					Ejector guide bushing M-EBD				
							D2 H7		D3	D4	Z1	D2 H7		D3	D4	Z1
10	10	+0.015 0	10	12	17	M5	16	+0.018 0	17	21	4	19	+0.021 0	20	25	1.2
12	12	+0.018 0			18	M6	18		19	23		21		22	27	
16	16				19		25	+0.021 0	26	31		28		29	35	
20	20	+0.021 0	20	22	30	M8	30	31	36	32		+0.025 0	33	39		
25	25				32	M10	35	+0.025 0	36	41			40	41	48	1.8







*1. D=10 and 12 of ejector guide bushing M-EBG cannot be specified.

L dimension to C dimension

D	L dimension setting method *2		Standard range of L dimension of part
	Catalog No. PEGB	Catalog No. PEGBT	
10	L=C+10	L=C	50 to 90 10 mm steps
12			50 to 110 10 mm steps
16			50 to 120 10 mm steps
20	L=C+20		60 to 170 10 mm steps
25			60 to 200 10 mm steps

*2. How to specify L dimension: → P.113

※ M-EGB ejector guide pins other than the above need to be custom made.

Position code **S021**

Position code **S023**

Position code **S041**

Position code **S022**

Position code **S024**

Position code **S042**


Catalog No.	D	Bushing code	Position code	A	B	X	Y	Optional spec
PEGB	10	EBB (plain type)	S021	In 1 mm steps	—	In 1 mm steps	In 1 mm steps	ECB CHL
	12	EBC (self-lubricating, high temp)	S022	—	—	—	—	CLK MLZ
PEGBT	16	EBG (self-lubricating, copper alloy)	S023	In 1 mm steps	In 1 mm steps	When X=KW/2, omit X	When Y=KL/2, omit Y	EPAT
	20	EBD (linear type)	S024	In 1 mm steps	In 1 mm steps	When X=KW/2, omit X	When Y=KL/2, omit Y	See page 113
	25	Details → P.110	S041 S042	In 1 mm steps	In 1 mm steps	When X=KW/2, omit X	When Y=KL/2, omit Y	See page 113

※ Specify adjustment of the ejector guide pin M-EGB (stuck-out type) and spacer block thickness with optional specification. If not specified, the adjustment will be made according to the accuracy requirements of respective parts.

How to order

Catalog No. — **D** — **Bushing code** — **Position code** — **A** — **B** — **X** — **Y**
PEGB — **D16** — **EBD** — **S041** — **A130** — **B200** — **X150** — **Y175**
 — **Optional spec.**
 — **ECB**

Added Ejector Guide Pin M-EGC

Install ejector guide pins M-EGC and ejector guide bushings.


For details on the installation specifications, refer to pages 110 to 119.

Ejector guide pin M-EGC → P.328

Ejector guide bushing M-EBB → P.330 M-EBC → P.333 M-EBG → P.332 M-EBD → P.331

Application Mold bases (excluding the types without ejector plates)

Catalog No. PEGC



Spacer type	Ejector guide bushing M-EBD	
	Counterbore type	Spacer type

※ In the cases where spacer type installation method is applied, or ejector guide bushing M-EBD is used, install as shown on the left.

D	D1 H7		P	H	K max	M	Ejector guide bushing M-EBB · M-EBC *1 · M-EBG *2					Ejector guide bushing M-EBD *3				
							D2 H7		D3	D4	Z1	D2 H7		D3	D4	Z1
20	8	+0.015 0	15	17	22	M8	30	+0.021 0	31	36	4	32	+0.025 0	33	39	1.5
25	10					M10	35	+0.025 0	36	41		40		41	48	1.8
30							40		41	46		—	—	—	—	—
40							50 (52)		51 (53)	56 (58)						
50							60 (62)	+0.030 0	61 (63)	67 (68)						

*1. D=40 and 50 of ejector guide bushing M-EBC cannot be specified.







*2. The hole dimensions of D=40 and 50 of ejector guide bushing M-EBG are values in parentheses ().

*3. D=30 to 50 of ejector guide bushing M-EBD cannot be specified.

L dimension to C dimension

D	L dimension setting method	Standard range of L dimension of part
20	L=C	50~100 in 10 mm steps
25		50~120 in 10 mm steps
30		50~150 in 10 mm steps
40		80~170 in 10 mm steps
50		80~200 in 10 mm steps (190 is not available)

※ M-EGC ejector guide pins other than the above need to be custom made.

Position code **S021**

Position code **S023**

Position code **S041**

Position code **S022**

Position code **S024**

Position code **S042**


Catalog No.	D	Bushing code	Position	A	B	X	Y	Optional spec
PEGC	20	EBB (plain type)	S021	In 1 mm steps	—	In 1 mm steps	In 1 mm steps	ECB ENP CLK EPAT
	25	EBC (self-lubricating, high temp)	S022	—	In 1 mm steps			
	30	EBG (self-lubricating, copper alloy)	S023	In 1 mm steps		When X=KW/2, omit X	When Y=KL/2, omit Y	
	40	EBD (linear type)	S024					
	50	Details ➡ P.110	S041 S042					
See page 114								

※ Specify adjustment of the ejector guide pin M-EGC and spacer block thickness with optional specification. If not specified, the adjustment will be made according to the accuracy requirements of respective parts.

How to order

Catalog No. — **D** — **Bushing code** — **Position code** — **A** — **B** — **X** — **Y**
PEGC — **D30** — **EBB** — **S041** — **A120** — **B240** — **X150** — **Y200**
 — **Optional spec.**
 — **CLK<+0.01/-0.01>**

Added Ejector Guide Pin M-EGBM

Install ejector guide pins M-EGBM and ejector guide bushings.



For details on the installation specifications, refer to pages 110 to 119.

Ejector guide pins M-EGBM → P.334


Ejector guide bushings M-EBBM → P.336 M-EBD → P.331

Application Mold bases (excluding the types without ejector plates)

Catalog No. PEGBM




Catalog No. PEGBMT




Sturck-out specification

※ The Installation method of Catalog No. PEGBMT does not provide positioning holes for ejector pins in Plate B or Plate U. Therefore, adequate precaution should be taken to avoid misalignment between centers of Plate B or U and Plate E.


Spacer type



Ejector guide bushing M-EBD



Counterbore type



Spacer type

※ In the cases where spacer type installation method is applied, or ejector guide bushing M-EBD is used, install as shown on the left.

D	D1 H7		P	H	K max	M	Ejector guide bushing M-EBBM					Ejector guide bushing M-EBD *1				
							D2 H7		D3	D4	Z1	D2 H7		D3	D4	Z1
10	10	+0.015 0	10	12	17	M5	18	+0.018 0	19	22	4	19	+0.021 0	20	25	1.2
13	13	+0.018 0			18	M6	22	+0.021 0	23	26		—		—	—	
16	16				19		25		26	29		28		29	35	1.5
20	20	+0.021 0	20	22	30	M8	30		31	34		32	+0.025 0	33	39	
25	25				32		35	+0.025 0	36	39		40	41	48	1.8	
30	30			30	32	43	M10	40		41		44		—	—	—







*1. D=13 and 30 of ejector guide bushing M-EBD cannot be specified.

L dimension to C dimension

D	L dimension setting method *2			D	L dimension setting method *2		
	Catalog No. PEGBM	Catalog No. PEGBMT	Standard range of L dimension of part		Catalog No. PEGBM	Catalog No. PEGBMT	Standard range of L dimension of part
10	L=C+10	L=C	50 to 100 in 10 mm steps	20	L=C+20	L=C	60 to 170 in 10 mm steps
13			50 to 110 in 10 mm steps	25			60 to 220 in 10 mm steps
16			50 to 120 in 10 mm steps	30			100 to 220 in 10 mm steps

*2. How to specify L dimension: → P.113

※ M-EGBM ejector guide pins other than the above need to be custom made.

Position code **S021**

Position code **S023**

Position code **S041**

Position code **S022**

Position code **S024**

Position code **S042**


Catalog No.	D	Bushing code	Position code	A	B	X	Y	Optional spec
PEGBM	10	EBBM (plain type) EBD (linear type)	S021	In 1 mm steps	In 1 mm steps	In 1 mm steps	In 1 mm steps	ECB CHL CLK MLZ EPAT
	13		S022	—				
PEGBMT	16	Details → P.110	S023	In 1 mm steps	In 1 mm steps	When X=KW/2, omit X	When Y=KL/2, omit Y	See page 113
	20		S024					
	25		S041					
	30		S042					

※ Specify adjustment of the ejector guide pin M-EGBM (stuck-out type) and spacer block thickness with optional specification. If not specified, the adjustment will be made according to the accuracy requirements of respective parts.

How to order

Catalog No. — **D** — **Bushing code** — **Position code** — **A** — **B** — **X** — **Y**
PEGBMT — **D16** — **EBBM** — **S041** — **A80** — **B180** — **X100** — **Y175**
 — **Optional spec.**
 — **CLK<+0.03/+0.01>**

Added Ejector Guide Pin M-EGCM

Install ejector guide pins M-EGCM and ejector guide bushings.



For details on the installation specifications, refer to pages 110 to 119.

Ejector guide pin M-EGCM → P.335


Ejector guide bushing M-EBBM → P.336 M-EBD → P.331

Application Mold bases (excluding the types without ejector plates)


Catalog No. PEGCM




Spacer type



Ejector guide bushing M-EBD



Counterbore type



Spacer type

※ In the cases where spacer type installation method is applied, or ejector guide bushing M-EBD is used, install as shown on the left.







D	D1 H7		P	H	K max	M	Ejector guide bushing M-EBBM					Ejector guide bushing M-EBD *1					
							D2 H7		D3	D4	Z1	D2 H7		D3	D4	Z1	
16	6	+0.012 0	15	17	21	M6	25	+0.021 0	26	29	4	28	+0.021 0	29	35	1.5	
20	8	+0.015 0	20	22	27	M8	30		31	34		32	+0.025 0	33	39		
25	10						35	36	39	40		41		48	1.8		
30	13	+0.018 0	25	27	33	M10	40	+0.025 0	41	44		—	—	—		—	—
35	16						45		46	49							
40							52	+0.030 0	53	56							
50							62		63	66							

*1. D=30 to 50 of ejector guide bushing M-EBD cannot be specified.

L dimension to C dimension

D	L dimension setting method	Standard range of L dimension of part
16	L=C	50 to 100 in 10 mm steps
20		50 to 130 in 10 mm steps
25		50 to 200 in 10 mm steps
30		
35		80 to 200 in 10 mm steps
40		
50		

※ M-EGCM ejector guide pins other than the above need to be custom made.

Position code **S021**

Position code **S023**

Position code **S041**

Position code **S022**

Position code **S024**

Position code **S042**


Catalog No.	D	Bushing code	Position code	A	B	X	Y	Optional spec
PEGCM	16	EBBM (plain type)	S021	In 1 mm steps	—	In 1 mm steps	In 1 mm steps	ECB ENP EPAT
	20		S022	—				
	25	EBD (linear type)	S023	In 1 mm steps	In 1 mm step	When X=KW/2, omit X	When Y=KL/2, omit Y	See page 114
	30		S024					
	35		S041					
	40		S042					
	50	Details ➡ P.110						

How to order

Catalog No. — **D** — **Bushing code** — **Position code** — **A** — **B** — **X** — **Y**
PEGCM — **D40** — **EBBM** — **S041** — **A150** — **B340** — **X200** — **Y300**
 — **Optional spec.**
 — **ECB**

Added Ejector Guide Pins M-GPHF and M-GPA

Use M-GPHF and M-GPA as ejector guide pins to install the ejector guide pins and ejector guide bushings.


For details on the installation specifications, refer to pages 110 to 119.

Ejector guide pin M-GPHF → P.279 M-GPA → P.274


Ejector guide bushing M-EBB → P.330 M-EBC → P.333 M-EBG → P.332 M-EBD → P.331

Application Mold bases (excluding the types without ejector plates)


Catalog No. PEGPHF




Catalog No. PEGPA




Spacer type



Ejector guide bushing M-EBD



Counterbore type



Spacer type

※ In the cases where spacer type installation method is applied, or ejector guide bushing M-EBD is used, install as shown on the left.

D *1	D1 H7		P *2	H *2	K *2 max	D5	Z2	Ejector guide bushing M-EBB • M-EBC • M-EBG *3					Ejector guide bushing M-EBD *4				
								D2 H7		D3	D4	Z1	D2 H7		D3	D4	Z1
10	10	+0.015 0	14	16	21	14	5	16	+0.018 0	17	21	4	19	+0.021 0	20	25	1.2
12	12	+0.018 0	14 (12)	16 (14)	22 (20)	18		18		19	23		21		22	27	
16	16		23 (21)	21	6	25	+0.021 0	26	31	28	29		35		1.5		
20	20	34 (32)	26	30		31		36	32	+0.025 0	33		39	1.8			
25	25	+0.021 0	24 (22)	26 (24)	8	35	+0.025 0	36	41		40		41			48	
30	30		29 (27)	31 (29)		42 (40)		36	40		41		46		—	—	—

*1. D=10 of the Catalog No. PEGPA cannot be specified.

*2. The dimensions of Catalog No. PEGPA are those in parentheses ().

*3. D=10 and 12 of ejector guide bushing M-EBG cannot be specified.

For Catalog No. PEGPA, ejector guide bushing M-EBG cannot be specified.

*4. For Catalog No. PEGPA, ejector guide bushing M-EBD cannot be specified.







For Catalog No. PEGPHF, φ 30 cannot be specified.

※ L=L0+C+P

Adjust the length of press-fit section of the guide pin so that "The length of press-fit section of the pin ≤ thickness of Plate L" is ensured. For this reason, in some cases guide pins may need to be custom-made.

The L dimension for Catalog No. PEGPHF calculated in the above +1 mm will be the nominal dimension of ejector guide pin M-GPHF.

For Catalog No. PEGPHF, when D=10, guide pin M-GPH is used. M-GPH → P.278

Position code **S021**

Position code **S023**

Position code **S041**

Position code **S022**

Position code **S024**

Position code **S042**


Catalog No.	D	Bushing code	Position code	A	B	X	Y	Optional spec
PEGPHF	10	EBB (plain type)	S021	In 1 mm step	—	In 1 mm steps	In 1 mm steps	CHL
	12	EBC (self-lubricating, high temperature)	S022	—	—	—	—	MLZ
	16	EBG (self-lubricating, copper alloy)	S023	In 1 mm steps	In 1 mm steps	When X=KW/2, omit X	When Y=KL/2, omit Y	EPAT
PEGPA	20	EBD (linear type)	S024	In 1 mm steps	—	—	—	—
	25	—	S041	—	—	—	—	—
	30	Details → P.110	S042	—	—	—	—	See page 115

How to order

Catalog No. — **D** — **Bushing code** — **Position code** — **A** — **B** — **X** — **Y**
PEGPHF — **D16** — **EBB** — **S041** — **A100** — **B280** — **X125** — **Y200**
 — **Optional spec.**
 — **CHL/H28/L120**


Added Guide Pins and Bushings — Standard Position

Specifications of ejector guide pins for standard mold bases have been now established.

For details on the installation specifications, refer to pages 110 to 119.

Application Mold bases (excluding the types without ejector plates)


Catalog No. PEGAS (M-EGA spec.)



2-guide specification


Catalog No. PEGBS (M-EGB spec.)

Catalog No. PEGBMS (M-EGBM spec.)





Catalog No. PEGBTS (M-EGB spec.)

Catalog No. PEGBMTS (M-EGBM spec.)



Stuck-out specification



※ $X = KW/2$, $Y = KL/2$

Catalog No.	Bushing code ^{*1}	Option code	*1. The combinations marked with ○ in the table below are supported.				
PEGAS PEGBS PEGBMS PEGBTS PEGBMTS	EBB (Plain type)	EPAT See page 115	Bushing code				
	EBBM (Plain type)		Catalog No.				
	EBC (self-lubricating, high temp. type)		PEGAS	PEGBS	PEGBMS	PEGBTS	PEGBMTS
	EBG (self-lubricating, copper alloy type)		EBB	○	○	○	○
	Details → P.110		EBBM		○		○
			EBC	○	○	○	
			EBG	D=16, 20, 25 supported	D=16, 20, 25 supported	D=16, 20, 25 supported	

How to order

Catalog No. — **Bushing code** — **Optional spec.**
 PEGAS — EBB

Application Mold base S series (excluding SE · SF types)
Mold base D · E series (excluding DE · DF · EE · EF types)
Mold base F · G series (excluding FE · FF · GE · GF types)

Nominal dimm.	D *2	Pitch of ejector guide pins				Nominal dimm.	D	Pitch of ejector guide pins					
		Traditional type mold bases		High rigidity type mold base				Traditional type mold bases		High-rigidity type mold bases			
		A *3	B	A *3	B			A *3	B	A *3	B		
1515	10	2-guide	114	2-guide	80	2930	16	134	172	—	—		
1518			144		110	2935			222				
1520			164		130	2940			272				
1523			194		160	3030			172	100	190		
1525			214		180	3032			192	—	—		
1530		48	216	—	—	3035			222	240			
1818		2-guide	138	2-guide	144	3040			272	100	290		
1820			158		164	3045		308	—	—			
1823			188		194	3050		358					
1825			208		214	3055		408					
1830			210		48	216		3060			458		
1835	68	260	—	—	3335	208							
2020		2-guide	150	2-guide	164	3340	258						
2023			180		194	3345	308						
2025			200		214	3350	358						
2030			194		48	212	3535	208					
2035	80		244		—	—	3540	258					
2040		294	3545	308									
2045		344	3550	358									
2323	12 (13)	2-guide	180	2-guide	188	3555	20	154	408	—	—		
2325			200		208	3560			458				
2327			220		—	4040			252				
2330		194	68	206	4045	302							
2335		244		256	4050	352							
2340		294		—	4055	402							
2525		16	2-guide	200	2-guide	200		4060	25			198	452
2527				220		—		4070					552
2530			110	190	80	190		4545					286
2535			102	230		240		4550					336
2540				280		290		4555					386
2545	330			—		4560	436						
2550	380					5050	336						
2730	114		172	90	190	5060	256	436					
2735			222		240	5070		536					
2740			272	—	—								
2750			372										

*2. The dimensions of **Catalog No. PEGBMS, PEGBMTS** are those in parenthesis ().

*3. 2-guide means 2-guide specification and the numbers show A dimension of 4-guide specification.

Application Mold base H series

Nominal dimm.	D	Pitch of ejector guide pins	
		A	B
2540	16	110	236
2545			286
2550			336
2740		120	236
2750	20	136	336
3045			284
3050			334
3055			384
3060		166	434
3350			334
3550			286
3555		176	336
3560			386
4060			388
4070	25	210	488


※ 4-guide specification is applied to all of H series mold bases.

Added Springs — Overview

Spring coils installation method


Spring coils for returning ejector plates can be installed in mold bases using two different installation methods.

Specification for installing spring coil over return pin section







How to order: ➡ P.136

Specification for installing spring coil on other locations





How to order: ➡ P.138

Optional specification (Specify only when necessary)

Option code	Specification
CCD	 Produce chamfers of C2 in spring holes. ※ This is not applied when the depth of counterbore is less than 5 mm. ■ Applicable item: Catalog No. PSH1N, PSH2N, PSH3N, PSH4N, PSH5N MSH1, MSH2, MSH3, MSH4, MSH5 ■ How to specify: CCD
CCW	 Produce chamfers of C2 on the mold plate side in spring holes. ※ This is not applied when the depth of counterbore is less than 5 mm. ■ Applicable item: Catalog No. PSHF, MSHF ■ How to specify: CCW
CCE	 Produce chamfers of C2 on the ejector plate in spring holes. ※ This is not applied when the depth of counterbore is less than 5 mm. ■ Applicable item: Catalog No. PSHF, MSHF ■ How to specify: CCE
CCR	 Produce chamfers of C2 on the ejector plate and mold plate in spring holes. ※ This is not applied when the depth of counterbore is less than 5 mm. ■ Applicable item: Catalog No. PSHF, MSHF ■ How to specify: CCR

Spring coil specification for installing over return pin section



Depending on the diameter of return pins, four types of spring coils and diameter of holes are available.

How to specify coil spring:



Part code/L [DIMM.]

[E.g.] FSB12/L50

Spring coil length and constant → P.396 - 405

Type	Spring coil M-FSB				Spring coil M-TY				Spring coil M-TR				Spring coil P-TF			
Color	Light green				Purple				Ivory				Yellow			
d	Part code	D	D1	d1	Part code	D	D1	d1	Part code	D	D1	d1	Part code	D	D1	d1
10	FSB10	19	17.5	10.5	TY17	19	17	11	TR17	19	17	11	TF20	22	20	11
													TF22	24	22	11
12	FSB12	23	21.5	13.2	TY21	23	21	13	TR21	23	21	13	TF25	27	25	13.5
													TF27	29	27	13.5
15	FSB15	28	26.5	15.5	TY26	28	26	16.5	TR26	28	26	16.5	TF30	32	30	16
20	FSB20	34	32.5	20.5	TY32	34	32	21	TR32	34	32	21	TF40	42	40	22
25	FSB25	41	39.5	25.5	TY39	41	39	26	TR39	41	39	26	TF50	52	50	27.5
30	FSB30	47	45.5	30.5	TY46	48	46	32	TR46	48	46	32	TF60	62	60	33

Specification for installing spring coil on other locations



Four types of coils are available for choice.

How to specify spring coil:

Part code/L [DIMM.]

[E.g.] TF25/L60

Spring coil length and constant → P.396 - 405

Type	Spring coil M-FSB			Spring coil M-TY			Spring coil M-TR			Spring coil P-TF		
Color	Light green			Purple			Ivory			Yellow		
	Part code	D1	d1	Part code	D1	d1	Part code	D1	d1	Part code	D1	d1
Spring coil specification	FSB10	17.5	10.5	TY15	14.5	9	TR15	14.5	9	TF14	14	7
	FSB12	21.5	13.2	TY17	17	11	TR17	17	11	TF16	16	8
	FSB15	26.5	15.5	TY21	21	13	TR21	21	13	TF18	18	9
	FSB20	32.5	20.5	TY26	26	16.5	TR26	26	16.5	TF20	20	11
	FSB25	39.5	25.5	TY32	32	21	TR32	32	21	TF22	22	11
	FSB30	45.5	30.5	TY39	39	26	TR39	39	26	TF25	25	13.5
				TY46	46	32	TR46	46	32	TF27	27	13.5
										TF30	30	16
										TF35	35	19
										TF40	40	22
										TF50	50	27.5
										TF60	60	33

Added Springs — ①

Install spring coils for returning ejector plates over return pins.

For details on the installation specifications, refer to pages 134 to 135.


Spring M-FSB M-FSB → P.396 M-TY → P.398 M-TR → P.400 P-TF → P.402

Application Mold bases (excluding the types without ejector plates)-

Catalog No. PSH1N

Apply to types with Plate U


Catalog No. MSH1



Catalog No. PSH2N

Apply to types with Plate U


Catalog No. MSH2



Catalog No. PSH3N

Apply to types with Plate U

Catalog No. MSH3




When $Z=B$, through hole is provided

Catalog No. PSH4N

Apply to types without Plate U

Catalog No. MSH4




When $Z=B$, through hole is provided

If installing additional Plate W

Catalog No. PSH1N, PSH2N, PSH3N, MSH1, MSH2, MSH3,


through holes will be machined in Plate W as spring holes.



Catalog No. PSH5N

Applies when spring holes in Plate W are counterbore.

Catalog No. MSH5



When Z =thickness of plate W, through plates are provided.

Specifications for installing spring coils

Depending on the diameter of return pins, four types of spring coils and diameter of holes are available.

Details on spring coil specifications → P.396 - 405

d	Spring coil M-FSB		Spring coil M-TY		Spring coil M-TR		Spring coil P-TF	
	Part code	D	Part code	D	Part code	D	Part code	D
10	FSB10	19	TY17	19	TR17	19	TF20	22
							TF22	24
12	FSB12	23	TY21	23	TR21	23	TF25	27
							TF27	29
15	FSB15	28	TY26	28	TR26	28	TF30	32
20	FSB20	34	TY32	34	TR32	34	TF40	42
25	FSB25	41	TY39	41	TR39	41	TF50	52
30	FSB30	47	TY46	48	TR46	48	TF60	62

Catalog No.	Z *1 *2	Part code	Spring coil length L	Optional spec.
PSH1N PSH2N PSH3N PSH4N PSH5N	In 1 mm steps For Z max, See table below	Select from the above table	Select from pages 396 to 405	CCD See page 134

*1. For **Catalog No. PSH1N**, no need to specify Z dimension.

*2. For **Catalog No. PSH2N, PSH4N, PSH5N**, when Z=0, spring holes ϕD will not be provided. Only spring coils are installed.



How to order

Catalog No. — **Z** — **Part code** / **L** — **Optional spec.**
PSH4N — **Z20** — **FSB12** / **L45** — **CCD**
PSH1N — — **TF25** / **L60**

Specification for spring hole only

d	Catalog No.	D	Recommended value	Z *3	Optional spec.
10	MSH1 MSH2 MSH3 MSH4 MSH5	15 to 65 in 1 mm steps Provided $D \geq d + 5$	19 22 24	In 1 mm steps	CCD
12			23 27 29		
15			28 32		
20			34 42	See table on the right	See page 134
25			41 52		
30			47 48 62		

*3. For **Catalog No. MSH1**, no need to specify Z dimension.

Relation of hole diameter & counterbore depth

D	Z max
15 to 19	$Z \leq 50$
20 to 27	$Z \leq 60$
28 to 34	$Z \leq 80$
35 to 44	$Z \leq 90$
45 to 65	$Z \leq 100$



How to order

Catalog No. — **D** — **Z** — **Optional spec.**
MSH4 — **D42** — **Z45** — **CCD**

Added Springs — ②

Install spring coils for returning ejector plates.

For details on the installation specification, refer to pages 134 to 135.

Spring coil M-FSB → P.396 M-TY → P.398 M-TR → P.400 P-TF → P.402




When compressed, spring coils may be deformed (side deflection) so as to jump out of place from its intended position. Secure sufficient depth of counterbores in spring holes.

Application Mold bases (excluding types without ejector plates)


Catalog No. PSHF with spring coil

Catalog No. MSHF without spring coil




W section specification code

W section spec code WZ Z DIMM




W section spec code WK




E section specification code

E section spec code EZ Z DIMM



E section spec code EK



Relation of hole diameter and counterbore depth

D	Z max
15~19	$Z \leq 50$
20~27	$Z \leq 60$
28~34	$Z \leq 80$
35~44	$Z \leq 90$
45~65	$Z \leq 100$


※ $Z \leq \text{thickness} - 5$

This formula is not a guarantee of strength.


Catalog No.	D	W section specification code	E section specification code	Position code	A	B	X	Y	Spring coil	Optional spec.
PSHF	In 1 mm steps	WZ Z DIMM WK	EZ Z DIMM EK	S011	—	—	In 1 mm steps	In 1 mm steps	Select from pages 396 to 405	CCW CCE CCR
				S021	In 1 mm steps					
				S022	—	In 1 mm steps	When X=KW/2, omit X	When Y=KL/2, Omit Y	No need to specify for MSHF	
				S023	In 1 mm steps					
S024										
MSHF	15 ~ 65	Z DIMM. In 1 mm steps	Z DIMM In 1 mm steps	S041	In 1 mm steps	In 1 mm steps				
				S042						

See page 134


Position code **S011**




Position code **S021**




Position code **S022**




Position code **S023**




Position code **S024**



Position code **S041**



Position code **S042**



How to order

Catalog No.	D	W section spec code	E section spec code	Position code	A	B
PSHF	D24	WZ22	EZ3	S041	A80	B130
MSHF	D28	WK	EK	S022		B250
	X	Y	Spring coil	Optional spec.		
	X100	Y125	FSB12/L70	CCW		
	X115	Y150		CCR		

Added Stop Pins or Stop Rings


Install stop pins or stop rings.

Stop pin, stop ring M-STP, M-STPH, M-STR ➔ P.345

Application Mold bases (excluding the types without ejector plates)


If installing additional Plate X or Plate Y, Additional plate specification ➔ P.38

Install stop pins or stop rings in Plate X or Plate Y.




Stop pin, stop ring installation specification


Catalog No. PSTP




Catalog No. PSTPH




Catalog No. PSTR



Stop ring threaded hole specification



Blind hole spec.



Through hole spec.

The threaded holes for stop ring are blind holes or through hole depending on the N dimension.








Blind hole specification	$N \geq 21$
Through hole specification	$N < 21$

Catalog No.	D *1	Position code	A	B	X	Y	Optional spec
PSTP PSTPH PSTR	16 20 25	S021	In 1 mm steps	—	In 1 mm steps	In 1 mm steps	EPAT
		S022	—	In 1 mm steps			
		S023					
		S024	In 1 mm steps	In 1 mm steps	When X=KW/2, omit X	When Y=KL/2, omit Y	
		S041					
		S042 S061					

*1. Specify this for Catalog No. PSTR.

※ Install return pins that are shorter by the amount of thickness of stop pins or stop rings (5mm).

※ Place stop pins or stop rings at four places or more. Use two Position code to specify stops pins or stop rings multiple times. This allows you to make various layout.

Position code **S021**

Position code **S023**

Position code **S041**

Position code **S022**

Position code **S024**

Position code **S042**

Position code **S061**



Optional specification (specify only when necessary)

Option code


Specification

EPAT

Only the holes for installing stop pins and stop rings will be machined.



Holes for stop pins



Holes for stop rings

How to order

Catalog No.

D

Position code

A

B

X

Y

Optional spec.

PSTPH

—

S041

—

A48

—

B144

—

X75

—

Y90

PSTR

—

D20

—

S061

—

A80

—

B250

—

X100


—

Y150


Added Support Pillars — Overview

Types and installation methods of support pillars


Three types of support pillars can be installed in mold bases using four different installation methods.



Installation specification in the case of installing additional Plate W, Plate X or Plate Y




Installation specification in the case of installing additional Plate W and Plate X



Installation specification in the case of installing additional Plate W and Plate Y

Bolt specification of support pillars


Bolt specification of support pillar M-SRD



M	Z	Bolt length coefficient
M6	7	12
M8	9	15
M12	13	22

※ Calculation of bolt length
Bolt length=Plate L thickness-Z+bolt length coefficient Round down the last digit of calculation result, 0-4 to 0 and 5-9 to 5.

Bolt specification of support pillar M-SRE






Blind hole spec.

M	F	K max	Blind hole spec.	Through hole spec.	Bolt length coefficient	N
M6	13	20	$N \geq 23$	$N < 23$	5	$N \geq 13$
M8	15	21	$N \geq 24$	$N < 24$	5	$N \geq 15$
M10	17	25	$N \geq 28$	$N < 28$	3	$N \geq 17$
M12	19	28	$N \geq 31$	$N < 31$	3	$N \geq 19$
M16	23	34	$N \geq 37$	$N < 37$	3	$N \geq 23$

Through hole spec.

※ Calculation of bolt length
Bolt length=support pillar length+bolt length coefficient Round down the last digit of calculation result, 0-4 to 0 and 5-9 to 5.


Optional specification (specify only when necessary)

Option code	Specification
CLK	 Change the limit deviation of support pillar L dimension. ■ How to specify: CLK < Upper deviation / Lower deviation > ※ Specify limit deviation in 0.01 mm steps ※ Tolerance: 0.02 mm or more Tolerance = Upper deviation – lower deviation [E.g.] CLK < +0.01/ -0.01 >
CDA	 Change the ejector plate D1 dimension. ■ How to specify: CDA [D1 DIMM] ※ Specify D1 dimension in 1 mm steps $D1 \geq D + 2$ [E.g.] CDA45
EPAT	 Only holes for installing support pillar will be machined.

※ Shown in the chart are support pillar M-SRD, but similar applications can also applied to M-SRC and M-SRE.

Knock pin hole specification of support pillars

Catalog No. **PSRC1**




Blind hole spec.

Through hole spec.

DN	D2	H	Blind hole spec	Through hole spec
8	8.2	17	$N \geq 22$	$17 \leq N < 22$
10	10.2	17	$N \geq 23$	$17 \leq N < 23$
16	16.2	22	$N \geq 30$	$22 \leq N < 30$

Catalog No. **PSRC2**



Blind hole spec.

Through hole spec

DN	D3 H7	H	K max	Blind hole spec	Through hole spec
8	8	17	22	$N \geq 24$	$17 \leq N < 24$
10	10	17	22	$N \geq 25$	$17 \leq N < 25$
16	16	22	29	$N \geq 32$	$22 \leq N < 32$


Added Support Pillars

Install support pillars. For details on installation specifications, refer to pages 142 to 143.


Support pillars M-SRC ► P.343 M-SRD ► P.342 M-SRE ► P.344

Application Mold bases


Catalog No. PSRC1




Catalog No. PSRC2



Catalog No. PSRD1



Catalog No. PSRE1










D	D1	D2	D3 H7		H	K max	M1	M2		
20	22	8.2	8	+0.015 0	17	22	M6	M6		
25	27	10.2	10				M8	M8	M10	
30	32									M12
35	37									
40	42							M16		
50	52	16.2	16	+0.018 0	22	29	M12			
60	63									
80	83									

Catalog No.	D	Position code	A	B	X	Y	Optional spec.
PSRC1 PSRC2 PSRD1 PSRE1	20 25 30 35 40 50 60 80	S011	—	In 1 mm steps	In 1 mm steps When X=KW/2, omit X	In 1 mm steps When Y=KL/2, omit Y	CLK CDA EPAT See page 143
		S021	In 1 mm steps				
		S022	—				
		S023 S024 S041 S042	In 1 mm steps				

※ Specify adjustments of the support pillars and spacer block thickness with optional specification.

If not specified, the adjustment will be made according to the accuracy requirements of respective parts.

Position code **S011**

Position code **S021**

Position code **S022**

Position code **S023**

Position code **S024**

Position code **S041**

Position code **S042**


How to order


Catalog No. — **D** — **Position code** — **A** — **B** — **X** — **Y** — **Optional spec.**
PSRD1 — **D30** — **S041** — **A100** — **B180** — **X150** — **Y175** — **CLK<+0.03/+0.01>**

Added Ejector Rods

Install ejector rods.


Ejector rods M-ERA → P.346, Machining only holes for ejector rods → P.236

Application Mold bases (excluding the types without ejector plates)




If installing additional Plate X or Plate Y: Additional plate specification → P.38

The holes for ejector rods will be machined in Plate X and Plate Y.



Additional plate X





Additional plate Y

※ Installing stops pins → P.140


D	D1	M	L1					L
			13 ≤ F < 15	15 ≤ F < 20	20 ≤ F < 25	25 ≤ F < 30	30 ≤ F	
20	24	M6	7	7	7	12	12	15 20 25 30 35 40
25	29	M8	Installation not allowed	9	9	14	14	20 25 30 35 40
30	34							20 25 30 35 40 50
35	40	M10	Installation not allowed	Installation not allowed	Installation not allowed	11	16	25 30 35 40 50
40	45							25 30 35 40 50
50	55							30 35 40 50 60

Optional specification (specify only when necessary)


Option code	Specification
CDA	 Change D1 dimension. ■ How to specify CDA D1 DIMM. ※ Specify D1 dimension in 1 mm steps $D1 \geq D + 2$ [E.g.] CDA45
EPAT	 Only holes for installing ejector rods will be machined.

Catalog No.	D	L	X	Y	Optional spec.	
PERA1 PERA2 *1 PERA3 PERA4A PERA4B *1 PERA5A PERA5B PERA7 PERA9	20 25 30 35 40 50	Select from above table	In 1 mm steps When $X=KW/2$, omit X	In 1 mm steps When $Y=KL/2$, omit Y	CDA EPAT *2	*1. The mold bases with nominal dimension range from 1113 through 2550 have holes for installing standard ejector rods at the center. If specifying PERA2 or PERA4B, the holes will be eliminated. *2. If selecting EPAT, it is not necessary to specify L dimension. ※ The mold bases with nominal dimension range from 1113 through 2550 have holes for installing standard ejector rods at the center. If specifying to install any ejector rods, the standard diameter will change to the specified diameter.


Catalog No. PERA1




Catalog No. PERA2




Catalog No. PERA3




Catalog No. PERA4A




Catalog No. PERA4B




Catalog No. PERA5A




Catalog No. PERA5B



Catalog No. PERA7



Catalog No. PERA9












How to order

Catalog No. — **D** — **L** — **X** — **Y** — Optional spec.
PERA3 — **D30** — **L25** — **X80** — **Y150** — **CDA40**

Added Puller Bolts — Overview ①

Puller bolt installation method





Puller bolts can be installed in mold bases in nine different ways of installation methods:

Mold opening control of Plate T and Plate R		Mold opening control of Plate T and Plate A
Catalog No. PPBB1 	Catalog No. PPBB2 	Catalog No. PPBB4 
How to order ➔ P.154	How to order ➔ P.156	How to order ➔ P.160
Mold opening control of Plate A and R		Mold opening control of Plate T & R, and R & A
Catalog No. PPBB3 	Catalog No. PPBAH1 Ground shank type 	Catalog No. PPBA1 
How to order ➔ P.158	How to order ➔ P.164	How to order ➔ P.166
Mold opening control of Plate A and B		
Catalog No. PPBB5 	Catalog No. PPBAH2 Ground shank type 	Catalog No. PPBA2 
How to order ➔ P.162	How to order ➔ P.168	How to order ➔ P.168


Optional Specification (specify only when necessary)	
Option code	Specification

Added Puller Bolts — Overview ②

Optional specification (specify only when necessary)

Option code	Specification												
MHD	Machine ϕ D holes in the plate specified as blind holes. ■ Applicable item: Catalog No. PPBB3, PPBB4, PPBB5, PPBAH1, PPBA1, PPBAH2, PPBA2, PPBAHS, PPBAS ■ Not applicable: ① If the ϕD2 holes pass through Plate C, E, F and additional Plate Y, the Plate C cannot be specified. ② Plate E, F and additional Plate Y cannot be specified. ■ Not applicable: MHD/plate code/Z Z DIMM ※ Plate codes ➡ P.13 ※ Combined use of EHD is not allowed. [e.g.] MHD/C/Z30 												
CRD	Change the diameter of holes (ϕD3) for puller bolts in Plate R. <table><tr><td>D</td><td>10</td><td>13</td><td>16</td><td>20</td><td>25</td></tr><tr><td>D3</td><td>6.2</td><td>8.2</td><td>10.2</td><td>12.2</td><td>16.2</td></tr></table> ■ Applicable item: Catalog No. PPBAH1, PPBA1, PPBAHS, PPBAS ■ How to specify: CRD ※ Combined use with CRM is not allowed. 	D	10	13	16	20	25	D3	6.2	8.2	10.2	12.2	16.2
D	10	13	16	20	25								
D3	6.2	8.2	10.2	12.2	16.2								
CRM	Change the puller bolt holes to threaded holes. For details on the shape & dimensions of the threaded holes, see the right page. ■ Applicable item: Catalog No. PPBAH1, PPBAHS ■ How to specify: CRM ※ Combined use with CRD is not allowed. 												
EPAT	Only holes for installing puller bots are provided. ■ Applicable item: Catalog No. PPBB1, PPBB2, PPBB3, PPBB4, PPBB5, PPBAH1, PPBA1, PPBAH2, PPBA2, PPBAHS, PPBAS 												

Option code CRM detailed dimensions




D	M	D3	J	N								F (F=R·N·J)
				R=10	R=15	R=20	R=25	R=30	R=35	R=40	R=50	
10	M6	7	0	4	×	4	9					$6 \leq F \leq 16$
			1	8								
			2	7								
			3	6								
			4	5								
			5	×			4					
			6									
			7									
13	M8	9	0	×	5	5	10	15			$8 \leq F \leq 20$	
			1		×		5	9				14
			2					8				13
			3					7				12
			4					6				11
			5					5				10
			6	9								
			7	8								
16	M10	11	0	×	6	6	6	11	16			$10 \leq F \leq 24$
			1					10	15			
			2					9	14			
			3					8	13			
			4		7			12				
			5		6			11				
			6				10					
			7				9					
20	M12	13	0		7	7	7	12			$12 \leq F \leq 28$	
			1					11				
			2					10				
			3					9				
			4		8							
			5		7							
			6									
			7				×					
25	M16	17	0		×	8	8	8	8	18	$16 \leq F \leq 32$	
			1			×				8		17
			2									16
			3									15
			4									14
			5									13
			6			×	12					
			7				11					

※ The columns with × denote the combinations to which CRM cannot be specified. The blank columns show no M-PBCH puller bolts is available for application.

Added Puller Bolts — Overview ③

Select Puller bolt M-PBCH, M-PBC



The size of puller bolts M-PBCH and M-PBC are set according to the thickness of Plate T and Plate R. The combinations not listed herein cannot be specified with additional processing codes. Please specify us with drawing, etc.

Selection table of puller bolt M-PBCH (ground shank type)




D	T	V	H	N	F									
					R=10	R=15	R=20	R=25	R=30	R=35	R=40	R=50		
10	20	10	8	2	19	24								
	25	15					29							
	30	20					34							
13	20	10	8		22	27		32	37	42				
	25	15												47
	30	20												
	35	25					37	42	47					
	40	30												
	45	35												
16	25	10	13			30	35		40	45	50	55		
	30	15												
	35	20												
	40	25						35	40	45	50	55		
	45	30												
	50	35												
20	30	15	13					38	43	48	53	58		
	35	20												
	40	25												
	45	30						38	43	48	53	58		
	50	35												
	60	45												
25	35	15	18				44	49	54	59	64	74		
	40	20												
	45	25												
	50	30												
	60	40												

Selection table of puller bolt M-PBC

D	T	V	H	N	F						
					R=10	R=15	R=20	R=25	R=30	R=35	R=40
10	25	16	8	1	22	27					
	30	21									
13	25	14	10		30	30					
	30	19				35					
	35	24					40	40			
16	30	15	14			35	35				
	35	20					40				
	45	30						45	45		
20	35	20	14				45	45			
	45	30						50			
	50	35							55		
25	50	31	18						60	60	
	60	41								65	




Clearance hole specification for puller bolts

Depending on the length of puller bolts and installation methods, clearance hole $\phi D2$ will be as follows:

		
When the distance from the head of the puller bolt to the next plate is $L0 < 1$, the through hole of $\phi D2$ is machined in the next plate as well. ■ Applicable item: Catalog No. PPBB3, PPBB4, PPBAH1, PPBA1, PBAHS, PPBAS	Regardless of the length of puller bolts, $\phi D2$ hole will be machined through to Plate L. ■ Applicable item: Catalog No. PPBB5	Regardless of the length of puller bolts, $\phi D2$ hole will be machined through to Plate L, T. ■ Applicable item: Catalog No. PPBAH2, PPBA2

Clearance hole specification when puller bolt passes through Plate C, E, F and Y

If the puller bolt passes through Plate C, Plate E, Plate F or additional Plate Y, depending on the length of the puller bolt, the $\phi D2$ hole will be machined through to Plate E, Plate F, or additional Plate Y.

When the puller bolt is at the position which is inner side than Plate C	Shape of clearance hole
	
When the puller bolt passes through Plate C, E, F and Y	
	When the clearance hole $\phi D2$ for the puller bolt passes through Plate C, E, F and Y, the hole will be any of the shapes shown above. On MOLDZUKAN, holes are drawn to the circular shape (at the top of the list above). Note that the hole shape shown on the MOLDZUKAN may be different from the actual shape.


Added Puller Bolt — B1

Install puller bolt M-PBB. For details on installation specifications, see pages 148 to 153.


Puller bolts M-PBB → P.314

Application Mold bases D series and F series

Catalog No. PPBB1



Threaded hole specification



The threaded holes for puller bolts will be blind holes or through holes depending on the thickness of Plate R.







D	M	F	K max	Blind hole spec	Through hole spec.
10	M8	15	21	$R \geq 26$	$R < 26$
13	M10	16	24	$R \geq 31$	$R < 31$
16	M12	20	29	$R \geq 36$	$R < 36$
20	M16	26	37	$R \geq 41$	$R < 41$
25	M20	30	43	$R \geq 46$	$R < 46$

D	D1	D2	Z	M	H	L	T	R
10	11	19	T-Z ≥ 5 *1 If D=10 or 13, then T-Z ≥ 4 *1	M8	8	16	T ≥ 25	R ≥ 15
						21	T ≥ 30	
						26	T ≥ 35	
						31	T ≥ 40	
13	14	21		M10	10	14	T ≥ 25	R ≥ 15
						19	T ≥ 30	
						24	T ≥ 35	
						29	T ≥ 40	
16	17	27		M12	14	15	T ≥ 30	R ≥ 20
						20	T ≥ 35	
						25	T ≥ 40	
						30	T ≥ 45	
						35	T ≥ 50	
						20	T ≥ 35	
						25	T ≥ 40	
						30	T ≥ 45	
20	21	31		M16	14	35	T ≥ 50	R ≥ 25
						45	T ≥ 60	
						31	T ≥ 50	
						41	T ≥ 60	
25	26	36	M20	18	31	T ≥ 50	R ≥ 30	
					41	T ≥ 60		

*1. This formula is not a guarantee of strength.

※ Mold opening stroke between Plate T and Plate R

$$S1 = Z + L - T \quad Z = T + S1 - L \quad L = T + S1 - Z$$

Position code **S021**

Position code **S023**

Position code **S041**

Position code **S022**

Position code **S024**

Position code **S042**


Catalog No.	D	L	Z	Position code	A	B	X	Y	Optional spec.	
PPBB1	10	Select from left table	In 1 mm steps	S021	In 1 mm steps	—	In 1 mm steps	In 1 mm steps	EPAT	
	13			S022	—	In 1 mm steps				
	16		See Left table	S023	In 1 mm steps		When X=KW/2, omit X	When Y=KL/2, omit Y		See page 150
	20			S024						
25	S041									
			S042							

How to order

Catalog No. — **D** — **L** — **Z** — **Position code** — **A** — **B** — **X** — **Y**
 PPBB1 — D13 — L19 — Z16 — S041 — A140 — B200 — X90 — Y125
 — **Optional spec.**

Added Puller Bolts — B2

Install puller bolt M-PBB. For details on the installation specifications, see pages 148 to 153.

Puller bolt M-PBB → P.314



Application Mold bases D series and F series

Catalog No. **PPBB2**


If installing additional Plate O, Plate N:

Additional plate specifications → P.38

The through holes as shown below will be machined in the additional Plate O and N.



Threaded hole specification



Blind-hole spec.

Through-hole spec.

The threaded holes for puller bolts will be blind holes or through holes depending on the thickness of Plate T.

D	M	F	K max	Blind hole spec	Through hole spec
10	M8	15	21	$T \geq 26$	$T < 26$
13	M10	16	24	$T \geq 31$	$T < 31$
16	M12	20	29	$T \geq 36$	$T < 36$
20	M16	26	37	$T \geq 41$	$T < 41$
25	M20	30	43	$T \geq 46$	$T < 46$

D	D1	D2	Z	M	G *2 *3	S0	H	L	R+A *2
10	11	19	R-Z≥5 *1	M8	If G=L-R- (O+N)+11 and G≥A-10, then through hole is provided	13	8	13	R+A+ (O+N) ≥ 22
								16	R+A+ (O+N) ≥ 25
								21	R+A+ (O+N) ≥ 30
								26	R+A+ (O+N) ≥ 35
								31	R+A+ (O+N) ≥ 40
13	14	21		M10	If G=L-R- (O+N)+13 and G≥A-11, then through hole is provided	14	10	13	R+A+ (O+N) ≥ 24
								14	R+A+ (O+N) ≥ 25
								19	R+A+ (O+N) ≥ 30
								24	R+A+ (O+N) ≥ 35
								29	R+A+ (O+N) ≥ 40
16	17	27		M12	If G=L-R- (O+N)+17 and G≥A-12, then through hole is provided	18	14	13	R+A+ (O+N) ≥ 28
								15	R+A+ (O+N) ≥ 30
								20	R+A+ (O+N) ≥ 35
								25	R+A+ (O+N) ≥ 40
								30	R+A+ (O+N) ≥ 45
20	21	31		M16	If G=L-R- (O+N)+17 and G≥A-14, through hole is provided	24	14	35	R+A+ (O+N) ≥ 50
								16	R+A+ (O+N) ≥ 31
								20	R+A+ (O+N) ≥ 35
								25	R+A+ (O+N) ≥ 40
								30	R+A+ (O+N) ≥ 45
25	26	36		M20	If G=L-R- (O+N)+21 and G≥A-15 then, through hole is provided	28	18	35	R+A+ (O+N) ≥ 50
								45	R+A+ (O+N) ≥ 60
								31	R+A+ (O+N) ≥ 50
								41	R+A+ (O+N) ≥ 60







*1. This formula is not a guarantee of strength.

*2. If installing additional Plate O and N, add the thickness of Plate O and N.

*3. If G is negative value, the hole of $\phi D2$ will not be provided in Plate A.

※ Mold opening stroke between Plate T and Plate R

$S1=Z+L-R$ $Z=R+S1-L$ $L=R+S1-Z$

Position code **S021**

Position code **S023**

Position code **S041**

Position code **S022**

Position code **S024**

Position code **S042**


Catalog No.	D	L	Z	Position code	A	B	X	Y	Optional spec.	
PPBB2	10	Select from left table	In 1 mm steps	S021	In 1 mm steps	—	In 1 mm steps	In 1 mm steps	EPAT	
	13			S022	—					
	16		See left table	S023 S024 S041 S042	In 1 mm steps	In 1 mm steps	When X=KW/2, omit X	When Y=KL/2, omit Y		See page 150
	20									
	25									

How to order

Catalog No. — **D** — **L** — **Z** — **Position code** — **A** — **B** — **X** — **Y**
 PPBB2 — D16 — L20 — Z15 — S041 — A200 — B250 — X125 — Y150
 — **Optional spec.**


Added Puller Bolts — B3

Install puller bolt M-PBB. For details on installation specifications, see pages 148 to 153.


Puller bolt M-PBB → P.314

Application Mold bases D series and F series


Catalog No. PPBB3



If puller bolts are shorter than the thickness of Plate A, the clearance hole will not be provided on the moving side.



Threaded hole specification



The threaded holes for puller bolts will be blind holes or through holes depending on the thickness of Plate R.

D	M	F	K max	Blind hole spec	Through hole spec
10	M8	15	21	$R \geq 26$	$R < 26$
13	M10	16	24	$R \geq 31$	$R < 31$
16	M12	20	29	$R \geq 36$	$R < 36$
20	M16	26	37	$R \geq 41$	$R < 41$
25	M20	30	43	$R \geq 46$	$R < 46$

Diameter in the case of installing additional plates: Additional plate specification → P.38

Diameter of Plate O and N → $\phi D1$ If E dimension is specified, however, ϕE is used.

Diameter of Plate Q, Plate V, Plate W and Plate X → $\phi D2$

※ If installing either or both of additional Plate O or/ and Plate N, specifying E dimension and $G=0$, the counterbore holes in Plate A will be eliminated and ϕE through hole will be provided in Plate O or N.

D	D1	D2	P *1	E *1	Recommended value	G *1	M	H	R
10	11	19	$P \leq 80$	15 to 60	19 22 24	See table below	M8	8	$R \geq 15$
13	14	21	$P \leq 100$	In 1 mm steps	23 27 29		M10	10	$R \geq 15$
16	17	27	$P \leq 110$	Provided	28 37		M12	14	$R \geq 20$
20	21	31	$P \leq 130$		34 42		M16	14	$R \geq 25$
25	26	36	$P \leq 140$	$E \geq D+5$	41 52		M20	18	$R \geq 30$

*1. Specify P, E and G as necessary.

$P+G+5 \leq A$ (This formula is not a guarantee of strength.)

※ Mold opening stroke between Plate R and Plate A


$S2=L-A+P$ $P=S2+A-L$ $L=S2+A-P$

※ If the distance from the head of puller bolt to the next plate is $L0 < 1$, $\phi D2$ through hole is provided in the next plate as well.


Relation of counterbore diameter E and depth G

E	G max
15 to 19	$G \leq 50$
20 to 27	$G \leq 60$
28 to 34	$G \leq 80$
35 to 44	$G \leq 90$
45 to 60	$G \leq 100$


Position code **S021**




Position code **S023**




Position code **S041**




Position code **S022**



Position code **S024**



Position code **S042**



L dimension of puller bolt M-PBB

D	L																							
10	13	16	21	26	31	60	70	80	90	100	110	120	130	140	150	160								
13	13	14	19	24	29	70	80	90	100	110	120	130	140	150	160	170	180							
16	13	15	20	25	30	35	80	90	100	110	120	130	140	150	160	170	180	190	200					
20	16	20	25	30	35	45				100	110	120	130	140	150	160	170	180	190	200	220	240		
25	31	41												150	160	170	180	190	200	220	240	260		

Catalog No.	D	L	P	E	G	Position code	A	B	X	Y	Optional spec.
PPBB3	10	Select from above table	In 1 mm steps	See left table	Omit this if unnecessary	S021	In 1 mm steps	—	In 1 mm steps	In 1 mm steps	PSR CCE EHD MHD EPAT See page 149
	13					S022	—	In 1 mm steps			
	16		S023 S024 S041 S042			1 mm steps	When X=KW/2, omit X		When Y=KL/2, omit Y		
	20										
	25										

How to order

Catalog No. — **D** — **L** — **P** — **E** — **G** — Position code — **A** — **B**

PPBB3 — **D20** — **L200** — **P5** — **E34** — **G30** — **S024** — **A240** — **B200**

— **X** — **Y** — Optional spec.

— **X150** — **Y200** — **PSR/FSB20/LS50**


Added Puller Bolts — B4

Install puller bolt M-PBB. For details on the installation specifications, see pages 148 to 153.


Puller bolt M-PBB → P.314

Application Mold bases E series and G series


Catalog No. PPBB4



If puller bolts are shorter than the thickness of Plate A, the clearance hole will not be provided on the moving side.



Threaded hole specification



Blind-hole spec.

Through-hole spec.

The threaded holes for puller bolts will be blind holes or through holes depending on the thickness of Plate T.

D	M	F	K max	Blind hole spec	Through hole spec
10	M8	15	21	$T \geq 26$	$T < 26$
13	M10	16	24	$T \geq 31$	$T < 31$
16	M12	20	29	$T \geq 36$	$T < 36$
20	M16	26	37	$T \geq 41$	$T < 41$
25	M20	30	43	$T \geq 46$	$T < 46$

Diameter in the case of installing additional plates: Additional plate specification → P.38

Diameter of Plate N → $\phi D1$ If E dimension is specified, however, ϕE is used.

Diameter of Plate Q, Plate V, Plate W and Plate X → $\phi D2$.

※ If installing additional Plate N, specifying E dimension and $G=0$, the counterbore holes in Plate A will be eliminated and ϕE through hole will be provided in Plate N.

D	D1	D2	P*1	E*1	Recommended value	G*1	M	S0	H
10	11	19	$P \leq 80$	15 to 60	19 22 24	See table below	M8	13	8
13	14	21	$P \leq 100$	In 1 mm	23 27 29		M10	14	10
16	17	27	$P \leq 110$	steps	28 37		M12	18	14
20	21	31	$P \leq 130$	Provided	34 42		M16	24	14
25	26	36	$P \leq 140$	$E \geq D+5$	41 52		M20	28	18

*1. Specify P, E and G as necessary.

$P+G+5 \leq A$ (This formula is not a guarantee of strength.)

※ Mold opening stroke between Plate T and Plate A


$S2=L-A+P$ $P=S2+A-L$ $L=S2+A-P$

※ If the distance from the head of puller bolt to the next plate is $L0 < 1$, $\phi D2$ through hole will be provided in the next plate as well.


Relation of counterbore diameter E and depth G

E	G max
15 to 19	$G \leq 50$
20 to 27	$G \leq 60$
28 to 34	$G \leq 80$
35 to 44	$G \leq 90$
45 to 60	$G \leq 100$


Position code **S021**




Position code **S023**




Position code **S041**




Position code **S022**



Position code **S024**



Position code **S042**



L dimension of puller bolt M-PBB

D	L																						
10	13	16	21	26	31	60	70	80	90	100	110	120	130	140	150	160							
13	13	14	19	24	29	70	80	90	100	110	120	130	140	150	160	170	180						
16	13	15	20	25	30	35	80	90	100	110	120	130	140	150	160	170	180	190	200				
20	16	20	25	30	35	45				100	110	120	130	140	150	160	170	180	190	200	220	240	
25	31	41													150	160	170	180	190	200	220	240	260

Catalog No.	D	L	P	E	G	Position code	A	B	X	Y	Optional spec.
PPBB4	10	Select from above table	In 1 mm steps	See left table	Omit this if unnecessary	S021	In 1 mm steps	—	In 1 mm steps	In 1 mm steps	PSR CCE EHD MHD EPAT See page 149
	13					S022	—	In 1 mm steps			
	16		S023 S024 S041 S042			In 1 mm steps	When X=KW/2, omit X		When Y=KL/2, omit Y		
	20										
	25										

How to order

Catalog No. — **D** — **L** — **P** — **E** — **G** — Position code — **A** — **B**

PPBB4 — **D20** — **L200** — **P5** — **E34** — **G30** — **S023** — **A200** — **B150**

— **X** — **Y** — Optional spec.

— **X125** — **Y150** — **PSR/FSB20/LS50**


Added Puller Bolts — B5

Install puller bolt M-PBB. For details on installation specifications, see pages 148 to 153.


Puller bolts M-PBB → P.314

Application Mold bases D·E series, F·G series, H series (excluding the types with Plate S from each series)

Catalog No. PPBB5



Threaded hole specification



The threaded holes for puller bolts will be blind holes or through holes depending on the thickness of Plate A.

D	M	F	K max	Blind hole spec	Through hole spec
10	M8	15	21	$A \geq 24$	$A < 24$
13	M10	16	24	$A \geq 27$	$A < 27$
16	M12	20	29	$A \geq 32$	$A < 32$
20	M16	26	37	$A \geq 40$	$A < 40$
25	M20	30	43	$A \geq 46$	$A < 46$

Diameter in the case of installing additional plates:

Additional plate specification → P.38

Diameter of Plate W and Plate X → $\phi D2$

If installing either of additional plates of Plate Q or Plate V, order with additional processing codes is not allowed. Please order with drawings, etc.

D	D1	D2	P*1	M	S0	H	A
10	11	19	$P \leq 50$	M8	13	8	$A \geq 15$
13	14	21	$P \leq 60$	M10	14	10	$A \geq 15$
16	17	27	$P \leq 60$	M12	18	14	$A \geq 20$
20	21	31	$P \leq 80$	M16	24	14	$A \geq 25$
25	26	36	$P \leq 90$	M20	28	18	$A \geq 30$







*1. Specify P as necessary.

$P+5 \leq B$ (This formula is not a guarantee of strength.)

※ Regardless of the length of the puller bolt, the $\phi D2$ hole will be machined through to the Plate L.

※ Mold opening stroke between Plate A and Plate B

$S3=L+P-B$ $P=S3+B-L$ $L=S3+B-P$

Position code **S021**

Position code **S023**

Position code **S041**

Position code **S022**

Position code **S024**

Position code **S042**


L dimension of puller bolt M-PBB

D	L																						
10	13	16	21	26	31	60	70	80	90	100	110	120	130	140	150	160							
13	13	14	19	24	29	70	80	90	100	110	120	130	140	150	160	170	180						
16	13	15	20	25	30	35	80	90	100	110	120	130	140	150	160	170	180	190	200				
20	16	20	25	30	35	45					100	110	120	130	140	150	160	170	180	190	200	220	240
25	31	41													150	160	170	180	190	200	220	240	260

Catalog No.	D	L	P	Position code	A	B	X	Y	Optional spec.
PPBB5	10	Select from above table	In 1 mm steps	S021	In 1 mm steps	—	In	In	EHD MHD EPAT See page 149
	13		S022	—	In 1 mm steps	1 mm steps	1 mm steps		
	16		See left table	S023		When X=KW/2, omit X	When Y=KL/2, omit Y		
	20			S024					
	25			S041 S042					
			Omit this if unnecessary						

How to order

Catalog No. — **D** — **L** — **P** — **Position code** — **A** — **B** — **X** — **Y**
PPBB5 — **D16** — **L150** — **P30** — **S023** — **A160** — **B140** — **X100** — **Y150**
 — **Optional spec.**
 — **MHD/C/Z50**


Added Puller Bolts — AH1

Install puller bolts M-PBAH and M-PBCH. For details on the installation specifications, see pages 148 to 153.


Puller bolt M-PBAH → P.310 M-PBCH → P.308

Application Mold bases D series and F series

Catalog No. **PPBAH1** Ground shank type



If puller bolts are shorter than the thickness of Plate A, the clearance hole will not be provided only on the movable side.



Diameter in the case of installing additional plates: Additional plate specification → P.38

Diameter of Plate O and N → $\phi D1$ If E dimension is specified, however, ϕE is used.

Diameter of Plate Q, Plate V, Plate W and Plate X → $\phi D2$.

※ If installing either or both of additional Plate O or/ and Plate N, specifying E dimension and G=0, counterbore holes in Plate A will be eliminated and ϕE through hole will be provided.

D	D1	D2	D3	Z	P*1	E*1	Reccomended value	G*1	J*1	H	T	R	V	F
10	11	19	7	T-Z $\geq 5^{*2}$ When D=10, 13 T-Z $\geq 4^{*2}$	P ≤ 80	15 to 60	19 22 24	See table below	When J ≤ 7 R=10, J ≤ 5	8	See page 152			
13	14	21	9		P ≤ 100	In 1 mm	23 27 29			8				
16	17	27	11		P ≤ 110	steps	28 37			13				
20	21	31	13		P ≤ 130	provided	34 42			13				
25	26	36	17		P ≤ 140	E $\geq D+5$	41 52			18				

*1. Specify P, E, G, J as necessary.

P+G+5 $\leq$ A (this formula is not a guarantee of strength).

*2. This formula is not a guarantee of strength.

※ Mold opening stroke between Plate T and Plate R

S1=Z+V-T Z=T+S1-V V=T+S1-Z







※ Mold opening stroke between Plate R and Plate A

S2=L-A+P-J P=S2+A+J-L L=S2+A+J-P J=L+P-S2-A

※ If the distance from the head of puller bolt to the next plate is L0 < 1, $\phi D2$ through hole will be provided in the next plate as well.

Relation of counterbore diameter E and depth G

E	G max
15 to 19	G ≤ 50
20 to 27	G ≤ 60
28 to 34	G ≤ 80
35 to 44	G ≤ 90
45 to 60	G ≤ 100

Position code **S021**

Position code **S023**

Position code **S041**

Position code **S022**

Position code **S024**

Position code **S042**


L dimention of Puller bolt M-PBAH

D	L																											
10	50	60	70	80	90	100	110	120	130	140	150	160	170	180														
13		60	70	80	90	100	110	120	130	140	150	160	170	180	190	200	210	220	230	240	250	260	280					
16						100	110	120	130	140	150	160	170	180	190	200	210	220	230	240	250	260	280	300				
20								120	130	140	150	160	170	180	190	200	210	220	230	240	250	260	280	300	350			
25													170	180	190	200	210	220	230	240	250	260	280	300	350			

Catalog No.	D	L	Z	P	E	G	J	Position code	A	B	X	Y	Optional spec.
PPBAH1	10	Select from above table	In 1 mm steps	In 1 mm steps				S021	In 1 mm steps	—	In 1 mm steps	In 1 mm steps	PSR CCE EHD MHD CRD CRM EPAT See page 149
	13		S022					—					
	16		See left table					In 1 mm steps	When X=KW/2, omit X	When Y=KL/2, omit Y			
	20		Omit this if unnecessary								S023 S024 S041 S042		
	25												

How to order

Catalog No. — **D** — **L** — **Z** — **P** — **E** — **G** — **J** — **Position code**
PPBAH1 — **D13** — **L180** — **Z21** — **P15** — **E29** — **G30** — **J3** — **S041**
 — **A** — **B** — **X** — **Y** — **Optional spec.**
 — **A185** — **B100** — **X115** — **Y125** — **PSR/TF25/LS50**



Added Puller Bolts — A1

Install puller bolt M-PBA and M-PBC. For details on installation specifications, see pages 148 to 153.


Puller bolt M-PBA → P.313 M-PBC → P.312

Application Mold bases D series and F series

Catalog No. PPBA1



If puller bolts are shorter than the thickness of Plate A, the clearance hole will not be provided on the moving side.



Diameter in the case of installing additional plates: Additional plate specification → P.38

Diameter of Plate O and N → $\phi D1$ If E dimension is specified, however, ϕE is used.
Diameter of Plate Q, Plate V, Plate W and Plate X → $\phi D2$.

※ If installing either or both of additional Plate O or/ and Plate N, specifying E dimension and $G=0$, counterbore holes in Plate A will be eliminated and ϕE through hole will be provided.

D	D1	D2	D3	Z	P*1	E*1	Recommened value	G*1	H	T	R	V	F		
10	11	19	7	T-Z≥5*2 When D=10, 13 T-Z≥4*2	P≤ 80	15 to 60 in 1 mm steps provided E≥ D+5	19 22 24	See table below	8	25	10	16	22		
13	14	21	9		P≤100		23 27 29			10	25	15	16	27	
											30	15	21	27	
									25		10	15	14	30	
16	17	27	11		P≤110		28 37		14	30	15	20	19	35	
										35	20	25	24	40	
										30	15	20	15	35	
20	21	31	13		P≤130		34 42		14	35	20	25	20	40	
										45	25	30	30	45	
										45	35	30	30	50	
25	26	36	17		P≤140		41 52		18	35	20	25	20	45	
										45	25	30	30	50	
										45	35	30	35	55	
										18	50	30	35	31	60
											60	35	40	41	65

*1. Specify P, E and G as necessary.

$P+G+5 \leq A$ (this formula is not a guarantee of strength)

*2. This formula is not a guarantee of strength.

※ Mold opening stroke between Plate T and Plate R

$S1=Z+V-T$ $Z=T+S1-V$ $V=T+S1-Z$







※ Mold opening stroke between Plate R and Plate A

$S2=L-A+P$ $P=S2+A-L$ $L=S2+A-P$

※ If the distance from the head of puller bolt to the next plate is $L0 < 1$, the $\phi D2$ through holes will be provided in the next plate as well.

Relation of counterbore diameter E and depth G

E	G max
15 to 19	$G \leq 50$
20 to 27	$G \leq 60$
28 to 34	$G \leq 80$
35 to 44	$G \leq 90$
45 to 60	$G \leq 100$

Position code **S021**

Position code **S023**

Position code **S041**

Position code **S022**

Position code **S024**

Position code **S042**


L dimension of puller bolt M-PBA

D	L														
10	80	90	100	110	120	130	140	150	160	180					
13	80	90	100	110	120	130	140	150	160	170	180	200			
16			100	110	120	130	140	150	160	170	180	190	200		
20						130	140	150	160	170	180	190	200	220	240
25								150	160	170	180	190	200	220	240

Catalog No.	D	L	Z	P	E	G	Position code	A	B	X	Y	Optional spec.
PPBA1	10	Select from above table	In 1 mm steps	In 1 mm steps	See left table	Omit this if unnecessary	S021	In 1 mm steps	—	In 1 mm steps	In 1 mm steps	PSR CCE EHD MHD CRD EPAT See page 149
	13		S022				—	In 1 mm steps				
	16		See left table				S023		In 1 mm steps	When X=KW/2, omit X	When Y=KL/2, omit Y	
	20						S024					
	25						S041 S042					

How to order

Catalog No. — D — L — Z — P — E — G — Position code

PPBA1 — D13 — L200 — Z21 — P5 — E29 — G30 — S041

— A — B — X — Y — Optional spec.

— A160 — B140 — X100 — Y150 — PSR/TF25/LS45

Added Puller Bolts — AH2/A2


Install M-PBAH and M-PBA . For details on installation specifications, see pages 148 to 153.

Puller bolts M-PBAH → P.310, M-PBA → P.313

Application Mold bases D·E series, F·G series, H series (excluding the types with Plate S from each series)

Catalog No. PPBAH2 Install M-PBAH **Ground shank type**

Catalog No. PPBA2 Install M-PBA



Diameter in the case of installing additional plates:

Additional plate specification → P.38

Diameter of Plate O, Plate N, Plate W and Plate X → $\phi D2$

If installing either of additional plates of Plate Q or Plate V, order with additional processing codes is not allowed. Please order with drawings, etc.

D	D1	D2	J ^{*1}	P ^{*1}	H		H1
					Catalog No. PPBAH2	Catalog No. PPBA2	
10	11	19	$J \leq 50$	$P \leq 50$	8	8	12.5
13	14	21	$J \leq 60$	$P \leq 60$	8	10	16
16	17	27	$J \leq 60$	$P \leq 60$	13	14	20.5
20	21	31	$J \leq 80$	$P \leq 80$	13	14	25
25	26	36	$J \leq 90$	$P \leq 90$	18	18	32

*1. Specify J and P as necessary.

$J+5 \leq A$ $P+5 \leq B$ (this formula is not a guarantee of strength)

※ Regardless of the length of puller bolts, $\phi D2$ holes through to Plate T, Plate L will be provided.







※ Mold opening stroke between Plate A and Plate B

$S3=L+J+P-A-B$ $L=S3+A+B-J-P$ $J=S3+A+B-L-P$ $P=S3+A+B-L-J$

L dimension of puller bolts																												
D	L																											
10	50	60	70	80	90	100	110	120	130	140	150	160	170	180														
13		60	70	80	90	100	110	120	130	140	150	160	170	180	190	200	210	220	230	240	250	260	280					
16						100	110	120	130	140	150	160	170	180	190	200	210	220	230	240	250	260	280	300				
20									120	130	140	150	160	170	180	190	200	210	220	230	240	250	260	280	300	350		
25												150	160	170	180	190	200	210	220	230	240	250	260	280	300	350		

※ The dimensions written in red are applied to **Catalog No. PPBAH2** only.

※ The dimensions written in blue are applied to **Catalog No. PPBA2** only.

Position code **S021**

Position code **S023**

Position code **S041**

Position code **S022**

Position code **S024**

Position code **S042**


Catalog No.	D	L	J	P	Position code	A	B	X	Y	Optional spec.
PPBAH2	10	Select from left table	In 1 mm steps		S021	In 1 mm steps	—	In 1 mm steps	In 1 mm steps	EHD MHD EPAT See page 149
	13		See left table		S022	—	In 1 mm steps	When X=KW/2, omit X	When Y=KL/2, omit Y	
PPBA2	16				Omit this if unnecessary					
	20		S024							
	25		S041 S042							

How to order

Catalog No. — **D** — **L** — **J** — **P** — **Position code** — **A** — **B** — **X** — **Y**
 PPBAH2 — D16 — L160 — J15 — P30 — S041 — A200 — B170 — X125 — Y175
 — **Optional spec.**
 — MHD/C/Z50

Added Puller Bolts — Standard Position

The puller bolt specification of standard F series mold base has been now established.

For details on the installation specifications, see pages 148 to 153.

Application F series mold bases


(The use of this specification is not allowed when changing thickness of Plate T and Plate R (see pages → P.164 to 167))

Catalog No. PPBAHS


Install puller bolt M-PBAH and M-PBCH **Ground shank type**

Catalog No. PPBAS

Install puller bolt M-PBA and M-PBC



When providing counterbore holes for springs and those for adjusting stroke, specify them by using the instruction method shown in pages 164 to 167.



Diameter in the case of installing additional plates:

Diameter of Plate O and Plate N → $\phi D1$ shown in the chart on P.164

Diameter of Plate Q, Plate V, Plate W and Plate X → $\phi D2$ shown in the chart on P.164.

Additional plate specifications → P.38

L dimension of puller bolts

D	L																												
10	50	60	70	80	90	100	110	120	130	140	150	160	170	180															
13		60	70	80	90	100	110	120	130	140	150	160	170	180	190	200	210	220	230	240	250	260	280						
16						100	110	120	130	140	150	160	170	180	190	200	210	220	230	240	250	260	280	300					
20								120	130	140	150	160	170	180	190	200	210	220	230	240	250	260	280	300	350				
25											150	160	170	180	190	200	210	220	230	240	250	260	280	300	350				

※ The dimensions written in red are applied to **Catalog No. PPBAHS** only.

※ The dimensions written in blue are applied to **Catalog No. PPBAS** only.


Catalog No.	L	Z	Optional spec.	Remarks
PPBAHS	Select from above table	In 1 mm steps Thickness of plate T - $Z \geq 5$ *1	EHD MHD CRD CRM *2 EPAT See page 149	*1. This formula is not a guarantee of strength. *2. Applies to Catalog No. PPBAHS . ※ Mold opening stroke between Plate T and R $S1 = Z + V$ - Thickness of Plate T Z = thickness of Plate T + $S1 - V$ V = thickness of Plate T + $S1 - Z$ ※ Mold opening stroke between Plate R and A $S2 = L$ - thickness of Plate A, $L = S2$ + thickness of Plate A
PPBAS		When D=10 or 13, Thickness of Plate T - $Z \geq 4$ *1		

How to order


Catalog No. — **L** — **Z** — **Optional spec.**
PPBAHS — **L180** — **Z25** — **EHD/L**

Puller bolt standard position specification

Two-piece spec.



Four-piece spec.



※ X=KW/2, Y=KL/2

Nominal dimension	2-piece spec.	4-piece spec.		D	Plate T thickness	Plate R thickness	V *3	Nominal dimension	4-piece spec.		D	Plate T thickness	Plate R thickness	V *3						
	A	A	B						A	B										
1113	86	—	—	10	25	10	15 (16)	2730	215	116	20	35	20	(20)						
1313	106							2735		166										
1315								2740		216										
1515	120			2750		316														
1518	—	120	48	13		15	15 (14)	2930	235	116					25					
1520			68					2935		166										
1523			98					2940		216										
1525			118					3030		100										
1530			168					3032		120										
1818			145					—		—						30	15	20 (19)	3035	240
1820	145	48	3040				200													
1823		78	3045				244													
1825		98	3050		294															
1830		148	3335		150															
1835		198	3340		200															
2020		160	42		3345		244	270												
2023	72		3535	144	285															
2025	92		3540	194																
2030	142		3545	244		25														
2035	192		3550	272			50													
2040	242		3555	322					30											
2045	—		185	292				330		172	35	30	(31)							
2323				72	4040					222										
2325				92	4045					272										
2327				106	4050	322														
2330				136	4055	370	60			35				40	(41)					
2335				186	4545	204														
2340	236	4550	254																	
2525	200	70	4555	304	410	40		40	(41)											
2527		90	4560	354																
2530		120	5050	254																
2535		170	5060	354																
2540		216	5070	454																
2545		266																		
2550		316																		




*3. The dimensions in parentheses () are applied to **Catalog No. PPBAS**.

Added Tension Links — Overview ①

Tension link installation method




Two types of tensions links can be installed in mold bases.

Tension link M-HLA



W	19	25	32	38
W1	11	14	17	21
T	9	9	9	12
S	60 to 200 In 10 mm steps	80 to 250 In 10 mm steps	100 to 300 In 10 mm steps	100 to 300 In 10 mm steps
N	14.5	17	18.5	20.5
La	S+29	S+34	S+37	S+41

Tension link M-HLB




W	19	25	32	38
W1	11	14	17	21
T	9	9	9	12
S	50 to 170 In 10 mm steps	50 to 200 In 10 mm steps	80 to 200 In 10 mm steps	100 to 200 In 10 mm steps
N	14.5	17	18.5	20.5
E	20	23	30	33
Q	24	28	32	38
d	10.5	13.5	16.5	20.5
La	S+49	S+57	S+67	S+74

Specification of Bolts for Tension Link


Bolts for tension links are available in three types shown in the chart below:

Bolt code BT1




Link W DIMM	19	25	32	38
D	10	13	16	20
D1	16	18	24	28
B1	13	13	13	16
B2	21	23	27	30
D2	10	13	16	20
M	M8	M10	M12	M16
F	15	16	20	26
K max	22	24	29	36
M-PBB	10×13	13×13	16×13	20×16

Bolt code BT2



Link W DIMM	19	25	32	38
D	10	13	16	20
D1	13	16	19	23
B1	12	12	12	15
B2	22	24	26	31
D2	10	13	16	20
M	M6	M8	M10	M12
F	11	16	16	23
K max	19	23	24	32
Bolt	M6×25	M8×30	M10×30	M12×40
M-HRA	10	13	16	20


Bolt code BT3



Link W DIMM	19	25	32	38
D	10	13	16	20
D1	16	19	22	26
B1	17	17	17	20
B2	23	25	27	32
B3	11	11	11	14
D2	16	19	22	26
M	M6	M8	M10	M12
F	15	20	20	22
K max	23	27	28	31
Bolt	M6×30	M8×35	M10×35	M12×40
M-HRB	10	13	16	20

※ This bolt cannot be used for tension link M-HLB.

Request for setting for bolt position



Please set the position of the bolt hole so that the N1 and N2 dimensions shown in the left chart become 1.5 mm or more.

$$N1 \geq 1.5$$

$$N2 \geq 1.5$$

※ This value is not a guarantee of strength.

Added Tension Links — Overview ②




Optional specification (specify only when necessary)

Option code

Specification


Parts
Installation

Added Tension Links — Overview ②

MTZ
(T 板に加工)

MLZ
(L 板に加工)

If the clamping plate is machined, Z dimension of the plate must be measured from the surface.
Clamp machining → P.238

Produce oval holes in Plate T and Plate L for allowing clearance around the tension link.



W	19	25	32	38
G	32	38	45	54
T	9	9	9	12
V	13	13	13	16
C	Bolt code BT1, BT2	5	5	6.5
	Bolt code BT3	6.5	6.5	8
Z	Z ≤ 55			Z ≤ 65
	※ Z → Specify in 1 mm steps ※ Z ≤ Thickness - 5 If Z = thickness, however, through holes are provided.			



※ The dimensions of U ≥ 5, J ≥ 5 are required.

How to specify:

For Plate T: **MTZ** [Z DIMM]
[e.g.] MTZ18

For Plate L: **MLZ** [Z DIMM]
[e.g.] MLZ10


Relation of protrusion of Plate T and L and oval holes for clearance


EPAT


Only the holes for installing tension links are provided.

Mold opening stroke of tension link

In the case of using tension link M-HLA



Mold opening stroke $S1$

$$S1 = S - HA - HB + \alpha$$

α : The radius (R) of tension link's long hole and the radius of the bolt for the tension link are different in size. Thus, the difference in radius affects the amount of the mold opening


W	19	25	32	38
N	14.5	17	18.5	20.5

Features

- ① Supports the molds with larger mold opening stroke
- ② Operating noise is slightly high.
- ③ Does not allow increasing the mold opening and closing speed very much.

Reference: Yuichi Fukushima, "Comprehensible plastic injection molding design" The Nikkan Kogyo Shinbunsha

In the case of using tension link M-HLB



Mold opening stroke $S1$

$$S1 = S + E - HA - HB + \alpha$$

α : The radius (R) of tension link's long hole and the radius of the bolt for the tension link are different in size. Thus, the difference in radius affects the amount of the mold opening

W	19	25	32	38
E	20	23	30	33
N	14.5	17	18.5	20.5

Features

- ① One end of the link is secured with bolt, thereby ensuring reliable operations.
- ② Not suited for molds with larger mold opening stroke
- ③ Operating noise is low.
- ④ Realizes increased mold opening and closing speed.

Reference: Yuichi Fukushima, "Comprehensible plastic injection molding design" The Nikkan Kogyo Shinbunsha


Added Tension Link M-HLA

Install tension link M-HLA. For details on the installation specifications, see pages 172 to 175.

Tension link M-HLA → P.316


Application Mold bases

Catalog No. PHLA



Tension link	Bolt code
	Bolt code BT1
	Bolt code BT2
	Bolt code BT3

Position of bolt holes for tension link




※ For bolt holes for tension link, specify the code of plates in which to machine bolt holes and H dimensions that locate the position of the holes from the top surface side.


※ The first bolt and the second bolt are of the same type.

Catalog No.	Tension link.		Bolt code	Position code	P	First bolt		Second bolt		Optional spec.
	W	S				Plate code	H	Plate code	H	
PHLA	19	Select from page 172	BT1 BT2 BT3	SS02AC SS02BD	—	T (Plate T) R (Plate R) A (Plate A) S (Plate S) B (Plate B) U (Plate U) L (Plate L)	In 0.5 mm steps	T (Plate T) R (Plate R) A (Plate A) S (Plate S) B (Plate B) U (Plate U) L (Plate L)	In 0.5 mm steps	MTZ MLZ EPAT See page 174
	25			SS02ACL SS02ACR SS02BDL SS02BDR SS04ACP SS04BDP	In 1 mm steps	Additional plate N (Plate N) O (Plate O) Q (Plate Q) V (Plate V) W (Plate W) X (Plate X) Additional plate specifications ↓ P.38		Additional plate N (Plate N) O (Plate O) Q (Plate Q) V (Plate V) W (Plate W) X (Plate X) Additional plate specifications ↓ P.38		
	32									
	38									


Position code **SS02AC**




Position code **SS02ACL**




Position code **SS02ACR**




Position code **SS02BD**




Position code **SS02BDL**




Position code **SS02BDR**



Position code **SS04ACP**



Position code **SS04BDP**



How to order

Catalog No. — **W** — **S** — Bolt code — Position code — **P**

PHLA — **W25** — **S150** — **BT2** — **SS04BDP** — **P170**

First bolt Plate code/H	Second bolt Plate code/H	Optional spec.
A/H20	B/H15	MTZ15



Added Tension Link M-HLB

Install tension link M-HLB. For details of the installation specifications, see pages 172 to 175.


Tension Link M-HLB → P.317

Application Mold bases

Catalog No. **PHLB**











Position of bolt holes for tension link



※ For bolt holes for tension link, specify the code of plates in which to machine bolt holes and H dimensions that locate the position of the holes from the top surface side.

※ The first bolt and the second bolt are of the same type.

Catalog No.	Tension link.		Bolt code	Position code	P	First bolt		Second bolt		Optional spec.
	W	S				Plate code	H	Plate code	H	
PHLB	19 25 32 38	Select from page 172	BT1 BT2	SS02AC SS02BD	—	T (Plate T) R (Plate R) A (Plate A) S (Plate S) B (Plate B) U (Plate U) L (Plate L)	In 0.5 mm steps	T (Plate T) R (Plate R) A (Plate A) S (Plate S) B (Plate B) U (Plate U) L (Plate L)	In 0.5 mm steps	MTZ MLZ EPAT See page 174
				SS02ACL SS02ACR SS02BDL SS02BDR SS04ACP SS04BDP	In 1 mm steps	Additional plate N (Plate N) O (Plate O) Q (Plate Q) V (Plate V) W (Plate W) X (Plate X) Additional plate specifications ↓ P.38		Additional plate N (Plate N) O (Plate O) Q (Plate Q) V (Plate V) W (Plate W) X (Plate X) Additional plate specifications ↓ P.38		

Position code **SS02AC**

Position code **SS02ACL**

Position code **SS02ACR**

Position code **SS02BD**

Position code **SS02BDL**

Position code **SS02BDR**

Position code **SS04ACP**

Position code **SS04BDP**


How to order

Catalog No. — **W** — **S** — Bolt code — Position code — **P**
PHLB — **W19** — **S100** — **BT1** — **SS02BDL** — **P120**

First bolt Plate code/H	Second bolt Plate code/H	Optional spec.
A/H15	B/H20	MLZ15


Added PL Pullers

Install PL Pullers.


PL Pullers M-PLLA → P.320

Application Mold bases D · E series, F · G series, H series (excluding the types with Plate S from the all the series)


Catalog No. PPLLA1




Catalog No. PPLLA2



Catalog No. PPLLA3



Catalog No. PPLLA4



D	H min	H1	M	L	F	Scope of application			
						PPLLA1	PPLLA2	PPLLA3	PPLLA4
10	20	25	M5	7	12	20 ≤ A ≤ 60	20 ≤ B ≤ 60	A ≥ 35	B ≥ 35
12	22 *1	27	M6	12	17	20 ≤ A ≤ 80	20 ≤ B ≤ 80	A ≥ 40	B ≥ 40
13									
16	29 *2	34	M8	11.5	16	30 ≤ A ≤ 100	30 ≤ B ≤ 100	A ≥ 50	B ≥ 50

*1. When A or B=20, H=20

*2. When A or B=30, H=30

※ For D, boring is used.


Optional spec (specify only when necessary)

Option code


Specification

Only holes for installing PL Pullers are machined.


EPAT



Threaded hole specification









Blind hole spec.



Through hole spec.

The threaded hole for PL Pullers will be blind hole or through hole depending on N dimension.

M	F	K max	Blind hole spec	Through hole spec.
M5	12	18	N ≥ 24	N < 24
M6	17	24	N ≥ 30	N < 30
M8	16	22	N ≥ 28	N < 28

Position code **S021**

Position code **S023**

Position code **S041**

Position code **S022**

Position code **S024**

Position code **S042**


Catalog No.	D	Position code	A	B	X	Y	Optional spec.
PLLA1	10	S021	In 1 mm steps	—	In 1 mm steps	In 1 mm steps	EPAT
PLLA2	12	S022	—	—	When X=KW/2, omit X	When Y=KL/2, omit Y	
PLLA3	13	S023	In 1 mm steps	In 1 mm steps			
PLLA4	16	S024					
		S041					
		S042					


How to order

Catalog No. — **D** — **Position code** — **A** — **B** — **X** — **Y** — **Optional spec.**
PLLA1 — **D16** — **S041** — **A200** — **B180** — **X125** — **Y150**

Added Mold Opening Prevention Plates — Overview


Mold opening prevention plate installation specification

Install mold opening prevention plate in mold bases so that the mold does not open during transportation or storage.




Mold opening prevention plate M-OPB					Mold opening prevention plate M-OPC		
W	16	22	25	38	W	16	20
S	20 30 40 50 60	20 30 40 50 60 70	30 50 70 90	40 60 80 100	S	15 20 30 40 50 60 70	80 90 100
La	S+20	S+30	S+30	S+40	La	S+20 (When S=15, La=30)	S+20
T	6	9	12	12	T	5	5
M	M6	M8	M10	M12	M	M6	M8
F	12	16	20	24	F	12	16
K max	20	23	28	33	K max	20	23
Bolt	M6×15	M8×20	M10×30	M12×35	Bolt	M6×15	M8×20
Safety color	Black				Safety color	Red, yellow and black	
How to order ➡ P.184					How to order ➡ P.184		

Optional specification (specify only when necessary)

Option code	Specification
EPAT	 Only holes for installing mold opening prevention plate are machined.

Handling Precautions



Suspending a mold as shown above is dangerous. Doing so causes the mold opening prevention plate to be subjected to an excessive load of the mold and may lead to a breakage or injury. Never use the product in such a condition.

Added Mold Opening Prevention Plate (at One Place)

Install mold opening prevention plate M-OPB, M-OPC.

For details on the installation specification, see pages 182 to 183.


M-OPB → P.321 M-OPC → P.321

Application Mold bases, cavity retainer sets, cavity retainer sets for die cast

Catalog No. **POPB** Install M-OPB

Catalog No. **POPC** Install M-OPC

Position of bolt holes for mold opening prevention plate



Catalog No.	Mold opening prevention plate			Position code	L or R	First bolt		Second bolt		Optional spec.			
	W *1	S	Safety color *2			Plate code	H	Plate code	H				
POPB (M-OPB)	16	Select from page 182	R (Red) Y (yellow) N (Black)	SS01A	—	T (Plate T)	Additional plate N (Plate N) O (Plate O) Q (Plate Q) V (Plate V) W (Plate W) X (Plate X) Additional plate specifications ↓ P.38	T (Plate T)	Additional plate N (Plate N) O (Plate O) Q (Plate Q) V (Plate V) W (Plate W) X (Plate X) Additional plate specifications ↓ P.38	In 0.5 mm steps	EPAT See page 182		
	20			SS01B		R (Plate R)		O (Plate O)				R (Plate R)	O (Plate O)
	22			SS01C		A (Plate A)		Q (Plate Q)				A (Plate A)	Q (Plate Q)
	25			SS01D		S (Plate S)		V (Plate V)				S (Plate S)	V (Plate V)
POPC (M-OPC)	25			SS01AL	In 1 mm steps	B (Plate B)	W (Plate W)	B (Plate B)	W (Plate W)			In 0.5 mm steps	
	25			SS01CL		U (Plate U)	X (Plate X)	U (Plate U)	X (Plate X)				
	38			SS01DL		L (Plate L)		L (Plate L)					
				SS01AR									
				SS01BR									
				SS01CR									
				SS01DR									

*1. Catalog No. **POPB** is available in W=16, 22, 25, 38. Catalog No. **POPC** is available in W=16, 20.

*2. The safety color available for Catalog No. **POPB** is N (Black) only.

How to order


Catalog No. — W — S — Safety color — Position code — L or R

POPC — W16 — S40 — R — SS01AL — L70


First bolt — Second bolt — Optional spec.
Plate code/H — Plate code/H

A/H30 — B/H20


Position code **SS01A**




Position code **SS01AL**




Position code **SS01AR**




Position code **SS01B**




Position code **SS01BL**




Position code **SS01BR**




Position code **SS01C**




Position code **SS01CL**




Position code **SS01CR**




Position code **SS01D**



Position code **SS01DL**



Position code **SS01DR**



Added Mold Opening Prevention Plates (at Two or Four Place)

Install mold opening prevention plate M-OPB, M-OPC .

For detailed specifications, see pages 182 to 183


Mold opening prevention plate M-OPB ➔ P.321 M-OPC ➔ P.321

Application Mold bases, cavity retainer sets, cavity retainer sets for die cast

Catalog No. **POPB** Install M-OPB

Catalog No. **POPC** Install M-OPC

Position of bolt holes for mold opening prevention plate



※ For bolt holes for mold opening prevention plate, specify the code of plates in which to machine bolt holes and H dimensions that locate the position of the holes from the top surface side.

Catalog No.	Mold opening prevention plate			Position code	P	First bolt		Second bolt		Optional spec.
	W ^{*1}	S	Safety color ^{*2}			Plate code	H	Plate code	H	
POPB (M-OPB)	16	Select from page 182	R (Red) Y (yellow) N (Black)	SS02AC	—	T (Plate T)	In 0.5 mm steps	T (Plate T)	In 0.5 mm steps	EPAT See page 182
	20			SS02BD		R (Plate R)		R (Plate R)		
	22			SS04		A (Plate A)		A (Plate A)		
POPC (M-OPC)	25			SS02ACL	In 1 mm steps	S (Plate S)		S (Plate S)		
	25			SS02ACR		B (Plate B)		B (Plate B)		
	25			SS02BDL		W (Plate W)		W (Plate W)		
	25			SS02BDR		U (Plate U)		U (Plate U)		
	38			SS04ACP		L (Plate L)		L (Plate L)		
				SS04BDP		Additional plate specifications ↓ P.38		Additional plate specifications ↓ P.38		

*1. Catalog No. **POPB** is available in W=16, 22, 25, 38. Catalog No. **POPC** is available in W=16, 20.

*2. The safety color available for Catalog No. **POPB** is N (Black) only.


How to order

Catalog No. — W — S — Safety color — Position code — P


POPC — **W16** — **S40** — **R** — **SS02ACL** — **P200**

— First bolt Plate code/H — Second bolt Plate code/H — Optional spec.
— **A/H30** — **B/H20**


Position code **SS02AC**




Position code **SS02ACL**




Position code **SS02ACR**




Position code **SS02BD**




Position code **SS02BDL**




Position code **SS02BDR**




Position code **SS04ACP**



Position code **SS04BDP**



Position code **SS04**




Added Base Spacers®

Install base spacers.


Base spacer M-BSA ➔ P.394

Application Mold bases

Catalog No. PBSA



Base spacers are not designed to suspend molds. Never use the product in the way shown in the chart below.



※ Base spacers are installed in Plate T and Plate L.

※ The order on the installation can be made separately for either Plate T or Plate L, or together for both of them at a time.

D	M	F	K max	Mounting bolt
19	M6	12	20	M6 × 50
24	M8	16	23	M8 × 50
29	M10	20	28	M10 × 50
34	M12	24	33	M12 × 50

Catalog No.	Plate code	D	Position code	P	L	R	TH* ¹	LH* ¹	Optional spec.
PBSA	T (Plate T) L (Plate L) TL (Plate T, Plate L)	19 24 29 34	SS02AP	In 1 mm steps	—	—	In 0.5 mm steps	In 0.5 mm steps	EPAT* ²
			SS02BP						
			SS02CP						
			SS02DP						
		SS02AZ	—	In 1 mm steps	In 1 mm steps				
		SS02BZ							
		SS02CZ							
		SS02DZ							

*1. When specifying Plate code T, specify the TH dimension as well. No need to specify LH. When specifying plate code L, specify the LH dimension as well. No need to specify TH. When specifying Plate code TL, specify both TH and LH.

*2. Specify this option when you specify on only machining of holes with no installation of parts.

How to order


Catalog No. — Plate code — D — Position code — P — L — R — TH — LH

PBSA — TL — D19 — SS02CP — P150 — TH10 — LH10


PBSA — L — D24 — SS02CZ — L100 — R120 — LH15

— Optional spec.


Position code **SS02AP**




Position code **SS02BP**




Position code **SS02CP**




Position code **SS02AZ**




Position code **SS02BZ**




Position code **SS02CZ**



Position code **SS02DP**



Position code **SS02DZ**



※ Base Spacer is a registered trademark of Futaba Corporation.

Machining

Channels for Water, Oil and Heater

Channels for Water, Oil and Heater — Overview	192	Channels for Water, Oil and Heater —	
Channels for Water, Oil and Heater — 1 Hole	194	Entrance Counterbore Holes.....	200
Channels for Water, Oil and Heater — 2 Holes	196	Channels for Water, Oil and Heater —	
Channels for Water & Oil — Circulation Type.....	198	One Side Pipe Thread Holes.....	202

Rough Pockets Machining

Rough Pockets Machining — Overview	204	Pocket Gas Cutting — Rectangular & Circular Pocket.....	212
Rough Pockets Machining — Rectangular with Rounded		Rough Pockets Machining — Through Groove.....	214
Corners (Inside Corner R).....	206	Rough Pockets Machining — Slide Core Groove.....	216
Rough Pockets Machining — Rectangular with Rounded		Rough Pockets Machining — Blind Groove (Inside Corner R)...	218
Corners (Outside Corner R).....	208	Rough Pockets Machining — Blind Groove (Outside Corner R) ..	220
Rough Pockets Machining — Circular Pocket.....	210		

Threaded Holes for Eyebolt (Side Surface Threaded Holes)

Added Threaded Holes for Eyebolt		Added Threaded Holes for Eyebolt	
(Side Surface Threaded Holes) — Overview	222	(Side Surface Threaded Holes) (For C-Plate).....	228
Added Threaded Holes for Eyebolt		Added Threaded Holes for Eyebolt	
(Side Surface Threaded Holes) — 1 Hole	224	(Side Surface Threaded Holes) — Chamfering	230
Added Threaded Holes for Eyebolt		Added Eye Bolts	231
(Side Surface Threaded Holes) — 2 Holes or 4 Holes	226	Omit Threaded Holes for Standard Eyebolt.....	232
		Added Side Surface Threaded Holes with Counterbore	234

Ejector Rod Holes Addition or Omission

Added or Omitted Ejector Rod Holes.....	236
---	-----

Clamp Slot Addition (For Clamping Plate)

Added Clamp Slot (For Clamping Plate).....	238
--	-----

Addition of Clamping Hole or U Ditch for Clamping

Added Clamping Holes or U Ditch for Clamping	240
--	-----

Clamp Slot Addition (For A-Plate or B-Plate)

Added Clamp Slot (For A-Plate or B-Plate).....	241
--	-----




“Additional processing specifications” are provided to show customers how to advise us on additional processing. When designing molds, various conditions such as strength and accuracy need to be taken into account. Therefore, we shall not be responsible or liable for any loss or damage of any kind incurred as a result of, or in connection with your use of additional processing specifications or selection of mold bases.

Channels for Water, Oil and Heater — Overview

We perform deep-hole drilling of temperature control holes such as water channels, oil channels and cartridge heater insertion holes, etc. using special machines and tools.

※ Channels for Water, Oil and Heater ➡ How to order P.194 - 199

Hole diameter and drilling depth

Column 1 *1			Column 2 *1			Reference diagram	
Hole dia. D	Machining limit of blind hole Z	Machining limit of through hole L *2	Hole dia. D	Machining limit of blind hole Z	Machining limit of through hole L *2		
6.0	Z ≤ 600	L ≤ 1200	3.5	Z ≤ 300	L ≤ 600		
6.4			5.0				
7.0			5.1				
8.0			5.2				
8.1			5.5	Z ≤ 600	L ≤ 1200		
8.2			6.3				
8.3			9.5				
8.5			9.8				
9.6			10.3	Z ≤ 1000	L ≤ 1500		
10.0	Z ≤ 1000	L ≤ 1500	11.3	Z ≤ 600	L ≤ 1200		
10.1	Z ≤ 600	L ≤ 1200	12.0	Z ≤ 1000	L ≤ 1500		
10.2			12.5	Z ≤ 600	L ≤ 1200		
10.5			13.0	Z ≤ 1000	L ≤ 1500		
11.0	Z ≤ 1000	L ≤ 1500					
11.5	Z ≤ 600	L ≤ 1200	13.1	Z ≤ 600	L ≤ 1200		
12.1	Z ≤ 1000	L ≤ 1500	13.5				
12.2			14.5				
12.3			15.3	Z ≤ 1000	L ≤ 1500		
12.7			16.0				
14.0			16.5	Z ≤ 600	L ≤ 1200		
14.2			18.0	Z ≤ 1000	L ≤ 1500		
15.1			20.3	Z ≤ 600	L ≤ 1200		
16.1							

*1. Select hole diameter from Column 1. Select from Column 2 as necessary. For hole diameter not listed above, consult our sales office.


*2. The machining limits of through holes are calculated supposing that the holes are drilled from both sides and connected through in the center. Through hole can be drilled from both sides or from one side. If drilling from one side is desired, consult our sales office.

※ The shape of the bottom of the blind hole may not be isosceles triangle shown in the above diagram.

Machining region of channels for water, oil and heater

To prevent the interference of channels for water, oil and heater with other holes machined, we have set a machining region only as a guide as shown in the table below.

Please take into account when designing molds. These values are provided only as a guide and do not represent a guarantee of influence on accuracy and strength.



Do not perform other machining work within the area.


Machining region of channels for water, oil and heater

TP	N1	N2	N3
Rc1/8 Rp1/8	15	20	D+4
Rc1/4 Rp1/4	19	20	
Rc3/8 Rp3/8	22	25	

Relation of hole diameter D and pipe threads

TP	D max
Rc1/8 Rp1/8	8.5
Rc1/4 Rp1/4	11.5
Rc3/8 Rp3/8	14.5

Matters to be noted when protrusion amount of clamping plate is not even (For how to specify, see pages 198 to 203)



The reference position of L and R dimensions is set at the center of mold plate as shown in the left chart.


※ If $L=R$ and $P=L+R$, then specify with P.

Channels for Water, Oil and Heater — 1 Hole

Drill temperature control holes such as water channels, oil channels and cartridge heater insertion holes, etc.

Use this option to specify a temperature control hole at one place at a time.

Application Mold bases, cavity retainer sets, cavity retainer sets for die cast



Frequently used diameter of water channel and oil channel

Water & oil hole dia. (D)	8	8.5	10	11.5
Pipe thread to use (TP)	Rc1/8 Rc1/4 Rp1/8 Rp1/4		Rc1/4 Rp1/4	


※ Other hole diameter, pipe thread → P.192

Frequently used diameter of heater hole


Heater hole dia. (D)	8.1	8.2	10.1	10.2	12.1	12.2
----------------------	-----	-----	------	------	------	------

※ Other hole diameter → P.192


Catalog No. MHH1AKL




Catalog No. MHH1AKR




Catalog No. MHH1BKL




Catalog No. MHH1BKR




Catalog No. MHH1ATL




Catalog No. MHH1ATR




Catalog No. MHH1BTL




Catalog No. MHH1BTR




Catalog No. MHH1CTL




Catalog No. MHH1CTR





Catalog No. MHH1DTL



Catalog No. MHH1DTR



Specifying dimensions in thickness direction



Temp. Control hole	Catalog No.	Plate code	D	Z	Thread code *1 (TP)	L or R *2	H
Through hole	MHH1AKL MHH1AKR MHH1BKL MHH1BKR	T (Plate T) U (Plate U) R (Plate R) E (Plate E) A (Plate A) F (Plate F) S (Plate S) L (Plate L) B (Plate B)	Frequently used diameter of water & oil hole 8 8.5 10 11.5	Specify plate length Machining depth limit → P.192	RC1/8 RC1/4 RC3/8 RP1/8 RP1/4 RP3/8	In 1 mm steps	In 0.5 mm steps
	MHH1ATL MHH1ATR MHH1BTL MHH1BTR MHH1CTL MHH1CTR MHH1DTL MHH1DTR	Additional plate N (Plate N) V (Plate V) O (Plate O) W (Plate W) Q (Plate Q) X (Plate X) Y (Plate Y) Additional plate spec. → P.38	Frequently used diameter of heater hole 8.1 8.2 10.1 10.2 12.1 12.2 Other diameter of hole → P.192	In 1 mm steps Machining depth limit → P.192	Omit if no pipe thread is necessary		

*1. Although PT and PS codes are conventionally used for the nominal dimensions of pipe threads, we use codes defined based on JIS Rc and Rp for our additional processing specification. The relation of our thread codes for additional processing specifications, JIS standard nominal codes and conventional nominal size code are as follows:

Type of pipe thread	Our thread code for additional machining spec.	JIS standard nominal code	Conventional nominal code
Pipe taper internal thread	RC	Rc	PT
Pipe parallel internal thread (parallel internal thread for pipe taper external thread)	RP	Rp	PS

*2. When placing one hole at the center, specify L0 for L or R

※ Detailed specification of channels for water, oil and heater → P.192

※ How to specify when protrusion amount is not even → P.193 ※ Pipe thread specification → P.440

How to order

Catalog No. — Plate code — D — Z — Thread code *3 (TP) — L or R — H

If specifying pipe thread MHH1AKL — A — D8.5 — Z250 — RC1/8 — L50 — H15

If not specifying pipe thread MHH1BTR — B — D11.5 — Z150 — — R90 — H23

*3. Omit if no pipe thread is necessary.

※ Entrance counterbore hole → P.200


※ One-side pipe threaded hole → P.202

Channels for Water, Oil and Heater — 2 Holes

Drill temperature control holes such as water channels, oil channels and cartridge heater insertion holes, etc.

Use this option to specify temperature control holes at two places at the same time.

Application Mold bases, cavity retainer sets, cavity retainer sets for die cast



Frequently used diameter of water channel and oil channel


Water & oil hole dia. (D)	8	8.5	10	11.5
Pipe thread to use (TP)	Rc1/8 Rc1/4 Rp1/8 Rp1/4		Rc1/4 Rp1/4	

※ Other hole diameter, pipe thread → P.192


Frequently used diameter of heater hole

Heater hole dia. (D)	8.1	8.2	10.1	10.2	12.1	12.2
※ Other hole diameter → P.192						


Catalog No. MHH2AKP




Catalog No. MHH2BKP




Catalog No. MHH2AKZ




Catalog No. MHH2BKZ




Catalog No. MHH2ATP




Catalog No. MHH2BTP




Catalog No. MHH2CTP




Catalog No. MHH2DTP




Catalog No. MHH2ATZ




Catalog No. MHH2BTZ




Catalog No. MHH2CTZ




Catalog No. MHH2DTZ



Specifying dimensions in plate thickness direction



Position of H dimension



※ H dimension must be specified with a dimension from top surface side direction.

Temp. Control hole	Catalog No.	Plate code	D	Z	Thread code ^{*1} (TP)	P	L	R	H
Through hole	MHH2AKP	T (Plate T) U (Plate U)	Frequently used diameter of water & oil hole 8 8.5 10 11.5	Specify plate length Machining depth limit → P.192	RC1/8 RC1/4 RC3/8 RP1/8 RP1/4 RP3/8	In 1 mm steps	—	—	In 0.5 mm steps
	MHH2BKP	R (Plate R) E (Plate E)				—	In 1 mm steps	In 1 mm steps	
	MHH2AKZ	A (Plate A) F (Plate F)				—	In 1 mm steps	In 1 mm steps	
	MHH2BKZ	S (Plate S) L (Plate L)				—	In 1 mm steps	In 1 mm steps	
Blind hole	MHH2ATP	B (Plate B)	Frequently used diameter of heater hole 8.1 8.2 10.1 10.2 12.1 12.2	In 1 mm steps Machining depth limit → P.192	Omit if no pipe thread is necessary	In 1 mm steps	—	—	In 0.5 mm steps
	MHH2BTP	Additional plate N (Plate N) V (Plate V)				—	In 1 mm steps	In 1 mm steps	
	MHH2CTP	O (Plate O) W (Plate W)				—	In 1 mm steps	In 1 mm steps	
	MHH2DTP	Q (Plate Q) X (Plate X) Y (Plate Y)				—	In 1 mm steps	In 1 mm steps	
	MHH2ATZ	Additional plate spec. → P.38	Other diameter of hole → P.192			—	In 1 mm steps	In 1 mm steps	
	MHH2BTZ					—	In 1 mm steps	In 1 mm steps	
	MHH2CTZ								
	MHH2DTZ								

*1. Although PT and PS codes are conventionally used for the nominal dimensions of pipe threads, we use codes defined based on JIS Rc and Rp for our additional processing specification. The relation of our thread codes for additional processing specifications, JIS standard nominal codes and conventional nominal size code are as follows:

Type of pipe thread	Our thread code for additional machining spec.	JIS standard nominal code	Conventional nominal code
Pipe taper internal thread	RC	Rc	PT
Pipe parallel internal thread (parallel internal thread for pipe taper external thread)	RP	Rp	PS

※ Detailed specification of channels for water, oil and heater → P.192

※ How to specify when protrusion amount is not even → P.193 ※ Pipe thread specification → P.440

How to order

	Catalog No.	Plate code	D	Z	Thread code ^{*2} (TP)	P	L
If specifying pipe thread	MHH2AKP	A	D8.5	Z250	RC1/8	P110	
If not specifying pipe thread	MHH2BTZ	B	D11.5	Z150			L60
		R		H			
				H15			
		R40		H23			

*2. Omit if no pipe thread is necessary.

※ Entrance counterbore hole → P.200


※ One-side pipe thread hole → P.202

Channels for Water & Oil – Circulation Type

Drill temperature control holes such as water channels, oil channels and cartridge heater insertion holes, etc.

Use this option to specify temperature control holes of circulation type.


Application Mold bases, cavity retainer sets, cavity retainer sets for die cast




Frequently used diameter of water channel and oil channel

Water & oil hole dia. (D)	8	8.5	10	11.5
Pipe thread to use (TP)	Rc1/8 Rc1/4 Rp1/8 Rp1/4		Rc1/4 Rp1/4	
※ Other hole diameter, pipe thread ➡ P.192				


Catalog No. MHH3AZP




Catalog No. MHH3BZP




Catalog No. MHH3CZP




Catalog No. MHH3DZP




Catalog No. MHH3AZZ




Catalog No. MHH3BZZ




Catalog No. MHH3CZZ




Catalog No. MHH3DZZ




※ When specifying F code for clamping plates, use the dimension from the end surface of the plate as shown below.



Specifying dimensions in plate thickness direction



Position of H dimension



※ H dimension must be specified with a dimension from top surface side direction.

Catalog No.	Plate code	D	Thread code *1 (TP)	P	L	R	F	H
MHH3AZP MHH3BZP MHH3CZP MHH3DZP	T (Plate T) U (Plate U) R (Plate R) E (Plate E) A (Plate A) F (Plate F) S (Plate S) L (Plate L) B (Plate B)	Frequently used diameter of water & oil hole 8 8.5 10 11.5	RC1/8 RC1/4 RC3/8 RP1/8 RP1/4 RP3/8	In 1 mm steps	—	—	In 1 mm steps	In 0.5 mm steps
MHH3AZZ MHH3BZZ MHH3CZZ MHH3DZZ	N (Plate N) V (Plate V) O (Plate O) W (Plate W) Q (Plate Q) X (Plate X) Y (Plate Y) Additional plate spec. → P.38	Other diameter of hole → P.192	Omit if no pipe thread is necessary	—	In 1 mm steps	In 1 mm steps		

*1. Although PT and PS codes are conventionally used for the nominal dimensions of pipe threads, we use codes defined based on JIS Rc and Rp for our additional processing specification. The relation of our thread codes for additional processing specifications, JIS standard nominal codes and conventional nominal size code are as follows:

Type of pipe thread	Our thread code for additional machining spec.	JIS standard nominal code	Conventional nominal code
Pipe taper internal thread	RC	Rc	PT
Pipe parallel internal thread (parallel internal thread for pipe taper external thread)	RP	Rp	PS

※ Detailed specification of channels for water, oil and heater → P.192

※ Machining depth limit → P.192

※ How to specify when protrusion amount is not even → P.193 ※ Pipe thread specification → P.440

How to order

Catalog No. — Plate code — D — Thread code^{*2} (TP) — P — L — R

If specifying pipe thread MHH3AZP — A — D8.5 — RC1/8 — P110

If not specifying pipe thread MHH3BZZ — B — D11.5 — L60 — R40

— F — H

— F150 — H15

— F130 — H23



*2. Omit if no pipe thread is necessary.

※ Entrance counterbore hole → P.200

Channels for Water, Oil and Heater — Entrance Counterbore Holes


Produce counterbore holes at the entrance of water channel, oil channel and heater holes as shown below:

Application Mold bases, cavity retainer sets, cavity retainer sets for die cast



Detailed view of A section

※ Provide N1 and N2 dimensions of 1.5 mm or more. This value is not a guarantee of strength.



If the interval of counterbore holes is small, they are overlapped.

TP	E	G
Rc (PT) 1/8 Rp (PS) 1/8	$13 \leq E \leq 30$	$5 \leq G \leq 30$
Rc (PT) 1/4 Rp (PS) 1/4	$16 \leq E \leq 30$	$5 \leq G \leq 30$
Rc (PT) 3/8 Rp (PS) 3/8	$20 \leq E \leq 30$	$5 \leq G \leq 30$
No pipe thread hole	$13 \leq E \leq 30$ provided $E \geq D + 2$	$5 \leq G \leq 30$

Form of temperature control hole		Specify water, oil and heater channel specifications	Entrance counterbore spec. code	E	G	Counterbore position code (see right page)
Through hole	Both side counterbore	Specify as shown in pages 194 to 197.	ZHC	In 1mm steps See above table	In 1mm steps See above table	—
	One side counterbore					AH BH CH DH
Blind hole	—	Specify as shown in pages 198 to 199.				—
Circulation type hole	—					—

How to order

Specify water, oil and heater channel specifications
(See pages 194 to 199)

MHH2AKP-A-D8.5-Z250-RC1/8-P110-H15

MHH2BKP-B-D8.5-Z300-RC1/8-P150-H30

Entrance counterbore hole spec. code

ZHC

ZHC

E

E22

E24

G

G20

G25

Counterbore position code

BH

How to order when combining the above with one side pipe thread hole

(One side pipe thread hole spec. → P.202)

Specify water, oil and heater channel specifications
(See pages 194 to 197)

MHH2AKP-A-D8.5-Z250-RC1/8-P110-H15

Specify entrance counterbore hole specification

ZHC-E22-G20-AH

Specify one side pipe thread hole specification
(See pages 202)

TAP-AH

Entrance counterbore specifications

Depending on the specifications of channels for water, oil and heater, counterbores are produced as shown below.









Through hole	Blind hole	Circulation type hole
Counterbores are produced on both sides of the holes.	Counterbores are produced on one side of holes.	Counterbores are produced at the entrance of the holes.



When producing counterbores on one side of through holes, please specify as follows:

One-side counterbore specifications


When producing entrance counterbores on one side of channels for water, oil and heater, specify the counterbore position code of the side on which to produce counterbores from among AH, BH, CH and DH (the following eight combinations are available).

1 hole		2 holes	
Catalog No. MHH1AKL Counterbore position code: <u>AH</u>  Counterbore position code: <u>CH</u>	Catalog No. MHH1AKR Counterbore position code: <u>AH</u>  Counterbore position code: <u>CH</u>	Catalog No. MHH2AKP Counterbore position code: <u>AH</u>  Counterbore position code: <u>CH</u>	Catalog No. MHH2AKZ Counterbore position code: <u>AH</u>  Counterbore position code: <u>CH</u>
Catalog No. MHH1BKL Counterbore position code: <u>BH</u>  Counterbore position code: <u>DH</u>	Catalog No. MHH1BKR Counterbore position code: <u>BH</u>  Counterbore position code: <u>DH</u>	Catalog No. MHH2BKP Counterbore position code: <u>BH</u>  Counterbore position code: <u>DH</u>	Catalog No. MHH2BKZ Counterbore position code: <u>BH</u>  Counterbore position code: <u>DH</u>

Channels for Water, Oil and Heater — One Side Pipe Thread Holes

Produce pipe thread holes of channels for water, oil and heater only on one side as shown below:

Application Mold bases, cavity retainer sets, cavity retainer sets for die cast



[Applicable specifications]

One side pipe thread hole specification can be applied only to through holes of channels for water, oil and heater.

One side pipe thread hole specifications

When producing pipe thread hole only on one side of channels for water, oil and heater, specify the thread position code of the side on which to produce pipe thread holes from among **AH**, **BH**, **CH** and **DH** (the following eight combinations are available).

1 hole		2 holes	
Catalog No. MHH1AKL Pipe thread position code: AH Pipe thread position code: CH	Catalog No. MHH1AKR Pipe thread position code: AH Pipe thread position code: CH	Catalog No. MHH2AKP Pipe thread position code: AH Pipe thread position code: CH	Catalog No. MHH2AKZ Pipe thread position code: AH Pipe thread position code: CH
Catalog No. MHH1BKL Pipe thread position code: BH Pipe thread position code: DH	Catalog No. MHH1BKR Pipe thread position code: BH Pipe thread position code: DH	Catalog No. MHH2BKP Pipe thread position code: BH Pipe thread position code: DH	Catalog No. MHH2BKZ Pipe thread position code: BH Pipe thread position code: DH

Temperature control hole	Catalog No.	Specify water, oil and heater channel specifications	One side pipe thread hole specification code	Thread position code
1 hole	MHH1AKL	Specify as shown in pages 194 to 195.	TAP	AH CH
	MHH1AKR			BH DH
	MHH1BKL			
	MHH1BKR			
2 holes	MHH2AKP	Specify as shown in pages 196 to 197.	TAP	AH CH
	MHH2AKZ			BH DH
	MHH2BKP			
	MHH2BKZ			

**How to order**

Specify water, oil and heater channel specifications
(See pages 194 to 197)

One side pipe thread hole specification code

Thread position code

MHH1AKL-A-D8.5-Z250-RC1/8-L50-H15 —

TAP

— AH

MHH2BKP-B-D8.5-Z300-RC1/8-P150-H30 —

TAP

— BH

**How to order when combining the above with entrance counterbore holes**

(entrance counterbore spec. → P.200)

Specify water, oil and heater channel specifications
(See pages 194 to 197)

Specify entrance counterbore hole spec.
(see page 200)

Specify one side pipe thread hole specification

MHH2AKP-A-D8.5-Z250-RC1/8-P110-H15 —


ZHC-E22-G20-AH

— TAP-AH


Rough Pockets Machining — Overview

About our rough pocket machining

Our rough pocket machining is rough machining, leaving a finishing allowance of approx. 1 mm. We produce blind pockets and through pockets with a finishing allowance being left as shown below. Please advise us on the pocket dimensions with their finished dimensions. The finishing allowance for pocket gas cutting is set by plate thickness (see page 212).






Blind pocket



Through pocket


[Reference] Common machining procedures for pocket machining

Rough machining	Semi-finish machining	Finish machining
This is an initial process of pocket machining. During rough machining, a part is milled roughly to a general shape of final model, leaving a finishing allowance of a few millimeters. As this is a rough processing, the finishing allowance is not uniform.	A process following rough machining. At the semi-finishing stage, the part is milled to a nearer shape of the model, leaving extremely small amount of finishing allowance of generally 0.1 to 0.2 mm.	This is a final process of pocket machining. The part is milled to a specified limit deviation tolerance and surface roughness.



Limit deviations of thickness of plates with pocket machining


L dimension range ($W \leq L$)	Limit deviations of T	
	Upper deviation	Lower deviation
$L \leq 300$	+0.2	+0.05
$300 < L \leq 600$	+0.25	+0.05
$600 < L \leq 1000$	+0.3	+0.05



Points to be noted when specifying pocket machining



The charts shown in each page illustrate the states viewed when cavity plates on both the fixed and moving sides are open (status viewed from the parting line surface).

Ensure that the datum plane of the plate is aligned with the datum plane of the mold base.



Combination of multiple pocket machining and grooving


By repeatedly specifying machining, you can specify multiple pocket machining and grooving as shown below. Also, combined use of different shapes of pocket machining in a mold base is also possible.



Rough Pockets Machining – Rectangular with Rounded Corners (Inside Corner R)

Mill rectangular pockets with rounded corners (inside corner R) in mold plates.

Application Mold bases, cavity retainer sets, cavity retainer sets for die cast



※ We machine pockets leaving a finishing allowance of approximately 1 mm with respect to the finished dimension.

Please specify the dimension of pockets with their finished dimensions.

※ The table below shows our specifications of pocket corner R.


Pocket corner radius and pocket depth

Pocket corner radius R	R5	R6	R8	R10	R12.5	R15	R20	R25
Pocket depth Z	$Z \leq 45$	$Z \leq 55$	$Z \leq 65$	$Z \leq 90$	$Z \leq 110$	$Z \leq 120$	$Z \leq 130$	$Z \leq 150$

※ The maximum machining depth of pocket depth Z varies depending on the radius of rounded corners.

※ For pocket depth or corner radius not shown in the above table, consult our sales office.


Catalog No. MKKB1/PL (Machine pockets on **PL surface side**)



Applicable to Plate Q, S, V, B, U, W and X

Applicable to Plate R, O, N and A


Catalog No. MKKB1/UR (Machine pockets on **UR surface side**)



Applicable to Plate Q, S, V, B, U, W and X

Applicable to Plate R, O, N and A

Catalog No. MOKB1/PL



Applicable to Plate Q, S, V, B, U, W and X


Applicable to Plate R, O, N and A

※ Specify through pockets from **PL surface side**.
Specifying them from **UR surface side** is not allowed.

※ The position of the datum plane is that viewed at the time when cavity plates on both the fixed and moving sides are open (position viewed from the parting line surface).

Pocket machining applicable plates

The **PL surface side** and **UR surface side** of each plate are as follows:



※ For plates not shown the above, specify with a drawing, etc.


Shape	Catalog No.	Plate code	A	B	R	Z	X	Y
Blind pocket	MKKB1/PL MKKB1/UR	R (Plate R) A (Plate A) S (Plate S) B (Plate B) U (Plate U) Additional plate spec. → P.38	In 0.1 mm steps	In 0.1 mm steps	R5 R6 R8 R10 R12.5 R15 R20 R25	In 0.1 mm steps	In 0.1 mm steps	In 0.1 mm steps
Through pocket	MOKB1/PL	O (Plate O) N (Plate N) Q (Plate Q) V (Plate V) W (Plate W) X (Plate X)				—	Omit X and Y if pockets are machined at the center of the plate.	

※ Pocket machining details → P.204

※ Adding slide core groove, blind groove → P.216 ~ 221

How to order

	Catalog No.	Plate code	A	B	R	Z	X	Y
Blind pocket (Machining on PL side)	MKKB1/PL	A	A80	B100	R10	Z50	X30	Y40
Blind pocket (Machining on UR side)	MKKB1/UR	A	A90	B110	R8	Z10	X50	Y60
Through pocket	MOKB1/PL	B	A100	B150	R8		X40	Y50



Datum

※ If creating two pockets as shown on the left, repeat specifying twice.

If creating three or more pockets, repeat it multiple times accordingly.

An example of order:


Specify ① MKKB1/PL—B—A80—B50—R8—Z20—X50—Y40

Specify ② MKKB1/PL—B—A80—B50—R8—Z20—X50—Y110

Rough Pockets Machining – Rectangular with Rounded Corners (Outside Corner R)

Machine rectangular pockets with rounded corners (outside corner R) in mold plates.

Application Mold bases, cavity retainer sets, cavity retainer sets for die cast



※ We machine pockets leaving a finishing allowance of approximately 1 mm with respect to the finished dimension.

Please specify the dimension of pockets with their finished dimensions.


※ The table below shows our specifications of pocket corner R.

Pocket corner and pocket depth

Pocket corner R	R5	R6	R8	R10	R12.5	R15
Pocket depth Z	$Z \leq 45$	$Z \leq 55$	$Z \leq 65$	$Z \leq 90$	$Z \leq 110$	$Z \leq 120$

※ The maximum machining depth of pocket depth Z varies depending on the radius of rounded corners.
 ※ For pocket depth or corner R not shown in the above table, consult our sales office.


Catalog No. MKKB2/PL (Machine pockets on **PL surface side**)



Applicable to Plate Q, S, V, B, U, W and X

Applicable to Plate R, O, N and A


Catalog No. MKKB2/UR (Machine pockets on **UR surface side**)



Applicable to Plate Q, S, V, B, U, W and X

Applicable to Plate R, O, N and A

Catalog No. MOKB2/PL









Applicable to Plate Q, S, V, B, U, W and X

Applicable to Plate R, O, N and A

※ Specify through pockets from the **PL surface side**.
 Specifying them from the **UR surface side** is not allowed.


For blind pocket, specify the corner R specification:

Corner R specification		
R code: RD	R code: RF	R code: RK
		
		
The depth of corner R will be larger than the finished dimension of the pocket Z by 0.5 to 1 mm.	The corner R will be cut, leaving a finish allowance of 1 mm with respect to the finished dimension Z.	The depth of corner R will be larger than the finished dimension of the pocket Z by 0.5 to 1 mm.
※ RK form may be substituted by RD form due to production conditions.		

※ The position of the datum plane is that viewed at the time when mold plates on both the fixed and moving sides are open (position viewed from the parting line surface).

Pocket milling applicable plate

The **PL side** and the **UR side** of each plate are as follows:




※ For plates not shown the above, specify with a drawing, etc.

Corner radius dimension

【Reference】 Pocket corner R section

The values shown in the table below are reference values to set corner R.

Corner of sizes other than shown below will be machined to order.



R	U	N (Ref. value)
R5	3	0.8
R6	3.5	1.1
R8	5	0.9
R10	6.5	0.8
R12.5	8	1.2
R15	10	0.9

※ N is calculated value.

Shape	Catalog No.	Plate code	A	B	C *1	D *1	R	R code	Z	X	Y
Blind pocket	MKKB2/PL MKKB2/UR	R (Plate R) A (Plate A) S (Plate S) B (Plate B) U (Plate U) Additional plate spec. → P.38	In 0.1 mm steps	In 0.1 mm steps	In 0.1 mm steps	In 0.1 mm steps	R5 R6 R8 R10 R12.5 R15	RD RF RK	In 0.1 mm steps	In 0.1 mm steps	
Through pocket	MOKB2/PL	O (Plate O) N (Plate N) Q (Plate Q) V (Plate V) W (Plate W) X (Plate X)						—	—	Omit X and Y if pockets are machined at the center of the plate.	

*1. C and D dimensions are allocated to A and B as follows for machining.

$$C = A - 2 \times U$$


$$D = B - 2 \times U$$

※ Pocket machining details → P.204

※ Adding slide core groove, blind groove → P.216 ~ 221

How to order

Catalog No.	Plate code	A	B	C	D	R	R code
Blind pocket (PL side machining)	MKKB2/PL —	A —	A80 —	B100 —	C67 —	D87 —	R10 — RD
Blind pocket (UR side machining)	MKKB2/UR —	A —	A100 —	B120 —	C90 —	D110 —	R8 — RD
Through pocket	MOKB2/PL —	B —	A100 —	B150 —	C90 —	D140 —	R8
		Z	X	Y			
		Z50 —	X30 —	Y40			
		Z20 —	X40 —	Y50			
			X40 —	Y50			



Datum

※ If creating two pockets as shown on the left, repeat the specifying twice.

If creating three or more pockets, repeat it multiple times accordingly.

An example of order:


specify ① MKKB2/PL — B — A80 — B50 — C70 — D40 — R8 — RD
— Z20 — X50 — Y40

specify ② MKKB2/PL — B — A80 — B50 — C70 — D40 — R8 — RD
— Z20 — X50 — Y110

Rough Pockets Machining — Circular Pocket

Machine circular pockets in mold plates.

Application Mold bases, cavity retainer sets, cavity retainer sets for die cast



※ We machine pockets leaving a finishing allowance of approximately 1 mm with respect to the finished dimension.
Please specify the dimension of pockets with their finished dimensions.


Hole diameter and depth

Hole diameter	$10 \leq D < 42$	$42 \leq D < 55$	$55 \leq D$
Hole depth Z	$Z \leq D \times 3$	$Z \leq 130$	$Z \leq 150$

※ The maximum machining depth of hole depth Z varies depending on the hole diameter.
※ For hole depth not shown in the above table, consult our sales office.


Catalog No. MKKC1/PL (Machine blind pockets on **PL surface side**)

Catalog No. MOKC1/PL (Machine through pockets)



Applicable to Plate Q, S, V, B, U, W and X Applicable to Plate R, O, N and A

Catalog No. MKKC1/UR (Machine blind pockets on **UR surface side**)




Applicable to Plate Q, S, V, B, U, W and X Applicable to Plate R, O, N and A

※ Specify through circular pockets from the **PL surface side**.
Specifying them from the **UR surface side** is not allowed.


Catalog No. MKKC2/PL (Machine blind pockets on **PL surface side**)

Catalog No. MOKC2/PL (Machine through pockets)



Applicable to Plate Q, S, V, B, U, W and X Applicable to Plate R, O, N and A

Catalog No. MKKC2/UR (Machine blind pockets on **UR surface side**)




Applicable to Plate Q, S, V, B, U, W and X Applicable to Plate R, O, N and A

※ Specify through circular pockets from the **PL surface side**.
Specifying them from the **UR surface side** is not allowed.

※ The position of the datum plane is that viewed at the time when mold plates on both the fixed and moving sides are open (position viewed from the parting line surface).


Catalog No. MKKC4/PL (Machine blind pockets on **PL surface side**)

Catalog No. MOKC4/PL (Machine through pockets)



Applicable to Plate Q, S, V, B, U, W and X Applicable to Plate R, O, N and A

Catalog No. MKKC4/UR (Machine blind pockets on **UR surface side**)




Applicable to Plate Q, S, V, B, U, W and X Applicable to Plate R, O, N and A

※ Specify through circular pockets from the **PL surface side**.
Specifying them from the **UR surface side** is not allowed.

Pocket machining applicable plates

The **PL surface side** and the **UR surface side** of each plate are as follows:



※ For plates not shown the above, specify with a drawing, etc.

Shape	Catalog No.	Plate code	D	Z	A	B	X	Y
Circular blind pocket	MKKC1/PL	R (Plate R) A (Plate A) S (Plate S) B (Plate B) U (Plate U) Additional plate spec. → P.38	In 0.1 mm steps	In 0.1 mm steps	— In 0.1 mm steps — In 0.1 mm steps	— In 0.1 mm steps — In 0.1 mm steps	In 0.1 mm steps	Omit X and Y if pockets are machined at the center of the plate.
	MKKC1/UR							
	MKKC2/PL							
	MKKC2/UR							
Circular through pocket	MKKC4/PL	Additional plate spec. → P.38	In 0.1 mm steps	—	— In 0.1 mm steps	— In 0.1 mm steps	In 0.1 mm steps	Omit X and Y if pockets are machined at the center of the plate.
	MOKC1/PL							
	MOKC2/PL							
	MOKC4/PL							

※ Pocket machining details → P.204

※ Adding slide core groove, blind groove → P.216 ~ 221


How to order

Catalog No.	Plate code	D	Z	A	B	X	Y
Circular blind hole (PL side machining)	MKKC2/PL	A	D80	Z30	B100	X100	Y150
Circular through hole	MOKC4/PL	B	D60	A80	B80	X150	Y180

Pocket Gas Cutting — Rectangular & Circular Pockets

Gas cut through pockets in mold plates.

Application Mold bases, cavity retainer sets, cavity retainer sets for die cast



※ We machine pockets leaving finishing allowances shown in the table below.

Please specify the dimension of pockets with their finished dimensions.


※ The gas cutting of pockets are applicable to materials of F-S55C (F-S50C if plate thickness is 25 mm or less) and F-SS400.

This cutting method cannot be specified for other materials.

Plate thickness and finishing allowance

Plate thickness (T)	$T \leq 100$	$100 < T \leq 170$
Finishing allowance (S)	5	8
Corner radius R	R10 or more	


Catalog No. MYKC1/PL (Specify from the **PL surface side**.)



Applicable to Plate Q, S, V, B, U, W and X

Applicable to Plate R, O, N and A


Catalog No. MYKC2/PL (Specify from the **PL surface side**.)



Applicable to Plate Q, S, V, B, U, W and X

Applicable to Plate R, O, N and A


Catalog No. MYKC4/PL (Specify from the **PL surface side**.)



Applicable to Plate Q, S, V, B, U, W and X

Applicable to Plate R, O, N and A

Catalog No. MYKB1/PL (Specify from the **PL surface side**.)



Applicable to Plate Q, S, V, B, U, W and X


Applicable to Plate R, O, N and A

※ The position of the datum plane is that viewed at the time when mold plates on both the fixed and moving sides are open (position viewed from the parting line surface).

※ The gas cutting of pockets cannot be specified from the **UR surface side**. Please specify with a drawing, etc.

Pocket gas cutting applicable plates

The **PL side** and the **UR surface side** of each plate are as follows:



※ For plates not shown the above, specify with a drawing, etc.

Shape	Catalog No.	Plate code		D	A	B	R	X	Y
Circular	MYKC1/PL	R (Plate R) A (Plate A) S (Plate S) B (Plate B) U (Plate U) Additional plate spec. ➡ P.38	Additional plate O (Plate O) N (Plate N) Q (Plate Q) V (Plate V) W (Plate W) X (Plate X)	In 1 mm steps	—	—	—	In 1 mm steps	Omit X and Y if pockets are machined at the center of the plate.
	MYKC2/PL				In 1 mm steps	In 1 mm steps			
	MYKC4/PL								
Rectangular	MYKB1/PL			—	In 1 mm steps	In 1 mm steps	In 1 mm steps R ≥ 10		


How to order

	Catalog No.	Plate code	D	A	B	R	X	Y
Circular	MYKC2/PL	B	D80	—	B100	—	X100	Y150
Rectangular	MYKB1/PL	A	—	A200	B300	R20	X120	Y100

Rough Pockets Machining — Through Groove

Machine through groove shaped pockets in mold plates.

Application Mold bases, cavity retainer sets, cavity retainer sets for die cast




※ We machine pockets leaving a finishing allowance of approximately 1 mm with respect to the finished dimension.
Please specify the dimension of pockets with their finished dimensions.

Groove width and depth


Groove width (A or B DIMM shown below)	$10 \leq (A \text{ or } B) < 42$	$42 \leq (A \text{ or } B) < 55$	$55 \leq (A \text{ or } B)$
Groove depth Z	$Z \leq (A \text{ or } B) \times 3$	$Z \leq 130$	$Z \leq 150$
※ The maximum machining depth of groove depth Z varies depending on the width of the groove. ※ For groove depth not shown in the above table, consult our sales office.			

Catalog No. **MKKS1/PL** (Machine pockets on **PL** surface side)




Applicable to Plate Q, S, V, B, U, W and X Applicable to Plate R, O, N and A

Catalog No. **MKKS1/UR** (Machine pockets on **UR** surface side)




Applicable to Plate Q, S, V, B, U, W and X Applicable to Plate R, O, N and A

Catalog No. **MKKS2/PL** (Machine pockets on **PL** surface side)



Applicable to Plate Q, S, V, B, U, W and X Applicable to Plate R, O, N and A

Catalog No. **MKKS2/UR** (Machine pockets on **UR** surface side)




Applicable to Plate Q, S, V, B, U, W and X Applicable to Plate R, O, N and A

※ The position of the datum plane is that viewed at the time when mold plates on both the fixed and moving sides are open (position viewed from the parting line surface).

Pocket machining applicable plates

The **PL side** and the **UR surface side** of each plate are as follows:




※ For plates not shown the above, specify with a drawing, etc.

Catalog No.	Plate code	A	B	Z	X ^{*1}	Y ^{*1}
MKKS1/PL MKKS1/UR	R (Plate R) A (Plate A) S (Plate S) B (Plate B) U (Plate U)	In 0.1 mm steps	—	In 0.1 mm steps	In 0.1 mm steps	—
MKKS2/PL MKKS2/UR	O (Plate O) N (Plate N) Q (Plate Q) V (Plate V) W (Plate W) X (Plate X) Additional plate spec. → P.38	—	In 0.1 mm steps	—	—	In 0.1 mm steps

*1. Omit X and Y if grooves are machined at the center of the plate.
 ※ Pocket machining details → P.204

How to order

	Catalog No.	Plate code	A	B	Z	X	Y
Machining on the PL side	MKKS1/PL	A	A80		Z50	X30	
Machining on the UR side	MKKS2/UR	B		B150	Z30		Y50



※ If creating two grooves as shown on the left, repeat the specifying twice.
 If creating three or more grooves, repeat it multiple times accordingly.

An example of order:


Specify ① MKKS2/PL—B—B50—Z20—Y40

Specify ② MKKS2/PL—B—B50—Z20—Y110

Rough Pockets Machining — Slide Core Groove

Machine slide-core shaped pockets in mold plates.

Application Mold bases, cavity retainer sets, cavity retainer sets for die cast



※ We machine pockets leaving a finishing allowance of approximately 1 mm with respect to the finished dimension.


Please specify the dimension of pockets with their finished dimensions.

Groove width and depth

Groove width (A or B DIMM shown below)	$10 \leq (A \text{ or } B) < 42$	$42 \leq (A \text{ or } B) < 55$	$55 \leq (A \text{ or } B)$
Groove depth Z	$Z \leq (A \text{ or } B) \times 3$	$Z \leq 130$	$Z \leq 150$

※ The maximum machining depth of groove depth Z varies depending on the width of the groove.
 ※ For groove depth not shown in the above table, consult our sales office.


Catalog No. MKKMA/PL (Machine grooves on **PL surface side**)



Applicable to Plate Q, S, V, B, U, W and X

Applicable to Plate R, O, N and A


Catalog No. MKKMB/PL (Machine grooves on **PL surface side**)



Applicable to Plate Q, S, V, B, U, W and X

Applicable to Plate R, O, N and A


Catalog No. MKKMC/PL (Machine grooves on **PL surface side**)



Applicable to Plate Q, S, V, B, U, W and X

Applicable to Plate R, O, N and A

Catalog No. MKKMD/PL (Machine grooves on **PL surface side**)



Applicable to Plate Q, S, V, B, U, W and X


Applicable to Plate R, O, N and A

※ The position of the datum plane is that viewed at the time when mold plates on both the fixed and moving sides are open (position viewed from the parting line surface).


※ The slide core grooves cannot be specified from the **UR surface side**. Please specify with a drawing, etc.

Pocket machining applicable plates

The **PL side** and the **UR side** of each plate are as follows:



Machining specification of circular pockets



For circular pocket, M is a dimension to the contact point with the circular hole as shown on the left.

In the cases where the groove is located on the top, bottom or right, M is also measured to the contact point with the hole likewise.

※ For plates not shown the above, specify with a drawing, etc.

Catalog No.	Plate code	A	B	Z ^{*1}	X	Y	M ^{*2}
MKKMA/PL	R (Plate R) O (Plate O)	In 0.1 mm steps	—	In 0.1 mm steps	In 0.1 mm steps	In 0.1 mm steps	In 0.1 mm steps
MKKMB/PL	A (Plate A) N (Plate N)	—	In 0.1 mm steps		—	—	
MKKMC/PL	S (Plate S) Q (Plate Q)	In 0.1 mm steps	—		In 0.1 mm steps	—	
MKKMD/PL	B (Plate B) V (Plate V)	—	In 0.1 mm steps		—	In 0.1 mm steps	
	U (Plate U) W (Plate W) X (Plate X)	In 0.1 mm steps	—		In 0.1 mm steps	—	
	Additional plate spec. → P.38	—	In 0.1 mm steps		In 0.1 mm steps	In 0.1 mm steps	

*1. $Z \leq$ depth of pocket to be specified separately (For through pockets, $Z \leq$ plate thickness - 5)

*2. This is a through groove to a pocket. Specifying blind grooves extending halfway is not allowed with this option.


※ Be sure to specify pockets separately. Specifying slide core grooves only is not allowed.

※ Pocket machining details → P.204

※ Pocket machining to be specified separately → P.206 ~ 213

How to order

Catalog No.	Plate code	A	B	Z	X	Y	M
MKKMA/PL	B	A80		Z15	X70	Y200	M60



※ If creating two grooves as shown on the left, repeat the specifying twice.

If creating three or more grooves, repeat it multiple times accordingly.

An example of order:


Specify ① MKKMC/PL—B—A40—Z15—X55—M40

Specify ② MKKMB/PL—B—B80—Z20—Y60—M40

Rough Pockets Machining — Blind Groove (Inside Corner R)

Machine blind groove (inside corner R) shaped pockets in mold plates.

Application Mold bases, cavity retainer sets, cavity retainer sets for die cast



※ We machine pockets leaving a finishing allowance of approximately 1 mm with respect to the finished dimension.

Please specify the dimension of pockets with their finished dimensions.


※ The table below shows our specifications of blind groove corner R.

Corner R and depth of blind groove

Blind groove corner R	R5	R6	R8	R10	R12.5	R15	R20	R25
Blind groove depth Z	$Z \leq 45$	$Z \leq 55$	$Z \leq 65$	$Z \leq 90$	$Z \leq 110$	$Z \leq 120$	$Z \leq 130$	$Z \leq 150$

※ The maximum machining depth of blind groove depth Z varies depending on the width of the groove.
 ※ For groove depth and corner R not shown in the above table, consult our sales office.


Catalog No. MKKRA/PL (Machine grooves on PL surface side)



Applicable to Plate Q, S, V, B, U, W and X

Applicable to Plate R, O, N and A


Catalog No. MKKRB/PL (Machine grooves on PL surface side)



Applicable to Plate Q, S, V, B, U, W and X

Applicable to Plate R, O, N and A


Catalog No. MKKRC/PL (Machine grooves on PL surface side)



Applicable to Plate Q, S, V, B, U, W and X

Applicable to Plate R, O, N and A

Catalog No. MKKRD/PL (Machine grooves on PL surface side)



Applicable to Plate Q, S, V, B, U, W and X


Applicable to Plate R, O, N and A

※ The position of the datum plane is that viewed at the time when mold plates on both the fixed and moving sides are open (position viewed from the parting line surface).


※ The blind grooves cannot be specified from the UR surface side. Please specify with a drawing, etc.

Pocket machining applicable plates

The **PL side** and the **UR side** of each plate are as follows:



Machining specifications of circular pockets



For circular pocket, M is a dimension to the contact point with the circular hole as shown on the left. In the cases where the groove is located on the top, bottom or right, M is also measured to the contact point with the hole likewise.

※ For plates not shown the above, specify with a drawing, etc.

Catalog No.	Plate code	A	B	R	Z*1	X	Y	M
MKKRA/PL	R (Plate R) O (Plate O)	In 0.1 mm steps	—	R5 R6	In 0.1 mm steps			
MKKRB/PL	A (Plate A) N (Plate N)	—	In 0.1 mm steps	R8 R10				
MKKRC/PL	S (Plate S) Q (Plate Q)	In 0.1 mm steps	—	R12.5 R15	When Z= thickness, the groove passes through the plate.	In 0.1 mm steps	In 0.1 mm steps	In 0.1 mm steps
MKKRD/PL	B (Plate B) V (Plate V) U (Plate U) W (Plate W) X (Plate X) Additional plate spec. → P.38	—	In 0.1 mm steps	R20 R25				

*1. Z ≤ depth of pocket to be specified separately


※ Be sure to specify pockets separately. Specifying blind grooves only is not allowed.

※ Pocket machining details → P.204

※ Pocket machining to be specified separately → P.206 ~ 213

How to order

Catalog No. — Plate code — A — B — R — Z — X — Y — M
MKKRA/PL — A — A80 — R8 — Z15 — X70 — Y160 — M30



※ If creating two grooves as shown on the left, repeat the specifying twice.

If creating three or more grooves, repeat it multiple times accordingly.

An example of order:


Specify ① MKKRC/PL—A—A60—R8—Z15—X70—Y80—M40

Specify ② MKKRB/PL—A—B80—R8—Z20—X60—Y95—M30

Rough Pockets Machining — Blind Groove (Outside Corner R)

Machine blind groove (outside corner R) shaped pockets in mold plates.

Application Mold bases, cavity retainer sets, cavity retainer sets for die cast



※ We machine pockets leaving a finishing allowance of approximately 1 mm with respect to the finished dimension.

Please specify the dimension of pockets with their finished dimensions.

※ The table below shows our specifications of blind groove corner R.


Corner R and depth of blind groove

Blind groove corner R	R5	R6	R8	R10	R12.5	R15
Blind groove depth Z	$Z \leq 45$	$Z \leq 55$	$Z \leq 65$	$Z \leq 90$	$Z \leq 110$	$Z \leq 120$

※ The maximum machining depth of blind groove depth Z varies depending on the width of the groove.


※ For groove depth and corner R not shown in the above table, consult our sales office.

Catalog No. MKKJA/PL (Machine grooves on PL surface side)




Applicable to Plate Q, S, V, B, U, W and X Applicable to Plate R, O, N and A

Catalog No. MKKJB/PL (Machine grooves on PL surface side)




Applicable to Plate Q, S, V, B, U, W and X Applicable to Plate R, O, N and A

Catalog No. MKKJC/PL (Machine grooves on PL surface side)



Applicable to Plate Q, S, V, B, U, W and X Applicable to Plate R, O, N and A

Catalog No. MKKJD/PL (Machine grooves on PL surface side)



Applicable to Plate Q, S, V, B, U, W and X Applicable to Plate R, O, N and A

※ The position of the datum plane is that viewed at the time when mold plates on both the fixed and moving sides are open (position viewed from the parting line surface).

※ The blind grooves cannot be specified from the UR surface side. Please specify with a drawing, etc.


Corner R specifications

R code: RD	R code: RF	R code: RK
The depth of corner R will be larger than the finished dimension of the pocket Z by 0.5 to 1 mm.	The corner R will be cut, leaving a finish allowance of 1mm with respect to the finished dimension Z.	The depth of corner R will be larger than the finished dimension of the pocket Z by 0.5 to 1 mm.


※ RK form may be substituted by RD form due to production conditions.

Pocket machining applicable plates

The **PL side** and the **UR side** of each plate are as follows:



Machining specifications of circular pockets



For circular pocket, M is a dimension to the contact point with the circular hole as shown on the left. In the cases where the groove is located on the top, bottom or right, M is also measured to the contact point with the hole likewise.

※ For plates not shown the above, specify with a drawing, etc.

Catalog No.	Plate code	A	B	C	D	R	R code	Z*1	X	Y	M	Q
MKKJA/PL	R (Plate R)	In 0.1 mm steps	—	In 0.1 mm steps	—	R5	RD	In 0.1 mm steps	In 0.1 mm steps			
MKKJB/PL	A (Plate A)	—	In 0.1 mm steps	—	In 0.1 mm steps	R6	RF	When				
MKKJC/PL	S (Plate S)	In 0.1 mm steps	—	In 0.1 mm steps	—	R8	RK	Z= thickness, the groove passes through the plate.				
MKKJD/PL	B (Plate B)	—	In 0.1 mm steps	—	In 0.1 mm steps	R10	Omit for through holes					
	U (Plate U)	—	In 0.1 mm steps	—	In 0.1 mm steps	R12.5						
	Additional plate spec. → P.38					R15						

*1. Z ≤ depth of pocket to be specified separately


※ Be sure to specify pockets separately. Specifying blind grooves only is not allowed.

※ Pocket machining details → P.204

※ Pocket machining to be specified separately → P.206 ~ 213

How to order

Catalog No.	Plate code	A	B	C	D	R	R code
MKKJA/PL	A	A80	C70	R8	RD		
	Z	X	Y	M	Q		
	Z15	X70	Y160	M30	Q25		



※ If creating two grooves as shown on the left, repeat the specifying twice.

If creating three or more grooves, repeat it multiple times accordingly.

An example of order:

Specify ① MKKJC/PL—A—A60—C50—R8—RD—Z15—X70—Y80—M40—Q35

Specify ② MKKJB/PL—A—B80—D70—R8—RD—Z20—X60—Y95—M30—Q25


Ⓜ Datum

Added Threaded Holes for Eyebolt (Side Surface Threaded Holes) – Overview

Machine threaded holes for installing eye bolts or other parts on side surfaces (outer circumference).

Three types of specifications, "Standard specification of thread holes for eye bolts", "Thread depth designation specification" and "Prepared hole depth designation specification" are available. Use them according to your application requirement.

Specifications of threaded holes for eye bolt (side surface threaded holes)

	M	F dimension designation range *1		G	D Ref. value	Standard specification		Thread depth designation spec.		Prepared hole designation spec.	
		max	min			F	K	F	K	F	K
	M3	7	3	6	3.6	6	12	Specified value	K=F+G	F=K-G	Specified value
	M4	10	4	7	4.8	8	15				
	M5	12	5	7	6	10	17				
	M6	15	6	8	7	12	20				
	M8	20	8	7	11	16	23				
	M10	25	10	8	13	20	28				
	M12	28	12	9	16	24	33				
	M14	32	14	10	18	26	36				
	M16	32	16	10	20	29	39				
	M20	40	20	13	24	33	46				
	M24	50	24	15	28	41	56				
	M30	60	30	18	35	49	67				
	M36	72	36	23	41	59	82				
	M42	75	42	25	47	70	95				
	M48	80	48	28	54	75	103				


*1. Set F dimensions of "Thread depth designation specification" and "Prepared hole designation specification" within this range.

※ M8-M48 (excluding M14) of standard specification are threaded hole specification for eye bolts.

Machining region of threaded holes for eye bolts (side surface threaded holes)

To prevent the interference of threaded holes for eye bolts and side surfaces with other holes machined, we have set a machining region only as a guide as shown in the table below. Please take into account when designing molds.


These values are provided only as a guide and do not represent a guarantee of influence on accuracy and strength.




Do not perform other machining work within the area.

M	N1	N2
M3	6	N2 = K + 2
M4	7	
M5	8	
M6	9	
M8	13	N2 = K + 3
M10	15	
M12	18	
M14	20	
M16	22	
M20	26	
M24	30	N2 = K + 4
M30	37	
M36	43	
M42	49	
M48	56	

Matters to be noted when protrusion amount of clamping plate is not even (For how to specify, see pages 224 to 227)




The **reference position** of thread hole is set at the center of the mold plate as shown in the above chart, not at the center of width of the clamping plate.



The **reference position** of L and R dimensions is set at the center of the mold plate as shown in the above chart.

※ If $L=R$ and $P=L+R$, then specify with P.




Added Threaded Holes for Eyebolt (Side Surface Threaded Holes) – 1 Hole

Machine threaded holes for installing eye bolts or other parts on side surfaces (outer circumference).

Use this option to specify a threaded hole at a time.

Application Mold bases, cavity retainer sets, cavity retainer sets for die cast




M	F dimension designation range *1		G	D Ref. value	Standard specification		Thread depth designation spec.		Prepared hole designation spec.	
	max	min			F	K	F	K	F	K
M3	7	3	6	3.6	6	12	Specified value	K=F+G	F=K-G	Specified value
M4	10	4	7	4.8	8	15				
M5	12	5	7	6	10	17				
M6	15	6	8	7	12	20				
M8	20	8	7	11	16	23				
M10	25	10	8	13	20	28				
M12	28	12	9	16	24	33				
M14	32	14	10	18	26	36				
M16	32	16	10	20	29	39				
M20	40	20	13	24	33	46				
M24	50	24	15	28	41	56				
M30	60	30	18	35	49	67				
M36	72	36	23	41	59	82				
M42	75	42	25	47	70	95				
M48	80	48	28	54	75	103				


*1. Set F dimensions of "Thread depth designation specification" and "Prepared hole designation specification" within this range.

※ M8-M48 (excluding M14) of standard specification are threaded hole specification for eye bolts.


Catalog No. M□□1A




Catalog No. M□□1B




Catalog No. M□□1C




Catalog No. M□□1D




Catalog No. M□□1AL




Catalog No. M□□1BL




Catalog No. M□□1CL




Catalog No. M□□1DL




Catalog No. M□□1AR




Catalog No. M□□1BR




Catalog No. M□□1CR




Catalog No. M□□1DR



Specifying threaded holes in plate thickness direction



Position of H dimension



※ H dimension must be specified with a dimension from top surface side direction.

Catalog No.			Plate code	M	F	K	L or R	H
Standard spec.	Thread depth designation spec.	Prepared hole designation spec.						
MFK1A	MGK1A	MHK1A	T (Plate T) R (Plate R) A (Plate A) S (Plate S) B (Plate B) U (Plate U) E (Plate E) F (Plate F) L (Plate L)	M3	In 1 mm steps Specify only for Catalog No. MGK1□□	In 1 mm steps Specify only for Catalog No. MHK1□□	— In 1 mm steps	In 0.5 mm steps
MFK1B	MGK1B	MHK1B		M4				
MFK1C	MGK1C	MHK1C		M5				
MFK1D	MGK1D	MHK1D		M6				
MFK1AL	MGK1AL	MHK1AL		M8				
MFK1BL	MGK1BL	MHK1BL		M10				
MFK1CL	MGK1CL	MHK1CL		M12				
MFK1DL	MGK1DL	MHK1DL		M14				
MFK1AR	MGK1AR	MHK1AR		M16				
MFK1BR	MGK1BR	MHK1BR		M20				
MFK1CR	MGK1CR	MHK1CR		M24				
MFK1DR	MGK1DR	MHK1DR		M30				
				M36				
				M42				
				M48				

※ How to specify threaded holes for Plate C → P.228

※ Standard threaded hole for eye bolts for mold bases, cavity retainer sets and cavity retainer sets for die cast are machined.

If standard thread holes for eye bolts are not necessary, refer to page 232.

※ How to instruct when protrusion amount of a mounting plate is not even. → P.223

※ Detailed specification of threaded holes for eye bolts and side surfaces → P.222



How to order


	Catalog No.	Plate code	M	F	K	L or R	H
Standard specification	MFK1A	A	M12				H15
Thread depth designation spec.	MGK1BL	T	M6	F10		L50	H10
Prepared hole designation spec.	MHK1C	U	M10		K25		H20

Added Threaded Holes for Eyebolt (Side Surface Threaded Holes) – 2 Holes or 4 Holes

Machine threaded holes for installing eye bolts or other parts on side surfaces (outer circumference).

Use this option to specify threaded holes at two or four places at the same time.

Application Mold bases, cavity retainer sets, cavity retainer sets for die cast




M	F dimension designation range *1		G	D Ref. value	Standard specification		Thread depth designation spec.		Prepared hole designation spec.	
	max	min			F	K	F	K	F	K
M3	7	3	6	3.6	6	12	Specified value	K=F+G	F=K-G	Specified value
M4	10	4	7	4.8	8	15				
M5	12	5	7	6	10	17				
M6	15	6	8	7	12	20				
M8	20	8	7	11	16	23				
M10	25	10	8	13	20	28				
M12	28	12	9	16	24	33				
M14	32	14	10	18	26	36				
M16	32	16	10	20	29	39				
M20	40	20	13	24	33	46				
M24	50	24	15	28	41	56				
M30	60	30	18	35	49	67				
M36	72	36	23	41	59	82				
M42	75	42	25	47	70	95				
M48	80	48	28	54	75	103				


*1. Set F dimensions of "Thread depth designation specification" and "Prepared hole designation specification" within this range.

※ M8-M48 (excluding M14) of standard specification are threaded hole specification for eye bolts.


Catalog No. M□□2AC




Catalog No. M□□2BD




Catalog No. M□□2AP




Catalog No. M□□2BP




Catalog No. M□□2ACL




Catalog No. M□□2BDL




Catalog No. M□□2CP




Catalog No. M□□2DP




Catalog No. M□□2ACR




Catalog No. M□□2BDR




Catalog No. M□□4ACP




Catalog No. M□□4BDP




Catalog No. M□□4



Specifying threaded holes in plate thickness direction



Position of H dimension



※ H dimension must be specified with a dimension from top surface side direction.

Catalog No.			Plate code	M	F	K	P	H
Standard spec.	Thread depth designation spec.	Prepared hole designation spec.						
MFK2AC	MGK2AC	MHK2AC	T (Plate T) R (Plate R) A (Plate A) S (Plate S) B (Plate B) U (Plate U) C (Plate C) E (Plate E) F (Plate F) L (Plate L) Additional plate spec. ↓ P.38	M3	In 1 mm steps Specify only for Catalog No. MGK□□□□	In 1 mm steps Specify only for Catalog No. MHK□□□□	In 1 mm steps In 1 mm steps	In 0.5 mm steps
MFK2BD	MGK2BD	MHK2BD		M4				
MFK2ACL	MGK2ACL	MHK2ACL		M5				
MFK2ACR	MGK2ACR	MHK2ACR		M6				
MFK2BDL	MGK2BDL	MHK2BDL		M8				
MFK2BDR	MGK2BDR	MHK2BDR		M10				
MFK2AP	MGK2AP	MHK2AP		M12				
MFK2BP	MGK2BP	MHK2BP		M14				
MFK2CP	MGK2CP	MHK2CP		M16				
MFK2DP	MGK2DP	MHK2DP		M20				
MFK4ACP	MGK4ACP	MHK4ACP		M24				
MFK4BDP	MGK4BDP	MHK4BDP		M30				
MFK4	MGK4	MHK4		M36				
				M42				
				M48				

※ How to instruct on thread holes for Plate C → P.228

※ Standard threaded hole for eye bolts for mold bases, cavity retainer sets and cavity retainer sets for die cast are machined.

If standard thread holes for eye bolts are not necessary, refer to page 232.

※ How to instruct when protrusion amount of a mounting plate is not even. → P.223

※ Detailed specification of threaded holes for eye bolts and side surfaces → P.222

How to order

Catalog No. — Plate code — M — F — K — P — H

Standard specification MFK2AC — A — M20 — H50

Thread depth designation spec. MGK4ACP — T — M6 — F10 — P150 — H15


Prepared hole designation spec. MHK2BDR — U — M10 — K25 — P200 — H20

Added Threaded Holes for Eyebolt (Side Surface Threaded Holes) (For C-Plate)


Please specify threaded holes for eye bolts (side surface threaded holes) for Plate C in pairs as shown below. The specifications of the threaded holes (thread depth, chamfering method, etc.) are the same as those of other plates.

Application Mold bases


Catalog No. M□□1AL




Catalog No. M□□1BL




Catalog No. M□□1CL




Catalog No. M□□1DL




Catalog No. M□□1AR




Catalog No. M□□1BR




Catalog No. M□□1CR




Catalog No. M□□1DR




Catalog No. M□□1B




Catalog No. M□□1D




Catalog No. M□□1M




Catalog No. M□□1H




Catalog No. M□□1ML




Catalog No. M□□1MR




Catalog No. M□□1HL




Catalog No. M□□1HR




Catalog No. M□□2AP




Catalog No. M□□2BP




Catalog No. M□□2CP




Catalog No. M□□2DP




Catalog No. M□□2BD




Catalog No. M□□4ACP



Catalog No. M□□4BDP




Specify threaded hole in thickness direction



※ H dimension must be specified with a dimension from top surface side direction.

Shape of threaded hole

The shape of threaded hole will be as shown below, depending on Plate C width dimension (CW) and thread depth (F).



Catalog No.			Plate code	M	F	K	P, L, R	H		
Standard spec.	Thread depth designation spec.	Prepared hole designation spec.								
MFK1AL	MGK1AL	MHK1AL	C (Plate C)	M3 M4 M5 M6 M8 M10 M12 M14 M16 M20 M24 M30 M36 M42 M48	In 1 mm steps	In 1 mm steps	In 0.5 mm steps	In 0.5 mm steps		
MFK1BL	MGK1BL	MHK1BL								
MFK1CL	MGK1CL	MHK1CL								
MFK1DL	MGK1DL	MHK1DL								
MFK1AR	MGK1AR	MHK1AR								
MFK1BR	MGK1BR	MHK1BR								
MFK1CR	MGK1CR	MHK1CR								
MFK1DR	MGK1DR	MHK1DR								
MFK1B	MGK1B	MHK1B								
MFK1D	MGK1D	MHK1D								
MFK1M	MGK1M	MHK1M								
MFK1H	MGK1H	MHK1H								
MFK1ML	MGK1ML	MHK1ML								
MFK1MR	MGK1MR	MHK1MR								
MFK1HL	MGK1HL	MHK1HL								
MFK1HR	MGK1HR	MHK1HR								
MFK2AP	MGK2AP	MHK2AP								
MFK2BP	MGK2BP	MHK2BP								
MFK2CP	MGK2CP	MHK2CP								
MFK2DP	MGK2DP	MHK2DP								
MFK2BD	MGK2BD	MHK2BD								
MFK4ACP	MGK4ACP	MHK4ACP								
MFK4BDP	MGK4BDP	MHK4BDP								
							Specify only for Catalog No. MGK□□□□	Specify only for Catalog No. MHK□□□□	—	
									In 0.5 mm steps	




How to order

	Catalog No.	Plate code	M	F	K	P, L, R	H
Standard specification	MFK1B	C	M12				H35
Thread depth designation spec.	MGK2DP	C	M8	F12		P30	H20
Prepared hole designation spec.	MHK1AL	C	M10		K25	L100	H30

Added Threaded Holes for Eyebolt (Side Surface Threaded Holes) - Chamfering

Chamfer threaded holes for eye bolts (side surface threaded holes) as shown below:

Application Mold bases, cavity retainer sets, cavity retainer sets for die cast

Option code	Specification																																									
CC		Change the chamfering dimensions of threaded holes. ■ How to specify: CC/D DIMM ※ D → Specify in 1mm steps $M + 1 \leq D \leq M + 10$ [e.g.] CC/D20																																								
CHN		Change the dimensions of thread depth and shape of chamfer. If specifying "Thread depth designation" or "Prepared hole depth designation", only the dimension of chamfering section will be applied. ■ How to specify: CHN [e.g.] CHN <table><tr><th>M</th><th>M10</th><th>M12</th><th>M16</th><th>M20</th><th>M24</th><th>M30</th><th>M36</th></tr><tr><th>D1</th><td>15</td><td>18</td><td>23</td><td>27</td><td>35</td><td>42</td><td>50</td></tr><tr><th>F</th><td>22</td><td>26</td><td>32</td><td>40</td><td>50</td><td>60</td><td>72</td></tr><tr><th>K max</th><td>30</td><td>35</td><td>42</td><td>53</td><td>65</td><td>78</td><td>95</td></tr></table>	M	M10	M12	M16	M20	M24	M30	M36	D1	15	18	23	27	35	42	50	F	22	26	32	40	50	60	72	K max	30	35	42	53	65	78	95								
M	M10	M12	M16	M20	M24	M30	M36																																			
D1	15	18	23	27	35	42	50																																			
F	22	26	32	40	50	60	72																																			
K max	30	35	42	53	65	78	95																																			
CHZ		Change the dimensions of thread depth and shape of chamfer. If specifying "Thread depth designation" or "Prepared hole depth designation", only the dimension of chamfering section will be applied. ■ How to specify: CHZ [e.g.] CHZ <table><tr><th>M</th><th>M10</th><th>M12</th><th>M16</th><th>M20</th><th>M24</th><th>M30</th><th>M36</th></tr><tr><th>D2</th><td>12</td><td>14</td><td>18</td><td>22</td><td>28</td><td>34</td><td>40</td></tr><tr><th>Z</th><td>5</td><td>6</td><td>6</td><td>6</td><td>8</td><td>9</td><td>11</td></tr><tr><th>F</th><td>22</td><td>26</td><td>32</td><td>40</td><td>50</td><td>60</td><td>72</td></tr><tr><th>K max</th><td>30</td><td>35</td><td>42</td><td>53</td><td>65</td><td>78</td><td>95</td></tr></table>	M	M10	M12	M16	M20	M24	M30	M36	D2	12	14	18	22	28	34	40	Z	5	6	6	6	8	9	11	F	22	26	32	40	50	60	72	K max	30	35	42	53	65	78	95
M	M10	M12	M16	M20	M24	M30	M36																																			
D2	12	14	18	22	28	34	40																																			
Z	5	6	6	6	8	9	11																																			
F	22	26	32	40	50	60	72																																			
K max	30	35	42	53	65	78	95																																			

How to order

Specify threaded holes for eye bolts (side surface threaded holes) —

Option code

MFK2AC — A — M20 — H50

CC/D28

MFK4ACP — B — M16 — P150 — H30


CHZ

Added Eye Bolts

Install eye bolts in the thread holes for eye bolts.

Eye bolts → P.395

Application Mold bases, cavity retainer sets, cavity retainer sets for die cast



Thread diameter for eye bolts

M8 M10 M12 M16 M20
M24 M30 M36 M42 M48



Eye bolts are supplied with mold bases, not installed in them.

When installing eye bolts in standard threaded holes for eye bolts

If installing eye bolts in the threaded holes provided as standard, specify it as follows:

Catalog No.	Code of plates in which to install eye bolts ^{*1}	Number of eye bolts ^{*2}
PIBM	T (Plate T) C (Plate C) A (Plate A) E (Plate E) S (Plate S) F (Plate F) B (Plate B) L (Plate L) U (Plate U)	In 1 piece steps

*1. For plates in which standard threaded holes for eye bolts are provided, refer to page 232.

*2. The number of threaded holes for eye bolts and the number of eye bolts can be different.

How to order

Catalog No. — Code of plates in which to install eye bolts / Number of eye bolts
PIBM — B / 2

When installing eye bolts in separately specified threaded holes for eye bolt

If installing eye bolts in the threaded holes you have separately specified using a method shown in pages 224 to 227, specify it as follows:

Specify threaded holes for eye bolts	Eye bolt installation code	Number of eye bolts ^{*3}
Specify it using a method shown in pages 224 to 227.	PIBM	In 1 piece steps

*3. The number of threaded holes for eye bolts and the number of eye bolts can be different.

How to order

Specify threaded holes for eye bolts — Code of plates in which to install eye / Number of eye bolts
MFK2AC—A—M12—H20 — PIBM / 2

Omit Threaded Holes for Standard Eyebolt


Omit standard threaded holes for eye bolts from mold bases, etc.

Application Mold bases, cavity retainer sets, cavity retainer sets for die cast


Standard threaded hole specification for eye bolts

Standard threaded holes for eye bolts are provided as shown in the charts below.


Please specify the codes of plates in which standard threaded holes for eye bolts are unnecessary.




Name of plate in which standard threaded hole for eye bolts are provided	Applied product
Plate B	Mold bases nominal dimensions 1515 to 3560




Name of plate in which standard threaded hole for eye bolts are provided	Applied product
Plate B	Plastic main molds nominal dimensions 1515 to 3560




Name of plate in which standard threaded hole for eye bolts are provided	Applied product
Plate A, Plate B	Mold bases nominal dimensions 4040 to 5070



Name of plate in which standard threaded hole for eye bolts are provided	Applied product
Plate A, Plate B	Plastic main molds nominal dimensions 4040 to 6070



Name of plate in which standard threaded hole for eye bolts are provided	Applied product
All plates	Mold bases nominal dimensions 5555 to 7080



Name of plate in which standard threaded hole for eye bolts are provided	Applied product
Plate A, Plate B	Die cast main molds nominal dimensions 1518 to 5065

Catalog No.	Codes of plates in which to delete threaded holes for eye bolts	Machining code
ESM	T (Plate T) C (Plate C) A (Plate A) E (Plate E) S (Plate S) F (Plate F) B (Plate B) L (Plate L) U (Plate U)	FK



How to order

Catalog No.

ESM

Codes of plates in which to omit threaded holes for eye bolts

B

Machining code

FK




The threaded holes for eye bolts can also be omitted by following procedures using optional Specification shown in each page for mold bases, cavity retainer sets, and cavity retainer sets for die cast sections of BLUE BOOK Futaba Standard Plastic Mold Components VOL. 1.

E.g. MDCSC2530407070S-MN/#FK

Added Side Surface Threaded Holes with Counterbore

Machine threaded holes with a counterbore on the side surfaces of plates as shown below:

Application Mold bases, cavity retainer sets, cavity retainer sets for die cast




Detailed view of section A


※ Ensure that N1 and N2 dimensions are 1.5 mm or more.
However, this value is not a guarantee of strength.

M		M6	M8	M10	M12	M16
F dimension designation range	max	15	20	25	28	32
	min	6	8	10	12	16
G		8	7	8	9	10
K (max)		K=F+G				
D		10 ≤ D ≤ 30 provided D ≥ M+2				
Z		2 ≤ Z ≤ 5				


Catalog No. MZT2AC




Catalog No. MZT2ACL




Catalog No. MZT2ACR




Catalog No. MZT4ACP




Catalog No. MZT2BD




Catalog No. MZT2BDL




Catalog No. MZT2BDR



Catalog No. MZT4BDP




Machining



Added Side Surface Threaded Holes with Counterbore

- ※ Detailed specification of thread holes for eye bolts and side surfaces → P.222




Added or Omitted Ejector Rod Holes

Adding holes for ejector rods



Machine holes for ejector rods on the bottom clamping plate.

Ejector rods are not supplied with mold bases. ➔ P.146

Application Mold bases (this process can be specified for SE · SF · DE · DF · EE · EF · FE · FF · GE · GF types as well)



If adding additional Plate X or Plate Y: Additional plate spec. ➔ P.38
The hole will also pass through the Plate X or Plate Y.



Catalog No.	D		X	Y	*1. The mold bases of nominal dimension 1113 to 2550 have holes for standard ejector rods at the center. If specifying MEH2 or MEH4B, the holes will be eliminated. ※ The mold bases of nominal dimension 1113 to 2550 have holes for ejector rods at the center. If specifying the processing of the holes for ejector rods, the standard diameter of the holes will be replaced by the specified diameter.
	Recommended value	Free dimension			
MEH1 MEH2 *1 MEH3 MEH4A MEH4B *1 MEH5A MEH5B MEH7 MEH9	24 29 34 40 45 50 55	In 1 mm steps 15 ~ 60	In 1 mm steps When X=KW/2, omit X When Y=KL/2, omit Y		


How to order

Catalog No. — D — X — Y
MEH3 — D34 — X80 — Y100

Omitting standard holes for ejector rods

Delete the standard holes provided in mold bases for ejector rods.

Application Mold bases (nominal dimension: 1113 to 2550)




Catalog No.	Machining code	
ESM	EH	※ The holes for ejector rods can also be deleted by following procedures using optional specification shown in each page of mold bases. E.g. MDCSA2025404060SVMN/#EH


How to order

Catalog No. — Machining code
ESM — EH


Catalog No. MEH1




Catalog No. MEH2




Catalog No. MEH3




Catalog No. MEH4A




Catalog No. MEH4B




Catalog No. MEH5A




Catalog No. MEH5B




Catalog No. MEH7



Catalog No. MEH9



Reference: Positions of ejector rod holes (an excerpt from JIS B 6701-1992 dimensions relating to molds for plastic injection molding machines)



The position and the number of ejector rod holes may differ from the chart on the left depending on injection molding machines. Refer to the catalog or instruction manual of your particular injector molding machine for such information.


Added Clamp Slot (For Clamping Plate)

Mill the protrusion of clamping plate as shown below to reduce thickness of the clamp section.


Changing dimension and installation method of clamping plate → P.22

Application Mold bases


Catalog No. MFG



Add clamp slot only on Plate T



Add clamp slot only on Plate L



Add clamp slots both on Plate T and Plate L

Protrusion direction	Catalog No.	Plate code	T *1	Clamp code
2-direction protrusion	MFG	T (Plate T)	In 1 mm steps	AL
3-direction protrusion		L (Plate L)		AL MH US
4-direction protrusion		TL (Plate T, Plate L)		AL MH US



*1. If the dimensions of Plate T and Plate L are different, specifying with plate code TL is not allowed.
Specify the milling of Plate T and Plate L separately.

How to order

	Catalog No.	Plate code	T	Clamp code
Add clamp slot on Plate T	MFG	T	T20	AL
Add clamp slot on Plate L	MFG	L	T25	AL
Add clamp slots on Plate T & L	MFG	TL	T20	AL





2-direction protrusion ( areas are the protrusion sections that will be milled for clamping)

Clamp code AL Mill 2-direction protrusion sections for clamping





3-direction protrusion ( areas are the protrusion sections that will be milled for clamping)



Clamp code AL Mill 3-direction protrusion sections for clamping



Clamp code MH Mill the right and left direction protrusion sections for clamping




Clamp code US Mill top and bottom direction protrusion sections for clamping




4-direction protrusion ( areas are the protrusion sections that will be milled for clamping)


Clamp code AL Mill the 4-direction protrusion sections for clamping



Clamp code MH Mill the right and left direction protrusion sections for clamping



Clamp code US Mill the top and bottom direction protrusion sections for clamping




Added Clamping Holes or U Ditch for Clamping


Machine clamping holes and U-ditch for installing molding machine on the top and bottom clamping plates.

Application Mold bases


Catalog No. MCH



Catalog No. MUM1



Catalog No. MUM2



※ Machining is performed at the same position on the top and bottom clamping plates.

※ U-ditch can be specified in different variations up to half circles.

Catalog No.	D	A	B	X	Y
MCH MUM1 MUM2	In 1 mm steps 9 ~ 30	In 1 mm steps	In 1 mm steps	In 1 mm steps When X=KW/2, omit X	In 1 mm steps When Y=KL/2, omit Y

How to order

Catalog No. — **D** — **A** — **B** — **X** — **Y**

MCH — **D18** — **A500** — **B350** — **X270** — **Y180**


MUM1 — **D20** — **A350** — **B250** — **X150** — **Y150**

※ If placing 8 or 12 holes (in multiples of 4), specify the process multiple times.

E.g. In the case of 8 holes

MCH — D18 — A500 — B350 — X270 — Y180

MCH — D18 — A500 — B250 — X270 — Y180



If external dimension of the clamping plate aligns with the center of the rounded grooves, the grooves will be half circles.

■ Applicable items


Catalog No. MUM1、MUM2

Added Clamp Slot (For A-Plate or B-Plate)


Machine clamp slots on cavity retainer sets and cavity retainer sets for die cast.

Application Cavity retainer sets, cavity retainer sets for die cast

Catalog No. MCM



Machine clamp slots on Plate A




Machine clamp slots on Plate B

※ N dimension of 10 or more is required.


Clamp code

Clamp code MH




Machine right and left
direction clamp slots on Plate A

Clamp code US



Machine top and bottom
direction clamp slots on Plate A

Clamp code AL



Machine 4-direction clamp slot
on Plate A

Catalog No.	Plate code	W	Z	T	Clamp code
MCM	A (Plate A) B (Plate B)	15 20 25 30 35 40	In.1 mm steps 10 ~ 40	In.1 mm steps 15 ~ 40	MH US AL

How to order

Catalog No. — **Plate code** — **W** — **Z** — **T** — **Clamp code**
MCM — **A** — **W20** — **Z15** — **T20** — **MH**

※ The standard clamp slot for die cast main mold will be replaced with specified clamp slot.

※ When placing clamp slot in the die cast main molds, specify T dimension of the die cast main mold as 00.

E.g. MDE-A3035 100 100 S N : 00

Additional Plate Processing

Additional Plate Processing — Overview	244
Machining Channels of Water, Oil and Heater.....	246
Rough Pockets Machining	248
Machining Threaded Holes for Eye Bolt (Side Surface Threaded Holes).....	250






“Additional processing specifications” are provided to show customers how to instruct us on additional processing. When designing molds, various conditions such as strength and accuracy need to be taken into account. Therefore, we shall not be responsible or liable for any loss or damage of any kind incurred as a result of, or in connection with your use of additional processing specifications or selection of mold bases.

Additional Plate Processing — Overview


What is additional plate processing?

This is a term we use to describe a number of common processing additionally made to precision plates for use in building new mold bases or in adding plates to standard mold bases, the specifications of which are set in place with simple codes assigned to them so that customers can order required alternation or modification of plates easily with the codes without drawings. Additional plate processing includes machining of water & oil channels, heater holes and pockets as well as threaded holes for eye bolts and side surfaces, etc.

Additional Plate Processing Specifications

Channels for water, oil and heater ➡ P.246	Rough pocket machining ➡ P.248	Threaded holes for eye bolts (side surface threaded holes) ➡ P.250
		

Additionally processing plate item names

Precision plate material name	Additionally processing plate item name				Reference diagram
F-S55C *1	MPPSC	W	×	L × T	
F-S55C Block materials	MPKSC	W	×	L × T	
F-SS400	MPPSS	W	×	L × T	
F-SS400 Block materials	MPKSS	W	×	L × T	
HPM1	MPPHPM	W	×	L × T	
NAK55	MPP55N	W	×	L × T	
NAK80	MPP80N	W	×	L × T	
A7075	MPFAAS	W	×	L × T	
*1. When T dimension is 25 mm or less, F-S50C is used. ※ For precision of plates, refer to Plate General Catalog Red Book . ※ The precision of NAK55 and NAK80 plates are the same as that of F-S55C.					※ The relation of W and L shall be $W \leq L$.

How to order

Please order “additional processing specifications” by specifying additionally processing plate name and additional processing specifications with codes as shown in the order example below. Write the additional specifications by beginning a new line for each specification.

【Order example】

Additionally processing plate name ——— MPPSC 200 × 300 × 50

Additional processing specification { MHH2AKP—D8.5—Z300—RC1/8—P80—H35
MKKB1/PL—A100—B210—R10—Z25—X50—Y45
MFK2AC—M12—H25

Price

We will be pleased to provide you with a preliminary price quotation. Please request a quotation from our sales office.

Delivery date

Delivery dates will vary depending on the contents and volume of “Additional Processing Specifications”.

Please inquire with our sales office.

Specifications not listed in this catalog

“Additional processing specifications” are commonly used specifications that are set in place with codes assigned to them.

We also accept orders for processing or machining of plates not shown in our catalog. Please advise us on your application requirements with a drawing, etc. or consult our sales office. Plates of materials, sizes or precision not listed in the left table will also be made to order. Consult our sales office.

Using MOLDZUKAN®

MOLDZUKAN® is software that supports selection of additional processing specifications and issuance of purchase orders. Using MOLDZUKAN® allows customers to more easily select additional processing specifications and issue purchase orders. For details, refer to page 3.







Liability note

“Additional processing specifications” are provided to show customers how to order additional processings. When designing molds, various conditions such as strength and accuracy need to be taken into account. Therefore, we shall not be responsible or liable for any loss or damage of any kind incurred as a result of, or in connection with your use of additional processing specifications or selection of mold bases.

Machining Channels for Water, Oil and Heater


Machine channels for water, oil and heater in plates as shown below:

For details on the machining of channels for water, oil and heater, refer to each page shown below:


Through hole (1 Hole) → P.194	Through holes (2 Holes) → P.250	Through holes (circulation type) → P.198
		
Blind hole (1 Hole) → P.194	Blind holes (2 Holes) → P.196	Entrance counterbore → P.200 One side pipe threaded hole → P.202
		

Datum of specifying dimension

Please advise us on the dimensions of water, oil and heater channel machining with the datum at the right lower corner as shown in the right chart.



Proper way of specifying




Improper way of specifying

※ The relation of W and L shall be $W \leq L$.

Datum plane positions for additionally processing plates and precision plates

When ordering additional processing of plates, specify dimensions by aligning the datum plane position of the precision plates to be processed with the datum plane position for additionally processing plates as shown below.



Datum plane position for additionally processing plates

Position of the datum plane of a precision plate

How to order

※ The catalog numbers used when ordering additional processing of plates are the same as those used when ordering additional processing of mold bases. When ordering additional processing plates, however, omit specifying plate codes as shown below:

● How to order additional processing of plates

E.g. Machining Through Hole (1 Hole)

Catalog No.	—	D	—	Z	—	Thread code (TP)	—	L or R	—	Y
MHH1AKL	—	D8.5	—	Z250	—	RC1/8	—	L50	—	H15

● How to order additional processing of mold bases

E.g. Machining Through Hole (1 Hole)









Catalog No.	—	Plate code	—	D	—	Z	—	Thread code (TP)	—	L or R	—	H
MHH1AKL	—	A	—	D8.5	—	Z250	—	RC1/8	—	L50	—	H15

When ordering additional processing of plates, omit specifying plate codes.

Rough Pockets Machining


Mill pockets in plates as shown in charts below:

For more information on rough pocket machining, see the respective pages shown below:


Rectangular pocket (inside corner R) → P.206	Rectangular pocket (outside corner R) → P.208	Circular pocket → P.210	Pocket gas cutting → P.212
			
Through grooves → P.214	Slide core grooves → P.216	Blind grooves (Inside corner R) → P.218	Blind grooves (Outside corner R) → P.220
			

Datum of dimension instruction

Please advise us on the dimensions of pocket milling with the datum at the right lower corner as shown in the right chart.



Proper way of specifying dimension




Improper way of specifying dimension

※ Relation of W and L shall be $W \leq L$

Datum plane positions for additionally processing plates and precision plates

When ordering additional processing of plates, specify dimensions by aligning the datum plane position of the precision plates to be processed with the datum plane position for additionally processing plates as shown below.



Datum plane position for additionally processing plates

Position of the datum plane of a precision plate

How to order

※ The catalog numbers used when ordering additional processing of plates are the same as those used when ordering additional processing of mold bases. When ordering additional processing plates, however, omit specifying plate codes as shown below:

● How to order additional processing of plates

E.g. Rectangular pocket with rounded corners (inside corner R)

Catalog No.	—	A	—	B	—	R	—	Z	—	X	—	Y
MKKB1/PL	—	A80	—	B100	—	R10	—	Z50	—	X30	—	Y40

● How to order additional processing of mold bases

E.g. Rectangular pocket with rounded corners (inside corner R)




Catalog No.	—	Plate code	—	A	—	B	—	R	—	Z	—	X	—	Y
MKKB1/PL	—	A	—	A80	—	B100	—	R10	—	Z50	—	X30	—	Y40

When ordering additional processing of plates, omit specifying plate codes.

Machining Threaded Holes for Eyebolt (Side Surface Threaded Holes)


Machine threaded holes for eye bolts and side surfaces in plates as shown in charts below:

For more information on threaded holes for eye bolts and side surfaces, see the respective pages shown below:


1 Hole → P.224	2 Holes → P.226	4 Holes → P.226
		

Datum of dimension instruction

Please advise us on the dimensions of threaded holes for eye bolts and side surfaces with the datum at the right lower corner as shown in the right chart.



Proper way of specifying dimension




Improper way of specifying dimension

※ Relation of W and L shall be $W \leq L$

Datum plane positions for additionally processing plates and precision plates

When ordering additional processing of plates, specify dimensions by aligning the datum plane position of the precision plates to be processed with the datum plane position for additionally processing plates as shown below.



Datum plane position for additionally processing plates

Position of the datum plane of a precision plate

How to order

※ The catalog numbers used when ordering additional processing of plates are the same as those used when ordering additional processing of mold bases. When ordering additional processing plates, however, omit specifying plate codes as shown below:

● How to order additional processing of plates

E.g. Threaded hole (1 Hole)

Catalog No. — **M** — **L or R** — **H**
 MFK1A — M12 — H15

● How to order additional processing of mold bases

E.g. Threaded hole (1 hole)

Catalog No. — **Plate code** — **M** — **L or R** — **H**
 MFK1A — A — M12 — H15


When ordering additional processing of plates, omit specifying plate codes.

Mold Parts

General Table of Contents

General Table of Contents 1

Insert Blocks & Plates



Product name	High-precision plates	
Catalog No.	High-precision milling finish	High-precision grinding finish
Page	HF	HG
	P.262	P.264


Guide & Positioning Parts



Product name	Guide pins -head type-				Straight guide pins		
	With oil groove	No oil groove	Press-fit length designation type (no oil groove)	Press-fit length designation type (with spiral oil groove)	Press-fit length designation type (no oil groove)	Press-fit length designation type (with oil groove)	Press-fit length designation type (with spiral oil groove)
Catalog No.	M-GPA	M-GPH	M-GPHF	M-GPHFS	M-GPSF	M-GPSFR	M-GPSFS
Page	P.274	P.278	P.279	P.280	P.282	P.283	P.284



Guide bushings		Precision guide bushings		Guide bushings	
Shoulder type (no oil groove)	Straight type (no oil groove)	Shoulder type (With oil groove)	Straight type (With oil groove)	Shoulder type (With oil groove)	Straight type (With oil groove)
M-GBA	M-GBB	M-GBHF	M-GBSF	M-GBGF	M-GBRF
P.286	P.287	P.288	P.289	P.290	P.291



Guide bushing self lubricating, copper alloy type		Support pins				
	Straight type	Head type (With oil groove)	Head, press-fit length designation type (no oil groove)	Head, press-fit length designation type (with spiral oil groove)	Support pin collars	Support pin collars (for setting 5mm)
M-GBGDF	M-GBRDF	M-SPN	M-SPHF	M-SPHFS	M-SPC	M-SPD
P.292	P.293	P.294	P.295	P.296	P.297	



Tapered Lock Pins -bolt PL Installation type-		Tapered Lock Pins -basic type-		Tapered Lock Pins
Precision type	Super precision type	Precision type	Super precision type	Precision JIS type
M-TLC□	M-TLD□	M-TLG□	M-TLH□	M-TLB□
P.298		P.299		P.300



Mold opening control parts



Disc spacers					
For M-TLBS					
M-DSA	M-DSB	M-DSC	M-DSD	M-DSE	M-DSF
P.301			P.302		

Angular pins
M-AGA
P.303


Product name
Catalog No.
Page

Ground puller bolts	
M-PBCH	M-PBAH
P.308	P.310



Puller bolts					
			Puller bolt collars		
M-PBC	M-PBA	M-PBB	M-PCA	M-PCB	
P.312	P.313	P.314	P.315		

Tension links
M-HLA
P.316



Tension links
M-HLB
P.317

Bolts/retainers for tension link		
M-PBB	M-HRA	M-HRB
P.318		

PL Pullers
M-PLL
P.320

Mold opening prevention plates
M-OPB
P.321



Ejector, space parts



Mold opening prevention plates
M-OPC
P.321


Product name
Catalog No.
Page

Ejector guide pins		
Retaining ring type	JIS centering location type	JIS stuck-out type
M-EGA	M-EGB	M-EGC
P.326	P.327	P.328



Ejector guide bushings			
JIS type	Linear motion bearing type	Self lubricating, copper alloy type	Self lubricating, heat-resisting type
M-EBB	M-EBD	M-EBG	M-EBC
P.330	P.331	P.332	P.333

General Table of Contents 2



Ejector guide pins 5 μ m range type		
Centering location type	Stuck-out type	Bushings
M-EGBM	M-EGCM	M-EBBM
P.334	P.335	P.336


Return pins						
Head thick 8mm type	L dimension designation type (Unit 1 mm)		L dimension designation type (Unit 0.1 mm)		L dimension designation type (Unit 0.01 mm)	
	M-RP8B	M-RPN	M-RP8N	M-RPL	M-RP8L	M-RPM M-RP8M
P.337	P.338		P.340			



Support pillars		
Screw hole type	Dowel hole type	Bolt hole type
M-SRD	M-SRC	M-SRE
P.342	P.343	P.344

Spacer rings	
D-cut type	Circle type
M-SPR	M-SPR□B
P.345	

Stop pins	
	Heat treated type
M-STP	M-STPH
P.345	



Locating ring,
Sprue bushing,
runner & gate
parts




Stop rings
M-STR
P.345

Ejector rods
M-ERA
P.346

Product name
Catalog No.
Page

Locating rings		
M-LRA	M-LRH	M-LRC
P.352		



Locating rings		
M-LRB	M-LRJ	M-LRG
P.354		

Locating rings		
M-LRD	M-LRE	M-LRF
P.356		



Sprue bushings									
Miniature hot type	Cooling channel type	Bolt hole, straight type (Futaba original)		Shoulder, straight type (Futaba original)		Bolt hole, straight type (JIS)		Shoulder, straight type (JIS) type	
H-HSB	M-SBLH	M-SBA	M-SBC	M-SBB	M-SBD	M-SJA□	M-SJB□	M-SJC□	M-SJD□
P.358	P.362	P.372		P.373		P.374		P.376	



Sprue bushings blank
Bolt hole type
M-SAG
P.378

Sprue bushings			
Bolt hole, straight, head thick 10 mm type		Bolt hole, straight, head thick 15 mm type	
M-SBG	M-SBH	M-SBI	M-SBJ
P.380		P.382	



**Screw,
coil spring
parts**

Sprue bushings	
Shoulder, straight type	
M-SBE	M-SBF
P.384	

Runner lock pins
M-RLA
P.387

Pin-point gate bushings	
M-PGBA	M-PGBB
P.388	

Product name
Catalog No.
Page




Base spacers
M-BSA
P.394

Eye bolts
M-IBM
P.395

Coil springs			
High deflection FSB type	High deflection TY type	High deflection TR type	Strong coil spring TF type
M-FSB	M-TY	M-TR	P-TF
P.396	P.398	P.400	P.402

**Heat
insulator
sheet**



Product name
Catalog No.
Page

Heat insulator sheets					
Bakelite paper	Bakelite cloth	Basic grade	Heat resisting grade	High strength grade	High temperature resisting grade
M-DNAP	M-DNAC	M-DNBR	M-DNHR	M-DNSR	M-DNLR
P.410	P.412	P.414	P.416	P.418	P.420

Insert Blocks & Plates

Insert Blocks & Plates — Overview..... 260

High-Precision Plates

High-precision milling finish	HF.....	262
High-precision grinding finish	HG.....	264


Material

Category	Material name
Carbon steel	SS400
	S50C (for plates with a thickness of 25 mm or less) S55C (for plates with a thickness of over 25 mm)
pre-hardened steel	HPM7 PX5 HPM1 NAK55 NAK80 CENA1® DH2F FDAC HPM38 STAVAX ESR®
Quenched and tempered steel	SK3 SKS3 SKD11 ARK1® HPM31 PD613 SKD61 HPM38 STAVAX ESR®

Insert Blocks & Plate — Overview

CAVITY INSERT BLOCKS

High precision plates



- ① These plates have steel grade and precision grade that are best suited for applications such as insert blocks, etc.
- ② Industry's top level high-precision milling finish type ([Catalog No. HF](#)) and high-precision grinding finish type ([Catalog No. HG](#)) are available.
- ③ High-quality finishes and squareness will help customers significantly increase the efficiency and effectiveness of their subsequent additional machining work.
- ④ Product will be made to orders in the external dimensions specified in 0.01 mm units.

[Catalog No.](#) HF High-precision plate milling finish type

Dimensional limit deviations of X, Y and Z

Dimensional limit deviations can be changed according to the customer requirements.

Please specify desired values with tolerances shown in the charts below as limits.

Tolerance = upper deviation – lower deviation

Dimensional limit deviations can be specified at minimum in 0.01 mm steps.

Catalog No.	Shortest dimension of X, Y and Z (thickness)	Largest dimension of X, Y and Z (length)		
		20 or more and 200 or less	More than 200 and 300 or less	More than 300 and 500 or less
HF	10 or more and less than 20	Tolerance 0.02 mm at minimum	—	—
	20 or more and 100 or less		Tolerance	Tolerance
	More than 100 and 200 or less		0.03 mm at minimum	0.04 mm at minimum

Squareness

Catalog No.	Shortest dimension of X, Y and Z (thickness)	Largest dimension of X, Y and Z (length)		
		20 or more and 200 or less	More than 200 and 300 or less	More than 300 and 500 or less
HF	10 or more and less than 20	0.01 mm	—	—
	20 or more and 100 or less		0.015 mm	0.02 mm
	More than 100 and 200 or less			

Shipping & delivery

Catalog No.	Shipment		
	One business day shipping	Order reception time	Exceptional cases
HF		AM9:00~PM4:00	If an order is placed in the afternoon, and the size of the order is 200×200 to 300×500 mm square by 100 mm or less thick: → Two business day shipping For sizes exceeding the above, please inquire your nearest Futaba dealer or sale office

※ Depending on its material and size, your order may be shipped in two business days or later.

※ Depending on the time that the order is received and delivery location, delivery times may vary slightly.

[Catalog No.](#) HG High-precision plates grinding finish type

Dimensional limit deviations of X, Y and Z

Tolerance 0.01 mm at minimum

Dimensional limit deviations can be changed according to the customer requirements. Please specify desired values with tolerances shown in the charts below as limits.

Tolerance = upper deviation – lower deviation

Dimensional limit deviations can be specified at minimum in 0.005 mm steps.

Squareness... within 0.005 or less

Shipping & delivery

Catalog No.	Shipment	
	One business day shipping	Order reception time
HG	One business day shipping	AM9:00~PM4:00

※ Depending on its material and size, your order may be shipped in two business days or later.

※ Depending on the time that the order is received and delivery location, delivery times may vary slightly.

High-precision plate materials

Category	Material name	Hardness at delivery ^{*4}		Hardness for use ^{*4}	
		HRC	HB	HRC	HB
Carbon steel	SS400	—	116~150	—	116~150
	S50C ^{*1} S55C ^{*2}	—	170~240	—	170~240
Pre-hardend steel	HPM7	29~33	(279~311)	29~33	(279~311)
	PX5	30~33	(286~311)	30~33	(286~311)
	HPM1	37~41	(344~381)	37~41	(344~381)
	NAK55	37~43	(344~400)	37~43	(344~400)
	NAK80	37~43	(344~400)	37~43	(344~400)
	CENA1 [®]	37~42	(344~390)	37~42	(344~390)
	DH2F	38~42	(353~390)	38~42	(353~390)
	FDAC	38~42	(353~390)	38~42	(353~390)
	HPM38 ^{*3}	29~33	(279~311)	29~33	(279~311)
	STAVAX ESR [®] ^{*3}	27~35	(264~327)	27~35	(264~327)
Quenched and tempered steel	SK3	—	212 or less	58~63	—
	SKS3	—	217 or less	60~62	—
	SKD11	—	248 or less	58~63	—
	ARK1 [®]	—	248 or less	58~62	—
	HPM31	—	248 or less	55~60	—
	PD613	—	248 or less	56~61	—
	SKD61	—	229 or less	53 or less	—
	HPM38 ^{*3}	29~33	(279~311)	50~55	—
	STAVAX ESR [®] ^{*3}	27~35	(264~327)	50~55	—

*1. S50C is used when the smallest dimension (thickness) of X, Y and Z of the plate is 25 mm or less.

*2. S55C is used when the smallest dimension (thickness) of X, Y and Z of the plate is over 25 mm.



*3. HPM38 and STAVAX ESR[®] are prehardened steel. We recommend to perform quenching and tempering to obtain appropriate hardness of 50 to 54 HRC before use if you apply mirror finish or precision texture to the surfaces. Although the hardness of 50 to 54 HRC is obtained at any quenching temperature below 500°C, the lower the quenching temperature is, the more superior corrosion resistant property can be achieved.

*4. The above material property (hardness) data is subject to change without notice due to improvement by the material manufacturers. Use the data only as reference (the values in the above table are as of September 2005). The hardness values in parentheses are those converted from hardness test values that are managed in the manufacturing process.

High Precision Plates High-Precision Milling Finish

CAVITY INSERT BLOCKS

Catalog No.	Material
HF	See right page



※ The surface roughness symbols in the above chart denote calculated average roughness (Ra)

Dimensional limit deviations of X, Y and Z

Dimensional limit deviations can be changed according to the customer requirements.

Please specify your desired values with the tolerances shown in the charts below as limits.

Tolerance = upper deviation – lower deviation

Dimensional limit deviations can be specified at minimum in 0.01 mm steps.

Shortest dimension of X, Y and Z (thickness)	Largest dimension of X, Y and Z (length)		
	20 or more and 200 or less	More than 200 and 300 or less	More than 300 and 500 or less
10 or more and less than 20	Tolerance 0.02 mm at minimum	—	—
20 or more and 100 or less		Tolerance 0.03 mm at minimum	Tolerance 0.04 mm at minimum
More than 100 and 200 or less			

Squareness

Shortest dimension of X, Y and Z (thickness)	Largest dimension of X, Y and Z (length)		
	20 or more and 200 or less	More than 200 and 300 or less	More than 300 and 500 or less
10 or more and less than 20	0.01 mm	—	—
20 or more and 100 or less		0.015 mm	0.02 mm
More than 100 and 200 or less			

※ Datum plane for squareness shall be the one with a larger surface area of the two planes that form a right angle.

Chamfering around the entire circumference

Chamfer dimension

C0 C0.2 C0.5 C1 C2

※ If not specified, C0.2 is used.

Production size

20 × 20 × 10 ~ 200 × 200 × 100 ~ 400 × 500 × 200

※ The dimension can be specified at minimum in 0.01 mm units.

※ Depending on material or size, we may not be able to accept your order. Inquire your nearest Futaba dealers or sales office.

Material

Category	Material name
Carbon steel	SS400
	S50C (for plates with a thickness of 25 mm or less) S55C (for plates with a thickness of over 25 mm)
Prehardened steel	HPM7, PX5, HPM1, NAK55, NAK80, CENA1® DH2F, FDAC, HPM38*2, STAVAX ESR®*2
Quenched and tempered steel	SK3, SKS3, SKD11, ARK1® HPM31*1, PD613, SKD61, HPM38*2, STAVAX ESR®*2

※ The materials indicated in **red** are used for production of plates with a size of up to 200×200×100.

*1. HPM31 is used when the smallest dimension of X, Y and Z (thickness) of plates is 50 mm or less.

*2. One point advice: HPM38 and STAVAX ESR® are prehardened steel. We recommend to perform quenching and tempering treatment to obtain appropriate hardness of 50 to 54 HRC before use if you apply mirror finish or precision texture to the surfaces. Although the hardness of 50 to 54 HRC is obtained at any quenching temperature below 500°C, the lower the quenching temperature is, the more superior corrosion resistant property can be achieved.



How to order

Product will be made to orders in the external dimensions specified in 0.01 mm units.

Catalog No.

HF

HF

Material name

HPM1

S55C

X Upper deviation
Lower deviation

150.01

88.00

×

Y Upper deviation
Lower deviation

99.98

77.00

×

Z Upper deviation
Lower deviation

60.00

66.00

×

Chamfering specification

C1



Shipping

One
business
day
shipping

Order reception time

AM9:00~PM4:00

Exceptional cases

If an order is placed in the afternoon, and the size of the order is 200×200 to 300×500 mm square by 100 mm or less thick: → Two business day shipping

For sizes exceeding the above, please inquire your nearest Futaba dealer or sale office

※ Depending on its material and size, your order may be shipped in two business days or later.

※ Depending on the time that the order is received and delivery location, delivery times may vary slightly.

Price



Contact your nearest Futaba dealer or sales office.

High-Precision Plates

High-precision grinding finish

CAVITY INSERT BLOCKS

Catalog No.	Material
HG	See right page



※ The surface roughness symbols in the above chart denote calculated average roughness (Ra)

Dimensional limit deviations of X, Y and Z

Tolerance 0.01 mm at minimum

Dimensional limit deviation tolerance can be changed according to the customer requirements.

Tolerance = upper deviation – lower deviation

Dimensional limit deviations can be specified at minimum in 0.005 mm steps.

Squareness

Within 0.005 or less

※ Datum plane for squareness shall be the one with a larger surface area of the two planes that form a right angle.

Chamfering around the entire circumference.

Chamfer dimension

C0 C0.2 C0.5 C1 C2

※ If not specified, **C0** is used.

Production size

20 × 20 × 10 ~ 200 × 200 × 100

※ The dimension can be specified at minimum in 0.01 mm units.

※ Depending on material or size, we may not be able to accept your order.

Inquire your nearest Futaba dealers or sales office.

Material

Category	Material name
Carbon steel	SS400
	S50C (for plates with a thickness of 25 mm or less)
	S55C (for plates with a thickness of over 25 mm)
Prehardened steel	HPM7, PX5, HPM1, NAK55, NAK80, CENA1®
	DH2F, FDAC, HPM38 *2, STAVAX ESR® *2
Quenched and tempered steel	SK3, SKS3, SKD11, ARK1®
	HPM31 *1, PD613, SKD61, HPM38 *2, STAVAX ESR® *2

*1. HPM31 is used when the smallest dimension of X, Y and Z (thickness) of plates is 50 mm or less.

*2. One point advice: HPM38 and STAVAX ESR® are prehardened steel. We recommend to perform quenching and tempering treatment to obtain appropriate hardness of 50 to 54 HRC before use if you apply mirror finish or precision texture to the surfaces. Although the hardness of 50 to 54 HRC is obtained at any quenching temperature below 500°C, the lower the quenching temperature is, the more superior corrosion resistant property can be achieved.



How to order

Product will be made to orders in the external dimensions specified in 0.01 mm units.

Catalog No.	Material name	X Upper deviation Lower deviation	Y Upper deviation Lower deviation	Z Upper deviation Lower deviation	Chamfering specification
HG	HPM1	120 $\begin{smallmatrix} 0 \\ -0.01 \end{smallmatrix}$	60 $\begin{smallmatrix} 0 \\ -0.01 \end{smallmatrix}$	40 ± 0.005	
HG	STAVAX ESR	40 $\begin{smallmatrix} 0 \\ -0.02 \end{smallmatrix}$	30 $\begin{smallmatrix} 0 \\ -0.02 \end{smallmatrix}$	39.99 $\begin{smallmatrix} +0.01 \\ 0 \end{smallmatrix}$	C0.2



Shipping

One business day shipping	Order reception time
	AM9:00~PM4:00

※ Depending on its material and size, your order may be shipped in two business days or later.

※ Depending on the time that the order is received and delivery location, delivery times may vary slightly.

Price

Contact your nearest Futaba dealer or sales office.

Guide & Positioning Parts

Guide & Position Parts Overview.....	268
--------------------------------------	-----

Guide Pins

Head type (With Oil Groove)	M-GPA.....	274
Head type (No Oil Groove)	M-GPH	278
Head, Press-Fit Length Designation Type (No Oil Groove)	M-GPHF	279
Head, Press-Fit Length Designation Type (With Spiral Oil Groove)	M-GPHFS.....	280

Straight Guide Pins

Straight, Press-Fit Length Designation Type (No Oil Groove)	M-GPSF	282
Straight, Press-Fit Length Designation Type (With Oil Groove)	M-GPSFR.....	283
Straight, Press-Fit Length Designation Type (With Spiral Oil Groove)	M-GPSFS	284

Guide Bushings

Shoulder Type (No Oil Groove)	M-GBA	286
Straight Type (No Oil Groove)	M-GBB	287

Precision Guide Bushings

Shoulder Type (With Oil Groove)	M-GBHF	288
Straight Type (With Oil Groove)	M-GBSF	289

Guide Bushings

Shoulder Type (With Oil Groove)	M-GBGF	290
Straight Type (With Oil Groove)	M-GBRF	291

Guide Bushings, Self Lubricating, Copper Alloy Type

Shoulder Type	M-GBGDF	292
Straight Type	M-GBRDF	293

Support Pins

Head Type (With Oil Groove)	M-SPN.....	294
Head, Press-Fit Length Designation Type (No Oil Groove)	M-SPHF	295
Head, Press-Fit Length Designation Type (With Spiral Oil Groove)	M-SPHFS	296
Support Pin Collars	M-SPC.....	297
Support Pin Collars For Setting 5mm	M-SPD.....	297

Tapered Lock Pins

Bolt PL Installation Type(Precision)	M-TLC□.....	298
Bolt PL Installation Type (Super Precision)	M-TLD□.....	298
Basic Type (Precision)	M-TLG□.....	299
Basic Type (Super Precision)	M-TLH□.....	299
JIS Type (Precision)	M-TLB□.....	300
Disc Spacers for M-TLBS	M-DSA M-DSB M-DSC.....	301
Disc Spacers	M-DSD M-DSE M-DSF	302

Angular Pins

M-AGA.....	303
------------	-----

Guide & Positioning Parts Overview 1

Guide pins –head type-

Additional processing to MDC



Catalog No.	M-GPA
Type	With oil groove
Shipping	In-stock item
Page	P.274

Additional processing to MDC



Catalog No.	M-GPH
Type	No oil groove
Shipping	In-stock item
Page	P.278

Additional processing to MDC

Press-fit length
designation type

Catalog No.	M-GPHF
Type	No oil groove
Shipping	In 3-5 days
Page	P.279

Additional processing to MDC

Press-fit length
designation type

Catalog No.	M-GPHFS
Type	With spiral oil groove
Shipping	In 5 days
Page	P.280

Straight guide pins

Additional processing to MDC

Press-fit length
designation type

Catalog No.	M-GPSF
Type	No oil groove
Shipping	d25 - 40 In 3 days d50 In 5 days
Page	P.282

Additional processing to MDC

Press-fit length
designation type

Catalog No.	M-GPSFR
Type	With oil groove
Shipping	In 5 days
Page	P.283

Additional processing to MDC

Press-fit length
designation type

Catalog No.	M-GPSFS
Type	With spiral oil groove
Shipping	In 5 days
Page	P.284

Guide bushings

Additional processing to MDC

Shoulder type



Catalog No.	M-GBA
Type	No oil groove
Shipping	In-stock item
Page	P.286

Additional processing to MDC

Straight type



Catalog No.	M-GBB
Type	No oil groove
Shipping	In-stock item
Page	P.287

Additional processing to MDC

Shoulder type



Catalog No.	M-GBHF
Type	With oil groove
Shipping	In-stock item
Page	P.288

Additional processing to MDC

Straight type



Catalog No.	M-GBSF
Type	With oil groove
Shipping	In-stock item
Page	P.289

Guide bushings

Additional processing to MDC

Shoulder type



Catalog No.	M-GBGF
Type	With oil groove
Shipping	In-stock item
Page	P.290

Additional processing to MDC

Straight type



Catalog No.	M-GBRF
Type	With oil groove
Shipping	In-stock item
Page	P.291

Additional processing to MDC

Shoulder type



Catalog No.	M-GBGDF
Type	Copper alloy (with solid lubricant)
Shipping	In 3 days
Page	P.292

Additional processing to MDC

Straight type



Catalog No.	M-GBRDF
Type	Copper alloy (with solid lubricant)
Shipping	In 3 days
Page	P.293

Guide bushings self lubricating copper alloy type

Additional processing to MDC denotes the parts that support additional processing to mold bases.
Shipping schedules are shown in business days (excluding the day of order).

Support pins

Additional processing to MDC

**Press-fit length
designation type**



Catalog No.	M-SPN
Type	With oil groove
Shipping	In-stock item
Page	P.294

Additional processing to MDC

**Press-fit length
designation type**



Catalog No.	M-SPHF
Type	No oil groove
Shipping	L ≤ 450 In 3 days L > 450 In 5 days
Page	P.295

Additional processing to MDC

**Press-fit length
designation type**



Catalog No.	M-SPHFS
Type	With spiral oil groove
Shipping	In 5 days
Page	P.296

Support pin callars

Additional processing to MDC



Catalog No.	M-SPC
Type	In-stock item
Shipping	P.297

Additional processing to MDC



Catalog No.	M-SPD
Type	For setting 5mm
Shipping	In-stock item
Page	P.297

Tapered Lock Pins PL installation type

Additional processing to MDC



Catalog No.	M-TLC□	M-TLD□
Type	Precision type	Super precision type
Shipping	In-stock item	
Page	P.298	

Tapered Lock Pins basic type

Additional processing to MDC



Catalog No.	M-TLG□	M-TLH□
Type	Precision type	Super precision type
Shipping	In-stock item	
Page	P.299	

Tapered Lock Pins JIS type (precision)

Additional processing to MDC



Catalog No.	M-TLB□
Type	JIS type (precision)
Shipping	In-stock item
Page	P.300

Disc spacers

Additional processing to MDC



Catalog No.	M-DSA	M-DSD	M-DSB	M-DSE	M-DSC	M-DSF
Type	For M-TLBS		For M-TLBS		For M-TLBS	
Shipping	In-stock item					
Page	P.301	P.302	P.301	P.302	P.301	P.302








Angular pins



Catalog No.	M-AGA
Shipping	In-stock item
Page	P.303

Guide & Positioning Parts Overview 2

Guide pin, support pin and guide bushing combination table

Guide bushings Guide pins Support pins	No oil groove		Precision, with oil groove		With oil groove		Self lubricating, copper alloy type	
								
	M-GBA → P.286	M-GBB → P.287	M-GBHF → P.288	M-GBSF → P.289	M-GBGF → P.290	M-GBRF → P.291	M-GBGDF → P.292	M-GBRDF → P.293
Guide pin M-GPA With ring oil groove → P.274 	Combination used for standard mold bases							
Guide pin M-GPH No oil groove → P.278 			Recommended combination		Recommended combination			
Guide pin M-GPHF No oil groove → P.279 			Recommended combination		Recommended combination		Recommended combination	
Guide pin M-GPHFS With spiral oil groove → P.280 	Recommended combination							
Guide pin M-GPSF No oil groove → P.282 			Recommended combination		Recommended combination		Recommended combination	
Guide pin M-GPSFR With oil groove → P.283 	Recommended combination							
Guide pin M-GPSFS With spiral oil groove → P.284 	Recommended combination							
Support pin M-SPN With oil groove → P.294 	Combination used for standard mold bases							
Support pin M-SPHF No oil groove → P.295 			Combining these parts is not allowed.		Recommended combination		Recommended combination	
Support pin M-SPHFS With spiral oil groove → P.296 	Recommended combination							

Clearance of guide pin, support pin and guide bushing combinations

Clearance table by type for combinations of guide pin with oil groove and guide bushings without oil grooves

(Unit: mm)

Guide pin			Guide bushing	Clearance of the combination	Guide pin				Guide bushing	Clearance of the combination
Dia.	M-GPA With oil groove	Limit deviations of sliding section	M-GBA M-GBB No oil groove Limit deviations of ID		M-GPHFS With spiral oil groove	M-GPSFR With ring oil groove	M-GPSFS With spiral oil groove	Limit deviations of sliding section	M-GBA M-GBB Without oil groove Limit deviations of ID	
12	○	−0.016	+0.017	0.022 to 0.044	○			−0.020	+0.017	0.026 to 0.042
16	○	−0.027	+0.006		○			−0.025	+0.006	
20	○	−0.020 −0.033	+0.020 +0.007	0.027 to 0.053	○			−0.025 −0.030	+0.020 +0.007	0.032 to 0.050
25	○				○	○				
30	○				○	○				
35	○	−0.025 −0.041	+0.025 +0.009	0.034 to 0.066	○	○	○	−0.030 −0.035	+0.025 +0.009	0.039 to 0.060
40	○				○	○	−0.030	0.039 to 0.065		
50	○				○	○	−0.040			
60	○	−0.040	0.049 to 0.080							
70	○	−0.055								

Clearance table by type for combinations of guide pins without oil groove and self-lubricating guide bushings with oil groove

(Unit: mm)

Guide pin					Precision guide bushing	Clearance of the combination	Guide bushing	Clearance of the combination	Guide bushing	Clearance of the combination
Dia.	M-GPH No oil groove	M-GPHF No oil groove	M-GPSF No oil groove	Limit deviations of sliding section	M-GBHF M-GBSF With oil groove Limit deviations of ID		M-GBGF M-GBRF With oil groove Limit deviations of ID		M-GBGDF M-GBRDF Self lubricating copper alloy Limit deviation tolerance of ID	
8	○			-0.015	0		+0.014	0.020		
10	○			-0.020	-0.005		+0.005	~0.034		
12	○	○				0.010				
16		○		-0.020	-0.005	~0.020	+0.017	0.026	+0.017	0.026
20		○		-0.025	-0.010		+0.006	~0.042	+0.006	~0.042
25		○	○	-0.030	-0.015		+0.020	0.032	+0.020	0.032
30		○	○				+0.007	~0.050	+0.007	~0.050
35		○	○	-0.030				0.039		0.039
40		○	○	-0.035			+0.025	~0.060	+0.025	~0.060
50		○	○	-0.040			+0.009	0.039	+0.009	0.039
								~0.065		~0.065

Clearance table by type for combinations of support pins and guide bushings

(Unit: mm)

Support pin		Guide bushing	Clearance of the combination	Support pin	Guide bushing	Clearance of the combination	Support pin	Guide bushing	Clearance of the combination	Support pin	Guide bushing	Clearance of the combination
Dia.	M-SPN With ring oil groove	M-GBA M-GBB No oil groove		M-SPHFS With spiral oil groove	M-GBA M-GBB Without oil groove		M-SPHF No oil groove	M-GBGF M-GBRF With oil groove		M-SPHF No oil groove	M-GBGDF M-GBRDF Self lubricating copper alloy	
	Limit deviations of sliding section	Limit deviations of ID		Limit deviations of sliding section	Limit deviations of ID		Limit deviations of sliding section	Limit deviations of ID		Limit deviations of sliding section	Limit deviations of ID	
12												
16	-0.016 -0.027	+0.017 +0.006	0.022 ~0.044	-0.020 -0.025	+0.017 +0.006	0.026 ~0.042	-0.020 -0.025	+0.017 +0.006	0.026 ~0.042	-0.020 -0.025		
											+0.017 +0.006	0.026 ~0.042
20												
25	-0.020 -0.033	+0.020 +0.007	0.027 ~0.053	-0.025 -0.030	+0.020 +0.007	0.032 ~0.050	-0.025 -0.030	+0.020 +0.007	0.032 ~0.050	-0.025 -0.030	+0.020 +0.007	0.032 ~0.050
30												
35												
	-0.025 -0.041	+0.025 +0.009	0.034 ~0.066	-0.030 -0.035	+0.025 +0.009	0.039 ~0.060	-0.030 -0.035	+0.025 +0.009	0.039 ~0.060	-0.030 -0.035	+0.025 +0.009	0.039 ~0.060
40				-0.030 -0.040		0.039 ~0.065	-0.030 -0.040		0.039 ~0.065	-0.030 -0.040		0.039 ~0.065


Guide & Positioning Parts Overview 3

About use of guide pins (no oil groove) & precision guide bushings

Clearance table for combinations of guide pins (no oil groove) and precision guide bushings (Unit: mm)



Guide pin (no oil groove)				Precision guide bushing	Clearance of the combination
Dia	M-GPH	M-GPHF	M-GPSF	M-GBHF M-GBSF Limit deviations of ID	
8	○			0	0.010 ~0.020
10	○			-0.005	
12	○	○		-0.005	
16		○		-0.010	
20		○		-0.010	
25		○	○	-0.015	

Pull-out prevention measure for guide bushing



d	M
8 10 12	M4
16	M5
20	M6
25	M8



Air vent



When using guide pins without oil grooves M-GPH, M-GPHF and M-GPSF in combination with precision guide bushings M-GBHF and M-GBSF, the clearance between a pin and a bushing is small as shown in the above table. Therefore, please take the following matters into account in designing:

- As the press-fit allowance becomes larger as shown in the graph below, the inside diameter (ID) of the guide bushing will be deformed and the clearance becomes even smaller. As a small clearance could cause scuffing, install the guide bushing in a light press-fit to prevent it. Also, take a pull-out prevention measure such as retaining the guide bushing with a screw from the side as shown in the above chart.
- As the clearance between a guide pin and a guide bushing is small, we recommend to provide an air vent as shown in the above chart.
- Ensure to eliminate the difference in temperature of retainer plates in which guide pins and guide bushing bushings are installed respectively during the molding operations. Differential expansion of both plates due to the temperature difference could compromise the pitches between the guide pin holes and the guide bushing holes, resulting in scuffing.

Press-fit allowance and inside diameter deformation amount of precision guide bushings:



※ The values indicated above are an example of measurements and not guaranteed values.

※ The amount of deformation is also affected by the size of guide bushing (diameter, length and thickness) and the precision of guide bushing and installation hole.

How to order installation of guide pins without oil groove and precision guide bushings in the mold bases → P.42

- Advise us on the details via MOLDZUKAN® or with a drawing, etc.
- For plates in which to install guide pins and precision guide bushing, surface grinding will be applied. The limit deviations of plate thickness is required. Please specify it.
- To maintain the accuracy of holes in plates, we also recommend rough machining of pockets and slide core grooves, etc.
- We recommend to provide an air vent in the plate in which to install guide bushings.

Calculation of thermal expansion of retainer plates

In order to obtain good molded parts, the temperature control of molds is important. If a difference in temperature occurs between the retainer plate with guide pins installed and the retainer plate with guide bushings installed, differential thermal expansion of the plates can change the positions of guide pins and guide bushings and may cause insufficient motions or scuffing.

Dimensional change due to thermal expansion can be calculated by using a formula shown below:

$$\lambda = \alpha \times L_o \times (t - t_o)$$

λ : increase in length (mm)

α : expansion coefficient ($1/^\circ\text{C}$)

L_o : original length (mm)

t : final temperature ($^\circ\text{C}$)

t_o : original temperature ($^\circ\text{C}$)

Calculation example

Supposing that there is a difference of 10°C in temperature between the retainer plate in which guide pins are installed and the plate in which the guide bushings are installed, and the pitch of guide pins is 150 mm, calculate how much difference occurs between the pitch of pins and that of guide bushings.

For this example, we will assume the material used is S55C, and thermal expansion coefficient is $12.6 \times 10^{-6}/^\circ\text{C}$.


α : thermal expansion coefficient ($1/^\circ\text{C}$) $\rightarrow 12.6 \times 10^{-6}/^\circ\text{C}$

L_o : original length (mm) $\rightarrow 150 \text{ mm}$

$t - t_o$: difference in temperature ($^\circ\text{C}$) $\rightarrow 10^\circ\text{C}$

$$\begin{aligned}\lambda &= \alpha \times L_o \times (t - t_o) \\ &= 12.6 \times 10^{-6} \times 150 \times 10 \\ &= 0.0189 \text{ mm}\end{aligned}$$

If there is a difference of 10°C in temperature of retainer plates, a difference of 0.0189 mm in dimension occurs between Pitch A and Pitch B.



Thermal expansion coefficients of main steel materials used for mold bases

Material	Thermal expansion coefficient $\times 10^{-6}/^\circ\text{C}$
S55C	12.6 (25 to 200°C)
PX5	12.7 (30 to 200°C)
HPM1	11.8 (20 to 200°C)
NAK55	12.5 (20 to 200°C)
NAK80	12.5 (20 to 200°C)


※ Thermal expansion coefficients other than the above $\rightarrow$ P.448

Guide Pins Head Type (With Oil Groove)

GUIDE PINS

Additional processing to mold bases → P.44

Catalog No.	Material	Hardness after heat treatment
M-GPA	SUJ2	60 to 64HRC (high frequency quenching)



Cylindricity of d

L	50 or less	51 to 100	101 or more
Tolerance	0.002	0.003	0.004

Circularity (roundness) of d

d	30 or less	31 or more
Tolerance	0.002	0.0025

 Catalog No.	d		d1		D	H	E
	Dimension	Limit deviations	Dimension	Limit deviations			
M-GPA	12	−0.016	12	+0.018	17	5	5
	16	−0.027	16	+0.007	20	6	
	20	−0.020 −0.033	20	+0.021 +0.008	25		
	25		25		30	8	8
	30		30		35		
	35	−0.025 −0.041	35	+0.025 +0.009	40	10	10
	40		40		45		
	50		50		56	12	12
	60	−0.040	60		66	15	15
	70	−0.055	70		76		

How to order

Catalog No.

M-GPA

d × L × L1
16 × 47 × 19



In-stock item

L1 dimension d12 to 30

L \ d	12			16			20			25			30		
37	19			19			19								
42	19			19			19								
47	19			19			19			24					
52	19			19			19			24					
57	19	29		19	29		19	34		24			29		
62	19	29		19	29		19	34		24			29		
67	19	29		19	29		19	34		24			29		
72	19	29		19	29		19	39		24			34		
77	19	29	39	19	29		19	39		24			29		
82	19	29		19	29		19	39		24	49		34		
87	19	29		19	29	34	19	39		24	39		29	49	
92	29			19	29	34	19	39		24	49		29	49	
97	29			19	29	39	19	39		24	49		29	49	
102	29			29	39		19	39	49	29	39		34	49	
107	29			19	29	39	19	39	49	24	39		29	49	
112				39			19	39	49	29	59		34	59	
117	29			24	29	39	19	39	49	24	49		29	59	
122				39			29	39	49	24	49	59	34	59	
127	29			29	39		19	39	49	24	49	59	29	49	
132				29			29	49		24	49	59	34	49	
137				39			19	39	49	24	49	59	29	59	69
142				29			49			49	59		34	59	69
147				39			29	49		24	49	59	29	59	69
152				39			49			49	59		34	59	69
157				39			49			24	49	59	29	59	69
162							39			59			59	69	
167				39			49			24	49	59	29	59	69
172										59			59		
177							49			49	59		29	59	69
182										59			59		
187							49			59			29	59	69
192										59			69		
197							49			59			39	69	
202										59			69		
207							49			59			59	69	
212										59			69		
217										59			69		
222													69		
227										59			69		
232													59		
237										59			69		
242															
247										59			69		
252															
257													69		
262															
267													69		
272															
277													69		

Guide Pins Head Type (With Oil Groove)

GUIDE PINS

L1 dimension d35 to 70

L \ d	35			40			50			60			70		
77	39			39											
82															
87	39			39											
92															
97	39			39			49								
102															
107	39	59		39			49								
112	39														
117	39	59		39			49								
122	39														
127	39	59		39	59		49	59							
132	39														
137	39	59		39	59		49	69							
142	39	59													
147	39	69		39	69		49	79							
152	39	59													
157	39	69		39	69		49	69	89						
162	39	59													
167	39	59	69	39	69	79	49	89							
172	39	59													
177	39	59	69	39	69	79	49	89							
182	59														
187	39	69	79	39	69	79	49	99							
192	59														
197	39	59	79	39	59	79	49	99		99			99		
202	69														
207	39	59	79	39	59	79	59	99		99			99		
212	69														
217	49	69		49	69		59	99		99			99		
222	69														
227	59	79		59	79		59	99		99			99		
232	69														
237	69	79		59	79		69	99		99			99		
242	69														
247	69			69			69	99		99			99		
252	69														
257	69			69			79	119		99			99		
262	69														
267	79			69			89	119		99			99		
272	69														
277	79			69			99	119		99			99		
287	79			69			99	119		99			99		
297	79			69			119			99			99		
307	79			79			119			99			99		
317	79			79			119			99			99		
327							119			99			99		
337							119			99			99		
347							119			99			99		
357							119			99			99		

Price list Unit price in yen


L \ d	12	16	20	25	30	35	40	50	60	70
37	290	310	360							
42	290	310	360							
47	290	310	370	450						
52	310	340	380	470						
57	320	340	380	490	600					
62	320	350	390	500	620					
67	320	350	400	520	620					
72	330	370	420	540	640					
77	340	380	440	570	670	890	1,660			
82	350	390	450	590	680					
87	360	400	460	620	700	940	1,710			
92	370	400	470	630	740					
97	390	420	480	640	770	970	1,750	3,040		
102	410	460	530	660	810					
107	420	460	530	690	850	1,000	1,800	3,180		
112		470	540	720	860	1,020				
117	440	470	540	740	880	1,050	1,850	3,310		
122		480	570	750	910	1,070				
127	460	480	590	760	920	1,100	1,900	3,450		
132		500	610	780	940	1,110				
137		500	630	790	970	1,130	1,950	3,580		
142		600	660	820	1,000	1,150				
147		620	690	860	1,050	1,170	2,000	3,720		
152		640	730	880	1,070	1,200				
157		690	780	900	1,100	1,240	2,050	3,860		
162			830	920	1,120	1,260				
167		780	900	950	1,130	1,280	2,110	3,990		
172				990	1,160	1,330				
177			970	1,050	1,170	1,350	2,170	4,130		
182				1,090	1,210	1,370				
187			1,020	1,160	1,240	1,390	2,230	4,260		
192				1,180	1,260	1,430				
197			1,080	1,190	1,290	1,450	2,300	4,400	5,530	6,930
202				1,250	1,320	1,480				
207			1,130	1,330	1,330	1,510	2,370	4,530	5,730	7,190
212				1,350	1,380	1,590				
217				1,360	1,450	1,660	2,580	4,670	5,930	7,460
222					1,460	1,670				
227				1,450	1,500	1,690	2,650	4,800	6,110	7,720
232					1,500	1,690				
237				1,650	1,690	1,750	2,780	4,940	6,310	7,990
242						1,870				
247				1,760	1,800	1,890	3,090	5,080	6,510	8,260
252						1,920				
257					1,870	1,950	3,210	5,210	6,710	8,520
262						1,970				
267					1,940	2,000	3,420	5,350	6,900	8,790
272						2,030				
277					2,000	2,050	3,750	5,480	7,100	9,050
287						2,110	3,850	5,620	7,290	9,310
297						2,160	4,020	5,750	7,480	9,580
307						2,210	4,190	5,890	7,690	9,840
317						2,280	4,370	6,030	7,880	10,120
327								6,160	8,070	10,380
337								6,300	8,270	10,640
347								6,430	8,460	10,920
357								6,570	8,660	11,180

Precision Guide Pins Head Type (No Oil Groove)

GUIDE PINS

Additional processing to mold bases → P.42 & 44

Catalog No.	Material	Hardness after heat treatment
M-GPH	SUJ2	60 to 64HRC (high frequency quenching)



DIMM	Limit deviations	DIMM	Limit deviations	D	H	E
8	-0.015 -0.020	8	+0.015 +0.006	11	5	4
10		10		13		
12	-0.020 -0.025	12	+0.018 +0.007	17		5

Cylindricity of d

L	50 or less	51 to 100	101 or more
Tolerance	0.002	0.003	0.004

Circularity (roundness) of d

d	12 or less
Tolerance	0.002

Catalog No.	d	L	L1	Unit price in yen
M-GPH	8	30 35 40 45	14	380
		50 55 60	19	
	10	30 35 40 45	14	380
		50 55 60	19	
		65 70	24	
		75	24	400
		80	14 24	
		90 100 110 120	14	500
	12	30 35 40 45	14	400
		50 55 60	19	
		65 70 75	24	
		80	19 24	
		85	24	600
		90	19 24	
		100 110 120	19	
		130 140 150	19	700

How to order

Catalog No. × ×
M-GPH 10 × 80 × 24




In-stock item

Precision Guide Pins Head, Press-Fit Length Designation Type (No Oil Groove)

GUIDE PINS

Additional processing to mold bases → P.42 & 44

Catalog No.	Material	Hardness after heat treatment
M-GPHF	SUJ2	60 to 64HRC (high frequency quenching)



d		d1		D	H	E
DIMM	Limit deviations	DIMM	Limit deviations			
12	-0.020	12	+0.018	17	5	5
16	-0.025	16	+0.007	20	6	
20	-0.025	20	+0.021	25	8	8
25	-0.030	25	+0.008	30		
30	-0.030	30		35		
35	-0.030/-0.035	35	+0.025	40	10	10
40	-0.030	40	+0.009	45		
50	-0.040	50		56		

Cylindricity of d

L	50 or less	51 to 100	101 or more
Tolerance	0.002	0.003	0.004

Circularity (roundness) of d

d	30 or less	31 or more
Tolerance	0.002	0.0025

Catalog No.	d	L In 5mm steps	L1 *1 In 1mm steps	Unit price in yen
M-GPHF	12	30 ~ 40	$10 \leq L1 \leq L \times 0.6$	630
		45 ~ 80		720
		85 ~ 120		840
		125 ~ 160		990
	16	30 ~ 40	$11 \leq L1 \leq L \times 0.6$	780
		45 ~ 80		900
		85 ~ 120		1,040
		125 ~ 160		1,200
	20	165 ~ 200		1,430
		30 ~ 50	$11 \leq L1 \leq L \times 0.6$	910
		55 ~ 90		1,040
		95 ~ 150		1,240
		155 ~ 200		1,480
	25	205 ~ 240		2,030
		40 ~ 60	$13 \leq L1 \leq L \times 0.7$	1,030
		65 ~ 110		1,300
		115 ~ 160		1,560
		165 ~ 200		1,940
		205 ~ 260		2,570
		265 ~ 300		3,260
		305 ~ 350		3,500

*1. If press-fit (L1) section is not required, specify L1 = 0.

Catalog No.	d	L In 5mm steps	L1 *1 In 1mm steps	Unit price in yen
M-GPHF	30	50 ~ 60	$13 \leq L1 \leq L \times 0.7$	1,280
		65 ~ 100		1,510
		105 ~ 160		1,740
		165 ~ 200		2,200
		205 ~ 260		2,800
		265 ~ 300		3,500
		305 ~ 350		3,700
		355 ~ 400		4,100
	35	60 ~ 100	$13 \leq L1 \leq L \times 0.7$	1,530
		105 ~ 160		1,850
		165 ~ 200		2,300
		205 ~ 260		2,900
		265 ~ 330		3,800
		335 ~ 400		4,500
	40	405 ~ 450	$15 \leq L1 \leq L \times 0.7$	5,000
		455 ~ 460		6,000
		80 ~ 140		2,500
		145 ~ 190		2,800
		195 ~ 240		3,500
		245 ~ 300		4,500
	50	305 ~ 380	$17 \leq L1 \leq L \times 0.7$	5,800
		385 ~ 450		6,500
		455 ~ 500		7,200
		100 ~ 150		3,800
		155 ~ 190		4,400
		195 ~ 240		5,500
		245 ~ 300		6,200
		305 ~ 360		7,000
		365 ~ 400		8,500
		405 ~ 460		10,000
		465 ~ 500		12,000
		505 ~ 550		13,500

How to order

Catalog No.

 d × L × L1
 M-GPHF 25 × 180 × 79

Shipping

If d12 to 40 and L ≤ 450:

Shipped out in 3 business days (excluding the day of order)

If d50 and L > 450:


Shipped out in 5 business days (excluding the day of order)

Precision Guide Pins Head, Press-Fit Length Designation Type (With Spiral Oil Groove)

GUIDE PINS

Additional processing to mold bases → P.44

Catalog No.	Material	Hardness after heat treatment
M-GPHFS	SUJ2	60 to 64HRC (high frequency quenching)



d		d1		D	H	E	Q
DIMM	Limit deviations	DIMM	Limit deviations				
12	-0.020	12	+0.018	17	5		
16	-0.025	16	+0.007	20	6	5	10
20	-0.025	20	+0.021	25			
25	-0.030	25	+0.008	30		8	13
30	-0.030	30		35			
35	-0.030	35	+0.025	40		10	15
40	-0.030	40	+0.009	45	10		
50	-0.040	50		56	12	12	17

Cylindricity of d

L	50 or less	51 to 100	101 or more
Tolerance	0.002	0.003	0.004

Circularity (roundness) of d

d	30 or less	31 or more
Tolerance	0.002	0.0025

Catalog No.	d	L In 5mm steps	L1 *1 In 1mm steps	S *2 In 1mm steps	Unit price in yen	P
M-GPHFS	12	50 ~ 70	$10 \leq L1 \leq (L - 30)$	$25 \leq S \leq L - (L1 + 5)$	1,420	10
		75 ~ 80	$10 \leq L1 \leq (L - 38)$	$33 \leq S \leq L - (L1 + 5)$	1,420	15
		85 ~ 120			1,540	
		125 ~ 160	$10 \leq L1 \leq (L - 45)$	$40 \leq S \leq L - (L1 + 5)$	1,690	20
		165 ~ 180			1,980	
	16	185 ~ 200	$10 \leq L1 \leq (L - 53)$	$48 \leq S \leq L - (L1 + 5)$	1,980	25
		50 ~ 70	$11 \leq L1 \leq (L - 30)$	$25 \leq S \leq L - (L1 + 5)$	1,600	10
		75 ~ 80	$11 \leq L1 \leq (L - 38)$	$33 \leq S \leq L - (L1 + 5)$	1,600	15
		85 ~ 120			1,740	
		125 ~ 160	$11 \leq L1 \leq (L - 45)$	$40 \leq S \leq L - (L1 + 5)$	1,900	20
	20	165 ~ 180			2,130	
		185 ~ 200	$11 \leq L1 \leq (L - 53)$	$48 \leq S \leq L - (L1 + 5)$	2,130	25
		205 ~ 250			2,470	
		50	$11 \leq L1 \leq (L - 30)$	$25 \leq S \leq L - (L1 + 5)$	1,610	10
		55 ~ 70			1,740	
		75 ~ 90	$11 \leq L1 \leq (L - 38)$	$33 \leq S \leq L - (L1 + 5)$	1,740	15
		95 ~ 120			1,940	
		125 ~ 150	$11 \leq L1 \leq (L - 45)$	$40 \leq S \leq L - (L1 + 5)$	1,940	20
		155 ~ 180			2,180	
		185 ~ 200			2,180	
		205 ~ 260	$11 \leq L1 \leq (L - 53)$	$48 \leq S \leq L - (L1 + 5)$	2,730	25
		265 ~ 300			3,350	

How to order

Catalog No. d × L × L1 N S

M-GPHFS 30 × 300 × 119 N 150



Orders will be shipped out in 5 business days (excluding the day of order).

Catalog No.	d	L In 5mm steps	L1 *1 In 1mm steps	S *2 In 1mm steps	Unit price in yen	P
M-GPHFS	25	50~60	$13 \leq L1 \leq (L-33)$	$28 \leq S \leq L - (L1+5)$	1,730	10
		65~70			2,000	
		75~110	$13 \leq L1 \leq (L-41)$	$36 \leq S \leq L - (L1+5)$	2,000	15
		115~120			2,260	
		125~160	$13 \leq L1 \leq (L-48)$	$43 \leq S \leq L - (L1+5)$	2,260	20
		165~180			2,640	
		185~200	$13 \leq L1 \leq (L-56)$	$51 \leq S \leq L - (L1+5)$	2,640	25
		205~260			3,270	
		265~300			3,960	
		305~350			4,200	
	30	50~60	$13 \leq L1 \leq (L-33)$	$28 \leq S \leq L - (L1+5)$	1,980	10
		65~70			2,210	
		75~100	$13 \leq L1 \leq (L-41)$	$36 \leq S \leq L - (L1+5)$	2,210	15
		105~120			2,440	
		125~160	$13 \leq L1 \leq (L-48)$	$43 \leq S \leq L - (L1+5)$	2,440	20
		165~180			2,900	
		185~200	$13 \leq L1 \leq (L-56)$	$51 \leq S \leq L - (L1+5)$	2,900	25
		205~260			3,500	
		265~300			4,200	
		305~350			4,400	
	35	60~70	$13 \leq L1 \leq (L-35)$	$30 \leq S \leq L - (L1+5)$	2,530	10
		75~100			2,530	
		105~120	$13 \leq L1 \leq (L-43)$	$38 \leq S \leq L - (L1+5)$	2,850	15
		125~160			2,850	
		165~180	$13 \leq L1 \leq (L-50)$	$45 \leq S \leq L - (L1+5)$	3,300	20
		185~200			3,300	
		205~260	$13 \leq L1 \leq (L-58)$	$53 \leq S \leq L - (L1+5)$	3,900	25
		265~300			4,800	
		305~330			4,800	
		335~400			5,500	
	40	405~450	$13 \leq L1 \leq (L-65)$	$60 \leq S \leq L - (L1+5)$	6,000	30
		455~460			7,000	
		80~120	$15 \leq L1 \leq (L-43)$	$38 \leq S \leq L - (L1+5)$	3,500	15
		125~140			3,500	
		145~180	$15 \leq L1 \leq (L-50)$	$45 \leq S \leq L - (L1+5)$	3,800	20
		185~190			3,800	
		195~240	$15 \leq L1 \leq (L-58)$	$53 \leq S \leq L - (L1+5)$	4,500	25
		245~300			5,500	
		305~380			6,800	
		385~450			7,500	
	50	455~500	$15 \leq L1 \leq (L-65)$	$60 \leq S \leq L - (L1+5)$	8,200	30
		100~120			4,800	
		125~150	$17 \leq L1 \leq (L-45)$	$40 \leq S \leq L - (L1+5)$	4,800	15
		155~180			5,400	
		185~190	$17 \leq L1 \leq (L-52)$	$47 \leq S \leq L - (L1+5)$	5,400	20
		195~240			5,400	
		245~300	$17 \leq L1 \leq (L-60)$	$55 \leq S \leq L - (L1+5)$	6,500	25
		305~360			7,200	
		365~400			8,000	
		405~460			9,500	
		465~500	$17 \leq L1 \leq (L-67)$	$62 \leq S \leq L - (L1+5)$	11,000	30
		505~550			13,000	
					14,500	

*1. If press-fit (L1) section is not required, specify L1=0.

*2. The number of turns of spiral grooves is set so that they make at minimum one and a half turns.


When L1=0 is specified, the range of S dimension that can be specified is the range derived by assigning the minimum value of L1 dimension designation range to L1 portion of each S dimension calculation formula shown above.

Precision Guide Pins Straight, Press-Fit Length Designation Type (No Oil Groove)

GUIDE PINS

Additional processing to mold bases → P.46

Catalog No.	Material	Hardness after heat treatment
M-GPSF	SUJ2	60 to 64HRC (high frequency quenching)



d		d1		M	F	E
DIMM	Limit deviations	DIMM	Limit deviations			
25	-0.025	25	+0.017	M12	24	8
30	-0.030	30	+0.008			
35	-0.030	35	+0.020	M16	32	10
40	-0.030	40	+0.009			
50	-0.040	50				

Cylindricity of d

L	60 to 100	101 or more
Tolerance	0.003	0.004

Circularity (roundness) of d

d	30 or less	31 or more
Tolerance	0.002	0.0025

Catalog No.	d	L In 5mm steps	L1*1 In 1mm steps	Unit price in yen
M-GPSF	25	60~110	$10 \leq L1 \leq L \times 0.6$	1,300
		115~160		1,500
		165~200		1,800
		205~260		2,300
	30	70~100		1,400
		105~160		1,700
		165~200		2,000
		205~260		2,600
	35	100~140		2,800
		145~190		3,100
		195~240		3,800
		245~300		4,800
	40	100~140		2,800
		145~190		3,100
		195~240		3,800
		245~300		4,800
	50	100~150		4,100
		155~190		4,700
		195~240		5,800
		245~300		6,500
		305~360		7,300
		365~400		8,800

*1. If press-fit (L1) section is not required, specify L1=0.

If L1=0 is specified, press-fit lead section will not be machined.

How to order

Catalog No. d × L × L1 N + Optional processing

M-GPSF 40 × 240 × 79
M-GPSF 25 × 190 × 59 N + DKC



d25~40:

d50:

shipped out in 3 business days (excluding the day of order).

shipped out in 5 business days (excluding the day of order).

Optional processing

Code	Specification	Unit price in yen	
DKC	Change the limit deviations of press-fit lead section d1 to $d1^{+0.005}_0$	d30 or less	d35 or more
		300	500


Code	Specification	Unit price in yen
DN	Eliminate press-fit lead section	— 300

Precision Guide Pins Straight, Press-Fit Length Designation Type (With Oil Groove)

GUIDE PINS

Additional processing to mold bases → P.46

Catalog No.	Material	Hardness after heat treatment
M-GPSFR	SUJ2	60 to 64HRC (high frequency quenching)



d		d1		M	F	E
DIMM	Limit deviations	DIMM	Limit deviations			
25	-0.025	25	+0.017	M12	24	8
30	-0.030	30	+0.008			
35	-0.030 -0.035	35	+0.020	M16	32	10
40	-0.030	40	+0.009			
50	-0.040	50				
						12

Cylindricity of d

L	60 to 100	101 or more
Tolerance	0.003	0.004

Circularity (roundness) of d

d	30 or less	31 or more
Tolerance	0.002	0.0025

Catalog No.	d	L In 5mm steps	L1*1	Q	Unit price in yen	P
M-GPSFR	25	60～70	Specify in 1 mm steps	Specify number of oil grooves	1,600	15
		75～110			1,800	20
		115～160			2,100	25
		165～180			2,600	
		185～200			2,900	
		205～260				3,300
	30	70	See lower right	See lower right	1,700	15
		75～100			2,000	20
		105～120			2,300	25
		125～160				
		165～200				
		205～260				
	35	100～140			3,300	25
		145～180			3,600	
		185～190			4,300	
		195～240			5,300	30
		245～300				

*1. If press-fit (L1) section is not required, specify L1=0.
If L1=0 is specified, press-fit lead section will not be machined.

Catalog No.	d	L In 5mm steps	L1*1	Q	Unit price in yen	P
M-GPSFR	40	100~140	Specify in 1 mm steps	Specify number of oil grooves	3,300	25
		145~180			3,600	
		185~190			4,300	30
		195~240			5,300	
		245~300			4,600	25
	50	100~120	See below	See below	4,600	
		125~150			5,200	
		155~180			6,300	35
		185~190			7,000	
		195~240			7,800	40
		245~300			9,300	
		305~360				
		365~400				

L1 designation range $10 \leq L1 \leq L \times 0.6$

d	Designation range of the number of oil grooves Q*2
25	$1 \leq Q \leq (L - L1 - 9)/P$
30	$1 \leq Q \leq (L - L1 - 10)/P$
35 40 50	$1 \leq Q \leq (L - L1 - 11)/P$

*2. When L1=0 is specified, the designation range of the number of oil grooves Q is the range derived by assigning 10 to the L1 portion of each formula for calculating the number of oil grooves shown above.

How to order

Catalog No.	d	L	L1	N	Q	Optional processing
M-GPSFR	40	290	149	N	4	
M-GPSFR	30	240	119	N	3	DKC



Orders will be shipped out in 5 business days (excluding the day of order).

Optional processing

Code	Specification	Unit price in yen
DKC		d30 or less
		d35 or more
		300 500


Code	Specification	Unit price in yen
DN		—300

Precision Guide Pins Straight, Press-Fit Length Designation Type (With Spiral Oil Groove)

GUIDE PINS

Additional processing to mold bases → P.46

Catalog No.	Material	Hardness after heat treatment
M-GPSFS	SUJ2	60 to 64HRC (high frequency quenching)



d		d1		M	F	E	Q
DIMM	Limit deviations	DIMM	Limit deviations				
25	-0.025	25	+0.017	M12	24	8	13
30	-0.030	30	+0.008				
35	-0.030 -0.035	35	+0.020 +0.009	M16	32	10	15
40	-0.030	40					
50	-0.040	50				12	17

Cylindricity of d

L	60 to 100	101 or more
Tolerance	0.003	0.004

Circularity (roundness) of d

d	30 or less	31 or more
Tolerance	0.002	0.0025

How to order

Catalog No.

d × **L** × **L1** N **S** + **Optional processing**

M-GPSFS

30 × 240 × 119 N 100



M-GPSFS

50 × 380 × 149 N 200 + **DKC**

Shipping

Orders will be shipped out in 5 business days (excluding the day of order).

Optional processing

Option code	Specification	Unit price in yen	
		d30 or less	d35 or more
DKC	 Change the limit deviations of press-fit lead section d1 to $d1 + 0.005$	300	500
DN	 Eliminate the processing of press-fit lead section	—300	

Catalog No.	d	L In 5mm steps	L1 *1 In 1mm steps	S *2 In 1mm steps	Unit price in yen	P
M-GPSFS	25	60～70	$10 \leq L1 \leq (L-33)$	$28 \leq S \leq L-(L1+5)$	2,000	10
		75～110	$10 \leq L1 \leq (L-41)$	$36 \leq S \leq L-(L1+5)$	2,200	15
		115～120	$10 \leq L1 \leq (L-48)$	$43 \leq S \leq L-(L1+5)$		20
		125～160		2,500	25	
		165～180	$10 \leq L1 \leq (L-56)$	$51 \leq S \leq L-(L1+5)$	3,000	
		185～200				
		205～260				
	30	70	$10 \leq L1 \leq (L-33)$	$28 \leq S \leq L-(L1+5)$	2,100	10
		75～100	$10 \leq L1 \leq (L-41)$	$36 \leq S \leq L-(L1+5)$	2,400	15
		105～120	$10 \leq L1 \leq (L-48)$	$43 \leq S \leq L-(L1+5)$		20
		125～160		2,700	25	
		165～180	$10 \leq L1 \leq (L-56)$	$51 \leq S \leq L-(L1+5)$	3,300	
		185～200				
		205～260				
	35	100～120	$10 \leq L1 \leq (L-43)$	$38 \leq S \leq L-(L1+5)$	3,800	15
		125～140	$10 \leq L1 \leq (L-50)$	$45 \leq S \leq L-(L1+5)$	4,100	20
		145～180	$10 \leq L1 \leq (L-58)$	$53 \leq S \leq L-(L1+5)$		25
		185～190		5,800		
		195～240				
		245～300				
	40	100～120	$10 \leq L1 \leq (L-43)$	$38 \leq S \leq L-(L1+5)$	3,800	15
		125～140	$10 \leq L1 \leq (L-50)$	$45 \leq S \leq L-(L1+5)$	4,100	20
		145～180	$10 \leq L1 \leq (L-58)$	$53 \leq S \leq L-(L1+5)$		25
		185～190		5,800		
		195～240				
		245～300				
	50	100～120	$10 \leq L1 \leq (L-45)$	$40 \leq S \leq L-(L1+5)$	5,100	15
		125～150	$10 \leq L1 \leq (L-52)$	$47 \leq S \leq L-(L1+5)$	5,700	20
		155～180	$10 \leq L1 \leq (L-60)$	$55 \leq S \leq L-(L1+5)$		25
		185～190		6,800		
		195～240			7,500	
		245～300			8,300	
		305～360	$10 \leq L1 \leq (L-67)$	$62 \leq S \leq L-(L1+5)$	9,800	30
		365～400				

*1. If press-fit (L1) section is not required, specify $L1=0$.

*2. The number of turns of spiral grooves is set so that they make at minimum one and a half turns.


When $L1=0$ is specified, the range of S dimension that can be specified is the range derived by assigning the minimum value of L1 dimension designation range to L1 portion of each S dimension calculation formula shown above.

Guide Bushings No Oil Groove

GUIDE BUSHES

Additional processing to mold bases → P.44

Catalog No.	Material	Hardness after heat treatment
M-GBA	SUJ2	58 to 62HRC



Cylindricity of d

L	30 or less	31 to 50	51 or more
Tolerance	0.003	0.0035	0.004

Circularity (roundness) of d

d	30 or less	31 to 40	41 or more
Tolerance	0.0025	0.003	0.0035

Catalog No.	d	Unit price in yen				
		L				
		19	24	29	34	39
M-GBA	12	400	430	460	550	640
	16	430	460	500	530	620
	20	480	510	560	610	670
	25		630	680	730	800
	30		800	800	870	960
	35			1,110	1,110	1,110
	40			1,450		1,450
	50					
	60					
	70					

d		d1		D	H	L1
DIMM	Limit deviations	DIMM	Limit deviations			
12	+0.017 +0.006	18	+0.018 +0.007	22	5	L ≤ 29 → L1 = L L ≥ 34 → L1 = 29
16		25	+0.021	30	6	L ≤ 39 → L1 = L L ≥ 44 → L1 = 35
20		30	+0.008	35	8	L ≤ 49 → L1 = L L ≥ 54 → L1 = 40
25	+0.020	35		40		L ≤ 59 → L1 = L L ≥ 64 → L1 = 50
30	+0.007	42	+0.025	47		L ≤ 69 → L1 = L L ≥ 74 → L1 = 60
35		48	+0.009	54	10	L ≤ 79 → L1 = L L ≥ 89 → L1 = 70
40		55		61		L ≤ 89 → L1 = L L ≥ 99 → L1 = 80
50	+0.025	70	+0.030	76	12	L ≤ 99 → L1 = L L ≥ 109 → L1 = 100
60	+0.009	80	+0.011	86		L ≤ 129 → L1 = L L ≥ 149 → L1 = 140
70		90		96	15	L ≤ 129 → L1 = L L ≥ 149 → L1 = 140

d	Unit price in yen																	
	L																	
	44	49	54	59	64	69	74	79	89	99	109	119	129	139	149	159	179	199
12		840		1,110														
16	730	730	790	790		910		1,210										
20	770	770	860	860	960	960	1,220	1,220	1,360	1,470								
25	910	910	1,040	1,040	1,180	1,180	1,310	1,310	1,540	1,660	2,000	2,240						
30	1,120	1,120	1,280	1,280	1,450	1,450	1,640	1,640	1,770	1,920	2,140	2,420	2,760	2,940	3,250			
35	1,250	1,250	1,440	1,440		1,670		1,910	2,090	2,280	2,450	2,580	2,890	3,230	3,550			
40		1,530		1,730		1,990		2,290	2,520	2,760	3,010	3,250	3,550	3,840	4,030	4,220		
50		3,420		4,100		4,780		5,470	6,150	6,840	7,520	8,200	8,890	9,570	10,260	10,940		
60										8,110	8,940	9,770	10,600		12,250	13,080	14,740	16,400
70										9,330	10,280	11,230	12,180		14,070	15,020	16,910	18,880

How to order

Catalog No.

M-GBA

d

25

×

L


24




In-stock item

How to install guide bushings

When installing guide bushings, apply some press-fitting oil in the hole and the surface of the guide bushing, and then install it straightly by applying even force using a tool shown on right or pad. Uneven force or tilting may lead to insufficient precision or damage.



Catalog No.	Material	Hardness after heat treatment
M-GBB	SUJ2	58 to 62HRC



Cylindricity of d

L	30 or less	31 to 50	51 or more
Tolerance	0.003	0.0035	0.004

Circularity (roundness) of d

d	30 or less	31 to 40	41 or more
Tolerance	0.0025	0.003	0.0035

d		d1		M	L1
DIMM	Limit deviations	DIMM	Limit deviations		
12	+0.017 +0.006	18	+0.018 +0.007	4	$L \leq 29 \rightarrow L1 = L$ $L \geq 34 \rightarrow L1 = 29$
16		25	+0.021 +0.008	$L \leq 19 \rightarrow M = 4$	$L \leq 49 \rightarrow L1 = L$
20		30		$L \geq 24 \rightarrow M = 6$	$L \leq 69 \rightarrow L1 = L$
25	+0.020 +0.007	35		8 (For M-GBB25 × 14, M = 6)	$L \leq 79 \rightarrow L1 = L$
30		42	+0.025 +0.009		$L \leq 99 \rightarrow L1 = L$
35		48			$L \leq 99 \rightarrow L1 = L$
40		55			$L \leq 99 \rightarrow L1 = L$
50	+0.025 +0.009	70	+0.030 +0.011	10	$L \leq 99 \rightarrow L1 = L$
60		80			$L \leq 129 \rightarrow L1 = L$
70		90			$L \leq 129 \rightarrow L1 = L$

Catalog No.	d	Unit price in yen														
		L														
		9	14	19	24	29	34	39	44	49	59	69	79	89	99	129
M-GBB	12	290	340	360	400	440	550									
	16		340	360	400	440	550	580	700	700						
	20		360	380	450	480	550	620	730	730	850	970				
	25		520	530	540	580	640	710	810	810	930	1,050	1,170			
	30			690	700	720	780	860	1,010	1,010	1,140	1,370	1,550	1,700	1,850	
	35			790	800	810	890	980		1,130	1,320	1,510	1,730	1,880	2,030	
	40				1,060	1,080	1,100	1,140		1,310	1,490	1,700	1,890	2,080	2,250	
	50					3,100		3,100		3,210	3,560	3,910	4,250	4,600	4,950	
	60										4,150	4,490				6,510
	70											4,820				7,130

How to order

Catalog No.

M-GBB

d × L


16 × 19



In-stock items

How to install guide bushings

When installing guide bushings, apply some press-fitting oil in the hole and the surface of the guide bushing, and then install it straightly by applying even force using a tool shown on right or pad. Uneven force or tilting may lead to insufficient precision or damage.




Precision Guide Bushings With Oil Groove

GUIDE BUSHES

Additional processing to mold bases → P.42

Catalog No.	Material	Hardness after heat treatment
M-GBHF	SUJ2	58 to 62HRC



Cylindricity of d

L	30 or less	31 to 50	51 or more
Tolerance	0.003	0.0035	0.004

Circularity (roundness) of d

d	25 or less
Tolerance	0.0025

d		d1		D	H	L1
DIMM	Limit deviations	DIMM	Limit deviations			
8	0	12	+0.010 +0.005	14	5	$L = 14 \rightarrow L1 = L$ $L \geq 19 \rightarrow L1 = 15$
10	-0.005	14		16		$L \leq 19 \rightarrow L1 = L$ $L \geq 24 \rightarrow L1 = 20$
12	-0.005	18		22		$L \leq 24 \rightarrow L1 = L$ $L \geq 29 \rightarrow L1 = 25$
16	-0.010	25		30	8	$L \leq 34 \rightarrow L1 = L$ $L \geq 39 \rightarrow L1 = 30$
20	-0.010	30		35		$L \leq 39 \rightarrow L1 = L$ $L \geq 49 \rightarrow L1 = 40$
25	-0.015	35		40		$L \leq 49 \rightarrow L1 = L$ $L \geq 59 \rightarrow L1 = 50$

Catalog No.	d	Unit price in yen										
		L										
		14	19	24	29	34	39	44	49	59	69	79
M-GBHF	8	740	740	830								
	10	740	740	830	830	980	980					
	12	780	780	780	880	880	880	1,030	1,030			
	16		800	800	800	900	900		1,050			
	20		950	950	950	950	1,100		1,100	1,250	1,250	
	25			1,200	1,200	1,200	1,200		1,350	1,350	1,600	1,600

How to order

Catalog No.

M-GBHF

d × L


16 × 39




In-stock item

How to install guide bushings

When installing guide bushings, apply some press-fitting oil in the hole and the surface of the guide bushing, and then install it straightly by applying even force using a tool shown on right or pad. Uneven force or tilting may lead to insufficient precision or damage.



Catalog No.	Material	Hardness after heat treatment
M-GBSF	SUJ2	58 to 62HRC



Cylindricity of d

L	30 or less	31 to 50
Tolerance	0.003	0.0035

Circularity (roundness) of d

d	25 or less
Tolerance	0.0025

d		d1		M	L1
DIMM	Limit deviations	DIMM	Limit deviations		
8	0	12	+0.010 +0.005	3	$L \leq 14 \rightarrow L1 = L$ $L \geq 19 \rightarrow L1 = 15$
10	-0.005	14			$L \leq 19 \rightarrow L1 = L$ $L \geq 24 \rightarrow L1 = 20$
12	-0.005	18		4	$L \leq 24 \rightarrow L1 = L$ $L \geq 29 \rightarrow L1 = 25$
16	-0.010	25			$L \leq 34 \rightarrow L1 = L$ $L \geq 39 \rightarrow L1 = 30$
20	-0.010	30		8	$L \leq 39 \rightarrow L1 = L$ $L \geq 49 \rightarrow L1 = 40$
25	-0.015	35			$L \leq 49 \rightarrow L1 = L$

Catalog No.	d	Unit price in yen							
		L							
		9	14	19	24	29	34	39	49
M-GBSF	8	650	650	650	700				
	10	650	650	650	700	700	800	800	
	12	680	680	680	730	730	830	830	
	16		700	700	700	750	750	850	
	20		800	800	800	800	950	950	950
	25			950	950	950	950	1,150	1,150

How to order

Catalog No.

M-GBSF

d × L


20 × 34



In-stock item

How to install guide bushings

When installing guide bushings, apply some press-fitting oil in the hole and the surface of the guide bushing, and then install it straightly by applying even force using a tool shown on right or pad. Uneven force or tilting may lead to insufficient precision or damage.




Guide Bushings With Oil Groove

GUIDE BUSHES

Additional processing to mold bases → P.44

Catalog No.	Material	Hardness after heat treatment
M-GBGF	SUJ2	58 to 62HRC



Cylindricity of d

L	30 or less	31 to 50	51 or more
Tolerance	0.003	0.0035	0.004

Circularity (roundness) of d

d	30 or less	31 to 40	41 or more
Tolerance	0.0025	0.003	0.0035

Catalog No.	d	Unit price in yen		
		L		
		14	19	24
M-GBGF	8	720	720	770
	10	460	460	560
	12	460	460	460
	16		480	480
	20		550	550
	25			680
	30			
	35			
	40			
	50			

d		d1		D	H	L1
DIMM	Limit deviations	DIMM	Limit deviations			
8	+0.014	12	+0.018	14	5	L=14→L1=L L≥19→L1=15
10	+0.005	14	+0.007	16		L≤19→L1=L L≥24→L1=20
12	+0.017	18		22		L≤24→L1=L L≥29→L1=25
16	+0.006	25	+0.021	30	6	L≤34→L1=L L≥39→L1=30
20		30	+0.008	35	8	L≤39→L1=L L≥49→L1=40
25	+0.020	35		40		L≤49→L1=L L≥59→L1=50
25	+0.007	42	+0.025	47		L≤59→L1=L L≥69→L1=60
30		48	+0.009	54	10	L≤69→L1=L L≥79→L1=70
35	+0.025	55	+0.030	61		L≤79→L1=L L≥89→L1=80
40	+0.009	70	+0.011	76		L≤99→L1=L L≥109→L1=100
50					12	

d	Unit price in yen															
	L															
	29	34	39	44	49	59	69	79	89	99	109	119	129	139	149	159
8																
10	560	590	590													
12	590	590	590	650	650	900										
16	480	590	590		700	950	950	1,300								
20	550	550	720		720	1,010	1,010	1,010	1,500	1,500						
25	680	680	680		940	940	1,500	1,500	1,500	1,500	2,110	2,110				
30	1,250	1,250	1,250		1,510	1,510	1,820	1,820	1,820	1,820	2,630	2,630	2,630			
35			1,370		1,370	1,760	1,760	1,890	1,890	3,330	3,330	3,330	3,330	3,700	3,700	
40			1,400		1,830	1,830	2,780	2,780	2,780	2,780	3,790	3,790	3,790	4,500	4,500	
50						4,300	4,300	4,300	4,300	6,370	6,370	6,370	8,720		8,720	11,000



How to order

Catalog No.

M-GBGF

d

25

×

L

49




Shipping


In-stock item

How to install guide bushings

When installing guide bushings, apply some press-fitting oil in the hole and the surface of the guide bushing, and then install it straightly by applying even force using a tool shown on right or pad. Uneven force or tilting may lead to insufficient precision or damage.



Catalog No.	Material	Hardness after heat treatment
M-GBRF	SUJ2	58 to 62HRC



Cylindricity of d

L	30 or less	31 to 50	51 or more
Tolerance	0.003	0.0035	0.004

Circularity (roundness) of d

d	30 or less	31 to 40	41 or more
Tolerance	0.0025	0.003	0.0035

d		d1		M	L1
DIMM	Limit deviations	DIMM	Limit deviations		
8	+0.014	12	+0.018	3	$L \leq 14 \rightarrow L1 = L$ $L \geq 19 \rightarrow L1 = 15$
10	+0.005	14	+0.007		$L \leq 19 \rightarrow L1 = L$ $L \geq 24 \rightarrow L1 = 20$
12	+0.017	18	+0.007		$L \leq 24 \rightarrow L1 = L$ $L \geq 29 \rightarrow L1 = 25$
16	+0.006	25	+0.021	$L \leq 19 \rightarrow M = 4$ $L \geq 24 \rightarrow M = 6$	$L \leq 34 \rightarrow L1 = L$ $L \geq 39 \rightarrow L1 = 30$
20	+0.006	30	+0.008		$L \leq 39 \rightarrow L1 = L$ $L \geq 49 \rightarrow L1 = 40$
25	+0.020	35	+0.025	8	L1 = L
30	+0.007	42	+0.009		
35	+0.007	48	+0.009		
40	+0.025	55	+0.030		
50	+0.009	70	+0.011	10	

Catalog No.	d	Unit price in yen												
		L												
		9	14	19	24	29	34	39	49	59	69	79	89	99
M-GBRF	8	420	420	420	500									
	10	350	350	350	420	420	480	480						
	12	350	350	350	420	420	480	480						
	16		350	350	350	440	440	560						
	20		430	430	430	430	580	580	580					
	25			550	550	550	550	790	790					
	30				1,170	1,170	1,170	1,170	1,420	1,420				
	35					1,190	1,190	1,190	1,370	1,370	1,670			
	40					1,210	1,210	1,210	1,680	1,680	2,210	2,210		
	50							1,900	2,820	2,820	4,080	4,080	4,080	5,300

How to order

Catalog No.

M-GBRF




In-stock item

d × L
16 × 39

How to install guide bushings

When installing guide bushings, apply some press-fitting oil in the hole and the surface of the guide bushing, and then install it straightly by applying even force using a tool shown on right or pad. Uneven force or tilting may lead to insufficient precision or damage.




Guide Bushings Self lubricating Copper Alloy Type

GUIDE BUSHES

Additional processing to mold bases → P.44

Catalog No.	Material
M-GBGDF	Copper alloy (with solid lubricant)



d		d1		D	H	L1
DIMM	Limit deviations	DIMM	Limit deviations			
16	+0.017 +0.006	25	+0.021 +0.008	30	6	$L \leq 29 \rightarrow L1 = L$ $L \geq 34 \rightarrow L1 = 30$
20	+0.020 +0.007	30	+0.025 +0.009	35	8	$L \leq 39 \rightarrow L1 = L$ $L \geq 49 \rightarrow L1 = 40$
25		35		40		$L \leq 49 \rightarrow L1 = L$ $L \geq 59 \rightarrow L1 = 50$
30		42		47		$L \leq 59 \rightarrow L1 = L$ $L \geq 69 \rightarrow L1 = 60$
35	+0.025 +0.009	48	+0.030 +0.011	54	10	$L \leq 69 \rightarrow L1 = L$ $L \geq 79 \rightarrow L1 = 70$
40		55		61		$L \leq 79 \rightarrow L1 = L$ $L \geq 89 \rightarrow L1 = 80$
50		70		76		$L \leq 89 \rightarrow L1 = L$ $L \geq 99 \rightarrow L1 = 90$

Catalog No.	d	Unit price in yen												
		L												
		19	24	29	34	39	49	59	69	79	89	99	109	119
M-GBGDF	16	2,100	2,100	2,100	2,550	2,550	2,800							
	20	2,350	2,350	2,350	2,350	2,850	2,850	3,400						
	25		2,750	2,750	2,750	2,750	3,600	3,600	4,300					
	30			3,100	3,100	3,100	4,000	4,000	5,000	5,000				
	35					4,300	4,300	5,300	5,300	6,200	6,200	7,700		
	40					4,500	5,400	5,400	7,200	7,200	7,200	7,200	9,200	
	50						7,900	7,900	7,900	7,900	10,400	10,400	12,400	12,400



How to order

Catalog No.

d

×

L




Shipping


Orders will be shipped out in
3 business days. (excluding the
day of order)

How to install guide bushings

When installing guide bushings, apply some press-fitting oil in the hole and the surface of the guide bushing, and then install it straightly by applying even force using a tool shown on right or pad. Uneven force or tilting may lead to insufficient precision or damage.



Catalog No.	Material
M-GBRDF	Copper alloy (with solid lubricant)



d		d1		M	L1
DIMM	Limit deviations	DIMM	Limit deviations		
16	+0.017 +0.006	25	+0.021 +0.008	L ≤ 19 → M=4 L ≥ 24 → M=6	L ≤ 34 → L1=L L = 39 → L1=35
20	+0.020 +0.007	30	+0.025 +0.009	8	L ≤ 39 → L1=L L = 49 → L1=40
25		35			L ≤ 49 → L1=L L = 59 → L1=50
30		42			L ≤ 59 → L1=L L ≥ 69 → L1=60
35	+0.025 +0.009	48	+0.030 +0.011	10	L ≤ 69 → L1=L L = 79 → L1=70
40		55			L ≤ 79 → L1=L L = 89 → L1=80
50		70			L ≤ 89 → L1=L L = 99 → L1=90

Catalog No.	d	Unit price in yen											
		L											
		14	19	24	29	34	39	49	59	69	79	89	99
M-GBRDF	16	1,500	1,500	1,500	1,800	1,800	2,000						
	20	1,700	1,700	1,700	1,700	2,000	2,000	2,300					
	25			1,900	1,900	2,300	2,300	2,300	3,200				
	30				2,600	3,200	3,200	3,200	4,800	4,800	4,800		
	35				3,000	3,000	3,000	3,600	3,600	5,500	5,500		
	40						3,200	4,400	4,400	5,700	5,700	7,200	
	50							5,500	5,500	7,000	7,000	9,000	9,000

How to order

Catalog No.

M-GBRDF

d

×

L

50

×

69




Shipping

Orders will be shipped out in
3 business days. (excluding the
day of order)

How to install guide bushings

When installing guide bushings, apply some press-fitting oil in the hole and the surface of the guide bushing, and then install it straightly by applying even force using a tool shown on right or pad. Uneven force or tilting may lead to insufficient precision or damage.




Support Pins Head Type (With Oil Groove)

SUPPORT PINS

Additional processing to mold bases → P.58

Catalog No.	Material	Hardness after heat treatment
M-SPN	SUJ2	60 to 64HRC (high frequency quenching)



d		d1		D	H	L1	M	F
DIMM	Limit deviations	DIMM	Limit deviations					
12	-0.016	12	+0.018	17	6	24	M6	12
16	-0.027	16	+0.007	20	8		M10	20
20		20		25	10	29	M12	25
25	-0.020	25	+0.021	30	12	34	M14	30
30	-0.033	30	+0.008	35	14	44		
35	-0.025	35	+0.025	40	16	49	M16	35
40	-0.041	40	+0.009	45	18	59		

Cylindricity of d

L	51 to 100	101 or more
Tolerance	0.003	0.004

Circularity (roundness) of d

d	30 or less	31 or more
Tolerance	0.002	0.0025

Catalog No.	d	Unit price in yen																	
		L																	
		60	70	80	90	100	110	120	130	140	150	160	170	180	190	200	210	220	230
M-SPN	12	420	440	450	490	520	540	580			660								
	16			450	480	520	580	630	680	740	800	900	950	990	1,040	1,100	1,150	1,200	
	20				510	630	660	700	790	840	920	1,000	1,060	1,100	1,180	1,290	1,450	1,600	1,690
	25					840	910	950	1,000	1,050	1,100	1,160	1,210	1,280	1,360	1,430	1,510	1,570	1,690
	30								1,170	1,290	1,410	1,540	1,660	1,710	1,820	2,020	2,160	2,280	2,400
	35											1,980	2,210	2,450	2,680	2,920	3,150	3,370	3,600
	40																3,630	3,870	4,100

d	Unit price in yen																	
	L																	
	240	250	260	270	280	290	300	310	320	330	340	350	360	380	400	420	440	460
20	1,780	1,930	2,090	2,250	2,400													
25	1,840	1,970	2,400	2,580	2,790	2,990	3,190		3,590									
30	2,510	2,640	2,760	2,990	3,230	3,470	3,700	4,150	4,370	4,580	4,800	5,020	5,250	5,500	5,750			
35	3,830	4,070	4,300	4,580	4,770	4,990	5,240	5,480	5,710	5,940	6,170	6,400	6,620	7,080	7,540	8,000	8,500	9,000
40	4,590	4,830	5,070	5,380	5,560	5,790	6,030	7,410	7,690	7,960	8,240	8,390	8,630	9,110	9,600	10,100	10,600	11,100

How to order

Catalog No. d × L N + Optional processing

M-SPN 20 × 200

M-SPN 30 × 260 N + WKC



In-stock item

Orders requiring optional processing will be shipped out in 3 business days. (excluding the day of order)

Check

Support pin deflection calculation

→ Technical reference in P.445

Optional processing

Option code	Specification										Unit price in yen
WKC											800
	d	12	16	20	25	30	35	40			
	W	13	17	22	27	30	36	41			


Adds two parallel flats on the head as shown on the left.

Precision Support Pins Head, Press-Fit Length Designation Type (No Oil Groove)

SUPPORT PINS

Additional processing to mold bases → P.58

Catalog No.	Material	Hardness after heat treatment
M-SPHF	SUJ2	60 to 64HRC (high frequency quenching)



d		d1		D	M	F
DIMM	Limit deviations	DIMM	Limit deviations			
12	-0.020	12	+0.018	17	M6	12
16	-0.025	16	+0.007	20	M10	20
20	-0.025	20	+0.021	25	M12	25
25	-0.030	25	+0.008	30	M14	30
30	-0.030	30		35		
35	-0.035	35	+0.025	40	M16	35
40	-0.040	40	+0.009	45		

Cylindricity of d

L	50 to 100	101 or more
Tolerance	0.003	0.004

Circularity (roundness) of d

d	30 or less	31 or more
Tolerance	0.002	0.0025

Catalog No.	d	L In 5 mm steps	L1 *1 In 1 mm steps	H (Thickness option)		Unit price in yen
				DIMM	Code	
M-SPHF	12	50~80	$11 \leq L1 \leq L \times 0.4$	6	→ A	920
		85~120		5	→ B	1,040
		125~160				1,190
		165~200				1,480
		205~250				1,630
	16	50~80	$13 \leq L1 \leq L \times 0.4$	8	→ A	1,100
		85~120		6	→ B	1,240
		125~160				1,400
		165~200				1,630
		205~250				1,970
	20	80~90	$15 \leq L1 \leq L \times 0.4$	10	→ A	1,240
		95~150		6	→ B	1,440
		155~200				1,680
		205~260				2,230
		265~300				2,850
	25	80~110	$17 \leq L1 \leq L \times 0.4$	12	→ A	1,500
		115~160		8	→ B	1,760
		165~200				2,140
		205~260				2,770
		265~300				3,460

*1. If press-fit (L1) section is not required, specify L1=0.

Catalog No.	d	L In 5 mm steps	L1 *1 In 1 mm steps	H (Thickness option)		Unit price in yen
				DIMM	Code	
M-SPHF	30	100	$19 \leq L1 \leq L \times 0.4$	14	→ A	1,710
		105~160		8	→ B	1,940
		165~200				2,400
		205~260				3,000
		265~300				3,700
	35	130~160	$21 \leq L1 \leq L \times 0.4$	16	→ A	2,250
		165~200		8	→ B	2,700
		205~260				3,300
		265~330				4,200
		335~400				4,900
	40	150~190	$23 \leq L1 \leq L \times 0.4$	18	→ A	5,400
		195~240		10	→ B	6,400
		245~300				7,600
		305~380				8,900
		385~450				9,900

How to order

Catalog No. d × L × L1 H N + Optional processing

M-SPHF 25 × 215 × 49 A

M-SPHF 20 × 180 × 39 B N + WKC



L ≤ 450 shipped in 3 business days (excluding the day of order).
L > 450 shipped in 5 business days (excluding the day of order).

Check

Support pin deflection calculation
→ Technical reference in P.445

Optional processing

Option code	Specification								Unit price in yen
WKC									800
	d	12	16	20	25	30	35	40	
	W	13	17	22	27	30	36	41	


Adds two parallel flats on the head as shown on the left.

Precision Support Pins Head, Press-Fit Length Designation Type (With Spiral Oil Groove)

SUPPORT PINS

Additional processing to mold bases → P.58

Catalog No.	Material	Hardness after heat treatment
M-SPHFS	SUJ2	60 to 64HRC (high frequency quenching)



d		d1		D	M	F	Q
DIMM	Limit deviations	DIMM	Limit deviations				
12	-0.020	12	+0.018	17	M6	12	
16	-0.025	16	+0.007	20	M10	20	10
20	-0.025	20	+0.021	25	M12	25	
25	-0.030	25	+0.008	30	M14	30	13
30	-0.030	30		35			
35	-0.030	35	+0.025	40	M16	35	15
40	-0.040	40	+0.009	45			

Cylindricity of d

L	50 to 100	101 or more
Tolerance	0.003	0.004

Circularity (roundness) of d

d	30 or less	31 or more
Tolerance	0.002	0.0025

Catalog No.	d	L In 5 mm steps	L1*1 In 1 mm steps	S*2 In 1 mm steps	H (Thickness option)		Unit price in yen	P
					DIMM	Code		
M-SPHFS	12	50 ~ 70	11 ≤ L1 ≤ (L - 30)	25 ≤ S ≤ L - (L1 + 5)	6 → A 5 → B		1,620	10
		75 ~ 80	11 ≤ L1 ≤ (L - 38)	33 ≤ S ≤ L - (L1 + 5)			1,620	15
		85 ~ 120	11 ≤ L1 ≤ (L - 38)	33 ≤ S ≤ L - (L1 + 5)			1,740	15
		125 ~ 160	11 ≤ L1 ≤ (L - 45)	40 ≤ S ≤ L - (L1 + 5)			1,890	20
		165 ~ 180	11 ≤ L1 ≤ (L - 53)	48 ≤ S ≤ L - (L1 + 5)			2,180	25
		185 ~ 200	11 ≤ L1 ≤ (L - 53)	48 ≤ S ≤ L - (L1 + 5)			2,180	25
	16	50 ~ 70	13 ≤ L1 ≤ (L - 30)	25 ≤ S ≤ L - (L1 + 5)	8 → A 6 → B		1,800	10
		75 ~ 80	13 ≤ L1 ≤ (L - 38)	33 ≤ S ≤ L - (L1 + 5)			1,800	15
		85 ~ 120	13 ≤ L1 ≤ (L - 38)	33 ≤ S ≤ L - (L1 + 5)			1,940	15
		125 ~ 160	13 ≤ L1 ≤ (L - 45)	40 ≤ S ≤ L - (L1 + 5)			2,100	20
		165 ~ 180	13 ≤ L1 ≤ (L - 53)	48 ≤ S ≤ L - (L1 + 5)			2,330	25
		185 ~ 200	13 ≤ L1 ≤ (L - 53)	48 ≤ S ≤ L - (L1 + 5)			2,330	25
	20	80 ~ 90	15 ≤ L1 ≤ (L - 38)	33 ≤ S ≤ L - (L1 + 5)	10 → A 6 → B		2,670	25
		95 ~ 120	15 ≤ L1 ≤ (L - 38)	33 ≤ S ≤ L - (L1 + 5)			2,930	25
		125 ~ 150	15 ≤ L1 ≤ (L - 45)	40 ≤ S ≤ L - (L1 + 5)			3,550	30
		155 ~ 180	15 ≤ L1 ≤ (L - 45)	40 ≤ S ≤ L - (L1 + 5)			1,940	15
		185 ~ 200	15 ≤ L1 ≤ (L - 53)	48 ≤ S ≤ L - (L1 + 5)			2,140	15
		205 ~ 260	15 ≤ L1 ≤ (L - 53)	48 ≤ S ≤ L - (L1 + 5)			2,140	15
	25	80 ~ 110	17 ≤ L1 ≤ (L - 41)	36 ≤ S ≤ L - (L1 + 5)	12 → A 8 → B		2,380	20
		115 ~ 120	17 ≤ L1 ≤ (L - 41)	36 ≤ S ≤ L - (L1 + 5)			2,380	20
		125 ~ 160	17 ≤ L1 ≤ (L - 48)	43 ≤ S ≤ L - (L1 + 5)			2,380	20
		165 ~ 180	17 ≤ L1 ≤ (L - 48)	43 ≤ S ≤ L - (L1 + 5)			2,380	20
		185 ~ 200	17 ≤ L1 ≤ (L - 56)	51 ≤ S ≤ L - (L1 + 5)			2,930	25
		205 ~ 260	17 ≤ L1 ≤ (L - 56)	51 ≤ S ≤ L - (L1 + 5)			3,550	30

How to order

Catalog No. d × L × L1 H N S + Optional processing

M-SPHFS 25 × 180 × 59 B N 100
M-SPHFS 35 × 400 × 79 A N 250 + WKC



Orders will be shipped out in 5 business days (excluding the day of order).

★ Check

Support pin deflection calculation

→ Technical reference in P.445

Precision Support Pins & Support Pin Collars

SUPPORT PIN COLLARS


Catalog No.	d	L In 5 mm steps	L1 *1 In 1 mm steps	S *2 In 1 mm steps	H (Thickness option)		Unit price in yen	P		
					DIMM	Code				
M-SPHFS	30	100	$19 \leq L1 \leq (L - 41)$	$36 \leq S \leq L - (L1 + 5)$	14 8	$\rightarrow$ $\rightarrow$ A B	2,410	15		
		105~120					2,640			
		125~160					2,640			
		165~180	$19 \leq L1 \leq (L - 48)$	$43 \leq S \leq L - (L1 + 5)$			3,100	20		
		185~200					3,100			
		205~260					3,700			
		265~300	$19 \leq L1 \leq (L - 56)$	$51 \leq S \leq L - (L1 + 5)$			4,400	25		
		305~350					4,600			
		355~400					5,000			
	35	130~160	$21 \leq L1 \leq (L - 50)$	$45 \leq S \leq L - (L1 + 5)$	16 8	$\rightarrow$ $\rightarrow$ A B	3,250	20		
		165~180					3,700			
		185~200					3,700			
		205~260	$21 \leq L1 \leq (L - 58)$	$53 \leq S \leq L - (L1 + 5)$			4,300	25		
		265~300					5,200			
		305~330					5,200			
		335~400	$21 \leq L1 \leq (L - 65)$	$60 \leq S \leq L - (L1 + 5)$			5,900	30		
		405~450					6,400			
		455~460					7,400			
	40	150~180	$23 \leq L1 \leq (L - 50)$	$45 \leq S \leq L - (L1 + 5)$	18 10	$\rightarrow$ $\rightarrow$ A B	4,200	20		
		185~190					4,200			
		195~240					4,900			
		245~300	$23 \leq L1 \leq (L - 58)$	$53 \leq S \leq L - (L1 + 5)$			5,900	25		
		305~380					7,200			
		385~450					7,900			
		455~500	$23 \leq L1 \leq (L - 65)$	$60 \leq S \leq L - (L1 + 5)$			8,600	30		

*1. If press-fit (L1) section is not required, specify L1=0.



*2. The number of turns of spiral grooves is set so that they make at minimum one and a half turns.

When L1=0 is specified, the range of S dimension that can be specified is the range derived by assigning the minimum value of L1 dimension designation range to L1 portion of each S dimension calculation formula shown above.



Optional Processing

Option code	Specification								Unit price in yen																	
WKC		<table><tr><td>d</td><td>12</td><td>16</td><td>20</td><td>25</td><td>30</td><td>35</td><td>40</td></tr><tr><td>W</td><td>13</td><td>17</td><td>22</td><td>27</td><td>30</td><td>36</td><td>41</td></tr></table>								d	12	16	20	25	30	35	40	W	13	17	22	27	30	36	41	800
		d	12	16	20	25	30	35	40																	
		W	13	17	22	27	30	36	41																	
Adds two parallel flats on the head as shown on the left.																										

Catalog No.	Material
M-SPC	S45C



Catalog No.	Material	Application
M-SPD	S45C	For setting 5 mm



Catalog No.	Applicable support pin d	Unit price in yen	T	D	d1	L2
M-SPC	12	140	5	16	6.1	12.5
	16	150	8	20	10.1	20.5
	20	180	10	26	12.1	25
	25	230	12	31	14.1	29.5
	30	280	14	38		34
	35	340	16	43	16.1	36
	40	400	18	48		38

Hexagon socket head cap screws with spring washer

Catalog No.	Applicable support pin d	Unit price in yen	T	D	d1	d2	L2
M-SPD	12	190	10	16	6.5	12.1	12.5
	16	200	13	20	10.5	16.1	20.5
	20	230	15	26	12.5	20.1	25
	25	280	17	31	14.5	25.1	29.5
	30	330	19	38		30.1	34
	35	390	21	43	16.5	35.1	36
	40	450	23	48		40.1	38

Hexagon socket head cap screws with spring washer



How to order

Catalog No.

Applicable support pin d

M-SPC
M-SPD

20
30



Shipping


In-stock item

Tapered Lock Pins Bolt PL Installation Type

TAPERED LOCK PINS

Additional processing to mold bases → P.98

Catalog No.			D	Material	Hardness after heat treatment	Concentricity of tapered section to the diameter of pin or bushing
Set	Pin only	Bushing only	Limit deviations			
M-TLCS	M-TLCP	M-TLCB	Dk6	SKS3	58 to 62HRC	0.005 or less
M-TLDS	M-TLDP	M-TLDB	$D \begin{smallmatrix} +0.005 \\ 0 \end{smallmatrix}$			0.003 or less



Precision M-TLC		Super Precision M-TLD		D1		d	Z	E	M	F	N	a	L1	L
D	Limit deviations	D	Limit deviations	D	Limit deviations									
16	$\begin{smallmatrix} +0.012 \\ +0.001 \end{smallmatrix}$	16	$\begin{smallmatrix} +0.005 \\ 0 \end{smallmatrix}$	16	$\begin{smallmatrix} -0.01 \\ -0.03 \end{smallmatrix}$	10	10.3	5	M5	10	M6	3	15	30
20	$\begin{smallmatrix} +0.015 \\ +0.002 \end{smallmatrix}$	20		20		13	14	6	M6	12	M8	4	20	40
25		25		25		16	19	9	M8	16	M10		25	50
30		30		30		20	24	12	M10	20	M12		30	60

Precision type	D	K	Unit price in yen		
Catalog No.			M-TLCS ①+②	M-TLCP ①	M-TLCB ②
M-TLCS (①+② set)	16	1 3 5	4,700	2,000	2,700
M-TLCP (① pin)	20		5,000	2,100	2,900
M-TLCB (② bushing)	25		5,200	2,200	3,000
	30		5,900	2,600	3,300

Super precision type	D	K	Unit price in yen		
Catalog No.			M-TLDS ①+②	M-TLDP ①	M-TLDB ②
M-TLDS (①+② set)	16	1 3 5	9,400	4,700	4,700
M-TLDP (① pin)	20		10,200	5,100	5,100
M-TLDB (② bushing)	25		10,800	5,400	5,400
	30		11,900	5,950	5,950

How to order


Catalog No.	D	×	K	N +	Optional processing
(①+② set) M-TLCS	16	×	1	N +	AC
(①+② set) M-TLDS	20	×	1		
(① pin only) M-TLCP	25	×	3		
(① pin only) M-TLDP	16	×	1		
(② bushing only) M-TLCB	30	×	5		
(② bushing only) M-TLDB	25	×	3		



In-stock item

Order requiring optional processing will be shipped in 3 business days (excluding the day of order).

How to remove bushings



As shown in the above chart, the bushing can be easily removed by screwing a bolt into its thread and extracting it.

Optional Processing



Option code	Specification	U/price (yen)
AC	Adds an air vent (single). A 0.2 mm deep flat chamfer is produced in parallel to the taper angle.	200

Tapered Lock Pins Basic Type

TAPERED LOCK PINS

Additional processing to mold bases → P.98

Catalog No.			D	Material	Hardness after heat treatment	Concentricity of tapered section to the diameter of pin or bushing
Set	Pin only	Bushing only	Limit deviations			
M-TLGS	M-TLGP	M-TLGB	Dk6	SKS3	58 to 62HRC	0.005 or less
M-TLHS	M-TLHP	M-TLHB	$D \begin{smallmatrix} +0.005 \\ 0 \end{smallmatrix}$			0.003 or less



Precision M-TLG□		Super Precision M-TLH□		D1		d	Z	E	M	F	a	L1	L
D	Limit deviations	D	Limit deviations										
DIMM	Limit deviations	DIMM	Limit deviations	DIMM	Limit deviations								
16	$\begin{smallmatrix} +0.012 \\ +0.001 \end{smallmatrix}$	16	$\begin{smallmatrix} +0.005 \\ 0 \end{smallmatrix}$	16	$\begin{smallmatrix} -0.01 \\ -0.03 \end{smallmatrix}$	10	8	5	M5	10	3	15	30
20	$\begin{smallmatrix} +0.015 \\ +0.002 \end{smallmatrix}$	20		20		13	11	8	M6	12	4	20	40
25		25		25		16	14	11	M8	16		25	50
30		30		30		20	17	14	M10	20		30	60

Precision type	D	K	Unit price in yen		
Catalog No.			M-TLGS ①+②	M-TLGP ①	M-TLGB ②
M-TLGS (①+② set)	16	1 3 5	4,700	2,000	2,700
M-TLGP (① pin only)	20		5,000	2,100	2,900
M-TLGB (② bushing only)	25		5,200	2,200	3,000
	30		5,900	2,600	3,300

Super precision type	D	K	Unit price in yen		
Catalog No.			M-TLHS ①+②	M-TLHP ①	M-TLHB ②
M-TLHS (①+② set)	16	1 3 5	9,400	4,700	4,700
M-TLHP (① pin only)	20		10,200	5,100	5,100
M-TLHB (② bushing only)	25		10,800	5,400	5,400
	30		11,900	5,950	5,950

How to order


Catalog No.	D	K	N +	Optional processing
(①+② set) M-TLGS	16	×	1	
(①+② set) M-TLHS	20	×	3	
(① pin only) M-TLGP	25	×	1	N + AC
(① pin only) M-TLHP	16	×	1	
(② bushing only) M-TLGB	30	×	5	
(② bushing only) M-TLHB	20	×	3	



In-stock item

Orders requiring optional processing will be shipped in 3 business days (excluding the day of order).

Installation of tapered lock pins



When the matching taper angle is 1° or 3°, it is necessary to consider possible seizure of the pin and bushing. Even if setting them slightly spaced from each other to avoid this seizure, the positioning performance is not compromised, because when the angle is small, the deviation of B to that of A is also small.

Optional processing

Option code	Specification	U/price (yen)
AC	Adds an air vent (single). A 0.2 mm deep flat chamfering is performed in parallel to the taper angle.	200

Deviation of B to that of A


Angle	0.1	0.3	0.5
1°	0.0018	0.005	0.009
3°	0.005	0.016	0.026

Tapered Lock Pins Sets JIS Type (Precision)

TAPERED LOCK PIN

Additional processing to mold bases → P.98

Catalog No.			Material	Hardness after heat treatment	Concentricity of tapered section to the diameter of pin or bushing
Set	Pin only	Bushing only			
M-TLBS	M-TLBP	M-TLBB	SKS3	58 to 62HRC	0.005 or less



D		D1		d	d1	Z	E	M	F	a	L1	L
DIMM	Limit deviations	DIMM	Limit deviations									
13	+0.012	13	-0.032	7	5.0	8	5	M4	11	3	16	32
16	+0.001	16	-0.050	10	8.0		6	M5				
20	+0.015	20	-0.040	12	8.6		9	M6	12	4	20	40
25	+0.002	25	-0.061	16	12.3		10		15		25	50
32		32		20	15.3	20	14	M8			30	60
40	+0.018	40	-0.050	25	19.0	25	18		18	5	40	80
50	+0.002	50	-0.075	32	25.0	30	20	M10	20		50	100

※ The old catalog No., M-TLB has been changed to M-TLBS due to a change in its standard.

How to order


Catalog No.	D
(① + ② set) M-TLBS	25
(① pin only) M-TLBP	25
(② bushing only) M-TLBB	25

Shipping **In-stock item**


Catalog No.	D	Unit price in yen		
		M-TLBS ① + ②	M-TLBP ①	M-TLBB ②
M-TLBS (① + ② set)	13	5,950	2,600	3,350
	16	6,000	2,620	3,380
M-TLBP (① pin)	20	6,500	2,800	3,700
	25	7,000	3,000	4,000
M-TLBB (② bushing)	32	7,500	3,200	4,300
	40	8,500	3,650	4,850
	50	10,000	4,300	5,700

Usage example:

Example of M-TLGS, M-TLHS and M-TLBS usage



Example of M-TLCS and M-TLDS usage



Tapered lock pin	Applicable disc spacers
M-TLCS, M-TLDS M-TLGS, M-TLHS	M-DSD, M-DSE, M-DSF → P.302
M-TLBS	M-DSA, M-DSB, M-DSC → P.301


Disc Spacers For M-TLBS

DISC SPACER


Additional processing to mold bases → P.98

Material	Hardness after heat treatment
SK3	48 to 52HRC


M-DSA



M-DSB



M-DSC



Supplied with hexagon socket flat head cap screw

Catalog No.	Applicable Tapered lock pin D	T	Unit price in yen	D1	d	h	Thickness of retainer plate
M-DSA	13	4	500	17	4.5	2.7	20
	16		650	20	5.5	3	20
	20	5	700	25	6.6	3.8	25
	25		800	30			30
	32	10	940	38	9	4.8	40
	40		1,060	45			50

Catalog No.	Applicable Tapered lock pin D	T	U/price (yen)	D1	d1	d2	h	Thickness of mold plate
M-DSB	13	9	600	17	4.5	8	4.8	25
		14	660					30
	16	9	670	20	5.5	9.5	5.8	25
		14	700					30
	20	10	730	25	6.6	11	7	30
		15	780					35
	25	10	820	30	6.6	11	7	35
		15	890					40
		20	1,090					50
	32	30	1,230	38	9	14	9	60
		20	1,220					60
	40	30	1,340	45	9	14	9	70
		20	1,340					70
	50	20	1,340	58	11	17.5	11.3	70
		30	1,560					80

Catalog No.	Applicable Tapered lock pin D	T	Unit price in yen	D1	d	Thickness of mold plate
M-DSC	13	4	490	13	4.5	20
		9	510			25
		14	530			30
	16	4	540	16	5.5	20
		9	580			25
		14	610			30
		19	660			35
		24	710			40
		34	750			50
	20	5	610	20	6.6	25
		10	640			30
		15	670			35
		20	760			40
		30	800			50
		40	880			60
	25	5	930	25	6.6	70
		10	940			30
		15	940			35
		20	860			40
		25	1,000			45
		35	1,120			50
	32	45	1,250	32	9	60
		5	740			70
		10	820			35
		20	940			40
		30	1,130			50
		40	1,260			60
	40	10	890	40	9	70
		20	1,000			80
		30	1,120			90
		40	1,300			100
		10	1,100			60
		20	1,300			70
	50	30	1,430	50	11	80
		40	1,530			90
		50	1,740			100
		20	1,430			70



How to order

Catalog No.

Applicable Tapered Lock Pin D × T

M-DSA

20

×

5

M-DSB

25

×

15

M-DSC

25

×

25



Shipping

In-stock item


Disc Spacers For M-TLBS

DISC SPACER

Additional processing to mold bases → P.98


Material	Hardness after heat treatment
SCM435	45 to 51HRC

M-DSD




Supplied with hexagon socket flat head cap screw

M-DSE



Supplied with hexagon socket head cap screw

M-DSF



Catalog No.	Applicable Tapered lock pin D	T	Unit price in yen	D1	d	h	Thickness of mold plate
M-DSD	16	5	160	20	5.5	3	20
		10	190				25
	20	5	200	25	6.5	4	25
		10	260				30
	25	5	290	30	8.5	4.4	30
		10	340				35
	30	10	410	35	10.5	7.5	40

Catalog No.	Applicable Tapered lock pin D	T	U/price (yen)	D1	d1	d2	h	Thickness of mold plate
M-DSE	16	15	270	20	5.5	9.5	7	30
		20	290					35
		25	320					40
		35	360					50
	20	15	330	25	6.5	11	9	35
		20	360					40
		30	420					50
		40	490					60
	25	15	420	30	8.5	14	10	40
		25	520					50
		35	610					60
		45	710					70
	30	20	580	35	10.5	17.5	12	50
		30	710					60
		40	830					70
		50	960					80

Catalog No.	Applicable Tapered lock pin D	T	Unit price in yen	D1	d	Thickness of mold plate
M-DSF	16	5	180	16	5.5	20
		10	200			25
		15	230			30
		20	260			35
		25	290			40
	20	5	230	20	6.5	25
		10	260			30
		15	290			35
		20	310			40
		30	340			50
	25	5	290	25	8.5	30
		10	320			35
		15	350			40
		25	380			50
		35	440			60
	30	5	380	30	10.5	35
		10	410			40
		20	500			50
		30	600			60
		40	670			70
		50	770			80

How to order

Catalog No.	Applicable Tapered Lock Pin D	×	T
M-DSD	16	×	5
M-DSE	20	×	20
M-DSF	25	×	45




In-stock item

Angular Pins

ANGULAR PINS

Catalog No.	Material	Hardness after heat treatment
M-AGA	SUJ2	60 to 64HRC (high frequency quenching)



d		d1		D	H	L1
DIMM	Limit deviations	DIMM	Limit deviations			
10	-0.013 -0.022	10	+0.015 +0.006	13	8	19
13	-0.016	13	+0.018	17	10	24
16	-0.027	16	+0.007	20	12	29
20	-0.020	20	+0.021	25	15	39
25	-0.033	25	+0.008	30		49

Catalog No.	d	Unit price in yen												
		L												
		40	50	60	70	80	90	100	110	120	130	140	150	160
M-AGA	10	390	400	430	470	500	540	570						
	13		440	470	510	550	580	620	660	700	740	780	810	
	16			550	590	620	660	700	730	760	790	820	850	870
	20					760	810	850	900	940	980	1,020	1,060	1,100
	25							950	1,000	1,050	1,100	1,150	1,200	1,250

d	Unit price in yen													
	L													
	170	180	190	200	210	220	230	240	250	260	270	280	290	300
10														
13														
16	900	930	960	990										
20	1,150	1,190	1,240	1,280	1,320	1,370	1,410	1,450	1,500					
25	1,300	1,350	1,400	1,450	1,500	1,550	1,590	1,640	1,690	1,740	1,790	1,840	1,890	1,940

How to order

Catalog No.

M-AGA

d × L × L1

10 × 70 × 19



Shipping

In-stock item

Mold Opening Control Parts

Mold Opening Control Parts Overview 306

Puller Bolts

Ground Puller Bolts	M-PBCH	308
Ground Puller Bolts	M-PBAH	310
Puller Bolts	M-PBC	312
Puller Bolts	M-PBA	313
Puller Bolts	M-PBB	314
Puller Bolts Collars	M-PCA M-PCB	315

Tension Links

Tension Links	M-HLA	316
Tension Links	M-HLB	317
Bolts/Retainers for Tension Link	M-PBB M-HRA M-HRB	318

PL Pullers

M-PLL□ 320

Mold Opening Prevention Plates

M-OPB	321
M-OPC	321

Mold Opening Control Parts Overview

Ground puller bolts

Additional processing to MDC



Catalog No.	M-PBCH
Hardness after heat treatment	33HRC or more
Shipping	1 day
Page	P.308

Additional processing to MDC



Catalog No.	M-PBAH
Hardness after heat treatment	33HRC or more
Shipping	1 day
Page	P.310

Puller Bolts

Additional processing to MDC



Catalog No.	M-PBC
Hardness after heat treatment	39 to 44HRC
Shipping	In-stock item
Page	P.312

Additional processing to MDC



Catalog No.	M-PBA
Hardness after heat treatment	39 to 44HRC
Shipping	In-stock item
Page	P.313

Additional processing to MDC



Catalog No.	M-PBB
Hardness after heat treatment	39 to 44HRC
Shipping	In-stock item
Page	P.314

Puller bolt collars



Catalog No.	M-PCA
Shipping	In-stock item
Page	P.315



Catalog No.	M-PCB
Shipping	In-stock item
Page	P.315

Additional processing to MDC denotes the parts that support additional processing to mold bases.
Shipping times are shown in business days (excluding the day of order).

Tension links

Additional processing to MDC



Catalog No.	M-HLA
Shipping	In-stock item
Page	P.316

Additional processing to MDC



Catalog No.	M-HLB
Shipping	In-stock item
Page	P.317

Bolts/retainers for tension link

Additional processing to MDC



Catalog No.	M-PBB
Hardness after heat treatment	39 to 44HRC
Shipping	In-stock item
Page	P.318

Additional processing to MDC



Catalog No.	M-HRA
Hardness after heat treatment	38 to 43HRC
Shipping	In-stock item
Page	P.318

Additional processing to MDC



Catalog No.	M-HRB
Hardness after heat treatment	38 to 43HRC
Shipping	In-stock item
Page	P.318

PL Pullers

Additional processing to MDC



Catalog No.	M-PLL□
Sleeve material	PAR
Shipping	In-stock item
Page	P.320


Mold opening prevention plates

Additional processing to MDC



Catalog No.	M-OPB
Safety color	Black
Shipping	In-stock item
Page	P.321

Additional processing to MDC




Catalog No.	M-OPC
Safety color	Red, yellow, black
Shipping	In-stock item
Page	P.321

Ground Puller Bolts

PULLER BOLTS

Additional processing to mold bases → P.148

Catalog No.	Material	Hardness after heat treatment
M-PBCH	SCM435	33HRC or more



Catalog No.	d	L	F	Unit price in yen	d		D	H	M	B
					DIMM	Limit deviations				
M-PBCH	10	10	19 24	190	10	-0.025 -0.083	16		M6 × full thread	6
		15	19 24 29	200						
		20	19 24 29 34	200						
	13	10	22 27	220	13	-0.032 -0.102	18	8	M8 × full thread	8
		15	22 27 32 37	220						
		20	22 27 32 37 42	220						
		25	27 32 37 42	250						
		30	27 32 37 42 47	260						
		35	37 42 47	270						
	16	10	30 35	300	16	-0.032 -0.102	24	13	M10 × full thread	10
		15	30 35 40	330						
		20	30 35 40 45	340						
		25	30 35 40 45	350						
		30	35 40 45 50 55	370						
		35	45 50 55	400						
	20	15	38 43	400	20	-0.040 -0.124	27	13	M12 × full thread	14
		20	38 43 48	420						
		25	38 43 48 53	440						
		30	43 48 53 58	470						
		35	48 53 58	500						
		45	53 58	530						
	25	15	44 49	800	25	-0.040 -0.124	33	18	M16 × full thread	17
		20	49 54 59	800						
		25	49 54 59	850						
		30	49 54 59 64	900						
		40	54 59 64 74	1,000						

※ The incomplete threaded section of full thread is 3-pitch long at maximum.

How to order

Catalog No.

d × L × F


M-PBCH

16 × 30 × 40



Orders will be shipped out in 1 business day (excluding the day of order).

Grounded puller bolt selection



The size of grounded puller bolts is set according to the thickness of Plate T and Plate R.

Relationship between the "mold opening stroke of Plate T and Plate R (ST)" and the "depth of counterbore machined in the Plate T (Z)" is:


$$ST = Z + L - T \quad Z = T + ST - L \quad L = T + ST - Z$$

d	T	L	H	F							
				R=10	R=15	R=20	R=25	R=30	R=35	R=40	R=50
10	20	10	8	19	24	29	34				
	25	15									
	30	20									
13	20	10	8	22	27	32	37	42	47		
	25	15									
	30	20									
	35	25									
	40	30									
	45	35									
16	25	10	13		30	35	40	45	50	55	
	30	15									
	35	20									
	40	25									
	45	30									
	50	35									
20	30	15	13			38	43	48	53	58	
	35	20									
	40	25									
	45	30									
	50	35									
	60	45									
25	35	15	18			44	49	54	59	64	74
	40	20									
	45	25									
	50	30									
	60	40									

How to use this product:

As this product is full threaded, it can be used as follows:


(1) Counterbore for springs



A counterbore to be machined in Plate R can be selected.

$J \leq 7\text{mm}$
However,
if $R = 10\text{mm}$,
 $J \leq 5\text{mm}$

(2) Horizontal deviation prevention



Cut a thread in the through hole of Plate R and use it to prevent horizontal deviation


※ For details, see option code CRM of , additional mold base processing in page 150

Ground Puller Bolts

PULLER BOLTS

Additional processing to mold bases → P.148

Catalog No.	Material	Hardness after heat treatment
M-PBAH	SCM435	33HRC or more



Catalog No.	d	L	Unit price in yen	d		D	H	M	S	B				
				DIMM	Limit deviations									
M-PBAH	10	50 60 70	350	10	—0.025 —0.083	16	8	M6	17	6				
		80 90	400											
		100 110 120	480											
		130 140 150	530											
		160 170 180	630											
	13	60 70	380	13	—0.032 —0.102	18		M8	20	8				
		80 90	420											
		100 110 120	530											
		130 140 150	600											
		160 170 180	800											
		190 200 210	920											
		220 230 240 250 260	1,370											
	280	1,680	16	24	M10	23	10							
	100 110 120	640												
	130 140 150	720												
	160 170 180	940												
	190 200 210	1,070												
	220 230 240 250 260	1,560												
	280 300	2,000												
	20	120 130 140 150						1,050	20	—0.040 —0.124	27	M12	26	14
		160 170 180						1,250						
		190 200 210						1,390						
		220 230 240 250 260	1,880											
		280 300	2,300											
		350	3,200											
	25	170 180	1,600	25	—0.040 —0.124	33	18	M16	32	17				
		190 200	1,730											
		210 220	2,030											
		230 240	2,180											
		250 260	2,430											
		280 300	2,800											
		350	3,800											

How to order

Catalog No.


d × L

M-PBAH


16 × 180



Orders will be shipped out in 1 business day (excluding the day of order).

Precision type	Measurement method (simplified diagram)	Precision standard
Squareness of end face and axis		Squareness of L dimension (full length) is within 0.4 mm.

Usage example




- (1) Puller bolt M-PBAH or M-PBA and hexagon socket head cap screw
- (2) Puller bolt M-PBAH or M-PBA and puller bolt collar M-PCA
- (3) Puller bolt M-PBB
- (4) Puller bolt M-PBB
- (5) Puller bolt M-PBB
- (6) Puller bolt M-PBB and puller bolt collar M-PCB
- (7) Puller bolt M-PBAH and Puller Bolt M-PBCH or Puller bolt M-PBA and puller bolt M-PBC

Puller Bolts

PULLER BOLTS

Additional processing to mold bases → P.148

Catalog No.	Material	Hardness after heat treatment
M-PBC	SCM435	39 to 44HRC



Catalog No.	d	L	F	Unit price in yen	d		D	H	M	S	B
					DIMM	Limit deviations					
M-PBC	10	16	22	200	10	0 −0.15	16	8	M6	18	6
		16	27	200							
		21	27	200							
	13	14	30	200	13		18	10	M8	24	8
		19	35	220							
		24	40	240							
	16	15	35	300	16		24	14	M10	26	10
		20	40	320							
		30	45	340							
		30	50	340							
	20	20	45	450	20	0 −0.20	28		M12	30	14
		30	50	470							
		30	55	480							
		35	55	490							
	25	31	60	1,200	25		33	18	M16	38	17
		41	65	1,300							



How to order

Catalog No.

d × L × F


M-PBC

10 × 16 × 27



In-stock item

Puller bolt M-PBC selection



Relationship between the "mold opening stroke of Plate T and Plate R (ST)" and the "depth of counterbore machined in the Plate T (Z)" is:

$$ST = Z + L - T$$


$$Z = T + ST - L$$

$$L = T + ST - Z$$

The size of M-PBC is set according to the thickness of Plate T and Plate R.

d	T	L	H	F						
				R=10	R=15	R=20	R=25	R=30	R=35	R=40
10	25	16	8	22	27					
	30	21								
	25	14		30	30					
13	30	19	10		35	35				
	35	24			40	40				
	30	15			35	35				
16	35	20	14			40	40			
	45	30				45	45	45	50	
	35	20				45	45			
20	45	30	14			50	50	50	55	
	50	35					55	55		
	50	31					60	60		
25	60	41	18					65	65	

Catalog No.	Material	Hardness after heat treatment
M-PBA	SCM435	39 to 44HRC



d		D	H	M	S	B
DIMM	Limit deviations					
10	0 -0.15	16	8	M6	12	6
13		18	10	M8	23	8
16		24	14	M10	25	10
20	0	28		M12	30	14
25	-0.20	33	18	M16	35	17

Catalog No.	d	Unit price in yen								
		L								
		80	90	100	110	120	130	140	150	160
M-PBA	10	290	310	320	340	370	380	400	410	500
	13	360	380	400	420	440	460	480	540	600
	16			480	510	540	560	580	600	700
	20						660	690	720	1,020
	25								1,440	1,490

d	Unit price in yen									
	L									
	170	180	190	200	220	240	260	280	300	350
10		550								
13	650	700		890						
16	750	800	850	900						
20	1,060	1,100	1,140	1,180	1,320	1,460	2,310	2,450	2,600	3,220
25	1,530	1,590	1,640	1,690	1,810	1,900	2,550	3,380	3,670	4,000



How to order

Catalog No.

d

×

L

M-PBA

20

×

300



Shipping


In-stock item

Puller Bolts

PULLER BOLTS

Additional processing to mold bases → P.148

Catalog No.	Material	Hardness after heat treatment
M-PBB	SCM435	39 to 44HRC



d		D	H	M	S	B
DIMM	Limit deviations					
10	0 -0.15	16	8	M8	13	6
13		18	10	M10	14	8
16		24	14	M12	18	10
20	0 -0.20	28		M16	24	14
25		33	18	M20	28	17

Catalog No.	d	Unit price in yen															
		L															
		13	14	15	16	19	20	21	24	25	26	29	30	31	35	41	45
M-PBB	10	100			100			110			110			120			
	13	130	150			160			170			170					
	16	240		250			260			260			270		270		
	20				370		400			410			420		440		460
	25													1,120		1,190	

d	Unit price in yen																	
	L																	
	60	70	80	90	100	110	120	130	140	150	160	170	180	190	200	220	240	260
10	130	140	150	170	190	210	230	250	270	290	350							
13		190	200	220	240	260	280	300	320	340	360	380	400					
16			290	300	320	350	380	410	440	470	530	560	590	620	650			
20					480	500	530	550	600	650	700	750	800	850	1,280	1,410	1,500	
25										1,510	1,660	1,710	1,810	1,880	1,930	2,090	2,230	2,490

How to order

Catalog No.

d

×

L

M-PBB

16

×

90




In-stock item

Puller Bolt Collars


PULLER BOLT COLLARS

Catalog No.	Material	Application
M-PCA	S45C	Applied to M-PBAH M-PBA



Supplied with a hexagon socket head cap screw and spring washer

Catalog No.	Material	Application
M-PCB	S45C	Applied to M-PBB



Supplied with a hexagon nut

Catalog No.	Applicable puller bolt d	Unit price in yen	T	D	d
M-PCA	10	130	5	16	6.1
	13	140	6	18	8.1
	16	160	8	24	10.1
	20	190	10	28	12.1
	25	250	12	33	16.1

Catalog No.	Applicable puller bolt d	Unit price in yen	T	D	M	B
M-PCB	10	270	6.5	16	M8	14
	13	300	8	18	M10	14
	16	320	10	24	M12	19
	20	400	13	28	M16	24
	25	500	16	33	M20	30

How to order

Catalog No.	Applicable puller bolt d
M-PCA	10
M-PCB	13




In-stock item

Tension Links

TENSION LINKS

Additional processing to mold bases → P.172

Catalog No.	Material
M-HLA	S45C



A	B	N	L	T
19	11	14.5	29 + S	9
25	14	17	34 + S	
32	17	18.5	37 + S	
38	21	20.5	41 + S	12

Catalog No.	A	Unit price in yen											
		S											
		60	70	80	90	100	110	120	130	140	150	160	170
M-HLA	19	700	700	750	750	800	800	850	850	900	900	950	950
	25			800	800	850	850	900	900	950	950	1,000	1,000
	32					1,000	1,000	1,050	1,050	1,100	1,100	1,150	1,150
	38					1,150	1,150	1,200	1,200	1,250	1,250	1,300	1,300

A	Unit price in yen												
	S												
	180	190	200	210	220	230	240	250	260	270	280	290	300
19	1,000	1,000	1,050										
25	1,050	1,050	1,100	1,150	1,200	1,250	1,300	1,350					
32	1,200	1,200	1,250	1,300	1,350	1,400	1,450	1,500	1,550	1,600	1,650	1,700	1,750
38	1,350	1,350	1,400	1,450	1,500	1,550	1,600	1,650	1,700	1,750	1,800	1,850	1,900

How to order

Catalog No.

A × S


M-HLA

19 × 200



In-stock item

Catalog No.	Material
M-HLB	S45C



A	B	F	E	N	L	d	T
19	11	24	20	14.5	49 + S	10.5	9
25	14	28	23	17	57 + S	13.5	
32	17	32	30	18.5	67 + S	16.5	
38	21	38	33	20.5	74 + S	20.5	12

Catalog No.	A	Unit price in yen															
		S															
		50	60	70	80	90	100	110	120	130	140	150	160	170	180	190	200
M-HLB	19	900	900	950	950	1,000	1,000	1,050	1,050	1,100	1,100	1,150	1,150	1,200			
	25	950	950	1,000	1,000	1,050	1,050	1,100	1,100	1,150	1,150	1,200	1,200	1,250	1,250	1,300	1,300
	32				1,200	1,250	1,250	1,300	1,300	1,350	1,350	1,400	1,400	1,450	1,450	1,500	1,500
	38						1,450	1,500	1,500	1,550	1,550	1,600	1,600	1,650	1,650	1,700	1,700



How to order

Catalog No.

A × S



M-HLB

25 × 180



In-stock item

Example of use





Bolts/Retainers for Tension Link

TENSION LINKS

Additional processing to mold bases → P.172

Catalog No.	Material	Hardness after heat treatment	Surface treatment
M-PBB	SCM435	39 to 44HRC	Alkaline blackening



Catalog No.	d	L	Unit price in yen	d		D	H	M	S	B	Applicable tension link M-HLA M-HLB
				DIMM	Limit deviations						
M-PBB	10	13	100	10	0	16	8	M8	13	6	Width 19
	13	13	130	13	-0.15	18	10	M10	14	8	Width 25
	16	16	240	16	0	24	14	M12	18	10	Width 32
	20	16	370	20	-0.20	28	14	M16	24	14	Width 38

How to order



Catalog No. **d** × **L**
M-PBB 13 × 13

Shipping In-stock item

Catalog No.	Retainer		
	Material	Hardness after heat treatment	Surface treatment
M-HRA	SCM435	38 to 43HRC	Alkaline blackening



Supplied with hexagon socket head cap screw



Catalog No.	D	Unit price in yen	L	M Bolt	L1	D1	d	Applicable tension link M-HLA M-HLB
M-HRA	10	150	16	M6×25	9	13	6.5	Width 19
	13	200	16	M8×30	14	16	9	Width 25
	16	250	19	M10×30	21	19	11	Width 32
	20	300	19	M12×40	21	23	13	Width 38

How to order



Catalog No. **D**
M-HRA 10

Shipping In-stock item

Catalog No.	Retainer		
	Material	Hardness after heat treatment	Surface treatment
M-HRB	SCM435	38 to 43HRC	Alkaline blackening



Supplied with hexagon socket head cap screw



Catalog No.	D	Unit price in yen	L	M Bolt	L1	D1	W	d	Applicable tension link M-HLA
M-HRB	10	200	11	M6×30	13	16	10	6.5	Width 19
	13	250	11	M8×35	18	19	13	9	Width 25
	16	300	14	M10×35	20	22	16	11	Width 32
	20	350	14	M12×40	20	26	20	13	Width 38


How to order

Catalog No. **D**
M-HRB 13


Shipping In-stock item

Example of tension link usage

Usage example of stripper plate type





Usage example of three-plate type




Feature of tension links

Feature of tension link M-HLA



As the tension links are not fixed with bolts, they become in a state shown in the left chart when the mold is closed. This allows to increase the amount of stroke and reduce the height of the mold.


Feature of tension link M-HLB




A 1 mm clearance is provided at the sliding section of the tension links to allow the mold to be opened or closed without coming in contact with the plate.

How to install tension links

Installing tension link M-HLA




Installing tension link M-HLB




- ※ Install the special bolts and retainers by creating counterbores on the retainer plate.
- ※ Tension link M-HLB and retainer M-HRB can not be combined.

How to install special retainer M-HRB



Insert the retainer by aligning its flat head side with the long hole width.



Turn the retainer by 90 degree and then fix it with a bolt.

Features


The head section of retainer functions as a step of 1 mm and mold can be opened and closed without having link and plate in contact.

PL Pullers

PL PULLERS

Additional processing to mold bases → P.180

Catalog No.	Product	Material
M-PLLA	① + ② set	
M-PLLS	① Plastic sleeve	PAR
M-PLLM	② Taper bolt	SCM435



Catalog No.	D	Unit price in yen		d	M	B	H	L	L1
		M-PLLA ① + ②	M-PLLS ①						
M-PLLA (① + ②)	10	600	200	8.5	M5	4	2	17	24
	12	630	300	11.5	M6	5	4	18	30
M-PLLS (①)	13								
	16	790	350	15	M8	6	5	23.5	35

Catalog No.	M	Unit price in yen	Applicable D
M-PLLM (②)	5	400	10
	6	330	12
	8	440	16



How to order



Shipping

In-stock item

Catalog No.

D

① + ②

M-PLLA

12

①

M-PLLS

12

Catalog No.

M

②

M-PLLM

6

Features


Allows adjustment of friction between the retainer plates and plastic sleeve by tightening the tapered bolt.

How to install

- ◆ Create a hole on the fixed side retainer plate and finish it to an H8 tolerance. Also, make sure to R-chamfer the inlet edge to prevent scuffing of the plastic sleeve.
- ◆ Embed the plastic sleeve about 3 mm in the Plate B (movable side retainer plate).
- ◆ The required tension can be obtained by adjusting the amount of tightening of the lock's taper bolt.

(Note) Do not lubricate this PL Puller as lubrication reduces its friction force.

Example of use



Mold Opening Prevention Plates


Green procurement compliant
Price revised

MOLD OPENING PROTECTION PLATES


Additional processing to mold bases → P.182

Catalog No.	Safety coloring	Material
M-OPB	Black	S45C
M-OPC	Red, yellow, black	

M-OPB



M-OPC



Catalog No.	W	P	Unit price in yen	L	T	d	Safety coloring
M-OPB	16	20	300	40	6	7	Black
		30		50			
		40		60			
		50	350	70			
		60		80			
	22	20	400	50	9	9	
		30		60			
		40	450	70			
		50		80			
		60	500	90			
		70		100			
	25	30	800	60	12	11	
		50	900	80			
		70	1,000	100			
		90	1,100	120			
	38	40	1,000	80		14	
		60	1,100	100			
		80	1,200	120			
100		1,300	140				

※ The old catalog No. M-OPA has been changed to M-OPB due to a change in its standard.

Catalog No.	P	Safety coloring Color Code	Unit price in yen	W	L	d
M-OPC	15	Red → R Yellow → Y Black → N	Red → 590	16	30	7
	20		Yellow → 590		40	
	30		Black → 190		50	
	40		Red → 610		60	
	50		Yellow → 610		70	
	60		Black → 210	20	80	9
	70		Red → 640		90	
	80		Yellow → 640		100	
	90		Black → 240		110	
	100				120	

How to order


Catalog No. d × L

M-OPB 16 × 50

Catalog No. P Safety coloring

M-OPC 50 R

Shipping In-stock item



Allowable load (reference value)


Catalog No.	W	Tensile stress on the side surface (one side)		Shear stress at the end	
		Shear load	Allowable load	Shear load	Allowable load
M-OPB	16	1,750	430	1,770	440
	22	3,800	950	4,300	1,070
	25	5,460	1,360	5,180	1,290
	38	9,360	2,340	7,090	1,770

Catalog No.	P	Tensile stress on the side surface (one side)		Shear stress at the end	
		Shear load	Allowable load	Shear load	Allowable load
M-OPC	15	1,460	360	910	220
	20 to 70			1,470	370
	80 to 100	1,780	440	1,250	310

※ Allowable load is calculated by assuming safety factor = 4.

※ Shear stress is derived by multiplying the tensile strength by 0.7.

Example of use



Ejector Space Parts

Ejector Space Parts Overview	324
Ejector Guide Pins	
Retainer Ring Type	M-EGA 326
JIS Centering Location Type	M-EGB 327
JIS Struck-Out Type	M-EGC 328
Ejector Guide Bushings	
JIS Type	M-EBB..... 330
Linear Motion Bearing Type	M-EBD..... 331
Ejector Guide Bushing Spacers	M-EBS..... 331
Self Lubricating Copper Alloy Type	M-EBG 332
Self Lubricating Heat Resisting Type	M-EBC..... 333
Ejector Guide Pins	
Centering Location Type (in 5 μ m Range)	M-EGBM 334
Struck-Out Type (in 5 μ m Range)	M-EGCM 335
Ejector Guide Bushings	
5 μ m Range Type	M-EBBM..... 336
Return Pins	
Head Thick 8mm Type	M-RP8B..... 337
L Dimension Designation Type (Unit 1 mm)	M-RPN M-RP8N 338
L Dimension Designation Type (Unit 0.1 mm)	M-RPL M-RP8L..... 340
L Dimension Designation Type (Unit 0.01 mm)	M-RPM M-RP8M..... 340
Support Pillars	
Screw Hole Type	M-SRD..... 342
Dowel Hole Type	M-SRC..... 343
Bolt Hole Type	M-SRE..... 344
Spacer Rings	
D-Cut Type	M-SPR..... 345
Circle Type	M-SPR□B..... 345
Stop Pins	
	M-STP 345
Heat Treated Type	M-STPH..... 345
Stop Rings	
	M-STR..... 345
Ejector Rods	
	M-ERA..... 346

Ejector Space Parts Overview

Ejector guide pins

Additional processing to MDC



Catalog No.	M-EGA
Type	Retaining ring type
Shipping	In-stock item
Page	P.326

Additional processing to MDC



Catalog No.	M-EGB
Type	JIS centering location type
Shipping	In-stock item
Page	P.327

Additional processing to MDC



Catalog No.	M-EGC
Type	JIS stuck out type
Shipping	In-stock item
Page	P.328

Ejector guide bushings

Additional processing to MDC



Catalog No.	M-EBB
Type	JIS Type
Shipping	In-stock item
Page	P.330

Additional processing to MDC



Catalog No.	M-EBD
Type	Linear motion bearing type
Shipping	In-stock item
Page	P.331

Additional processing to MDC



Catalog No.	M-EBG
Type	Copper Alloy (Solid lubricant)
Shipping	3 days
Page	P.332

Additional processing to MDC



Catalog No.	M-EBC
Type	Sintered copper powder
Shipping	In-stock item
Page	P.333

Ejector guide pins & bushings 5 μm range type

Additional processing to MDC



Catalog No.	M-EGBM
Type	Centering location type
Shipping	In-stock item
Page	P.334

Additional processing to MDC



Catalog No.	M-EGCM
Type	Stuck out type
Shipping	In-stock item
Page	P.335

Additional processing to MDC



Catalog No.	M-EBBM
Shipping	In-stock item
Page	P.336

Return pins

Additional processing to MDC



Catalog No.	M-RP8B
Type	Head thick 8 mm
Shipping	In-stock item
Page	P.337

Additional processing to MDC



Catalog No.	M-RPN	M-RP8N
Type	L dimension designation type (in 1 mm units)	
Shipping	In-stock item	2 days
Page	P.338	

Additional processing to MDC



Catalog No.	M-RPL	M-RP8L
Type	L dimension designation type (in 0.1 mm units)	
Shipping	2 days	
Page	P.340	

Additional processing to MDC



Catalog No.	M-RPM	M-RP8M
Type	L dimension designation type (in 0.01 mm units)	
Shipping	3 days	
Page	P.340	

Additional processing to MDC denotes the parts that support additional processing to mold bases.
Shipping times are shown in business days (excluding the day of order).

Support pillars

Additional processing to MDC



Catalog No.	M-SRD
Type	Screw hole type
Shipping	In-stock item
Page	P.342

Additional processing to MDC



Catalog No.	M-SRC
Type	Dowel hole type
Shipping	In-stock item
Page	P.343

Additional processing to MDC



Catalog No.	M-SRE
Type	Bolt hole type
Shipping	In-stock item
Page	P.344

Spacer rings

Stop pins

Stop rings

Ejector rods

Additional processing to MDC



Catalog No.	M-SPR	M-SPR-B
Type	D-cut type	Circle type
Shipping	In-stock item	
Page	P.345	



Catalog No.	M-STP	M-STPH
Material	S45C	SCM435
Hardness after heat treatment	—	45 to 51HRC
Shipping	In-stock item	
Page	P.345	

Additional processing to MDC



Catalog No.	M-STR
Material	SCM435
Hardness after heat treatment	45 to 51HRC
Shipping	In-stock item
Page	P.345

Additional processing to MDC



Catalog No.	M-ERA
Shipping	In-stock item
Page	P.346

About ejector guide pins & bushings

Ejector guide pins & bushings are available in two types:

Basic type a type combining a pin that has a sliding-section diameter tolerance of g6 and a bushing that has an inside diameter tolerance of G6.

5 μ m range type a type combining a pin that has a sliding-section tolerance of 5 μ m and a bushing that has an inside diameter tolerance of 5 μ m.

Clearance range of combinations of ejector pins and bushings by type

(unit: mm)

Basic type							5 μ m range type						
Ejector guide pin					Bushing	Combination clearance	Ejector guide pin				Bushing	Combination clearance	
Dia.	M-EGA Retaining ring type	M-EGB Centering location type	M-EGC Stuck-out type	Sliding-section diameter tolerance	M-EBB Inside diameter tolerance		Dia.	M-EGBM Retaining ring type	M-EGCM Centering location type	Sliding- section tolerance	M-EBBM Inside diameter tolerance		
							8	○			+ 0.015 + 0.010	0.025 ~0.035	
10	○	○		−0.005 −0.014	+ 0.014 + 0.005	0.010 ~0.028	10	○		−0.015 −0.020		0.030 ~0.040	
12	○	○		−0.006 −0.017	+ 0.017 + 0.006	0.012 ~0.034	13	○		−0.020 −0.025		−0.025 −0.030	0.035 ~0.045
16	○	○					16	○	○				
20	○	○	○				20	○	○				
25	○	○	○	−0.007 −0.020	+ 0.020 + 0.007	0.014 ~0.040	25	○	○				
30			○				30	○	○				
							35		○				
40			○	−0.009 −0.025	+ 0.025 + 0.009	0.018 ~0.050	40		○				
50			○				50		○				

※ Self-lubricating type ejector guide bushings **M-EBG** and **M-EBC** are applicable to basic type ejector guide pins.


※ Linear motion bearing type ejector guide bushing **M-EBD** is applicable to basic type and 5 μ m type ejector guide pins.

Ejector Guide Pins Retaining Ring Type

EJECTOR GUIDE PINS

Additional processing to mold bases ➡ P.110

Catalog No.	Material	Hardness after heat treatment
M-EGA	SUJ2	60 to 64HRC (high frequency quenching)



Cylindricity of d

L	100 or less	101 or more
Tolerance	0.003	0.004

Circularity (roundness) of d

d	25 or less
Tolerance	0.002

d		d1		t	D
DIMM	Limit deviations	DIMM	Limit deviations		
10	-0.005 -0.014	10	+0.010 +0.001	1.0	12.2
12	-0.006 -0.017	12	+0.012 +0.001		14.1
16	-0.007 -0.020	16	+0.015 +0.002		18.9
20	-0.007 -0.020	20	+0.015 +0.002	1.2	22.7
25	-0.007 -0.020	25	+0.015 +0.002		27.5

Catalog No.	d	Unit price in yen										
		L										
		80	90	100	110	120	130	140	150	160	170	190
M-EGA	10	440	450	460	470							
	12	460	470	480	490	500	510					
	16		510	530	550	570	590	610				
	20				610	630	650	670	690	720	750	810
	25							820	850	880	910	970



How to order

Catalog No.

d

×

L

M-EGA

12

×


120



Shipping

In-stock item

Example of use




Ejector Guide Pins JIS Centering Location Type

EJECTOR GUIDE PINS

Additional processing to mold bases → P.110

Catalog No.	Material	Hardness after heat treatment
M-EGB	SUJ2	60 to 64HRC (high frequency quenching)



Cylindricity of d

L	50 or less	51 to 100	101 or more
Tolerance	0.002	0.003	0.004

Circularity (roundness) of d

d	25 or less
Tolerance	0.002

d		M	F
DIMM	Limit deviations		
10	—0.005 —0.014	M5	12
12	—0.006 —0.017	M6	
16			
20	—0.007 —0.020	M8	16
25		M10	20


Catalog No.	d	Unit price in yen															
		L															
		50	60	70	80	90	100	110	120	130	140	150	160	170	180	190	200
M-EGB	10	410	420	430	440	450											
	12	430	440	450	460	470	480	490									
	16	480	490	500	510	520	530	540	550								
	20		530	540	560	580	600	620	640	660	680	700	720	750			
	25		730	740	750	760	770	790	810	830	850	870	890	910	1,100	1,200	1,300

How to order

Catalog No. **d** × **L**
M-EGB 16 × 120

Shipping In-stock item

Example of use




Ejector Guide Pins JIS Struck-Out Type

EJECTOR GUIDE PINS

Additional processing to mold bases → P.110

Catalog No.	Material	Hardness after heat treatment
M-EGC	SUJ2	60 to 64HRC (high frequency quenching)



Cylindricity of d

L	50 or less	51 to 100	101 or more
Tolerance	0.002	0.003	0.004

Circularity (roundness) of d

d	30 or less	31 or more
Tolerance	0.002	0.0025

d		d1	M	F	Supplies with a threaded dowel pin
DIMM	Limit deviations				
20	-0.007 -0.020	8	M8	16	φ8h7×35
25					
30					
40	-0.009 -0.025	10	M10	20	φ10h7×35
50					

Catalog No.	d	Unit price in yen															
		L															
		50	60	70	80	90	100	110	120	130	140	150	160	170	180	200	
M-EGC	20	1,100	1,120	1,140	1,160	1,180	1,200										
	25	1,120	1,140	1,160	1,180	1,200	1,220	1,260	1,300								
	30	1,840	1,860	1,880	1,900	1,920	1,940	1,960	1,980	2,000	2,050	2,100					
	40				2,300	2,350	2,400	2,450	2,500	2,550	2,600	2,650	2,700	2,750			
	50				3,150	3,200	3,250	3,300	3,400	3,600	3,700	3,800	3,900	4,000	4,100	4,200	



How to order


Catalog No.

d × L

M-EGC**30 × 120**


In-stock item

Example of use




Ejector Guide Bushing Usage Examples


EJECTOR GUIDE BUSHES




Counterbore type



Spacer type



Counterbore type




Spacer type

Ejector Guide Bushings JIS Type

EJECTOR GUIDE BUSHES

Additional processing to mold bases → P.110

Catalog No.	Material	Hardness after heat treatment
M-EBB	SUJ2	58 to 62HRC



Cylindricity of d

L	30 or less	31 to 50	51 or more
Tolerance	0.003	0.0035	0.004

Circularity (roundness) of d

d	30 or less	31 to 40	41 or more
Tolerance	0.0025	0.003	0.0035

Catalog No.	d	L	Unit price in yen	d		D h6		D1	L1	L2
				DIMM	Limit deviations	DIMM	Limit deviations			
M-EBB	10	23	750	10	+0.014 +0.005	16	0 -0.011	20	12	11
	12	25	780	12	+0.017 +0.006	18	0 -0.011	22	14	13
		32	820						14	18
	16	25	880	16	+0.017 +0.006	25	0 -0.013	30	12	13
		32	900						14	18
		42	950						19	23
	20	25	980	20	+0.020 +0.007	30	0 -0.016	35	12	13
		32	1,000						14	18
		42	1,070						19	23
		52	1,150						24	28
	25	25	1,100	25	+0.025 +0.009	35	0 -0.019	40	12	13
		32	1,150						14	18
		42	1,250						19	23
		52	1,350						24	28
	30	32	1,450	30	+0.025 +0.009	40	0 -0.016	45	14	18
		42	1,550						19	23
		52	1,650						24	28
	40	42	1,950	40	+0.025 +0.009	50	0 -0.016	55	19	23
		52	2,000						24	28
	50	52	2,600	50		60	0 -0.019	66	24	28

How to order

Catalog No. d × L

M-EBB 30 × 42


Shipping In-stock item

Ejector Guide Bushings Linear Motion Bearing Type

EJECTOR GUIDE BUSHES

Additional processing to mold bases → P.110


Catalog No.	Material	Hardness after heat treatment
M-EBD	SUJ2 (bush body, ball)	58HRC to



Features

- ◆ A linear type bushing developed for use with ejector guides.
- ◆ The snap ring is set in the L1 groove upon delivery. Relocating the ring to the L2 position allows it to be used with ejector plate of a different thickness.
- ◆ If the ejector plate is spacer type, use ejector guide bush spacer M-EBS.

Snap ring for M-EBD



d	SD	Sd	t
10	23.1	17.5	1.2
12	25.5	19.5	1.2
16	33.1	25.9	1.5
20	37.4	29.6	1.5
25	46.2	37.0	1.75

Catalog No.	d	Unit price in yen	d		D		D1	L		L1	L2	L3	t	W
			DIMM	Limit deviations	DIMM	Limit deviations								
M-EBD	10	1,400	10	0 −0.009	19	0 −0.013	23.6	29	0 −0.2	13	—	3.5	1.2	1.3
	12	1,400	12		21		26.0	30		13	—	3.5		
	16	1,800	16		28		34.2	37		15	20	5.25	1.5	1.6
	20	2,300	20	0 −0.010	32	0 −0.016	38.3	42	20	25	5.75			
	25	3,200	25		40		47.2	59	0 −0.3	20	25	9	1.75	1.85



How to order

Catalog No.

M-EBB

d

16




Shipping

In-stock item

Ejector guide bush spacer

Catalog No.	Material
M-EBS	S45C



Catalog No.	Applicable guide diameter d	Unit price in yen	D	d1	t
M-EBS	10	280	23	19	2.8
	12	310	26	21	2.8
	16	370	34	28	2.5
	20	460	38	32	2.5
	25	680	46	40	2.25



How to order

Catalog No.

M-EBS

Applicable guide diameter d

16



Shipping


In-stock item

Ejector Guide Bushings Self Lubricating Copper Alloy Type

EJECTOR GUIDE BUSHES

Additional processing to mold bases → P.110

Catalog No.	Material
M-EBG	Copper alloy (Solid lubricant embedded)



Catalog No.	d	L	Unit price in yen	d		D h6		D1	L1	L2
				DIMM	Limit deviations	DIMM	Limit deviations			
M-EBG	16	26	2,500	16	+0.017 +0.006	25	0 −0.013	30	12	14
		28							14	
		33	2,600						19	
	20	26	2,800	20	+0.020 +0.007	30	0 −0.013	35	12	
		28							14	
		33	3,000						19	
		38	3,300						24	
	25	26	3,000	25	+0.020 +0.007	35	0 −0.016	40	12	
		28							14	
		33	3,300						19	
		38							24	
	30	33	3,500	30	+0.025 +0.009	40	0 −0.019	45	14	
		38							19	
		43	3,700						24	
	40	48	5,400	40		52		57	24	24
	50	48	6,200	50		62		67		

How to order

Catalog No.

d × L

M-EBG

16 × 28




Orders will be shipped out in 3 business days (excluding the day of order).

Ejector Guide Bushings Self Lubricating Heat Resisting Type

EJECTOR GUIDE BUSHES

Additional processing to mold bases → P.110

Catalog No.	Material
M-EBC	Sintered copper power



Catalog No.	d	L	Unit price in yen	d		D h6		D1	L1	L2
				DIMM	Limit deviations	DIMM	Limit deviations			
M-EBC	10	23	2,100	10	+0.022 +0.013	16	0 -0.011	20	12	11
	12	25	2,300	12	+0.027 +0.016	18	0 -0.013	22	14	13
		32	2,500						18	
	16	25	2,600	16	+0.033 +0.020	25	0 -0.016	30	12	13
		32	2,800						14	18
		42	3,100						19	23
	20	25	3,000	20	+0.033 +0.020	30	0 -0.016	35	12	13
		32	3,300						14	18
		42	3,600						19	23
	25	25	3,100	25	+0.033 +0.020	35	0 -0.016	40	12	13
		32	3,400						14	18
		42	3,700						19	23
	30	32	3,700	30	+0.033 +0.020	40	0 -0.016	45	14	18
		42	4,200						19	23

How to order

Catalog No.

d × L

M-EBC

16 × 32



In-stock item

Ejector guide bushing M-EBC

This self-lubricating type bushing M-EBC is made of mainly copper with solid lubricant such as hexagonal boron nitride (h-BN) and black lead, etc. evenly distributed and sintered. Further, a solid lubricant with a superior sliding property is applied in the porous area (holes) of the sintered material. It is especially excellent in heat resisting and provides good friction resistance at high temperature range.



Features

1. Can be used without lubrication at high-temperature range.
2. Low/middle load. Delivers high performance at mid-speed range.
3. Less trouble such as scuffing or seizing, etc. compared to steel bushings.
4. Has excellent heat resistance and there is no worries about occurrence of deformation or cracking even under the repeated high temperature.
5. Has superior friction resistance and the amount of friction is small compared to other bearings in the high temperature environment.

Range of application

Allowable max. load	Allowable max. sliding speed	Allowable max. PV value	Recommend operating temperature
N/mm ² (kgf/cm ²)	m/sec (m/min)	N/mm ² · m/sec (kgf/cm ² · m/min)	°C
10 (100)	0.33 (20)	0.75 (450)	350 or less

Sliding property



Notes for use


This product is delivered with a solid lubricant with an excellent sliding property applied on the surface. If not desired, however, the lubricant can be wiped off with a waste cloth, etc.

Ejector Guide Pins Centering Location Type (in 5 μm range)

EJECTOR GUIDE PINS

Additional processing to mold bases → P.110

Catalog No.	Material	Hardness after heat treatment
M-EGBM	SUJ2	60 to 64HRC (high frequency quenching)



Cylindricity of d


L	50 or less	51 to 100	101 or more
Tolerance	0.002	0.003	0.004

Circularity (roundness) of d

L	30 or less
Tolerance	0.002

DIMM	d Limit deviations	M	F
8	-0.015	M5	12
10	-0.020		
13	-0.020	M6	13
16	-0.025		
20	-0.025	M8	16
25	-0.030		
30		M10	20

Example of use



Catalog No.	d	Unit price in yen																	
		L																	
M-EGBM	8	340	340	340	390														
	10	370	370	370	420	420													
	13	430	430	430	480	480	530												
	16	480	480	480	540	540	600	600											
	20		540	540	580	580	630	630	700	700	780	780	860	860					
	25		680	680	740	740	780	780	860	860	980	980	1,100	1,100	1,220	1,220	1,220	1,360	1,360
	30						1,160	1,160	1,250	1,250	1,340	1,340	1,480	1,480	1,630	1,630	1,630	1,690	1,690



How to order

Catalog No.

d × L N + Optional processing

M-EGBM

16 × 120

M-EGBM

20 × 148.8 N + LC

M-EGBM

25 × 200 N + LKC



Shipping

In-stock item

Orders will be shipped out in 3 business days (excluding the day of order).

Optional processing


Option code		Specification	Unit price (yen)
LC		Changes the full length to a designated dimension. (in 0.1 mm steps) ※ Designate L dimension directly. L min ≤ designated L value < L max ※ It will be machined to an upper size closest to the designated L value.	200
LKC		Changes the limit deviations of full length. $L \begin{smallmatrix} +0.25 \\ +0.20 \end{smallmatrix} \rightarrow L \begin{smallmatrix} +0.02 \\ 0 \end{smallmatrix}$ ※ When combined with LC, specify in 0.1 mm steps. L min ≤ designated L value < L max	400

Ejector Guide Pins Stuck-Out Type (in 5 μm Range)

EJECTOR GUIDE PINS

Additional processing to mold bases → P.110

Catalog No.	Material	Hardness after heat treatment
M-EGCM	SUJ2	60 to 64HRC (high frequency quenching)



Cylindricity of d


L	50 or less	51 to 100	101 or more
Tolerance	0.002	0.003	0.004

Circularity (roundness) of d

d	30 or less	31 or more
Tolerance	0.002	0.0025

d		M	F	d1		E	Supplies with a threaded dowel pin
DIMM	Limit deviations			DIMM	Limit deviations		
16	-0.020 -0.025	M6	13	6	+0.012 0	15	φ6h7×30
20	-0.025 -0.030	M8	16	8	+0.015 0	20	φ8h7×40
25				10			φ10h7×40
30				13			φ13h7×50
35		M10	20	16	+0.018 0	25	φ16h7×50
40							
50							

Example of use



Catalog No.	d	Unit price in yen															
		L															
		50	60	70	80	90	100	110	120	130	140	150	160	170	180	190	200
M-EGCM	16	980	980	980	1,030	1,030	1,030										
	20	1,130	1,130	1,130	1,130	1,130	1,190	1,190	1,190	1,330							
	25	1,200	1,200	1,200	1,200	1,200	1,380	1,380	1,380	1,530	1,530	1,530	1,680	1,680	1,680	1,680	1,680
	30	1,840	1,840	1,840	1,840	1,840	1,960	1,960	1,960	2,140	2,140	2,140	2,430	2,430	2,430	2,430	2,430
	35				2,500	2,500	2,500	2,500	2,500	2,690	2,690	2,690	3,000	3,000	3,000	3,000	3,000
	40				2,700	2,700	2,700	2,700	2,700	2,860	2,860	2,860	3,590	3,590	3,590	3,590	3,590
	50				3,620	3,620	3,620	3,620	3,620	3,940	3,940	3,940	5,000	5,000	5,000	5,000	5,000



How to order

Catalog No.

M-EGCM
M-EGCM

d × L N + Optional processing

26 × 120
50 × 172.3 N + LC

Shipping

In-stock item

Orders will be shipped out in 3 business days (excluding the day of order).

Optional processing


Option code	Specification	Unit price in yen	
LC	Changes the full length to a designated dimension (in 0.1 mm steps). ※ Designate L dimension directly. L min ≤ designated L value < L max (d30 or less) *1 L min ≤ 0 designated L value < 175 (d35 or more) *2 *1. It will be machined to an upper size closest to the designated L value. *2. It will be machined to an upper size closest to the designated L value +25.	d30 or less	d35 or more
		500	1,000

Ejector Guide Bushings 5 μm Range Type

EJECTOR GUIDE BUSHES

Additional processing to mold bases → P.110

Catalog No.	Material	Hardness after heat treatment
M-EBBM	SUJ2	58 to 62HRC



Cylindricity of d

L	30 or less	31 to 50	51 or more
Tolerance	0.003	0.0035	0.004

Circularity (roundness) of d

d	30 or less	31 to 40	41 or more
Tolerance	0.0025	0.003	0.0035

Catalog No.	d	L	Unit price in yen	D h6		D1	L1	L2	
				DIMM	Limit deviations				
M-EBBM	8	22	770	16	0 −0.011	19	10	12	
		25					13		
	10	22	820	18		21	10		
		25					13		
	13	27	870	22	0 −0.013	25	13	14	
		29					15		
	16	27	990	25		28	13		
		29					15		
		34	1,110	20					
	20	27	1,110	30		0 −0.016	33		13
		29							20
		34	25						
		39	1,280		15				
	25	27	1,280	35	0 −0.016		38	13	
		29	1,450					15	
		34						20	
		39						25	
		44				30			
	30	34	1,690	40		0 −0.019	43	15	
		39						20	
		44						25	
		49						30	
	35	44	1,860	45			0 −0.019	48	20
		49							25
		54							30
	40	44	2,330	52	0 −0.019			55	20
		49				25			
		54				30			
	50	49	2,900	62		65		25	
		54						30	

How to order

Catalog No. d × L

M-EBBM 16 × 34




In-stock item

Return Pins Head Thick 8 mm Type

RETURN PINS

Catalog No.	Material	Hardness after heat treatment
M-RP8B	SUJ2	60 to 64HRC (high frequency quenching)



Catalog No.	d	Unit price in yen									d		D
		L											
		127	152	202	252	302	352	402	452	502	DIMM	Limit deviations	
M-RP8B	10	550									10	—0.013 —0.022	15
	12		620	800							12	—0.016 —0.027	17
	15		630	820	1,250						15		20
	20		720	900	1,510	1,760	2,060				20	—0.020 —0.033	25
	25		900	1,150	1,600	2,040	2,200	2,550			25		30
	30		1,100	1,400	1,740	2,320	3,050	3,510	4,000	4,600	30		35

How to order

Catalog No. d × L

M-RP8B 12 × 202


Shipping In-stock item

Return Pins L Dimensional Designation Type (Unit 1mm)

RETURN PINS

Additional processing to mold bases → P.64 & P.66

Catalog No.	Material	Hardness after heat treatment	H	N
M-RPN	SUJ2	60 to 64HRC	4	8
M-RP8N		(High frequency quenching)	8	12



DIMM	d	
	Limit deviations	D
8	-0.013	12
10	-0.022	15
12	-0.016	17
15	-0.027	20
20	-0.020 -0.033	25
25		30
30		35
35		40

M-RPN Price list

L	Unit price in yen							
	d							
	8	10	12	15	20	25	30	35
47	220	220						
50				320				
52	220	220						
55			270	320				
57	240	240						
60			280	320				
62	260	260						
65			280	320	410			
67	260	260						
70			290	330	420			
72	260	270						
75			290	330	430			
77		280						
80			300	350	440	590		
82		280						
85			300	360	460	600		
87		290						
90			310	360	480	620		
92		290						
95			310	370	500	630		
97		300						
100			330	390	520	650		
102		300						
105			350	410	530	660		
107		310						
110			350	410	540	670	780	
112		310						
115			360	420	540	680		
117		350						
120			400	420	550	720	830	
122		380						
125			400	440	550	720		
127		420						
130			410	460	560	740	860	
135			410	470	560	740		
140			470	480	600	800	920	
145			470	480	600	810		

L	Unit price in yen							
	d							
	8	10	12	15	20	25	30	35
150			520	510	620	830	970	
155			540	560	650	850		
160				630	680	890	1,020	
165			600	630	700	890		
170				640	720	900	1,060	
175			620	660	740	940		
180				680	750	970	1,110	
185			670	700	760	1,000		
190				720	780	1,020	1,170	
195			690	750	790	1,040		
200				780	800	1,050	1,220	
205			710	800	850	1,070		
210				840	870	1,080	1,340	
215			750	920	880	1,100		
220				950	1,050	1,120	1,350	
225				960	1,070	1,140		
230				1,050	1,120	1,160	1,370	
235				1,070	1,130	1,300		
240				1,150	1,320	1,390	1,450	
245					1,400	1,500		
250				1,250	1,510	1,600	1,740	2,480
255					1,590	1,660		
260					1,660	1,720	1,870	
265					1,700	1,800		
270						1,850	1,950	
275					1,760	1,880		
280						1,890	2,070	
290						1,960	2,230	
300						2,040	2,320	3,300
310						2,120	2,410	
320						2,200	2,500	
330							2,590	
380							3,050	4,620
430							3,510	
480							4,000	
530							4,420	
580							4,870	
630							5,330	

※ To specify L dimensions in 1 mm steps, use optional processings.

To specify L dimensions in 0.1 mm or 0.01 mm steps, use M-RPL, M-RPM in page 340.

M-RP8N Price list

L In 1mm steps	Unit price in yen					
	d					
	10	12	15	20	25	30
30~125	950	1,020	1,030	1,170	1,350	1,600
126~150		1,020	1,030	1,170	1,350	1,600
151~200		1,200	1,220	1,350	1,600	1,900
201~250			1,650	1,960	2,050	2,240
251~300				2,210	2,490	2,820
301~350				2,510	2,650	3,550
351~400					3,000	4,010
401~450						4,500
451~500						5,100

※ To specify L dimensions in 0.1 mm or 0.01 mm steps, use M-RP8L, M-RP8M in page 340.

How to order

Catalog No. d × L N + Optional processing

M-RPN 20 × 150
M-RPN 25 × 187
M-RPN 15 × 115 N + **M6**
M-RP8N 20 × 160
M-RP8N 12 × 154
M-RP8N 15 × 180 N + **M5**





M-RPN: In-stock item

M-RP8N: Shipped in 2 business day (excluding the day of order).

However, orders requiring optional processing will be shipped in 2 business days (excluding the day of order)

Optional processing

Option code	Specification		Unit price in yen																											
Applicable to M-RPN Designate L dimensions directly		<table><tr><th>d</th><th>L dimension designation range</th></tr><tr><td>8</td><td>30~ 72</td></tr><tr><td>10</td><td>30~127</td></tr><tr><td>12</td><td>30~215</td></tr><tr><td>15</td><td>30~250</td></tr><tr><td>20</td><td>30~275</td></tr><tr><td>25</td><td>30~320</td></tr><tr><td>30</td><td>30~630</td></tr><tr><td>35</td><td>30~380</td></tr></table>	d	L dimension designation range	8	30~ 72	10	30~127	12	30~215	15	30~250	20	30~275	25	30~320	30	30~630	35	30~380	Changes the full length of M-RPN to a designated dimension (in 1 mm steps). ※ Designate L dimensions directly. ※ It will be machined to an upper size closest to the designated L value.	<table><tr><th>d</th><th>U/price (yen)</th></tr><tr><td>d ≤ 15</td><td>400</td></tr><tr><td>20 25</td><td>450</td></tr><tr><td>30 35</td><td>500</td></tr></table>	d	U/price (yen)	d ≤ 15	400	20 25	450	30 35	500
		d	L dimension designation range																											
8	30~ 72																													
10	30~127																													
12	30~215																													
15	30~250																													
20	30~275																													
25	30~320																													
30	30~630																													
35	30~380																													
d	U/price (yen)																													
d ≤ 15	400																													
20 25	450																													
30 35	500																													
M		<table><tr><th>d</th><th>M (options)</th></tr><tr><td>10</td><td>4 5</td></tr><tr><td>12</td><td>4 5 6</td></tr><tr><td>15</td><td>5 6 8</td></tr><tr><td>20</td><td>6 8 10</td></tr><tr><td>25</td><td></td></tr><tr><td>30</td><td>8 10 12</td></tr><tr><td>35</td><td></td></tr></table>	d	M (options)	10	4 5	12	4 5 6	15	5 6 8	20	6 8 10	25		30	8 10 12	35		Creates a threaded hole on the end face. ※ This option cannot be specified when d=8. Thread depth M4~M6=M diameter × 2.5 M8~M12=M diameter × 2	<table><tr><th>M</th><th>U/Price (yen)</th></tr><tr><td>M4 M5 M6</td><td>400</td></tr><tr><td>M8 M10 M12</td><td>600</td></tr></table>	M	U/Price (yen)	M4 M5 M6	400	M8 M10 M12	600				
		d	M (options)																											
10	4 5																													
12	4 5 6																													
15	5 6 8																													
20	6 8 10																													
25																														
30	8 10 12																													
35																														
M	U/Price (yen)																													
M4 M5 M6	400																													
M8 M10 M12	600																													


Return Pins L Dimensional Designation Type (Unit 0.1mm and 0.01mm)

RETURN PINS

Additional processing to mold bases → P.64 & P.66

Catalog No.	Material	Hardness after heat treatment	H	N	Limit deviations
M-RPL	SUJ2	60 to 64HRC (High-frequency quenching)	4	8	$\begin{smallmatrix} +0.2 \\ 0 \end{smallmatrix}$
M-RP8L			8	12	
M-RPM			4	8	$L \leq 200 \rightarrow \begin{smallmatrix} +0.02 \\ 0 \end{smallmatrix}$
M-RP8M			8	12	$L > 200 \rightarrow \begin{smallmatrix} +0.05 \\ 0 \end{smallmatrix}$

DIMM	Limit deviations	D
8	-0.013	12
10	-0.022	15
12	-0.016	17
15	-0.027	20
20	-0.020 -0.033	25
25		30
30		35
35		40



M-RPL Price list

L In 0.1mm steps	U/price (yen)	
	d	10
30.0 ~ 52.0	620	620
52.1 ~ 57.0	640	640
57.1 ~ 67.0	660	660
67.1 ~ 72.0	660	670
72.1 ~ 82.0	680	
82.1 ~ 92.0	690	
92.1 ~ 102.0	700	
102.1 ~ 112.0	710	
112.1 ~ 117.0	750	
117.1 ~ 122.0	780	
122.1 ~ 127.0	820	

L In 0.1mm steps	Unit price in yen					
	d					
30.0 ~ 55.0	670	720	860	1,040	1,280	2,980
55.1 ~ 65.0	680	720	860	1,040	1,280	2,980
65.1 ~ 70.0	690	730	870	1,040	1,280	2,980
70.1 ~ 75.0	690	730	880	1,040	1,280	2,980
75.1 ~ 80.0	700	750	890	1,040	1,280	2,980
80.1 ~ 85.0	700	760	910	1,050	1,280	2,980
85.1 ~ 90.0	710	760	930	1,070	1,280	2,980
90.1 ~ 95.0	710	770	950	1,080	1,280	2,980
95.1 ~ 100.0	730	790	970	1,100	1,280	2,980
100.1 ~ 105.0	750	810	980	1,110	1,280	2,980
105.1 ~ 110.0	750	810	990	1,120	1,280	2,980
110.1 ~ 115.0	760	820	990	1,130	1,330	2,980
115.1 ~ 120.0	800	820	1,000	1,170	1,330	2,980
120.1 ~ 125.0	800	840	1,000	1,170	1,360	2,980
125.1 ~ 130.0	810	860	1,010	1,190	1,360	2,980
130.1 ~ 135.0	810	870	1,010	1,190	1,420	2,980
135.1 ~ 140.0	870	880	1,050	1,250	1,420	2,980
140.1 ~ 145.0	870	880	1,050	1,260	1,470	2,980
145.1 ~ 150.0	920	910	1,070	1,280	1,470	2,980
150.1 ~ 155.0	940	960	1,100	1,300	1,520	2,980
155.1 ~ 160.0	1,000	1,030	1,130	1,340	1,520	2,980
160.1 ~ 165.0	1,000	1,030	1,150	1,340	1,560	2,980
165.1 ~ 170.0	1,020	1,040	1,170	1,350	1,560	2,980
170.1 ~ 175.0	1,020	1,060	1,190	1,390	1,610	2,980
175.1 ~ 180.0	1,070	1,080	1,200	1,420	1,610	2,980
180.1 ~ 185.0	1,070	1,100	1,210	1,450	1,670	2,980
185.1 ~ 190.0	1,090	1,120	1,230	1,470	1,670	2,980
190.1 ~ 195.0	1,090	1,150	1,240	1,490	1,720	2,980

L In 0.1mm steps	Unit price in yen					
	d					
195.1 ~ 200.0	1,110	1,180	1,250	1,500	1,720	2,980
200.1 ~ 205.0	1,110	1,200	1,300	1,520	1,840	2,980
205.1 ~ 210.0	1,150	1,240	1,320	1,530	1,840	2,980
210.1 ~ 215.0	1,150	1,320	1,330	1,550	1,850	2,980
215.1 ~ 220.0		1,350	1,500	1,570	1,850	2,980
220.1 ~ 225.0		1,360	1,520	1,590	1,870	2,980
225.1 ~ 230.0		1,450	1,570	1,610	1,870	2,980
230.1 ~ 235.0		1,470	1,580	1,750	1,950	2,980
235.1 ~ 240.0		1,550	1,770	1,840	1,950	2,980
240.1 ~ 245.0		1,650	1,850	1,950	2,240	2,980
245.1 ~ 250.0		1,650	1,960	2,050	2,240	2,980
250.1 ~ 255.0			2,040	2,110	2,370	3,800
255.1 ~ 260.0			2,110	2,170	2,370	3,800
260.1 ~ 265.0			2,150	2,250	2,450	3,800
265.1 ~ 270.0			2,210	2,300	2,450	3,800
270.1 ~ 275.0			2,210	2,330	2,570	3,800
275.1 ~ 280.0				2,340	2,570	3,800
280.1 ~ 290.0				2,410	2,730	3,800
290.1 ~ 300.0				2,490	2,820	3,800
300.1 ~ 310.0				2,570	2,910	5,120
310.1 ~ 320.0				2,650	3,000	5,120
320.1 ~ 330.0					3,090	5,120
330.1 ~ 380.0					3,550	5,120
380.1 ~ 430.0					4,010	
430.1 ~ 480.0					4,500	
480.1 ~ 530.0					4,920	
530.1 ~ 580.0					5,370	
580.1 ~ 630.0					5,830	

M-RP8L Price list

L In 0.1 mm steps	Unit price in yen					
	d					
	10	12	15	20	25	30
30.0~125.0	950	1,020	1,030	1,170	1,350	1,600
125.1~150.0		1,020	1,030	1,170	1,350	1,600
150.1~200.0		1,200	1,220	1,350	1,600	1,900
200.1~250.0			1,650	1,960	2,050	2,240
250.1~300.0				2,210	2,490	2,820
300.1~350.0				2,510	2,650	3,550
350.1~400.0					3,000	4,010
400.1~450.0						4,500
450.1~500.0						5,100

M-RPM、M-RP8M Price list

L In 0.01 mm steps	M-RPM Unit price in yen						M-RP8M Unit price in yen					
	d						d					
	10	12	15	20	25	30	10	12	15	20	25	30
30.00~125.00	1,570	1,650	1,670	1,790	2,000	2,230	1,570	1,650	1,670	1,790	2,000	2,230
125.01~150.00		1,650	1,670	1,790	2,000	2,230		1,650	1,670	1,790	2,000	2,230
150.01~200.00		1,830	1,860	1,970	2,250	2,530		1,830	1,860	1,970	2,250	2,530
200.01~250.00				2,580	2,700	2,870			2,290	2,580	2,700	2,870
250.01~300.00					3,140	3,450				2,830	3,140	3,450
300.01~350.00						4,180				3,130	3,300	4,180
350.01~400.00						4,640					3,650	4,640
400.01~450.00						5,130						5,130

How to order


Catalog No. × N +

M-RPL 10 × 100.0
 M-RP8L 15 × 220.1 N + M5
 M-RPM 20 × 240.00 N + M8
 M-RP8M 30 × 349.95



M-RPL & M-RP8L: shipped in 2 business days (excluding the day of order)
 M-RPM & M-RP8M: shipped in 3 business days (excluding the day of order)

Optional processing


Option code	Specification		U/ price in yen																							
M		<table><tr><th>d</th><th>M options</th></tr><tr><td>10</td><td>4 5</td></tr><tr><td>12</td><td>4 5 6</td></tr><tr><td>15</td><td>5 6 8</td></tr><tr><td>20</td><td>6 8 10</td></tr><tr><td>25</td><td></td></tr><tr><td>30</td><td>8 10 12</td></tr><tr><td>35</td><td></td></tr></table>	d	M options	10	4 5	12	4 5 6	15	5 6 8	20	6 8 10	25		30	8 10 12	35		Creates a threaded hole on the end face. ※ This option cannot be specified when d=8. Thread depth M4~M6=M diameter×2.5 M8~M12=M diameter×2	<table><tr><th>M</th><th>U/price (yen)</th></tr><tr><td>M4 M5 M6</td><td>400</td></tr><tr><td>M8 M10 M12</td><td>600</td></tr></table>	M	U/price (yen)	M4 M5 M6	400	M8 M10 M12	600
		d	M options																							
		10	4 5																							
		12	4 5 6																							
		15	5 6 8																							
		20	6 8 10																							
		25																								
		30	8 10 12																							
		35																								
		M	U/price (yen)																							
M4 M5 M6	400																									
M8 M10 M12	600																									

Support Pillars Screw Hole Type

SUPPORT PILLARS

Additional processing to mold bases → P.142

Catalog No.	Material
M-SRD	S45C



Catalog No.	D	Unit price in yen															M	F
		L																
		50	60	70	80	90	100	110	120	130	140	150	160	170	180	200		
M-SRD	20	350	360	370	380	390	400										M6	13
	25	450	460	480	490	500	520										M8	16
	30	600	620	640	650	670	690	720	750									
	35		670	690	710	730	750	780	830	880	930	980						
	40			740	760	790	810	840	870	1,030	1,060	1,090						
	50				1,210	1,240	1,470	1,510	1,540	1,580	1,620	1,660	1,880	2,100	2,160	2,220	M12	24
	60						1,710	1,830	1,940	2,080	2,180	2,270	2,320	2,370	2,450	2,530		
	80						2,380	2,550	2,630	2,720	2,810	2,890	2,980	3,070	3,200	3,320		



How to order

Catalog No. D × L N + Optional processing

M-SRD 50 × 200

M-SRD 40 × 144

M-SRD 80 × 185.95 N + LKC




Shipping

In-stock item

Orders requiring optional processing will be shipped
in 3 business days (excluding the day of order)

Example of use



Optional processing


Option code		Specification	Unit price in yen	
Designate L dimensions directly		Changes the full length to a designated dimension. (in 1 mm steps) ※ Designate L dimension directly. L min ≤ designated L value < L max ※ It will be machined to an upper size closest to the designated L value.	D50 or less	D60 or more
			200	400
LKC		Changes the limit deviations of full length. L $\begin{smallmatrix} +0.25 \\ +0.20 \end{smallmatrix} \rightarrow L \begin{smallmatrix} +0.02 \\ 0 \end{smallmatrix}$ ※ When combined with full length designation, specify in 0.01 mm steps. L min ≤ designated L value < L max	D50 or less	D60 or more
			400	600

Support Pillars Dowel Hole Type

SUPPORT PILLARS

Additional processing to mold bases → P.142

Catalog No.	Material
M-SRC	S45C



※ The ground face has been changed from left end face to right end face.

Please note that the products of old and new specifications may be delivered mixed during the stock replacement period.

D	d H7	F	Supplies with a threaded dowel pin
20	8	15	$\phi 8h7 \times 30$
25	10	20	$\phi 10h7 \times 35$
30			
35			
40			
50			
60	16	30	$\phi 16h7 \times 50$
80			

Catalog No.	D	Unit price in yen														
		L														
M-SRC	20	470	490	500	510	530	540									
	25	570	590	600	610	630	640									
	30	730	750	770	790	800	820	850	880							
	35		810	830	850	880	910	930	960	1,140	1,170	1,190				
	40			880	900	930	960	980	1,010	1,190	1,220	1,240				
	50				1,380	1,410	1,650	1,700	1,730	1,770	1,810	1,850	2,090	2,320	2,380	2,440
	60						2,030	2,150	2,270	2,410	2,500	2,590	2,640	2,690	2,770	2,850
	80						2,780	2,860	2,950	3,040	3,130	3,210	3,300	3,380	3,510	3,640

How to order

Catalog No. D × L N + Optional processing

M-SRC 50 × 120

M-SRC 60 × 165


M-SRC 25 × 98.95 N + LKC



In-stock item

Orders requiring optional processing will be shipped in 3 business days (excluding the day of order).

Example of use



Optional processing


Option code	Specification	Unit price in yen	
Designate L dimensions directly	Changes the full length to a designated dimension. (in 1 mm steps) ※ Designate L dimension directly. $L_{\min} \leq \text{designated } L \text{ value} < L_{\max}$ ※ It will be machined to an upper size closest to the designated L value.	D50 or less	D60 or more
LKC	Changes the limit deviations of full length. $L_{+0.25}^{+0.20} \rightarrow L_{+0.02}^{+0.02}$ ※ When combined with full length designation, specify in 0.01 mm steps. $L_{\min} \leq \text{designated } L \text{ value} < L_{\max}$	D50 or less	D60 or more
		200	400
		400	600

Support Pillars Bolt Hole Type

SUPPORT PILLARS

Additional processing to mold bases → P.142

Catalog No.	Material
M-SRE	S45C



D	Applicable bolts	d	D1	H
20	M6	7	11	7
25	M8	9	14	9
30				
35	M10	11	18	13
40	M12	14	20	15
50	M16	18	26	19
60				
80				

Catalog No.	D	Unit Price in yen										
		L										
		50	60	70	80	90	100	110	120	130	140	150
M-SRE	20	490	590	590	590	590	590					
	25	610	730	730	730	730	730					
	30	720	840	840	840	840	840	1,000	1,000			
	35		1,040	1,040	1,040	1,040	1,040	1,260	1,260	1,260	1,260	1,260
	40			1,290	1,290	1,290	1,290	1,670	1,670	1,670	1,670	1,670
	50				2,050	2,050	2,050	2,090	2,090	2,090	2,090	2,090
	60						2,780	3,490	3,490	3,490	3,490	3,490
	80						4,800	5,500	5,500	5,500	5,500	5,500



How to order

Catalog No. D × L N + Optional processing

M-SRE 50 × 150

M-SRE 40 × 144


M-SRE 35 × 120.95 N + LKC



In-stock item

Orders requiring optional processing will be shipped
in 3 business days (excluding the day of order).

Example of use



Optional processing

Option code	Specification	Unit price in yen	
Designate L dimensions directly	Changes the full length to a designated dimension. (in 1 mm steps) ※ Designate L dimension directly. L min ≤ designated L value < L max ※ It will be machined to an upper size closest to the designated L value.	D50 or less	D60 or more
		200	400
LKC	Changes the limit deviations of full length. L $\begin{smallmatrix} +0.25 \\ +0.20 \end{smallmatrix} \rightarrow L \begin{smallmatrix} +0.02 \\ 0 \end{smallmatrix}$ ※ When combined with full length designation, specify in 0.01 mm steps. L min ≤ designated L value < L max	D50 or less	D60 or more
		400	600


Spacer Rings/Stop Pins/Stop Rings

SPACER RINGS/STOP RINGS/STOP PINS


Spacer rings

Catalog No.	Material	Specification
M-SPR	S45C	D-cut type
M-SPR□B		Circle type

M-SPR



M-SPR□B



Catalog No.	Applicable bolt diameter	Unit price in yen	D	d	K
M-SPR D-cut type	5	150	13	5.5	5
	6		14	6.5	6
	8		18	8.5	7
	10		22	10.5	9
	12		24	12.5	9

Catalog No.	Applicable bolt diameter	Unit price in yen	D	d
M-SPR□B Circle type	5	100	13	5.5
	6		14	6.5
	8		18	8.5
	10	140	22	10.5
	12		24	12.5

How to order

Catalog No.

M-SPR
M-SPRApplicable
bolt diameter8
10 B

Shipping


In-stock item

Stop pins


Additional processing to mold bases → P.140

Catalog No.	Material	Hardness after heat treatment
M-STP	S45C	—
M-STPH	SCM435	45 to 51HRC

M-STP



M-STPH



Catalog No.	Unit price in yen
M-STP	100
M-STPH	250

How to order

Catalog No.

M-STP
M-STPH


Shipping

In-stock item

Stop rings

Additional processing to mold bases → P.140

Catalog No.	Material	Hardness after heat treatment
M-STR	SCM435	45 to 51HRC



Supplied with Hexagon socket flat head
cap screw M5 × 12

Catalog No.	D	Unit price in yen
M-STR	16	150
	20	200
	25	250

How to order

Catalog No.

M-STR

D

20



Shipping


In-stock item

Ejector Rods

EJECTOR RODS

Additional processing to mold bases → P.146

Catalog No.	Material
M-ERA	S45C (body)



Supplied with hexagon socket head cap screw and spring washer


Catalog No.	D	L	L1		Unit price in yen	M	d	D1	H
			DIMM	Code					
M-ERA	20	15 20 25 30 35 40	7 12	→ A → B	320	M6	7	11	8.6
	25	20 25	9 14	→ A → B	390	M8	9	14	11
		30 35 40			470				
	30	20 25			430				
		30 35 40			520				
		50			630				
	35	25			470				
		30 35 40			580				
		50			720				
	40	25 30 35 40	11 16	→ A → B	670	M10	11	17	13.5
		50			890				
	50	30 35 40			1,060				
		50 60			1,290				

How to order

Catalog No. ×
 M-ERA 35 × 25 B


Shipping In-stock item

Spring washers for ejector rods





Applicable bolts	d		E	t
M6	6.1	$+0.5$ 0	10.0	1.6
M8	8.2		13.0	2.0
M10	10.2		16.0	2.5

Example of use





Features of ejector rods

Allows lengthening the ejection stroke by L dimension



Allows shortening ejection time by $T2 - T1$



Locating Rings, Sprue Bushings, Runner & Gate Parts

Locating Rings, Sprue Bushings, Runner and Gate Parts Overview	350
--	-----

Locating Rings

M-LRA, M-LRH and M-LRC	352
M-LRB, M-LRJ and M-LRG.....	354
M-LRD, M-LRE and M-LRF	356

Sprue Bushings

Miniature Hot Sprue Bushings	H-HSB	358
Cooling Channel Type	M-SBLH	362
Bolt Hole, Straight Type (Futaba Original)	M-SBA and M-SBC.....	372
Shoulder, Straight Type (Futaba Original)	M-SBB and M-SBD	373
Bolt Hole Type (JIS)	M-SJA□ and M-SJB□	374
Shoulder Type (JIS)	M-SJC□ and M-SJD□	376
Sprue Bushings Bolt Hole Type	M-SAG□	378
Bolt Hole, Head Thick 10mm Type	M-SBG□ and M-SBH□.....	380
Bolt Hole, Head Thick 15mm Type	M-SBI□ and M-SBJ□	382
Shoulder Type	M-SBE□ and M-SBF□.....	384

Working Limits for Sprue Bushings	386
---	-----

Runner Lock Pins

M-RLA.....	387
------------	-----

Pin-Point Gate Bushings

M-PGBA and M-PGBB.....	388
------------------------	-----

Locating Rings, Sprue Bushings, Runner & Gate Parts Overview

Locating rings

Additional processing to MDC



Catalog No.	M-LRA
Shipping	In-stock item
Page	P.352

Additional processing to MDC



Catalog No.	M-LRH
Shipping	In-stock item
Page	P.352

Additional processing to MDC



Catalog No.	M-LRC
Shipping	In-stock item
Page	P.352

Locating rings

Additional processing to MDC



Catalog No.	M-LRB
Shipping	In-stock item
Page	P.354

Additional processing to MDC



Catalog No.	M-LRJ
Shipping	In-stock item
Page	P.354

Additional processing to MDC



Catalog No.	M-LRG
Type	Reversible type
Shipping	In-stock item
Page	P.354

Locating rings

Additional processing to MDC



Catalog No.	M-LRD
Shipping	In-stock item
Page	P.356

Additional processing to MDC



Catalog No.	M-LRE
Shipping	In-stock item
Page	P.356

Additional processing to MDC



Catalog No.	M-LRF
Type	Large bore type
Shipping	In-stock item
Page	P.356

Miniature hot sprue bushings



Catalog No.	H-HSB
Type	Bolt hole type
Shipping	In-stock item
Page	P.358

Sprue bushings (cooling channel type)



Catalog No.	M-SBLH
Type	Bolt hole type
Shipping	In-stock item
Page	P.362

Sprue bushings (Futaba original)

Additional processing to MDC



Catalog No.	M-SBA	M-SBC
Type	Bolt hole type	
Shipping	In-stock item	
Page	P.372	

Additional processing to MDC




Catalog No.	M-SBB	M-SBD
Type	Shoulder type	
Shipping	In-stock item	
Page	P.373	

Additional processing to MDC denotes the parts that support additional processing to mold bases.
Shipping times are shown in business days (excluding the day of order).

Sprue bushings JIS type

Additional processing to MDC



Catalog No.	M-SJA□	M-SJB□
Type	Bolt hole type	
Shipping	5 days	
Page	P.374	

Additional processing to MDC



Catalog No.	M-SJC□	M-SJD□
Type	Shoulder type	
Shipping	5 days	
Page	P.376	

Sprue bushings

Additional processing to MDC



Catalog No.	M-SAG□
Type	Bolt hole type
Shipping	3 days
Page	P.378

Additional processing to MDC



Catalog No.	M-SBG□	M-SBH□
Type	Bolt hole, head thick 10 mm type	
Shipping	5 days	
Page	P.380	

Sprue bushings bolt hole type

Additional processing to MDC



Catalog No.	M-SBI□	M-SBJ□
Type	Bolt hole, head thick 15 mm type	
Shipping	5 days	
Page	P.382	

Sprue bushing shoulder type

Additional processing to MDC



Catalog No.	M-SBE□	M-SBF□
Type	Shoulder type	
Shipping	5 days	
Page	P.384	

Runner lock pins



Catalog No.	M-RLA
Material	SKS3
Shipping	In-stock item
Page	P.387

Pin-point gate bushings





Catalog No.	M-PGBA	M-PGBB
Material	SKH51	
Shipping	8 days	
Page	P.388	

Locating Rings



LOCATING RINGS

Additional processing to mold bases → P.86



Catalog No.	Material
M-LRA60×36	S45C



Catalog No.	Material
M-LRH60×15	S45C



Catalog No.	Material
M-LRC	S45C



*1. Only when D=60, $\phi d \begin{smallmatrix} +0.2 \\ +0.1 \end{smallmatrix}$
 *2. When T=10, 2

Unit price 700 yen

 How to order

Catalog No.

M-LRA60 × 36

 Shipping In-stock item

Unit price 700 yen

 How to order

Catalog No.

M-LRH60 × 15

 Shipping In-stock item

Catalog No.	D	T	Unit price in yen	d	P	Bolt hole			Applicable bolt	
						d1	D1	t		
M-LRC	60	10	460	40	50	5.5	9	4.5	M5	
		15	490							
		20	530							
		25	570							
	100	10	530	70	85	6.5	11	3.5	M6	
		15	570					8		
		20	610							
		25	680							
		30	760							
	110	10	570	80	95			3.5		
		15	610					8		
		20	680							
	120	10	650	90	105			3.5		
		15	680					8		
		20	760							
		25	910							
	150	15	910	110	130			9		14
		20	1,060							
		25	1,120							

 How to order

Catalog No.

M-LRC

 Shipping

D × T
100 × 20

In-stock item

Catalog No.	D	d	Unit price in yen	Applicable bolt
M-LRB	100	36	760	M6
	120		960	

The catalog numbers of the following products have been changed as shown below:

Former M-LRB100 × 50 → new M-LRJ100 × 15 × 50

Former M-LRB120 × 50 → new M-LRJ120 × 15 × 50

How to order

Catalog No. $D \times d$
M-LRB **100 × 36**

Shipping In-stock item

Catalog No.	D	T	d	Unit price in yen	P	Bolt hole			Applicable bolt
						d1	D1	t	
M-LRJ	100	15	35 40 50	720	85	6.5	11	8	M6
		20		800					
		25		870					
	120	15	35 40 50	910	100	9	14	6	M8
		20		1,030					
		25		1,140					
	150	15	35 40 50	1,220					
		20							
		25							

How to order

Catalog No. $D \times T \times d$
M-LRJ **100 × 15 × 40**

Shipping In-stock item


Catalog No.	D	Unit price in yen	V	d	P	Bolt hole			Applicable bolt
						d1	D1	t	
M-LRG	100	950	60	40	50	5.5	9	4.5	M5
	120	980	100	70	85	6.5	11	8	M6

How to order

Catalog No. D
M-LRG **100**

Shipping In-stock item

Example of use





※ Locate ring M-LRG is reversible type. It can be installed from both the front and back sides.

Locating Rings



LOCATING RINGS

Additional processing to mold bases → P.86



Catalog No.	Material
M-LRD	S45C



Catalog No.	Material
M-LRE	S45C



Catalog No.	Material	Type
M-LRF	S45C	Large bore type



Catalog No.	D	T	Unit price in yen	d	P	Bolt hole			R	Applicable bolt
						d1	D1	t		
M-LRD	60	10	630	40	50	5.5	9	4.5	5	M5
		15	650							
		20	680							
		25	720							
	100	10	700	70	85	6.5	11	3.5	10	M6
		15	720							
		20	800							
		25	870							
		30	950							
		35	1,030							
	110	15	760	80	95			8		
		20	840							
		25	910							
	120	15	910	90	105			6		
		20	1,030							
		25	1,140							
	150	15	1,140	110	130	9	14	6	M8	
		20	1,220							
		25	1,440							

How to order

Catalog No.

D

×

T

Shipping

In-stock item

M-LRD

100

×

30

Catalog No.	D	T	Unit price in yen	d	P	Bolt hole			R	Applicable bolt			
						d1	D1	t					
M-LRE	100	15	1,150	70	85	6.5	11	8	5	M6			
		20	1,200					20	10				
		35	1,240										
		40	1,400										
		45	1,560										
	120	15	1,350	90	105			8	5				
		20	1,400					20	10				
		35	1,480										
		40	1,680										
		45	1,880										

How to order

Catalog No.

D

×

T

Shipping

In-stock item

M-LRE

100

×

20

Catalog No.	D	Unit price in yen	V	d	P	Bolt hole		Applicable bolt
						d1	D1	
M-LRF	100	1,200	130	85	115	6.5	11	M6
	120	1,400	150	105	135			

How to order

Catalog No.

D

Shipping

In-stock item

M-LRF

100

Miniature Hot Sprue Bushings

SPRUE BUSHINGS

Features of Miniature Hot Sprue Bushing

In the plastic injection molding, the cooling process takes the longest time in a molding cycle. A commonly used way to shorten the cooling time is to use the temperature control channels created on the mold plate. Attempts to increase cooling efficiency, however, may sometimes lead to poor flow of resin, resulting in adverse affects on the quality of molded products.

A hot sprue bushing provides the ability to maintain the flow of resin by heating the sprue section with a heater. This allows the mold temperature to be set lower than its normal temperature, thereby reducing the cooling time and increasing the productivity of molding process.

This Miniature hot sprue bushing has been specifically developed for use in molds mounted on molding machines with a nozzle touch force of 20kN or less by adopting highly efficient small-diameter heater.

< Features >

● Compact design

Adopting a highly efficient small-diameter heater that has an outer diameter of 13.5 mm and inner diameter of 10 mm, this hot sprue bushing is specifically designed for molding small products.

● Simple and easy installation

This product complies with Futaba sprue bush (M-SJAD) standard and fits the Futaba standard mold bases. It can be installed even on a cold runner mold in use with a simple alternation and easily realize a hot runner system.


● Ease of maintenance

Easy to wear tip portion can endure continuous use by replacing its retainer tip.

Miniature hot sprue bushing



Components of Miniature hot sprue bushing



Effects of Miniature hot sprue bushings

Increased productivity

As the Miniature hot sprue bushing allows the mold temperature to be set lower compared to cold runner molds, the cooling time is reduced. This enables high-cycle molding, realizing increased efficiency in mass production, lower energy consumption and reduced production costs.

Effect verification example

<Molding conditions>

Molding material : LCP (liquid crystal polymer)
 Molded product : wiring cover (2 pieces/shot)
 Size of molded product : $30 \times 30 \times 1$ (mm)

Reduced molding cycle time

When a cold sprue bushings is used: 16 sec./pc.


When a Miniature hot sprue bushing is used: 13 sec./pc.

The molding cycle time is reduced by 3 seconds per shot.

In the case of 100,000 shots, $3 \text{ sec./shot} \times 100,000 \text{ shots} = 300,000 \text{ seconds}$... **molding cycle time can be reduced by approx. 84 hours**
 If assuming that the molding costs are 2,000 yen per hour, $84 \text{ hours} \times 2,000 \text{ yen/h} = 168,000 \text{ yen}$... **a significant cost reduction is achieved!**

Type of sprue bushing	Cooling time
When a cold sprue bushing is used	4 seconds
When a Miniature hot sprue bushing is used	Can be reduced to 1 second

Molding cycle model



Saved material costs


When a cold sprue bushings is used: 5.08 g / pc.

When a Miniature hot sprue bushing is used: 4.48 g / pc.


→ 0.34 g / pc. resin is saved.

In the case of 100,000 shots, $0.60 \text{ g/pc.} \times 100,000 \text{ shots} = \text{approx. } 60 \text{ kg}$... **approx. 11% of resin is saved!**
 If assuming that the resin material cost is 2,000 yen / kg, ... **a cost reduction of 120,000 yen is achieved!!**


When a cold sprue bushing is used



When a Miniature hot sprue bushing is used



Example of installation & machining



Range of application

< List of resins supported >

Abbreviation	Name of resin	Support
TPE	Thermoplastic elastomer	○
TPU	Thermoplastic polyurethane	○
PE	Polyethylene	○
PS	Polystyrene	○
AS	Acrylonitrile styrene	○
TPO	Aolefinic elastomer	○
PP	Polypropylene	○
ABS	Acrylonitrile styrene	○
PMMA	Metacrylate resin	○
POM	Polyacetal	○
PA	Polyamide	○
PPE	Polyphenylene ether	○
PBT	Polybutylene terephthalate	○
PET	Polyethylene terephthalate	○
PC	Polycarbonate	○

Abbreviation	Name of resin	Support
PPS	Poly phenylene Sulfide	△※1
PSU	Polysulfone	△※1
LCP	Liquid Crystal Polymer	△※1
PEI	Polyetherimide	△※1
PEEK	Polyether ether keton	×
PVC	Polyvinyl chloride	×

*1. To be inquired.

< A rough guide of resin amount > ※2

Melt flow index	g / shot less
Low viscosity (>16)	40
Middle viscosity (7-16)	30
High viscosity (<7)	20

*2. The values are provided only as a reference and not a guarantee of effects.

Cooling Channel Type

SPRUE BUSHINGS

Features of cooling channel type sprue bushings

In the plastic injection molding, the cooling process takes the longest time in a molding cycle. A sprue is one of the sections that require longer time to solidify because of its thickness. A commonly used way to cool the sprue section is to use the temperature control channels created on the mold plate. However, the efficiency of heat exchange of the sprue section may be low, because these channels are mainly used to cool the molded product section.

This cooling channel type sprue bushing has a cooling channel inside itself and cools the sprue section directly, thereby increasing the cooling efficiency and molding productivity.

● Increases molding productivity



- ① **Realizes high-cycle molding**
by reducing cooling time
- ② **Reduces costs** through high-cycle molding
(Increases mass-production efficiency and lowers power consumption)
- ③ **Prevents molding troubles and increases the service life of molds** by keeping the mold temperature from rising excessively and preventing stringing.

● Using the latest “Milling-Combined Laser Metal Sintering Method” technology, we developed a

small-diameter sprue bushing that has a slit-type cooling channel structure. As the cooling channel is integrated in the bushing, there is no worry about leaks.

- **We standardized a sprue bushing for exclusive use with 3-plate type, which fits Futaba standard mold bases.**

Cooling channel type sprue bushing structure diagram



Effects of cooling channel type sprue bushing

Stable molding quality


In the plastic injection molding, the temperature of molds has the greatest influence on the influence on product quality. Therefore, it is necessary to control temperature inside the mold that fluctuates between day and night or seasons. This cooling channel type sprue bushing provides the ability to control otherwise difficult-to-control temperature of sprue bushings and enables the production of molded products of stable quality.

Transition to stable molding in a short period of time


At the beginning of plastic injection molding, trial molding is required until the temperature of the mold is stabilized. By using this cooling channel type sprue bushing, stable molding can be achieved in a short period of time.

The charts below show the differences depending on whether or not to supply water to the sprue bushing. When not supplying water to the sprue bushing, temperature differences occur between the cavity and the sprue bushing sections, but the differences have been narrowed when supplying water to the sprue bushing.

Temperature transition in continuous molding of 10 shots when cooling water is supplied to sprue bushing



Temperature transition in continuous molding of 10 shots when cooling water is not supplied to sprue bushing



Molding condition

Molding resin: polypropylene

Resin temperature: 190°C

molding cycle: 22 sec.

Temperature of temperature-control media: 40°C (both mold and sprue bushing)

Temperature measurement: thermocouple

Mold structure: two plate type

Cooling Channel Type

SPRUE BUSHINGS

Effects of cooling channel type sprue bushing

We verified the states of plastic generation at the sprue & runner sections when supplying and when not supplying cooling water to the sprue bushing under the same molding conditions (resin temperature and holding pressure, etc.) and observed the differences in results as shown below depending on whether or not supplying cooling water to the sprue bushing.

When cooling water is supplied to sprue bushing

Molding resin: polycarbonate

A plastic of sufficient quality for continuous molding was formed at the sprue and runner sections. Cooling time of sprue section: 7 sec. Molding is possible.	A plastic of sufficient quality for continuous molding was formed at the sprue and runner sections. Cooling time of sprue section: 5 sec. Molding is possible.	The plastic at the second sprue section was deformed (a small bend occurred). The plastic was not solidified and deformed (mashed) by the take-out chuck. Cooling time of sprue section: 3 sec. Molding is not possible (risky state).

When cooling water is not supplied to sprue bushing


Molding resin: polycarbonate

The plastic at the sprue section was deformed (a small bend occurred). The plastic was not solidified and deformed (mashed) by the take-out chuck. Cooling time of sprue section: 8 sec. A sign of risk for poor molding quality is observed.	The plastic at the sprue and second sprue sections was deformed (a large bend occurred). The plastic was not solidified and deformed (mashed) by the take-out chuck. Cooling time of sprue section: 5 sec. Molding is impossible (risky state)	Stringing occurred. The plastic at the second sprue section was cut off. Cooling time of sprue section: 3 sec. Molding is impossible (risky state)

※ When not supplying cooling water to the sprue bushing, a plastic of sufficient quality for molding was formed after cooling of approx. 13 seconds.

With or without the supply of water to sprue bushing	Cooling time of sprue bushing
When not supplying cooling water	13 seconds
When supplying cooling water	Can be reduced to 5 seconds.

Molding cycle model



Cooling time was reduced by 60%

**Cooling time of the sprue section is shortened by approx.
60% by supplying cooling water to sprue bushing**

※ This verification results are only an example of verifying solidification states at the sprue and runner sections and not a guarantee of effects on the solidification or reduction of cooling time at the molded product section.

Notes for molding

About temperature controls

1. Temperature control media applicable to sprue bushing

The temperature control media that can be used for sprue bushing are water and air. Do not use oil or steam, etc.

2. Installation of temperature controllers


Install temperature controllers for molds and sprue bushings separately. This makes temperature controls easy.

3. Circulation water

Use the water that does not contain dust and sludge have been removed.

4. When not using molds

Remove water from the cooling channel and take anti-corrosion measures to prevent rust or corrosion from progressing in it.



About setting of molding conditions

When setting molding conditions, set the temperature controllers for molds and sprue bushings to the same temperature. After appropriate molding conditions are found, gradually lower the temperature of the controller for sprue bushings. This allows you to find appropriate molding conditions easier, rather than the setting of molding conditions with different temperatures from the beginning.

Effect of increasing production volume

An increase in production volume when cooling channel type sprue bushing is used.


With or without the use of cooling channel type sprue bushings	Reduced cooling time (sec.)	Number of shots per hour	Trial calculation based on the assumption that the molding cycle time (X) is 30 sec. when the cooling channel type sprue bushing is not used			
			Number of shots per hour	Number of shots per 24 hours	Number of increase in shots per 24 hours	Rate of increase in shots
When used	0	$3,600 \div X^{*1}$	120	2,880	—	—
When not used	1	$3,600 \div (X - 1)$	124	2,979	99	3 %
	2	$3,600 \div (X - 2)$	128	3,085	205	7 %
	3	$3,600 \div (X - 3)$	133	3,200	320	11 %
	4	$3,600 \div (X - 4)$	138	3,323	443	15 %
	5	$3,600 \div (X - 5)$	144	3,456	576	20 %

*1. X is molding cycle time.

Cooling Channel Type


SPRUE BUSHINGS

Specification of cooling channel type sprue bushing



※ Turning finish is used for the body section.

The cooling channel type sprue bushing is composed of a substrate with hardness of HRC40 and a molding section, which has been built by sintering special powers by laser using Milling -Combined Laser Metal Sintering Method. The interface between the substrate and the molding section is completely fused and free from leaks.



Sprue hole nitrided

D		V	D1	L	P1	P2	W	Item name
DIMM	Limit deviations							
13	0 -0.011	10	40	30	30	28	3	M-SBLH13×30
16		12		35				M-SBLH16×35
20	0 -0.013	14	50	45	36	35	4	M-SBLH20×45



1 business day (excl. the day of order)

Price

To be quoted.

Cooling media for sprue bushing

The cooling media that can be used for this sprue bushing is water and air.

Do not use oil, steam or other cooling media, which is likely to become high temperature or high pressure.

If using oil under low pressure at temperature of 100°C or less, be sure to use the oil with low viscosity. After use, clean the product so that the oil does not stick or stay inside the product.


Notes for use See page 370

Special orders See page 371


Installation specification of cooling channel type sprue bushings

Detailed view at the entrance of the cooling channel


Stem diameter $\phi 13$



Stem diameter $\phi 16$




Stem diameter $\phi 20$



※ The dimension of O-ring groove is based on JIS B 2406: 1991 O-rings housings -- Design criteria.


Thickness of top clamping plate and runner plate applied



Main installation dimensions

※ For dimensions not listed below, see the next page.


T	R	K	Z	H
25	15	15	10	7
30	15	15	15	7



Main installation dimensions

※ For dimensions not listed below, see the next page.

T	R	K	Z	H
30	15	20	10	7 ~ 12 (Rec.12)
30	20	15	15	7
35	20	15	20	7



Main installation dimensions

※ For dimensions not listed below, see the next page.

T	R	K	Z	H
35	20	25	10	7 ~ 17 (Rec.17)
35	25	20	15	7 ~ 12 (Rec.12)
45	25	20	25	7 ~ 12 (Rec.12)
45	30	15	30	7
50	30	15	35	7

Cooling Channel Type

SPRUE BUSHINGS

Cooling channel type sprue bushing installation steps

1. Set the thickness of plate and the length of sprue bushing

$$K \geq L - R \cdots \cdots (\text{formula 1})$$


K: 15 mm or more required

L: Sprue bushing length

Select sprue bushing from the following table.

D	13	16	20
L	30	35	45


R: Runner stripper plate thickness



2. Set the position of water channel (φ6), H dimension.

To secure the space for creating the Rc(PT)1/8 threaded hole, H dimension of 7 mm or more is required.


H dimension adapted to K dimension			
K	15	20	25
H	7	7 ~ 12 (Rec. 12)	7 ~ 17 (Rec. 17)



3. Place water channels

The charts below show examples of placement of water channels on the top clamping plate.


Design so that the machining regions for the water channels do not interfere with those for other holes.



4. Install O-ring and assembly screw

Be sure to install O-ring.

D	13	16	20
O-ring	P5	P5	P6
Assembly screw	M5 × 12		




Installation specification to mold bases

The table below shows cooling channel type sprue bushings that fit Futaba standard mold bases. Please use this table to select cooling channel type sprue bushings while designing molds.

【Applicable mold bases】 D series, F series and H series 3-plate type mold bases

※ The D and L dimensions of sprue bushings are determined by T and R dimensions.




Nominal dimensions of mold base	T	R	D	L	K	Z	H	Applicable sprue bushings
1515 1518 1520 1523 1525 1530	25	15	13	30	15	10	7	M-SBLH13×30
1818 1820 1823 1825 1830 1835	30	15	13	30	15	15	7	M-SBLH13×30
			16	35	20	10	12	M-SBLH16×35
2020 2023 2025 2030 2035 2040 2045 2323 2325 2327 2330 2335 2340	30	20	16	35	15	15	7	M-SBLH16×35
2525 2527 2530 2535 2540 2545 2550 2730 2735 2740 2750 2930 2935 2940	35	25	20	45	20	15	12	M-SBLH20×45
		20	16	35	15	20	7	M-SBLH16×35
			20	45	25	10	17	M-SBLH20×45
3030 3032 3035 3040 3045 3050 3055 3060 3335 3340 3345 3350	45	30	20	45	15	30	7	M-SBLH20×45
		25	20	45	20	25	12	M-SBLH20×45
3535 3540 3545	45	30	20	45	15	30	7	M-SBLH20×45
3550 3555 3560 4040 4045 4050 4055 4060 4070	50	30	20	45	15	35	7	M-SBLH20×45

※ Nominal dimension 3535 to 4070 are applicable when R=30.

When ordering the installation of cooling channel type sprue bushings in mold bases, please advise us on your specification requirements with a drawing.

◆ Example of the installation of a cooling channel type sprue bushing.



Cooling Channel Type


SPRUE BUSHINGS

Notes for use


We recommend to install cooling channel type sprue bushings as they are after purchase. In the cases that any alternation is required, however, please note the followings:

Chucking the body section is forbidden

This sprue bushing has holes for water channel inside its body. Tightening the body with a chuck such as lathe, etc. may cause a crack in the body or damage the internal structure of the bushing. When chucking the sprue bushing, do not chuck it directly and use a spring collet, etc. to distribute the tightening force exerted on the body.




◆ Avoid chucking sprue bushing directly.



◆ Use spring collet, etc. and lightly chuck the body.


Machining outer shape or holes is forbidden

Do not perform the machining as shown on the right as it may interfere with cooling channels, etc. in the body.



Additional machining


For machining of runner grooves, etc. consult us as it may interfere with cooling channel inside the body.



About special orders for cooling channel sprue bushing

The cooling channel of this sprue bushing is formed through "milling -combined laser metal sintering method". Due to the various conditions imposed on this technology, special orders for production of cooling channel type sprue bushings not listed in this catalog are restricted to the range shown below:

Also, depending on the respective combinations of dimensions, the production may not be allowed.



※ The material and hardness are the same as standard products (see page 366).

※ The supplied accessories such as hexagon socket head cap screw and O-rings are the same as standard products (see page 366).

※ Products of specification without nitriding treatment will be made to order.

Applicable to straight type

D		D1	P1	P2	W	SR	d	α	G
DIMM	Limit deviations								
13	0 -0.011	40	30	28	3	10.5	11	2.5 3 3.5	1 2 5 10
16						12	13		
20	0 -0.013	50	36	35	4	16	20		

D	L In 0.01 mm steps
13	31.50 ~ 40.00
16	34.00 ~ 45.00
20	38.00 ~ 55.00

Applicable to tapered type

D	V	G	L In 0.01 mm steps	Restrictions
13	8	5	Production not allowed	$d=2.5, \alpha=1$ only acceptable
		10	$36 \leq L \leq 40$	
	9	5	Production not allowed	If $d \geq 3$ and $\alpha=2$, production not allowed.
		10	$33 \leq L \leq 40$	
	10	5	$39 \leq L \leq 40$	
		10	$30 \leq L \leq 40$	
16	11	5	$34 \leq L \leq 40$	
		10	$28 \leq L \leq 40$	
	10	5	Production not allowed	
		10	$41 \leq L \leq 45$	
	11	5	Production not allowed	
		10	$39 \leq L \leq 45$	
	12	5	Production not allowed	
		10	$35 \leq L \leq 45$	
	13	5	$42 \leq L \leq 45$	
		10	$33 \leq L \leq 45$	
	14	5	$36 \leq L \leq 45$	
		10	$30 \leq L \leq 45$	

D	V	G	L In 0.01 mm steps
20	12	5	Production not allowed
		10	$51 \leq L \leq 55$
	13	5	Production not allowed
		10	$48 \leq L \leq 55$
	14	5	Production not allowed
		10	$45 \leq L \leq 55$
	15	5	Production not allowed
		10	$42 \leq L \leq 55$
	16	5	$51 \leq L \leq 55$
		10	$40 \leq L \leq 55$
	17	5	$46 \leq L \leq 55$
		10	$37 \leq L \leq 55$
	18	5	$40 \leq L \leq 55$
		10	$35 \leq L \leq 55$

Shipping to be quoted.


Unit price to be quoted.

Sprue Bushings Bolt Hole, Straight Type (Futaba Original)



SPRUE BUSHINGS

Additional processing to mold bases → P.92

Catalog No.	Material	Hardness after heat treatment
M-SBA	SK3	Not heat treated



Catalog No.	Material	Hardness after heat treatment
M-SBC	SKD61	48 HRC or more



Catalog No.	D	L	d		Unit price in yen	D		M	α
			DIMM	Limit deviations		DIMM	Limit deviations		
M-SBA	16	50	3.5 → A		2,900	16	0 -0.011	40	3
		70			3,400			60	2
		90			3,800			80	
		130			4,400			120	3
	20	50	4.5 → B		2,900	20	0 -0.013	40	
		70			3,400			60	
		90			3,800			80	
		130			4,400			120	

Catalog No.	D	L	Unit price in yen	D		D1	P	M
				DIMM	Limit deviations			
M-SBC	13	50	6,300	13	0 −0.011	36	26	40
		70	8,000					60
	16	50	6,300	16		50	36	40
		70	8,000					60
		90	10,000					80
	20	50	6,300	20	0 −0.013			40
		70	8,000					60
		90	10,000					80

How to order

Catalog No. **M-SBA** $D \times L \times 10$ d
16 $\times$ **70** $\times$ 10 **A**



In-stock item

How to order

Catalog No. **M-SBC** $D \times L \times 10A$
13 $\times$ **70** $\times$ 10A






In-stock item

Sprue Bushings Bolt Hole Type (JIS)

SPRUE BUSHINGS




Additional processing to mold bases → P.92

Catalog No.	Material	Hardness after heat treatment
M-SJAC	S45C	Not heat treated
M-SJAF	HPM1	37 to 41HRC
M-SJAD	SKD61	48 HRC or more



Supplied with hexagon socket head cap screw M5 × 12 (2 pcs.)

Catalog No.	Material	Hardness after heat treatment
M-SJBF	HPM1	37 to 41HRC
M-SJBD	SKD61	48 HRC or more



Supplied with hexagon socket head cap screw M5 × 12 (2 pcs.)

Catalog No.	D	L *2 In 0.1 mm steps	SR		d		α	V In 0.1 mm steps	G In 1° steps		D		D1	P			
			DIMM	Code	DIMM	Code			DIMM	Code	DIMM	Limit deviations					
Straight type M-SJAC (S45C) M-SJAF (HPM1) M-SJAD (SKD61)	10	10.0 ~ 100.0	0 → Z				1 *3 2 3 4	Specify only for tapered type D>V≥E+2	Specify only for tapered type 1 → 1 2 → 2 3 → 3 4 → 4 5 → 5 6 → 6 7 → 7 8 → 8 9 → 9 10 → A	10	0 —0.009	35	25				
	13		10.5 → Y		2 *3 → A					13	0 —0.011						
			11 → A		2.5 *3 → B						16						
			12 → B		3 *3 → C						20						
Tapered type M-SJBF (HPM1) M-SJBD (SKD61)	16			0 → Z		3.5 → D								16	0 —0.011	50	36
			10.5 → Y		4 → E												
			11 → A		4.5 → F												
	20		12 → B		5 → G									20	0 —0.013		

*1. E dimension is set in accordance with L dimension.

*2. L dimension is restricted by d, V and alpha. Also, G is restricted by L dimension.

*4. When SR=0, the value is +10.

*3. L dimension limits

alpha	d	2	2.5	3
1	50	50	85	
2 3 4	85	85	L max	

Working limit details → P.386

Straight type D - E ≥ 2

Tapered type V - E ≥ 2

When G ≥ 6, L - F ≥ 3

When G < 6, L - F ≥ $\frac{0.15}{\tan G} + 1.5$ Calculation of E
E = d + 2 (L + (U) + 7.5) tan(alpha/2)
U: when additional processing of ZC is specifiedCalculation of F
F = $\frac{D-V}{2 \tan(G-0.25)}$

*0.25 is a value that takes G tolerance into account.

How to order

Catalog No.	D	×	L	SR	d	alpha	N	V	-	G	+	Optional processing
M-SJAC	10	×	62.5	A	C	1			-		+	
M-SJBF	13	×	48.0	A	E	2	N	10.0	-	5	+	LKC



Orders are shipped out in 5 business days (excluding the day of order).

Price list

Straight type




Catalog No.		Unit price in yen					
L	D	M-SJAC		M-SJAF		M-SJAD	
		10•13	16•20	10•13	16•20	10•13	16•20
10.0 ~ 20.0		2,820	3,100	3,200	3,480	3,670	3,850
20.1 ~ 40.0		2,820	3,100	4,230	4,700	4,790	5,260
40.1 ~ 60.0		3,290	3,670	5,550	6,110	6,200	6,770
60.1 ~ 80.0		3,850	4,040	7,240	7,990	8,080	8,840
80.1 ~ 100.0		5,450	5,920	9,680	10,620	10,620	11,660

Tapered type

Catalog No.		Unit price in yen			
L	D	M-SJBF		M-SJBD	
		10•13	16•20	10•13	16•20
10.0 ~ 20.0		3,670	3,950	4,140	4,320
20.1 ~ 40.0		4,790	5,260	5,360	5,830
40.1 ~ 60.0		6,110	6,670	6,770	7,330
60.1 ~ 80.0		7,900	8,650	8,740	9,490
80.1 ~ 100.0		10,430	11,370	11,370	12,410

Optional processing

Runner groove machining

Specification	Code	Shape	Code	Shape	Code	Shape	Dimension option	Unit price in yen														
Shape A (trapezoid)  ◆ Working limits for A (T, J, L or P) W: (E-0.4) ≥ W Combination with ZC is not available	AIW		AHW		AXW		W dimension options <table><tr><th>W</th><th>t</th></tr><tr><td>3</td><td>2.5</td></tr><tr><td>4</td><td>3</td></tr><tr><td>5</td><td>3.5</td></tr><tr><td>6</td><td>4</td></tr><tr><td>8</td><td>5.5</td></tr><tr><td>10</td><td>7</td></tr></table> How to specify: AIW5	W	t	3	2.5	4	3	5	3.5	6	4	8	5.5	10	7	AIW AHW 1,000 AXW 1,800 ATW AJW 2,000 ALW APW 1,500
W	t																					
3	2.5																					
4	3																					
5	3.5																					
6	4																					
8	5.5																					
10	7																					
Shape B (semicircle)  ◆ Working limits for B (T, J, L or P) R: (E-0.4) ≥ 2 × R Combination with ZC is not available	BIR		BHR		BXR		R dimension options <table><tr><td>1</td></tr><tr><td>1.25</td></tr><tr><td>1.5</td></tr><tr><td>1.75</td></tr><tr><td>2</td></tr><tr><td>2.5</td></tr><tr><td>3</td></tr><tr><td>4</td></tr></table> How to specify: BXR3	1	1.25	1.5	1.75	2	2.5	3	4	BIR BHR 1,000 BXR 1,800 BTR BJR 2,000 BLR BPR 1,500						
1																						
1.25																						
1.5																						
1.75																						
2																						
2.5																						
3																						
4																						
Shape C (Arc+Tangent)  ◆ Working limits for C (T, J, L or P) Q: (E-0.4) ≥ Q × 1.09 Combination with ZC is not available	CIQ		CHQ		CXQ		Q dimension options <table><tr><td>2</td></tr><tr><td>2.5</td></tr><tr><td>3</td></tr><tr><td>3.5</td></tr><tr><td>4</td></tr><tr><td>5</td></tr><tr><td>6</td></tr><tr><td>8</td></tr></table> How to specify: CTQ4	2	2.5	3	3.5	4	5	6	8	CIQ CHQ 1,000 CXQ 1,800 CTQ CJQ 2,000 CLQ CPQ 1,500						
2																						
2.5																						
3																						
3.5																						
4																						
5																						
6																						
8																						

Code	Specification	U/price (yen)
BC		500
BN		—500
NC		200
LKC		600




Code	Specification	U/price (yen)
GKC		1,800
ZC		1,000

Sprue Bushings Shoulder Type (JIS)




SPRUE BUSHINGS

Additional processing to mold bases → P.92

Catalog No.	Material	Hardness after heat treatment
M-SJCC	S45C	Not heat treated
M-SJCF	HPM1	37 to 41 HRC
M-SJCD	SKD61	48 HRC or more



Catalog No.	Material	Hardness after heat treatment
M-SJDF	HPM1	37 to 41 HRC
M-SJDD	SKD61	48 HRC or more



Catalog No.	D	H		L ^{*2}		SR		d		α	V	G		D							
		DIMM	Code	In 0.1 mm steps	DIMM	Code	DIMM	Code	In 1° steps			DIMM	Limit deviations								
Straight type M-SJCC (S45C) M-SJCF (HPM1) M-SJCD (SKD61)	10	25	→ A	10.0 ~ 100.0		0 → Z 11 → A 12 → B 13 → C	2 ^{*3} 2.5 ^{*3} 3 ^{*3} 3.5	→ A → B → C → D	1 ^{*3} 2 3 4	Specify only for tapered type D>V≥E+2	Specify only for tapered type 1 → 1 2 → 2 3 → 3 4 → 4 5 → 5 6 → 6 7 → 7 8 → 8 9 → 9 10 → A	10	0 —0.009								
		30	→ B									13	0 —0.011								
	13	25	→ A									16	0 —0.013								
		30	→ B									20	0 —0.013								
Tapered type M-SJDF (HPM1) M-SJDD (SKD61)	16	25	→ A									16	→ E	4	→ E					16	0 —0.013
		30	→ B									20	→ J	4.5	→ F					20	0 —0.013
	20	25	→ A									21	→ K	5	→ G						
		30	→ B																		

*1. E dimension is set in accordance with L dimension.

*2. L dimension is restricted by d, V and α . Also, G is restricted by L dimension.

*4. When SR=0, the value is -0.

*3. L dimension limits

α	d	2	2.5	3
1	50	50	85	
2 3 4	85	85	L max	

Working limit → P.386

Straight type $D - E \geq 2$

Tapered type $V - E \geq 2$

When $G \geq 6$, $L - F \geq 3$

When $G < 6$, $L - F \geq \frac{0.15}{\tan G} + 1.5$

Calculation of E

$E = d + 2 \{L + (U) + H - 3\} \tan(\alpha/2)$

U: when additional processing of ZC is specified

Calculation of F $F = \frac{D - V}{2 \tan(G - 0.25)}$

*0.25 is a value that takes G tolerance into account.

How to order

Catalog No.	D	H	L	SR	d	α	N	V	G	Optional processing
M-SJCC	16	A	72.0	A	E	2	N	18.0	- 5	+
M-SJDD	20	B	56.2	A	C	2	N	18.0	- 5	+









Orders are shipped out in 5 business days (excluding the day of order).



Price list

L	Unit price in yen				
	Straight type			Tapered type	
	M-SJCC	M-SJCF	M-SJCD	M-SJDF	M-SJDD
10.0 ~ 20.0	2,630	3,570	3,950	4,140	4,510
20.1 ~ 40.0	2,630	4,700	5,080	5,260	5,640
40.1 ~ 60.0	3,100	6,110	6,490	6,770	7,140
60.1 ~ 80.0	3,670	7,800	8,180	8,460	8,840
80.1 ~ 100.0	5,450	10,150	10,530	10,900	11,280

Optional processing

Specification	Code	Shape	Code	Shape	Code	Shape	Code	Shape	Dimension option	Unit price in yen																
Shape A (trapezoid)  ◆ Working limits for A (T, J, K, E, L, P, U or C) W: (E-0.4) ≥ W Combination with ZC is not available	AIW		AHW		AXW		 Whirl-stop pin hole position  KC position		W dimension option <table><tr><th>W</th><th>t</th></tr><tr><td>3</td><td>2.5</td></tr><tr><td>4</td><td>3</td></tr><tr><td>5</td><td>3.5</td></tr><tr><td>6</td><td>4</td></tr><tr><td>8</td><td>5.5</td></tr><tr><td>10</td><td>7</td></tr></table> How to specify: AIW5	W	t	3	2.5	4	3	5	3.5	6	4	8	5.5	10	7	AIW	AHW	1,000
W	t																									
3	2.5																									
4	3																									
5	3.5																									
6	4																									
8	5.5																									
10	7																									
	ATW		AJW		AKW		AEW			AXW	1,800															
	ALW		APW		AUW		ACW			ATW	AJW	2,000														
										AKW	AEW															
										ALW	APW	1,500														
										AUW	ACW															
Shape B (semicircle)  ◆ Working limits for B (T, J, K, E, L, P, U or C) R: (E-0.4) ≥ 2 × R Combination with ZC is not available	BIR		BHR		BXR		 Whirl-stop pin hole position  KC position		R dimension option <table><tr><td>1</td></tr><tr><td>1.25</td></tr><tr><td>1.5</td></tr><tr><td>1.75</td></tr><tr><td>2</td></tr><tr><td>2.5</td></tr><tr><td>3</td></tr><tr><td>4</td></tr></table> How to specify: BXR3	1	1.25	1.5	1.75	2	2.5	3	4	BIR	BHR	1,000						
1																										
1.25																										
1.5																										
1.75																										
2																										
2.5																										
3																										
4																										
	BTR		BJR		BKR		BER			BXR	1,800															
	BLR		BPR		BUR		BCR			BTR	BJR	2,000														
										BKR	BER															
										BLR	BPR	1,500														
										BUR	BCR															
Shape C (Arc+Tangent)  ◆ Working limits for C (T, J, K, E, L, P, U or C) Q: (E-0.4) ≥ Q × 1.09 Combination with ZC is not available	CIQ		CHQ		CXQ		 Whirl-stop pin hole position  KC position		Q dimension option <table><tr><td>2</td></tr><tr><td>2.5</td></tr><tr><td>3</td></tr><tr><td>3.5</td></tr><tr><td>4</td></tr><tr><td>5</td></tr><tr><td>6</td></tr><tr><td>8</td></tr></table> How to specify: CTQ4	2	2.5	3	3.5	4	5	6	8	CIQ	CHQ	1,000						
2																										
2.5																										
3																										
3.5																										
4																										
5																										
6																										
8																										
	CTQ		CJQ		CKQ		CEQ			CXQ	1,800															
										CTQ	CJQ	2,000														
		CLQ		CPQ		CUQ		CCQ			CKQ	CEQ														
										CLQ	CPQ	1,500														
										CUQ	CCQ															





Code	Specification	U/price (yen)
KC	 Single head cutting	200
WKC	 Two head cutting	400
LKC	 L dimension can be specified directly in 0.01 mm steps. $L + 0.1 \rightarrow L - 0.02$ ※ Combination with ZC is not available.	600

Code	Specification	U/price (yen)
GKC	 Changes G tolerance. $G^{\circ} - 30^{\circ} \rightarrow G^{\circ} - 15^{\circ}$ Available for taper type when $F \leq 15$ and $(L-F) \geq 10$ ※ Combination with ZC is not available.	1,800
ZC	 S, T and U can be specified in 0.1 mm steps. ◆ Working limits → P.386 $S \geq E + 2$ Straight type $E + 2 \leq T \leq D$ Tapered type $E + 2 \leq T \leq V - 2U \tan G$ $2 \leq U \leq 5$ Specification $L_{max} \geq L + U$ How to specify: ZC-S3.5-T4.0-U2.0	1,000

Price list

L	Catalog No.	Unit price in yen		
		M-SAGF	M-SAGD	M-SAGS
40		4,500	5,000	6,500
60		5,900	6,200	8,200
80		7,700	7,900	10,400

Optional processing


	Specification	Code	Shape	Code	Shape	Code	Shape	Dimension option	Unit price in yen																
Runner groove machining	Shape A (trapezoid)  Only available when LC or LKC is specified ◆ Working limits for A (T, J, L or P) W: (E-0.4) ≥ W	AIW		AHW		AXW		W dimension option <table><tr><th>W</th><th>t</th></tr><tr><td>3</td><td>2.5</td></tr><tr><td>4</td><td>3</td></tr><tr><td>5</td><td>3.5</td></tr><tr><td>6</td><td>4</td></tr><tr><td>8</td><td>5.5</td></tr><tr><td>10</td><td>7</td></tr></table> How to specify: AIW5	W	t	3	2.5	4	3	5	3.5	6	4	8	5.5	10	7	AIW	AHW	1,000
	W	t																							
	3	2.5																							
	4	3																							
	5	3.5																							
	6	4																							
	8	5.5																							
	10	7																							
	ATW		AJW		+ Bolt hole position		AXW		1,800																
	ALW		APW				ATW	AJW	2,000																
				ALW			APW	1,500																	
	Shape B (semicircle)  Only available when LC or LKC is specified ◆ Working limits for B (T, J, L or P) R: (E-0.4) ≥ 2 × R	BIR		BHR		BXR		R dimension option <table><tr><td>1</td></tr><tr><td>1.25</td></tr><tr><td>1.5</td></tr><tr><td>1.75</td></tr><tr><td>2</td></tr><tr><td>2.5</td></tr><tr><td>3</td></tr><tr><td>4</td></tr></table> How to specify: BXR3	1	1.25	1.5	1.75	2	2.5	3	4	BIR	BHR	1,000						
1																									
1.25																									
1.5																									
1.75																									
2																									
2.5																									
3																									
4																									
BTR		BJR		+ Bolt hole position		BXR		1,800																	
BLR		BPR				BTR	BJR	2,000																	
			BLR			BPR	1,500																		
Shape C (Arc+Tangent)  Only available when LC or LKC is specified ◆ Working limits for C (T, J, L or P) Q: (E-0.4) ≥ Q × 1.09	CIQ		CHQ		CXQ		Q dimension option <table><tr><td>2</td></tr><tr><td>2.5</td></tr><tr><td>3</td></tr><tr><td>3.5</td></tr><tr><td>4</td></tr><tr><td>5</td></tr><tr><td>6</td></tr><tr><td>8</td></tr></table> How to specify: CTQ4	2	2.5	3	3.5	4	5	6	8	CIQ	CHQ	1,000							
2																									
2.5																									
3																									
3.5																									
4																									
5																									
6																									
8																									
CTQ		CJQ		+ Bolt hole position		CXQ		1,800																	
CLQ		CPQ				CTQ	CJQ	2,000																	
			CLQ			CPQ	1,500																		
Length change		LC	Specify L dimension directly in 0.1 mm steps. When combined with LKC, specify it in 0.01 mm steps. 40 ≤ LC ≤ 80 When LC is used, $L \begin{smallmatrix} +5 \\ -0.1 \end{smallmatrix} \rightarrow L \begin{smallmatrix} +0.1 \\ -0 \end{smallmatrix}$					200																	
Length tolerance change		LKC	$L \begin{smallmatrix} +5 \\ -0.1 \end{smallmatrix} \rightarrow L \begin{smallmatrix} -0 \\ -0.02 \end{smallmatrix}$ When L40, L60 or L80 is selected, no need to specify LC.					600																	

Sprue Bushings Bolt Hole, Head Thick 10 mm Type

SPRUE BUSHINGS


Additional processing to mold bases → P.92

Catalog No.	Material	Hardness after heat treatment
M-SBGF	HPM1	37 to 41 HRC
M-SBGD	SKD61	48 HRC or more
M-SBGS	SKD11 (improved steel)	58 HRC or more





Supplied with hexagon socket head cap screw M5 × 12 (2 pcs.)

Catalog No.	Material	Hardness after heat treatment
M-SBHF	HPM1	37 to 41 HRC
M-SBHD	SKD61	48 HRC or more
M-SBHS	SKD11 (improved steel)	58 HRC or more



Supplied with hexagon socket head cap screw M5 × 12 (2 pcs.)



Catalog No.	D	L ^{*2}	SR		d		α	V	G		D	
			In 0.1 mm steps	DIMM	Code	DIMM			Code	In 1° steps		DIMM
Straight type	10	10.0 ~ 100.0	0 → Z 11 → A 12 → B 13 → C 16 → F 20 → J	2 ^{*3} → A 2.5 ^{*3} → B 3 ^{*3} → C 3.5 → D 4 → E 4.5 → F 5 → G 5.5 → H 6 → I 6.5 → J 7 → K 8 → M	1 ^{*3} 2 3 4	Specify only for tapered type	Specify only for tapered type	1 → 1 2 → 2 3 → 3 4 → 4 5 → 5 6 → 6 7 → 7 8 → 8 9 → 9 10 → A	10	0 —0.009		
M-SBGF (HPM1)												
M-SBGD (SKD61)												
M-SBGS (SKD11 improved steel)												
Tapered type	13										10.0 ~ 150.0	10 → A 11 → B 12 → C 13 → D 16 → F 20 → J
M-SBHF (HPM1)												
M-SBHD (SKD61)												
M-SBHS (SKD11 improved steel)												
	16	10.0 ~ 150.0	10 → A 11 → B 12 → C 13 → D 16 → F 20 → J	2 ^{*3} → A 2.5 ^{*3} → B 3 ^{*3} → C 3.5 → D 4 → E 4.5 → F 5 → G 5.5 → H 6 → I 6.5 → J 7 → K 8 → M	1 ^{*3} 2 3 4	Specify only for tapered type	Specify only for tapered type	1 → 1 2 → 2 3 → 3 4 → 4 5 → 5 6 → 6 7 → 7 8 → 8 9 → 9 10 → A	16	0 —0.013		
M-SBHF (HPM1)												
M-SBHD (SKD61)												
M-SBHS (SKD11 improved steel)												
	20 ^{*4}										10.0 ~ 150.0	10 → A 11 → B 12 → C 13 → D 16 → F 20 → J
M-SBHF (HPM1)												
M-SBHD (SKD61)												
M-SBHS (SKD11 improved steel)												

*1. E dimension is set in accordance with L dimension.

*2. L dimension is restricted by d, V and α. Also, G is restricted by L dimension.

*4. D 20 for MBGS and M-SBHS is not available.

*5. When SR=0, the value is +10.

*3. L dimension limits

α	d	2	2.5	3
1	50	50	85	
2 3 4	85	85	L max	

Working limit → P.386

Straight type D - E ≥ 2

Tapered type V - E ≥ 2

When G ≥ 6, L - F ≥ 3

When G < 6, L - F ≥ $\frac{0.15}{\tan G} + 1.5$ Calculation of E^{*5}

E = d + 2(L + (U) + 7) tan(α/2)

U: when additional processing of ZC is specified

Calculation of F $F = \frac{D-V}{2 \tan(G-0.25)}$

*0.25 is a value that takes G tolerance into account.

How to order

Catalog No.	D	×	L	SR	d	α	N	V	-	G	+	Optional processing
M-SBGF	16	×	60.1	A	D	2						
M-SBHF	20	×	58.0	A	C	3	N	14.0	-	5	+	AIW5








Orders are shipped out in 5 business days (excluding the day of order).



Price list

L	Unit price in yen			
	Straight type		Tapered type	
	M-SBIF	M-SBID	M-SBJF	M-SBJD
30.0 ~ 60.0	9,700	10,700	10,900	12,000
60.1 ~ 80.0	11,000	12,100	12,200	13,400
80.1 ~ 100.0	14,200	15,600	15,300	16,800
100.1 ~ 120.0	16,200	17,800	17,400	19,100
120.1 ~ 140.0	19,300	21,200	20,500	22,600
140.1 ~ 150.0	24,200	26,600	25,500	28,100

Optional processing

Specification	Code	Shape	Code	Shape	Code	Shape	Dimension option	Unit price in yen																
Shape A (trapezoid)  ◆ Working limits for A (T, J, L or P) W: (E-0.4) ≥ W Combination with ZC is not available	AIW		AHW		AXW		W dimension option <table><tr><th>W</th><th>t</th></tr><tr><td>3</td><td>2.5</td></tr><tr><td>4</td><td>3</td></tr><tr><td>5</td><td>3.5</td></tr><tr><td>6</td><td>4</td></tr><tr><td>8</td><td>5.5</td></tr><tr><td>10</td><td>7</td></tr></table> How to specify: AIW5	W	t	3	2.5	4	3	5	3.5	6	4	8	5.5	10	7	AIW	AHW	1,000
	W	t																						
	3	2.5																						
	4	3																						
5	3.5																							
6	4																							
8	5.5																							
10	7																							
ATW		AJW				AXW		1,800																
ALW		APW				ATW	AJW	2,000																
							ALW	APW	1,500															
Shape B (semicircle)  ◆ Working limits for B (T, J, L or P) R: (E-0.4) ≥ 2 × R Combination with ZC is not available	BIR		BHR		BXR		R dimension option <table><tr><td>1</td></tr><tr><td>1.25</td></tr><tr><td>1.5</td></tr><tr><td>1.75</td></tr><tr><td>2</td></tr><tr><td>2.5</td></tr><tr><td>3</td></tr><tr><td>4</td></tr></table> How to specify: BXR3	1	1.25	1.5	1.75	2	2.5	3	4	BIR	BHR	1,000						
	1																							
	1.25																							
	1.5																							
1.75																								
2																								
2.5																								
3																								
4																								
BTR		BJR				BXR		1,800																
BLR		BPR				BTR	BJR	2,000																
						BLR	BPR	1,500																
Shape C (Arc+Tangent)  ◆ Working limits for C (T, J, L or P) Q: (E-0.4) ≥ Q × 1.09 Combination with ZC is not available	CIQ		CHQ		CXQ		Q dimension option <table><tr><td>2</td></tr><tr><td>2.5</td></tr><tr><td>3</td></tr><tr><td>3.5</td></tr><tr><td>4</td></tr><tr><td>5</td></tr><tr><td>6</td></tr><tr><td>8</td></tr></table> How to specify: CTQ4	2	2.5	3	3.5	4	5	6	8	CIQ	CHQ	1,000						
	2																							
	2.5																							
	3																							
3.5																								
4																								
5																								
6																								
8																								
CTQ		CJQ				CXQ		1,800																
CLQ		CPQ				CTQ	CJQ	2,000																
						CLQ	CPQ	1,500																

Code	Specification	U/price (yen)
BC	 Increases the number of bolt holes # of bolts holes 2 → 4 (Supplied bolts: 4) ※ Combination with NC is not available.	500
BN	 Decreases the number of bolt holes # of bolts holes 2 → 0 (Supplied bolts: 0) Available for material HPM1.	—500
NC	 Creates a whirl-stop pin hole on the head.	200
LKC	 L dimension can be directly specified in 0.01 mm steps. $L + \frac{+0.1}{0} \rightarrow L - \frac{0}{-0.02}$ ※ Combination with ZC is not available.	600



Code	Specification	U/price (yen)
GKC	 Changes G tolerance. $G^{\circ} -\frac{0}{30'} \rightarrow G^{\circ} -\frac{0}{15'}$ Available for taper type when $F \leq 15$ and $(L-F) \geq 10$ ※ Combination with ZC is not available.	1,800
ZC	 S, T and U can be specified in 0.1 mm steps. ◆ Working limits → P.386 $S \geq E + 2$ Straight type $E + 2 \leq T \leq D$ Tapered type $E + 2 \leq T \leq V - 2U \tan G$ $2 \leq U \leq 5$ Specification $L_{max} \geq L + U$ How to specify: ZC-S3.5-T4.0-U2.0	1,000

Sprue Bushings Shoulder Type



SPRUE BUSHINGS

Additional processing to mold bases → P.92

Catalog No.	Material	Hardness after heat treatment
M-SBEF	HPM1	37 to 41 HRC
M-SBED	SKD61	48 HRC or more
M-SBES	SKD11 (Improved steel)	58 HRC or more



Catalog No.	Material	Hardness after heat treatment
M-SBFF	HPM1	37 to 41 HRC
M-SBFD	SKD61	48 HRC or more
M-SBFS	SKD11 (Improved steel)	58 HRC or more



Catalog No.	D	L *2 In 0.1 mm steps	SR		d		α	V In 0.1 mm steps	G In 1° steps		D	
			DIMM	Code	DIMM	Code			DIMM	Code	DIMM	Limit deviations
Straight type M-SBEF (HPM1) M-SBED (SKD61) M-SBES (SKD11 improved steel)	10	10.0 ~ 100.0	0 → Z		2 *3 → A		1 *3 2 3 4	Specify only for tapered type $D > V \geq E + 2$	Specify only for tapered type 1 → 1 2 → 2 3 → 3 4 → 4 5 → 5 6 → 6 7 → 7 8 → 8 9 → 9 10 → A		10	0 -0.009
	13		11 → A		2.5 *3 → B						13	0 -0.011
	16		12 → B		3 → C						16	
	20 *4		13 → C		4 → D						20	0 -0.013
Tapered type M-SBFF (HPM1) M-SBFD (SKD61) M-SBFS (SKD11 improved steel)	20 *4	10.0 ~ 150.0	16 → F		4.5 → E						25	
	25 *4		20 → J		5 → G						25	
			21 → K		5.5 → H							
			23 → M		6 → I							

*1. E dimension is set in accordance with L dimension.

*2. L dimension is restricted by d, V and α . Also, G is restricted by L dimension.

*4. D 20 and 25 for M-SBES and M-SBFS is not available.

*5. When SR=0, the value is +15.

*3. L dimension limits

α	d	2	2.5	3
1	50	50	85	
2 3 4	85	85	L max	

Working limits → P.386

Straight type $D - E \geq 2$

Tapered type $V - E \geq 2$

When $G \geq 6$, $L - F \geq 3$

When $G < 6$, $L - F \geq \frac{0.15}{\tan G} + 1.5$

Calculation of E *5

$E = d + 2 \{L + (U + 12) \tan(\alpha/2)\}$

U: when additional processing of ZC is specified

Calculation of F $F = \frac{D - V}{2 \tan(G - 0.25)}$

*0.25 is a value that takes G tolerance into account.

How to order

Catalog No.	D	L	SR	d	α	N	V	G	Optional processing
M-SBED	16	72.2	A	C	3				
M-SBFF	20	58.5	A	D	2	N	18.0	5	AIW6






Orders are shipped out in 5 business days (excluding the day of order).

Price list

L	Unit price in yen					
	Straight type			Tapered type		
	M-SBEF	M-SBED	M-SBES	M-SBFF	M-SBFD	M-SBFS
10.0 ~ 20.0	3,700	4,200	5,000	4,300	4,800	5,800
20.1 ~ 40.0	4,900	5,400	6,500	5,500	6,000	7,200
40.1 ~ 60.0	6,400	6,900	8,300	7,100	7,600	9,100
60.1 ~ 80.0	8,200	8,700	10,400	8,900	9,400	11,300
80.1 ~ 100.0	9,180	11,200	13,400	9,860	12,000	14,400
100.1 ~ 120.0	10,710	13,200		11,560	14,200	
120.1 ~ 140.0	13,430	16,500		14,450	17,700	
140.1 ~ 150.0	15,470	19,100		16,660	20,000	

Optional processing

Specification	Code	Shape	Code	Shape	Code	Shape	Code	Shape	Dimension option	Unit price in yen																
Shape A (trapezoid)  ◆ Working limits for A (T, J, K, E, L, P, U or C) W: (E-0.4) ≥ W Combination with ZC is not available	AIW		AHW		AXW				W dimension option <table><tr><th>W</th><th>t</th></tr><tr><td>3</td><td>2.5</td></tr><tr><td>4</td><td>3</td></tr><tr><td>5</td><td>3.5</td></tr><tr><td>6</td><td>4</td></tr><tr><td>8</td><td>5.5</td></tr><tr><td>10</td><td>7</td></tr></table> How to specify: AIW5	W	t	3	2.5	4	3	5	3.5	6	4	8	5.5	10	7	AIW	AHW	1,000
	W	t																								
	3	2.5																								
	4	3																								
5	3.5																									
6	4																									
8	5.5																									
10	7																									
ATW		AJW		AKW		AEW		AXW		1,800																
ALW		APW		AUW		ACW		ATW	AJW	2,000																
								AKW	AEW																	
Shape B (semicircle)  ◆ Working limits for B (T, J, K, E, L, P, U or C) R: (E-0.4) ≥ 2 × R Combination with ZC is not available	BIR		BHR		BXR				R dimension option <table><tr><th>R</th></tr><tr><td>1</td></tr><tr><td>1.25</td></tr><tr><td>1.5</td></tr><tr><td>1.75</td></tr><tr><td>2</td></tr><tr><td>2.5</td></tr><tr><td>3</td></tr><tr><td>4</td></tr></table> How to specify: BXR3	R	1	1.25	1.5	1.75	2	2.5	3	4	BIR	BHR	1,000					
	R																									
	1																									
	1.25																									
1.5																										
1.75																										
2																										
2.5																										
3																										
4																										
BTR		BJR		BKR		BER		BXR		1,800																
BLR		BPR		BUR		BCR		BTR	BJR	2,000																
								BKR	BER																	
Shape C (Arc+Tangent)  ◆ Working limits for C (T, J, K, E, L, P, U or C) Q: (E-0.4) ≥ Q × 1.09 Combination with ZC is not available	CIQ		CHQ		CXQ				Q dimension option <table><tr><th>Q</th></tr><tr><td>2</td></tr><tr><td>2.5</td></tr><tr><td>3</td></tr><tr><td>3.5</td></tr><tr><td>4</td></tr><tr><td>5</td></tr><tr><td>6</td></tr><tr><td>8</td></tr></table> How to specify: CTQ4	Q	2	2.5	3	3.5	4	5	6	8	CIQ	CHQ	1,000					
	Q																									
	2																									
	2.5																									
3																										
3.5																										
4																										
5																										
6																										
8																										
CTQ		CJQ		CKQ		CEQ		CXQ		1,800																
CLQ		CPQ		CUQ		CCQ		CTQ	CJQ	2,000																
								CKQ	CEQ																	









Code	Specification	U/price (yen)
KC	 Single head cutting	200
WKC	 Two head cutting	400
LKC	 L dimension can be specified directly in 0.01 mm steps. $L + 0.1 \rightarrow L - 0.02$ ※ Combination with ZC is not available.	600

Code	Specification	U/price (yen)
GKC	 Changes G tolerance. $G^{\circ} 0' -30' \rightarrow G^{\circ} 0' -15'$ Available for taper type when $F \leq 15$ and $(L-F) \geq 10$ ※ Combination with ZC is not available.	1,800
ZC	 S, T and U can be specified in 0.1 mm steps. ◆ Working limits → P.386 $S \geq E + 2$ Straight type $E + 2 \leq T \leq D$ Tapered type $E + 2 \leq T \leq V - 2U \tan G$ $2 \leq U \leq 5$ Specification $L_{max} \geq L + U$ How to instruct: ZC-S3.5-T4.0-U2.0	1,000

Working Limits for Sprue Bushings

SPRUE BUSHINGS


The sprue bushings shown in pages 374 to 377 and pages 380 to 385 are produced on the following conditions.
Each dimension differs depending on the type of sprue bushing. For details, refer to respective pages.

Bolt hole type	Shoulder type	Working limits
		Working limits $D - E \geq 2$ Calculation of E: $E = d + 2 \{L + H - Z\} \tan(\alpha/2)$
		Working limits $S \geq E + 2$ $E + 2 \leq T \leq D$ Calculation of E : $E = d + 2 \{L + U + H - Z\} \tan(\alpha/2)$
		Working limits $V - E \geq 2$ When $G \geq 6$, $L - F \geq 3$ When $G < 6$, $L - F \geq \frac{0.15}{\tan G} + 1.5$ Calculation of E $E = d + 2 \{L + H - Z\} \tan(\alpha/2)$ Calculation of F $F = \frac{D - V}{2 \tan(G - 0.25)}$ ※ 0.25 is a value that takes G tolerance into account.
		Working limits $S \geq E + 2$ $E + 2 \leq T \leq V - 2U \tan G$ When $G \geq 6$, $L - F \geq 3$ When $G < 6$, $L - F \geq \frac{0.15}{\tan G} + 1.5$ Calculation of E $E = d + 2 \{L + U + H - Z\} \tan(\alpha/2)$ Calculation of F $F = \frac{D - V}{2 \tan(G - 0.25)}$ ※ 0.25 is a value that takes G tolerance into account.

Runner Lock Pins

PULLER PINS

Catalog No.	Material	Hardness after heat treatment
M-RLA	SKS3	58 to 62 HRC



Catalog No.	d	Unit price in yen										d		D	H	d1	d2	h
		L																
		24	29	30	35	40	45	50	60	70	80	DIMM	Limit deviations					
M-RLA	4	590	600		610	620	630	640	650			4	−0.010 −0.022	6	4	2.8	2.3	2.5
	5			690	700	710	720	730	740	750		5		7		3.3	2.8	3
	6					720		740	760	780	800	6		8		3.8	3.0	
	8							750	770	790	810	8	−0.013 −0.028	10	8	4.8	4.0	4
	10								850	870	890	10		13		6.0	4.8	5

How to order


Catalog No. ×
M-RLA 5 × 30

Shipping In-stock item

Pin-Point Gate Bushings


SPRUE BUSHINGS

Catalog No.	Material	Hardness after heat treatment
M-PGBA	SKH51	59 to 61 HRC




Enlarged view of the tip

*1. This bushing has a flat area of 0 to 0.1 on the tip (P dimension).




Eccentricity between D and P is 0.05 or less.
Eccentricity between D and V is 0.05 or less.

Catalog No.	Material	Hardness after heat treatment
M-PGBB	SKH51	59 to 61 HRC



Enlarged view of the tip

*2. This bushing has a flat area of 0 to 0.1 on the tip (P dimension).



Eccentricity between D and P is 0.05 or less.

Catalog No.	D	L	P	A	K	C (M-PGBA only)	H	G	V	B	SR
		In 0.01 mm steps				In 0.1 mm steps					
M-PGBA	2	6.00 ~ 20.00	0.3 0.4	1	20	0.2 ~ 0.4	3	0.7	1.3	3	0.60
	2.5	8.00 ~ 25.00	0.3 0.4 0.5			0.2 ~ 0.5	4	1.0	1.5	4	0.75
	3	10.00 ~ 40.00	0.5 0.6 0.8			0.3 ~ 0.8	5	1.2	2.0	6	1.00
	4		0.6				6		1.00		
M-PGBB	5	15.00 ~ 60.00	0.8 1.0	2	30	0.5 ~ 1.5	8	1.5	3.5	10	1.25
			1.2								1.50
	6		1.0	3			9		4.0		1.25
			1.2 1.4								1.50
	8		1.2 1.4	11			4.5		1.50		
			1.6						2.00		

How to order

Catalog No.	D	L	P	N	A	K	C
M-PGBA	4	24.10	0.8	N	2	20	0.5
M-PGBB	5	38.20	1.0	N	1	20	



Orders are shipped out in 8 business days (excluding the day of order).


Price list

Catalog No.	D	L	Unit price in yen
M-PGBA	2	6.00 ~ 20.00	18,520
	2.5	8.00 ~ 25.00	18,520
	3	10.00 ~ 25.00	12,970
		25.01 ~ 40.00	13,910
	4	10.00 ~ 25.00	13,250
		25.01 ~ 40.00	14,010
	5	15.00 ~ 25.00	12,690
		25.01 ~ 40.00	13,250
		40.01 ~ 60.00	14,010
	6	15.00 ~ 25.00	12,690
		25.01 ~ 40.00	13,250
		40.01 ~ 60.00	14,010
	8	15.00 ~ 25.00	12,880
		25.01 ~ 40.00	13,540
		40.01 ~ 60.00	14,380


Catalog No.	D	L	Unit price in yen
M-PGBB	2	6.00 ~ 20.00	17,110
	2.5	8.00 ~ 25.00	17,110
	3	10.00 ~ 25.00	11,560
		25.01 ~ 40.00	12,500
	4	10.00 ~ 25.00	11,840
		25.01 ~ 40.00	12,600
	5	15.00 ~ 25.00	11,280
		25.01 ~ 40.00	11,840
		40.01 ~ 60.00	12,600
	6	15.00 ~ 25.00	11,280
		25.01 ~ 40.00	11,840
		40.01 ~ 60.00	12,600
	8	15.00 ~ 25.00	11,470
		25.01 ~ 40.00	12,130
		40.01 ~ 60.00	12,970

Calculation of the inlet diameter E $E = 2SR + 2(L - G - SR) \tan \frac{A^\circ}{2}$


M-PGBA



M-PGBB



Example of use




Screws, Coil Springs and Other Parts

Screws, Coil Springs and Other Parts Overview.....		392
Base Spacers		
	M-BSA.....	394
Eye Bolts		
	M-IBM.....	395
Coil Springs		
High Deflection FSB Type	M-FSB.....	396
High Deflection TY Type	M-TY.....	398
High Deflection TR Type	M-TR	400
Strong Coil Spring TF Type	P-TF	402

Screws, Coil Springs and Other Parts Overview

Base spacers

Additional processing to MDC



Catalog No.	M-BSA
Material	S45C
Shipping	In-stock item
Page	P.394

Eye bolts



Additional processing to MDC



Catalog No.	M-IBM
Material	SS400
Shipping	In-stock item
Page	P.395

Coil springs

Additional processing to MDC



Catalog No.	M-FSB	M-TY	M-TR	P-TF
Shipping	In-stock item	3 days		
Page	P.396	P.398	P.400	P.402

Pin dia.	Catalog No.		Catalog No.		Catalog No.		Load N {kgf}				Load N {kgf}				Load N {kgf}			
	M-FSB		M-TY M-TR		P-TF		L × 40%				L × 45%				L × 50%			
	D	d	D	d	D	d	M-FSB	M-TY	M-TR	P-TF	M-FSB	M-TY	M-TR	P-TF	M-FSB	M-TY	M-TR	P-TF
8	—	—	14.5	9	18	9	—	147.1 {15.0}	88.3 {9.0}	206 {21.0}	—	166.7 {17.0}	98.1 {10.0}	226 {23.0}	—	186.3 {19.0}	107.9 {11.0}	255 {26.0}
10	17.5	10.5	17	11	20	11	216 {22}	215.7 {22.0}	147.1 {15.0}	255 {26.0}	235 {24}	245.2 {25.0}	166.7 {17.0}	284 {29.0}	265 {27}	274.6 {28.0}	186.3 {19.0}	314 {32.0}
					22	11				314 {32.0}				353 {36.0}				392 {40.0}
12	21.5	13.2	21	13	25	13.5	255 {26}	284.4 {29.0}	166.7 {17.0}	392 {40.0}	284 {29}	313.8 {32.0}	186.3 {19.0}	441 {45.0}	314 {32}	353.0 {36.0}	205.9 {21.0}	490 {50.0}
					27	13.5				471 {48.0}				530 {54.0}				588 {60.0}
15	26.5	15.5	26	16.5	30	16	451 {46}	411.9 {42.0}	323.6 {33.0}	569 {58.0}	500 {51}	470.7 {48.0}	362.8 {37.0}	637 {65.0}	559 {57}	519.8 {53.0}	402.1 {41.0}	706 {72.0}
20	32.5	20.5	32	21	40	22	628 {64}	559.0 {57.0}	402.1 {41.0}	1,000 {102.0}	706 {72}	627.6 {64.0}	451.1 {46.0}	1,128 {115.0}	785 {80}	696.3 {71.0}	500.1 {51.0}	1,255 {128.0}
25	39.5	25.5	39	26	50	27.5	981 {100}	725.7 {74.0}	431.5 {44.0}	1,569 {160.0}	1,108 {113}	823.8 {84.0}	490.3 {50.0}	1,765 {180.0}	1,226 {125}	912.0 {93.0}	539.4 {55.0}	1,961 {200.0}
30	45.5	30.5	46	32	60	33	1,295 {132}	970.9 {99.0}	490.3 {50.0}	2,260 {230.5}	1,461 {149}	1,098 {112.0}	549.2 {56.0}	2,540 {259.0}	1,618 {165}	1,216 {124.0}	608.0 {62.0}	2,820 {287.6}
	M-FSB → P.396		M-TY → P.398 M-TR → P.400		P-TF → P.402													

※ Pin diameter represents the diameter of return pin used.

※ For details, see the respective pages of the springs.

Additional processing to MDC denotes the parts that support additional processing to mold bases.
Shipping times are shown in business days (excluding the day of order).

Precautions for use of coil springs

Load

◆ About spring constant:

Spring constant is a rough guide used to calculate the load required to cause a specific amount of deflection.

◆ About load:

The actual load may be lower than the value calculated using the spring constant at the beginning of deflection and may become higher as the deflection approaches the maximum deflection (maximum allowable deflection). Thus, the actual load may deviate from the range specified with limit deviation tolerance.

Condition of use

◆ Surface flaws

Any flaw on the surface of a coil spring will lead to early breakage. If any flaw is caused by dropping, etc. it is recommended to replace the spring.

◆ Operating environment

Do not use springs in a corrosive environment. If rust started, replace the spring with a new one as it will cause early breakage. Even if rust-proof cutting oil is applied on coil springs, rust may start over a long period of time.

◆ Operating temperature

Item name	Operating temperature
M-FSB	130°C or less
M-TY	−30°C to 150°C
M-TR	−30°C to 150°C
P-TF	−30°C to 150°C

◆ Setting condition (initial load)

When setting a coil spring, it is recommended to apply an initial load (set up an initial deflection). Otherwise, the spring receives an impact force or uneven load that will cause early breakage.

◆ Keep mounting and loading faces parallel (see Figure 1)

Coil spring should be mounted properly with the mounting face and the loading face parallel to each other throughout the entire stroke of the spring. If loaded in a tilted state, the spring receives uneven load that will damage it.

◆ Use of multiple springs (see Figure 2)

Use of multiple springs on the same plane. In this case, it is essential to use same type of coil springs. If use of multiple types or a large number of coil springs is inevitable, be sure to consider the overall load balance and allowable deflection amount of respective springs.

◆ Prohibition of use of coil springs in series (see Figure 3)

Do not use coil springs in series vertically as it causes a damage to the springs.

◆ Prohibition of coaxial use of two coil springs (see Figure 4)

Do not use two coil springs coaxially by putting a spring in a larger diameter spring. Doing so may result in the coils of one spring being sandwiched between the coils of the other spring, when they contact, resulting in a damage of the springs.

◆ Avoid entrapment of debris foreign matter

Foreign matter caught between the coils may cause uneven loading and impact loading, eventually causing it to break. Be careful not to allow foreign matter to clog the coils.

◆ Allowable deflection

Please select coil springs so as not to use them in excess of the allowable deflection.

◆ Solid height (solid length)

This is the height when a coil spring is compressed until the coils come in contact with each other. The use of coil springs by compressing them until the coils are in close contact with each other is not allowed.

◆ Friction of load-applying portions on coil springs

The coil springs are made of hard steel. Because of the characteristics of steel, the load-applying portions of the coil spring may be cut due to the friction. If it is not allowed for your application, please take appropriate protection or reinforcement measure.

◆ Buckling

When compressed, coil springs may be deformed (buckling or lateral deflection) so as to jump out of place from its intended position, which is dangerous. Also, the deformation of springs may cause it to come in contact with surrounding devices. It is necessary to take a workaround measure such as putting a pin through the spring, etc.

Measured point

◆ About outside diameter & inside diameter of coil springs

Outside and inside diameters are dimensions of the first to second turns of the coils.

Handling

◆ Application

The coil springs are designed for compression and cannot be used for other applications, such as torsion or tension. Improper use of the coil springs will cause breakage, settling or deformation. Using the springs for other purposes such as a hammer or weight may lead to an unexpected accident. poses such as a hammer or weight may lead to an unexpected accident.

◆ Periodical inspection and storage

Replace the coil springs as necessary. Coil springs settle as the frequency of use increases. Avoid leaving the coil springs in locations where they may be exposed to high temperature and humidity and store them in a safe location.

◆ Disposal

As the coil springs are made of low-alloy steel, they can be disposed as regular metal waste.

Keep top and bottom faces parallel and apply load perpendicularly




Figure 1

Keep top and bottom faces parallel and apply load perpendicularly





Figure 2



Do not stack spring vertically.

Figure 3



Do not set the springs as shown as coils of one spring may be sandwiched between the coils of the other spring.



Figure 4

Base Spacers®

BASE SPACER

Additional processing to mold bases → P.188

Catalog No.	Material
M-BSA	S45C (body)



Supplied with hexagon socket head cap screw

Catalog No.	D	Unit price in yen	d	D1	H	L	Supplied screw
M-BSA	19	340	7	11	9	9	M6 × 50
	24	430	9	14	12	12	M8 × 50
	29	550	11	17	15	15	M10 × 50
	34	690	13	19	18	18	M12 × 50

How to order

Catalog No.

D

M-BSA


24



Shipping

In-stock item

Example of use



Please use the base spacers as the legs of molds when they are mounted on the floor or for the purpose of protection of devices.



Base spacer is a registered trade mark of Futaba Corporation.

Eye Bolts With Liability Insurance

EYE BOLTS

Additional processing to mold bases → P.231

Catalog No.	Material
M-IBM	SS400



When using a pair of eye bolts for lifting, mount them in alignment as shown.

Catalog No.	M	¥ U/price	M	Pitch	a	b	C	D	H	L1	e	g	R	da	A Type		B Type	
															kN/1P	{kgf/1P}	kN/2P	{kgf/2P}
M-IBM	8	85	M8	P1.25	32.6	20	6.3	16	33.3	15	3	6	1	9.2	0.785	{80}	0.785	{80}
	10	90	M10	P1.5	41	25	8	20	41.5	18	4	7.7	1.2	11.2	1.47	{150}	1.47	{150}
	12	100	M12	P1.75	50	30	10	25	51	22	5	9.4	1.4	14.2	2.16	{220}	2.16	{220}
	16	145	M16	P2.0	60	35	12.5	30	60	27	5	13	1.6	18.2	4.41	{450}	4.41	{450}
	20	220	M20	P2.5	72	40	16	35	71	30	6	16.4	2	22.4	6.18	{630}	6.18	{630}
	24	440	M24	P3.0	90	50	20	45	90	38	8	19.6	2.5	26.4	9.32	{950}	9.32	{950}
	30	830	M30	P3.5	110	60	25	60	110	45	8	25	3	33.4	14.7	{1,500}	14.7	{1,500}
	36	1,600	M36	P4.0	133	70	31.5	70	131.5	55	10	30.3	3	39.4	22.6	{2,305}	22.6	{2,305}
	42	3,000	M42	P4.5	151	80	35.5	80	150.5	65	12	35.6	3.5	45.6	33.3	{3,396}	33.3	{3,396}
	48	5,300	M48	P5.0	170	90	40	90	170	70	12	41	4	52.6	44.1	{4,497}	44.1	{4,497}
Applied load																		

How to order

Catalog No.

M

M-IBM

16


Shipping

In-stock item

Precaution for use


- (1) Do not use the eye bolt in excess of maximum allowable load value.
Please note that the maximum allowable load values are the same for all the cases of one-piece lifting, two-piece lifting and four-piece lifting regardless of the number of eye bolts used.
- (2) Do not use the eye bolts for horizontal lifting.
- (3) When lifting a load, lift it slowly and avoid sudden movement in up and down or left and right directions.
- (4) When using a pair of eye bolts for lifting, mount them in alignment as shown above.
- (5) When using a pair of eye bolts for lifting, be sure to use one rope and one chain for each eye bolt. Do not lift a load vertically using a single rope for 2 eye bolts. Doing so may cause the slackening of rope or an excessive tightening torque, which is dangerous.
- (6) When any deformation or crack or flaw is caused on the eye bolt, immediately stop using it.

Bad example



Specification of eye bolt holes (mold base machining standard)

M	D1	F	K
M8	11	16	23
M10	13	20	28
M12	16	24	33
M16	20	29	39
M20	24	33	46
M24	28	41	56
M30	35	49	67
M36	41	59	82
M42	47	70	95
M48	54	75	103



How to mount:


Fasten the eye bolt lightly by hand until its seat firmly sits on the plate.

Coil Springs High Deflection FSB Type

SPRINGS

Additional processing to mold bases → P.134

Catalog No.	L		Load	Winding direction	Material	Color
	L ≤ 50	L ≥ 55				
M-FSB	±0.5	±2%	±10%	Right	SWOSC-V	Light green



How to order

Catalog No.

Nominal dimension × L

M-FSB

15

× 70



Shipping

In-stock item

Catalog No.	Nominal dimension	L	U/price in yen	D	d	Solid length (Ref. value) L0	Spring constant N/mm {kgf/mm}	F=L×40%		F=L×45%		F=L×50%	
								F mm	Load N {kgf}	F mm	Load N {kgf}	F mm	Load N {kgf}
M-FSB	10	35	210	17.5	10.5	17.5	15.10 {1.54}	14.0	216 {22}	15.8	235 {24}	17.5	265 {27}
		40	220			20.0	13.24 {1.35}	16.0		18.0		20.0	
		45	230			22.5	11.77 {1.20}	18.0		20.3		22.5	
		50	260			24.5	10.59 {1.08}	20.0		22.5		25.0	
		55	265			26.5	9.61 {0.98}	22.0		24.8		27.5	
		60	270			28.5	8.83 {0.90}	24.0		27.0		30.0	
		65	280			30.0	8.14 {0.83}	26.0		29.3		32.5	
		70	290			32.5	7.55 {0.77}	28.0		31.5		35.0	
		75	295			35.0	7.06 {0.72}	30.0		33.8		37.5	
	80	300	36.5	6.67 {0.68}	32.0	36.0	40.0						
	12	30	260	21.5	13.2	15.0	20.89 {2.13}	12.0	255 {26}	13.5	284 {29}	15.0	314 {32}
		35	270			17.5	17.95 {1.83}	14.0		15.8		17.5	
		40	280			20.0	15.69 {1.60}	16.0		18.0		20.0	
		45	290			22.0	13.93 {1.42}	18.0		20.3		22.5	
		50	300			24.0	12.55 {1.28}	20.0		22.5		25.0	
		55	305			26.0	11.38 {1.16}	22.0		24.8		27.5	
		60	310			28.0	10.49 {1.07}	24.0		27.0		30.0	
		65	315			30.0	9.71 {0.99}	26.0		29.3		32.5	
		70	320			32.0	8.92 {0.91}	28.0		31.5		35.0	
		75	330			34.0	8.34 {0.85}	30.0		33.8		37.5	
		80	340			36.0	7.85 {0.80}	32.0		36.0		40.0	
		85	350			38.5	7.35 {0.75}	34.0		38.3		42.5	
		90	360			41.0	6.96 {0.71}	36.0		40.5		45.0	
		100	370			45.5	6.28 {0.64}	40.0		45.0		50.0	
		110	380			48.0	5.69 {0.58}	44.0		49.5		55.0	
Standard operation frequency (reference value)								500,000 times or more					


※ When installing a coil spring, apply an initial load.

※ Load calculation method: load (N) = Spring constant (N/mm) × Deflection (mm)
kgf=N×0.101972

Catalog No.	Nominal dimension	L	U/price (in yen)	D	d	Solid length (ref. value) L0	Spring constant N/mm {kgf/mm}		F=L×40%		F=L×45%		F=L×50%			
									F mm	Load N {kgf}	F mm	Load N {kgf}	F mm	Load N {kgf}		
M-FSB	15	35	320	26.5	15.5	19.0	34.91	{3.56}	14.0	490	{50}	15.8	549	{56}	—	—
		40	330			20.0	27.95	{2.85}	16.0	451 {46}	18.0	500 {51}	20.0	559 {57}		
		45	340			22.5	24.81	{2.53}	18.0		20.3		22.5			
		50	360			25.0	22.36	{2.28}	20.0		22.5		25.0			
		55	370			27.5	20.30	{2.07}	22.0		24.8		27.5			
		60	380			29.5	18.63	{1.90}	24.0		27.0		30.0			
		65	385			31.5	17.16	{1.75}	26.0		29.3		32.5			
		70	390			33.5	15.98	{1.63}	28.0		31.5		35.0			
		75	400			35.5	14.91	{1.52}	30.0		33.8		37.5			
		80	420			37.5	14.02	{1.43}	32.0		36.0		40.0			
		85	430			39.5	13.14	{1.34}	34.0		38.3		42.5			
		90	440			41.0	12.45	{1.27}	36.0		40.5		45.0			
		100	470			46.0	11.18	{1.14}	40.0		45.0		50.0			
		110	500			51.0	10.20	{1.04}	44.0		49.5		55.0			
		120	520			56.0	9.32	{0.95}	48.0		54.0		60.0			
		130	540			61.0	8.63	{0.88}	52.0		58.5		65.0		785 {80}	
	20	40	370	20.0	39.23	{4.00}	16.0	628 {64}	18.0	706 {72}	20.0					
		50	400	25.0	31.38	{3.20}	20.0		22.5		25.0					
		60	430	29.5	26.18	{2.67}	24.0		27.0		30.0					
		70	460	34.0	22.46	{2.29}	28.0		31.5		35.0					
		80	490	38.0	19.61	{2.00}	32.0		36.0		40.0					
		90	530	41.0	17.46	{1.78}	36.0		40.5		45.0					
		100	550	44.5	15.69	{1.60}	40.0		45.0		50.0					
		110	580	50.0	14.22	{1.45}	44.0		49.5		55.0					
		120	600	55.0	13.04	{1.33}	48.0		54.0		60.0					
		130	620	58.0	12.06	{1.23}	52.0		58.5		65.0					
	25	50	530	27.0	53.45	{5.45}	20.0	1,069	{109}	22.5	1,206	{123}	—	—		
		60	560	30.0	40.89	{4.17}	24.0	981 {100}	27.0	1,108 {113}	30.0	1,226 {125}				
		70	590	35.0	35.01	{3.57}	28.0		31.5		35.0					
		80	630	40.0	30.69	{3.13}	32.0		36.0		40.0					
		90	680	45.0	27.26	{2.78}	36.0		40.5		45.0					
		100	700	49.5	24.52	{2.50}	40.0		45.0		50.0					
		110	740	54.5	22.26	{2.27}	44.0		49.5		55.0					
		120	770	59.0	20.40	{2.08}	48.0		54.0		60.0					
		130	800	64.0	18.83	{1.92}	52.0		58.5		65.0					
		140	830	69.0	17.55	{1.79}	56.0		63.0		70.0					
	150	870	74.0	16.38	{1.67}	60.0	67.5		75.0							
	30	80	760	40.0	40.50	{4.13}	32.0	1,295 {132}	36.0	1,461 {149}	40.0	1,618 {165}				
		90	780	45.0	35.99	{3.67}	36.0		40.5		45.0					
		100	810	50.0	32.36	{3.30}	40.0		45.0		50.0					
		110	840	55.0	29.42	{3.00}	44.0		49.5		55.0					
		120	900	60.0	26.97	{2.75}	48.0		54.0		60.0					
		130	940	65.0	24.91	{2.54}	52.0		58.5		65.0					
		140	980	70.0	23.14	{2.36}	56.0		63.0		70.0					
		150	1,020	75.0	21.57	{2.20}	60.0		67.5		75.0					
Standard operation frequency (reference value)									500,000 times or more							

※ When installing a coil spring, apply an initial load.

※ Load calculation method: Load (N) = Spring constant (N/mm) × deflection (mm)
kgf=N×0.101972



Calculation example of spring length

$$L = (\text{Stroke} + \text{Initial load}) \div \text{Deflection rate}$$

L: Free length of Spring

Stroke=C − E − F − SP1 − SP2 − SP3

Initial load: 5 to 10 mm or L × (5 to 10) %


Deflection rate: 40 to 50%

Coil Springs High Deflection TY Type

SPRINGS

Additional processing to mold bases → P.134

Catalog No.	L		Load	Winding direction	Maximum deflection F max (Ref. value)	Material	Color
	L ≤ 50	L ≥ 55					
M-TY	±0.5	±2%	±10%	Right	L × 0.6	Chrome silicon spring steel	Purple



How to order

Catalog No.

D × L

M-TY

21 × 70

※ When D=14.5, specify 15. [e.g.] M-TY15×80



Orders are shipped out in 3 business days (excluding the day of order).

Catalog No.	D	L	Unit price (in yen)			d	Spring constant		F=L×40%		F=L×45%		F=L×50%	
			1-19 pcs.	20-49 pcs.	50 pcs.		N/mm	{kgf/mm}	F mm	Load N {kgf}	F mm	Load N {kgf}	F mm	Load N {kgf}
M-TY	14.5	20	183	165	146	9	18.52	1.89	8.0	147.1 {15.0}	9.0	166.7 {17.0}	10.0	186.3 {19.0}
		25	189	170	151		14.82	1.51	10.0		11.3		12.5	
		30	198	178	158		12.35	1.26	12.0		13.5		15.0	
		35	204	184	163		10.58	1.08	14.0		15.8		17.5	
		40	218	196	174		9.26	0.94	16.0		18.0		20.0	
		45	224	202	179		8.23	0.84	18.0		20.3		22.5	
		50	239	215	191		7.41	0.76	20.0		22.5		25.0	
		55	260	234	208		6.74	0.69	22.0		24.8		27.5	
		60	266	239	213		6.17	0.63	24.0		27.0		30.0	
		65	288	259	230		5.70	0.58	26.0		29.3		32.5	
		70	295	266	236		5.29	0.54	28.0		31.5		35.0	
		75	309	278	247		4.94	0.50	30.0		33.8		37.5	
		80	324	292	259		4.63	0.47	32.0		36.0		40.0	
		90	351	316	281		4.12	0.42	36.0		40.5		45.0	
		100	373	336	298		3.70	0.38	40.0		45.0		50.0	
		125	406	365	325		2.96	0.30	50.0		56.3		62.5	
	17	25	198	178	158	11	21.80	2.22	10.0	215.7 {22.0}	11.3	245.2 {25.0}	12.5	274.6 {28.0}
		30	211	190	169		18.16	1.85	12.0		13.5		15.0	
		35	218	196	174		15.57	1.59	14.0		15.8		17.5	
		40	224	202	179		13.62	1.39	16.0		18.0		20.0	
		45	231	208	185		12.11	1.23	18.0		20.3		22.5	
		50	253	228	202		10.90	1.11	20.0		22.5		25.0	
		55	260	234	208		9.91	1.01	22.0		24.8		27.5	
		60	266	239	213		9.08	0.93	24.0		27.0		30.0	
		65	288	259	230		8.38	0.85	26.0		29.3		32.5	
		70	295	266	236		7.78	0.79	28.0		31.5		35.0	
		75	309	278	247		7.27	0.74	30.0		33.8		37.5	
		80	324	292	259		6.81	0.69	32.0		36.0		40.0	
		90	351	316	281		6.05	0.62	36.0		40.5		45.0	
		100	373	336	298		5.45	0.56	40.0		45.0		50.0	
		125	406	365	325		4.36	0.44	50.0		56.3		62.5	
		150	449	404	359		3.63	0.37	60.0		67.5		75.0	
Standard operation frequency (reference value)							1000,000 times		500,000 times		300,000 times			

※ Do not use the spring exceeding the deflection of L × 50%.

※ When installing a coil spring, apply an initial load.

※ Load calculation method: Load (N) = Spring constant (N/mm) × deflection (mm)
kgf=N×0.101972

Catalog No.	D	L	U/price (in yen)			d	Spring constant		F=L×40%		F=L×45%		F=L×50%	
			1-19 pcs.	20-49 pcs.	50 pcs.		N/mm	{kgf/mm}	F mm	Load N {kgf}	F mm	Load N {kgf}	F mm	Load N {kgf}
M-TY	21	30	253	228	202	13	23.24	2.37	12.0	284.4 {29.0}	13.5	313.8 {32.0}	15.0	353.0 {36.0}
		35	260	234	208		19.92	2.03	14.0		15.8		17.5	
		40	266	239	213		17.43	1.78	16.0		18.0		20.0	
		45	274	247	219		15.50	1.58	18.0		20.3		22.5	
		50	281	253	225		13.95	1.42	20.0		22.5		25.0	
		55	288	259	230		12.68	1.29	22.0		24.8		27.5	
		60	288	259	230		11.62	1.19	24.0		27.0		30.0	
		65	301	271	241		10.73	1.09	26.0		29.3		32.5	
		70	309	278	247		9.96	1.02	28.0		31.5		35.0	
		75	315	284	252		9.30	0.95	30.0		33.8		37.5	
		80	324	292	259		8.72	0.89	32.0		36.0		40.0	
		90	344	310	275		7.75	0.79	36.0		40.5		45.0	
		100	358	322	286		6.97	0.71	40.0		45.0		50.0	
		125	393	354	314		5.58	0.57	50.0		56.3		62.5	
		150	428	385	342		4.65	0.47	60.0		67.5		75.0	
	26	30	266	239	213	16.5	34.87	3.56	12.0	411.9 {42.0}	13.5	470.7 {48.0}	15.0	519.8 {53.0}
		35	288	259	230		29.89	3.05	14.0		15.8		17.5	
		40	301	271	241		26.15	2.67	16.0		18.0		20.0	
		45	315	284	252		23.24	2.37	18.0		20.3		22.5	
		50	330	297	264		20.92	2.13	20.0		22.5		25.0	
		55	338	304	270		19.02	1.94	22.0		24.8		27.5	
		60	351	316	281		17.43	1.78	24.0		27.0		30.0	
		65	351	316	281		16.09	1.64	26.0		29.3		32.5	
		70	364	328	291		14.94	1.52	28.0		31.5		35.0	
		75	379	341	303		13.95	1.42	30.0		33.8		37.5	
		80	393	354	314		13.08	1.33	32.0		36.0		40.0	
		90	406	365	325		11.62	1.19	36.0		40.5		45.0	
		100	435	392	348		10.46	1.07	40.0		45.0		50.0	
		110	464	418	371		9.51	0.97	44.0		49.5		55.0	
		32	125	499	449		399	21	8.37		0.85		50.0	
	150		548	493	438	6.97	0.71		60.0	67.5	75.0			
	175		583	525	466	5.98	0.61		70.0	78.8	87.5			
	200		633	570	506	5.23	0.53		80.0	90.0	100.0			
	40		330	297	264	34.87	3.56		16.0	18.0	20.0			
	45		351	316	281	30.99	3.16		18.0	20.3	22.5			
	50		373	336	298	27.89	2.84		20.0	22.5	25.0			
	60		415	374	332	23.24	2.37		24.0	27.0	30.0			
	70		441	397	353	19.92	2.03		28.0	31.5	35.0			
	80		484	436	387	17.43	1.78		32.0	36.0	40.0			
	90		526	473	421	15.50	1.58		36.0	40.5	45.0			
	100		541	487	433	13.95	1.42		40.0	45.0	50.0			
	110		569	512	455	12.68	1.29		44.0	49.5	55.0			
	125		590	531	472	11.16	1.14		50.0	56.3	62.5			
	39		150	604	544	483	26		9.30	0.95	60.0	725.7 {74.0}	67.5	823.8 {84.0}
		175	639	575	511	7.97		0.81	70.0	78.8	87.5			
		200	695	626	556	6.97		0.71	80.0	90.0	100.0			
		250	800	720	640	5.58		0.57	100.0	112.5	125.0			
		300	899	809	719	4.65		0.47	120.0	135.0	150.0			
		40	415	374	332	45.77		4.67	16.0	18.0	20.0			
		45	441	397	353	40.68		4.15	18.0	20.3	22.5			
		50	464	418	371	36.61		3.73	20.0	22.5	25.0			
		60	491	442	393	30.51		3.11	24.0	27.0	30.0			
		70	505	455	404	26.15		2.67	28.0	31.5	35.0			
		80	526	473	421	22.88		2.33	32.0	36.0	40.0			
		90	541	487	433	20.34		2.07	36.0	40.5	45.0			
		100	568	511	454	18.31		1.87	40.0	45.0	50.0			
		110	583	525	466	16.64		1.70	44.0	49.5	55.0			
		46	125	610	549	488		32	14.65	1.49	50.0		970.9 {99.0}	
	150		633	570	506	12.20	1.24		60.0	67.5	75.0			
	175		645	581	516	10.46	1.07		70.0	78.8	87.5			
	200		681	613	545	9.15	0.93		80.0	90.0	100.0			
	250		821	739	657	7.32	0.75		100.0	112.5	125.0			
	300		934	841	747	6.10	0.62		120.0	135.0	150.0			
	50		526	473	421	48.81	4.98		20.0	22.5	25.0			
	60		541	487	433	40.68	4.15		24.0	27.0	30.0			
	70		548	493	438	34.87	3.56		28.0	31.5	35.0			
	80		568	511	454	30.51	3.11		32.0	36.0	40.0			
	90		583	525	466	27.12	2.77		36.0	40.5	45.0			
	100		596	536	477	24.41	2.49		40.0	45.0	50.0			
	110		618	556	494	22.19	2.26		44.0	49.5	55.0			
	125		639	575	511	19.53	1.99		50.0	56.3	62.5			
	150		668	601	534	16.27	1.66		60.0	67.5	75.0			
	175	701	631	561	13.95	1.42	70.0	78.8	87.5					
	200	730	657	584	12.20	1.24	80.0	90.0	100.0					
	250	828	745	662	9.76	1.00	100.0	112.5	125.0					
	300	969	872	775	8.14	0.83	120.0	135.0	150.0					
Standard operation frequency (reference value)							1000,000 times		500,000 times		300,000 times			

※ Do not use the spring exceeding the deflection of L × 50%.

※ When installing a coil spring, apply an initial load.

※ Load calculation method: Load (N) = Spring constant (N/mm) × deflection (mm)


kgf=N×0.101972

Coil Springs High Deflection TR Type

SPRINGS

Additional processing to mold bases ➡ P.134

Catalog No.	L		Load	Winding direction	Maximum deflection F max (Ref. value)	Material	Color
	L ≤ 50	L ≥ 55					
M-TR	±0.5	±2%	±10%	Right	L×0.6	Chrome silicon spring steel	Ivory



How to order

Catalog No.

D × L

M-TR

32 × 80

※ When D=14.5, specify 15. [E.g.] M-TR15×60



Orders are shipped out in 3 business days (excluding the day of order).

Catalog No.	D	L	U/price (in yen)			d	Spring constant N/mm {kgf/mm}		F=L×40%		F=L×45%		F=L×50%	
			1-19 pcs.	20-49 pcs.	50 pcs.				F mm	Load N {kgf}	F mm	Load N {kgf}	F mm	Load N {kgf}
M-TR	14.5	20	168	151	134	9	10.90	1.11	8.0	88.3 {9.0}	9.0	98.1 {10.0}	10.0	107.9 {11.0}
		25	173	156	139		8.72	0.89	10.0		11.3		12.5	
		30	189	170	151		7.27	0.74	12.0		13.5		15.0	
		35	194	175	155		6.23	0.64	14.0		15.8		17.5	
		40	200	180	160		5.45	0.56	16.0		18.0		20.0	
		45	210	189	168		4.84	0.49	18.0		20.3		22.5	
		50	226	203	181		4.36	0.44	20.0		22.5		25.0	
		55	242	217	193		3.96	0.40	22.0		24.8		27.5	
		60	252	227	202		3.63	0.37	24.0		27.0		30.0	
		65	268	241	214		3.35	0.34	26.0		29.3		32.5	
		70	278	250	223		3.11	0.32	28.0		31.5		35.0	
		75	289	260	231		2.91	0.30	30.0		33.8		37.5	
		80	299	269	239		2.73	0.28	32.0		36.0		40.0	
		90	326	293	260		2.42	0.25	36.0		40.5		45.0	
		100	347	312	277		2.18	0.22	40.0		45.0		50.0	
		125	383	345	307		1.74	0.18	50.0		56.3		62.5	
	17	25	189	170	151	11	14.82	1.51	10.0	147.1 {15.0}	11.3	166.7 {17.0}	12.5	186.3 {19.0}
		30	194	175	155		12.35	1.26	12.0		13.5		15.0	
		35	200	180	160		10.58	1.08	14.0		15.8		17.5	
		40	210	189	168		9.26	0.94	16.0		18.0		20.0	
		45	215	194	172		8.23	0.84	18.0		20.3		22.5	
		50	231	208	185		7.41	0.76	20.0		22.5		25.0	
		55	242	217	193		6.74	0.69	22.0		24.8		27.5	
		60	247	222	197		6.17	0.63	24.0		27.0		30.0	
		65	268	241	214		5.70	0.58	26.0		29.3		32.5	
		70	278	250	223		5.29	0.54	28.0		31.5		35.0	
		75	289	260	231		4.94	0.50	30.0		33.8		37.5	
		80	299	269	239		4.63	0.47	32.0		36.0		40.0	
		90	326	293	260		4.12	0.42	36.0		40.5		45.0	
		100	347	312	277		3.70	0.38	40.0		45.0		50.0	
		125	383	345	307		2.96	0.30	50.0		56.3		62.5	
		150	420	378	336		2.47	0.25	60.0		67.5		75.0	
Standard operation frequency (reference value)								1000,000 times		500,000 times		300,000 times		

※ Do not use the spring exceeding the deflection of L × 50%.

※ When installing a coil spring, apply an initial load.

※ Load calculation method: Load (N) = Spring constant (N/mm) × deflection (mm)

kgf=N×0.101972

Catalog No.	D	L	U/price (in yen)			d	Spring constant N/mm {kgf/mm}			F=L×40%		F=L×45%		F=L×50%					
			1-19 pcs.	20-49 pcs.	50 pcs.		F mm	Load N {kgf}	F mm	Load N {kgf}	F mm	Load N {kgf}							
21		30	231	208	185	13	13.80	1.41	12.0	166.7 {17.0}	13.5	186.3 {19.0}	15.0	205.9 {21.0}					
		35	236	213	189		11.83	1.21	14.0		15.8		17.5						
		40	247	222	197		10.35	1.06	16.0		18.0		20.0						
		45	257	232	206		9.20	0.94	18.0		20.3		22.5						
		50	263	236	210		8.28	0.84	20.0		22.5		25.0						
		55	268	241	214		7.53	0.77	22.0		24.8		27.5						
		60	273	246	218		6.90	0.70	24.0		27.0		30.0						
		65	284	255	227		6.37	0.65	26.0		29.3		32.5						
		70	289	260	231		5.91	0.60	28.0		31.5		35.0						
		75	294	265	235		5.52	0.56	30.0		33.8		37.5						
		80	299	269	239		5.18	0.53	32.0		36.0		40.0						
		90	320	288	256		4.60	0.47	36.0		40.5		45.0						
		100	331	298	265		4.14	0.42	40.0		45.0		50.0						
		125	368	331	294		3.31	0.34	50.0		56.3		62.5						
		150	399	359	319		2.76	0.28	60.0		67.5		75.0						
		30	252	227	202	16.5	26.87	2.74	12.0	323.6 {33.0}	13.5	362.8 {37.0}	15.0	402.1 {41.0}					
		35	268	241	214		23.03	2.35	14.0		15.8		17.5						
		40	278	250	223		20.16	2.06	16.0		18.0		20.0						
		45	294	265	235		17.92	1.83	18.0		20.3		22.5						
		50	310	279	248		16.12	1.64	20.0		22.5		25.0						
55		315	284	252	14.66		1.49	22.0	24.8		27.5								
60		320	288	256	13.44		1.37	24.0	27.0		30.0								
65		331	298	265	12.40		1.26	26.0	29.3		32.5								
70		341	307	273	11.52		1.17	28.0	31.5		35.0								
75		352	317	281	10.75		1.10	30.0	33.8		37.5								
80		362	326	290	10.08		1.03	32.0	36.0		40.0								
90		378	340	302	8.96		0.91	36.0	40.5		45.0								
100		404	364	323	8.06		0.82	40.0	45.0		50.0								
26			40	436	392		349	21	7.33		0.75		44.0		402.1 {41.0}	49.5	451.1 {46.0}	55.0	500.1 {51.0}
			125	467	421		374		6.45		0.66		50.0			56.3		62.5	
	150		509	458	407	5.37	0.55		60.0	67.5	75.0								
	175		546	491	437	4.61	0.47		70.0	78.8	87.5								
	200		588	529	470	4.03	0.41		80.0	90.0	100.0								
	40		310	279	248	26	25.06		2.56	16.0	431.5 {44.0}	18.0	490.3 {50.0}	20.0		539.4 {55.0}			
	45		326	293	260		22.28		2.27	18.0		20.3		22.5					
	50		347	312	277		20.05		2.04	20.0		22.5		25.0					
	60		383	345	307		16.71		1.70	24.0		27.0		30.0					
	70		415	373	332		14.32		1.46	28.0		31.5		35.0					
	80		446	402	357		12.53		1.28	32.0		36.0		40.0					
	90		483	435	386		11.14		1.14	36.0		40.5		45.0					
	100		504	454	403		10.02		1.02	40.0		45.0		50.0					
	110		530	477	424		9.11		0.93	44.0		49.5		55.0					
	125		546	491	437		8.02		0.82	50.0		56.3		62.5					
	150	572	515	458	6.68		0.68	60.0	67.5	75.0									
	175	599	539	479	5.73		0.58	70.0	78.8	87.5									
	200	651	586	521	5.01		0.51	80.0	90.0	100.0									
	250	746	671	596	4.01		0.41	100.0	112.5	125.0									
	300	840	756	672	3.34		0.34	120.0	135.0	150.0									
39		40	389	350	311	26	27.24	2.78	16.0	431.5 {44.0}	18.0	490.3 {50.0}	20.0	539.4 {55.0}					
		45	410	369	328		24.21	2.47	18.0		20.3		22.5						
		50	436	392	349		21.79	2.22	20.0		22.5		25.0						
		60	457	411	365		18.16	1.85	24.0		27.0		30.0						
		70	473	425	378		15.57	1.59	28.0		31.5		35.0						
		80	483	435	386		13.62	1.39	32.0		36.0		40.0						
		90	504	454	403		12.11	1.23	36.0		40.5		45.0						
		100	530	477	424		10.90	1.11	40.0		45.0		50.0						
		110	541	487	433		9.91	1.01	44.0		49.5		55.0						
		125	567	510	454		8.72	0.89	50.0		56.3		62.5						
		150	593	534	475		7.26	0.74	60.0		67.5		75.0						
		175	604	543	483		6.23	0.63	70.0		78.8		87.5						
		200	635	572	508		5.45	0.56	80.0		90.0		100.0						
		250	767	690	613		4.36	0.44	100.0		112.5		125.0						
		300	872	784	697		3.63	0.37	120.0		135.0		150.0						
		50	483	435	386	32	24.41	2.49	20.0	490.3 {50.0}	22.5	549.2 {56.0}	25.0	608.0 {62.0}					
		60	504	454	403		20.34	2.07	24.0		27.0		30.0						
		70	509	458	407		17.43	1.78	28.0		31.5		35.0						
		80	530	477	424		15.26	1.56	32.0		36.0		40.0						
		90	541	487	433		13.56	1.38	36.0		40.5		45.0						
100		562	506	449	12.20		1.24	40.0	45.0		50.0								
110		572	515	458	11.09		1.13	44.0	49.5		55.0								
125		599	539	479	9.76		1.00	50.0	56.3		62.5								
150		620	558	496	8.14		0.83	60.0	67.5		75.0								
175		651	586	521	6.97		0.71	70.0	78.8		87.5								
200		683	614	546	6.10		0.62	80.0	90.0		100.0								
250		772	695	617	4.88		0.50	100.0	112.5		125.0								
300		903	813	722	4.07		0.41	120.0	135.0		150.0								
Standard operation frequency (reference value)							1000,000 times		500,000 times		300,000 times								

※ Do not use the spring exceeding the deflection of L × 50%.

※ When installing a coil spring, apply an initial load.


※ Load calculation method: Load (N) = Spring constant (N/mm) × deflection (mm)
kgf=N×0.101972

Coil Springs Strong Coil TF Type

SPRINGS

Additional processing to mold bases → P.134

Catalog No.	L		Load	Winding direction	Maximum deflection F max (Ref. value)	Material	Color
	L ≤ 50	L ≥ 55					
P-TF	±0.5	±1%	±10%	Right	L × 0.53	Chrome silicon spring steel	Yellow



How to order

Catalog No.

D × L

P-TF

20 × 50



Orders are shipped out in 3 business days (excluding the day of order).

Catalog No.	D	L	U/price (in yen)			d	Spring constant		F=L×40%		F=L×45%		F=L×50%					
			1-19 pcs.	20-49 pcs.	50 pcs.		N/mm	{kgf/mm}	F mm	Load N {kgf}	F mm	Load N {kgf}	F mm	Load N {kgf}				
P-TF	8	10	90	85	81	4	15.24	{1.55}	4.0	58.8 {6.0}	4.5	68.6 {7.0}	5.0	78.5 {8.0}				
		15	94	89	84		10.16	{1.04}	6.0		6.8		7.5					
		20	105	100	94		7.62	{0.78}	8.0		9.0		10.0					
		25	127	120	114		6.10	{0.62}	10.0		11.3		12.5					
		30	127	120	114		5.08	{0.52}	12.0		13.5		15.0					
		35	138	131	124		4.36	{0.44}	14.0		15.8		17.5					
		40	149	141	134		3.81	{0.39}	16.0		18.0		20.0					
		45	160	152	144		3.39	{0.35}	18.0		20.3		22.5					
		50	171	162	154		3.05	{0.31}	20.0		22.5		25.0					
		55	182	172	163		2.77	{0.28}	22.0		24.8		27.5					
	60	193	183	173	2.54	{0.26}	24.0	27.0	30.0									
	65	204	194	184	2.35	{0.24}	26.0	29.3	32.5									
	70	215	204	194	2.18	{0.22}	28.0	31.5	35.0									
	75	226	215	203	2.03	{0.21}	30.0	33.8	37.5									
	80	237	225	213	1.91	{0.19}	32.0	36.0	40.0									
	10	20	130	123	117	5	9.81	{1.00}	8.0	78.5 {8.0}	9.0	88.3 {9.0}	10.0	98.1 {10.0}				
		25	130	123	117		7.85	{0.80}	10.0		11.3		12.5					
		30	130	123	117		6.54	{0.67}	12.0		13.5		15.0					
		35	130	123	117		5.61	{0.57}	14.0		15.8		17.5					
		40	145	137	130		4.91	{0.50}	16.0		18.0		20.0					
		45	155	147	139		4.36	{0.44}	18.0		20.3		22.5					
		50	170	161	153		3.92	{0.40}	20.0		22.5		25.0					
		55	180	171	162		3.57	{0.36}	22.0		24.8		27.5					
		60	195	185	175		3.27	{0.33}	24.0		27.0		30.0					
		65	209	199	189		3.02	{0.31}	26.0		29.3		32.5					
		70	209	199	189		2.80	{0.29}	28.0		31.5		35.0					
		75	234	223	211		2.62	{0.27}	30.0		33.8		37.5					
		80	259	246	233		2.45	{0.25}	32.0		36.0		40.0					
		90	309	294	278		2.18	{0.22}	36.0		40.5		45.0					
Standard operation frequency (reference value)								1000,000 times			500,000 times		300,000 times					

※ Do not use the spring exceeding the deflection of L × 50%.

※ When installing a coil spring, apply an initial load.

※ Load calculation method: Load (N) = Spring constant (N/mm) × deflection (mm)
kgf=N×0.101972

Catalog No.	D	L	U/price (in yen)			d	Spring constant		F=L×40%		F=L×45%		F=L×50%				
			1-19 pcs.	20-49 pcs.	50 pcs.		N/mm	{kgf/mm}	F mm	Load N {kgf}	F mm	Load N {kgf}	F mm	Load N {kgf}			
P-TF	12	20	145	137	130	6	13.62	{1.39}	8.0	107.9 {11.0}	9.0	122.6 {12.5}	10.0	137.3 {14.0}			
		25	155	147	139		10.90	{1.11}	10.0		11.3		12.5				
		30	170	161	153		9.08	{0.93}	12.0		13.5		15.0				
		35	170	161	153		7.78	{0.79}	14.0		15.8		17.5				
		40	180	171	162		6.81	{0.69}	16.0		18.0		20.0				
		45	195	185	175		6.05	{0.62}	18.0		20.3		22.5				
		50	209	199	189		5.45	{0.56}	20.0		22.5		25.0				
		55	219	208	198		4.95	{0.51}	22.0		24.8		27.5				
		60	234	223	211		4.54	{0.46}	24.0		27.0		30.0				
		65	244	232	220		4.19	{0.43}	26.0		29.3		32.5				
		70	259	246	233		3.89	{0.40}	28.0		31.5		35.0				
		75	274	261	247		3.63	{0.37}	30.0		33.8		37.5				
		80	299	284	269		3.41	{0.35}	32.0		36.0		40.0				
		90	339	322	305		3.03	{0.31}	36.0		40.5		45.0				
		25	190	180	171		13.95	{1.42}	10.0		11.3		156.9 {16.0}		12.5		
		30	200	190	180		11.62	{1.19}	12.0		13.5				15.0		
		35	209	199	189		9.96	{1.02}	14.0		15.8				17.5		
		40	224	213	202		8.72	{0.89}	16.0		18.0				20.0		
	45	234	223	211	7.75	{0.79}	18.0	20.3	22.5								
	50	239	227	215	6.97	{0.71}	20.0	22.5	25.0								
	55	249	237	224	6.34	{0.65}	22.0	24.8	27.5								
	60	259	246	233	5.81	{0.59}	24.0	27.0	30.0								
	65	269	256	242	5.36	{0.55}	26.0	29.3	32.5								
	70	279	265	251	4.98	{0.51}	28.0	31.5	35.0								
	75	289	275	260	4.65	{0.47}	30.0	33.8	37.5								
	80	299	284	269	4.36	{0.44}	32.0	36.0	40.0								
	90	324	308	292	3.87	{0.40}	36.0	40.5	45.0								
	100	349	332	314	3.49	{0.36}	40.0	45.0	50.0								
	16	25	209	199	189	8	16.56	{1.69}	10.0	166.7 {17.0}	11.3	186.3 {19.0}		12.5			
		30	219	208	198		13.80	{1.41}	12.0		13.5			15.0			
		35	229	218	206		11.83	{1.21}	14.0		15.8			17.5			
		40	249	237	224		10.35	{1.06}	16.0		18.0			20.0			
		45	259	246	233		9.20	{0.94}	18.0		20.3		22.5				
		50	264	251	238		8.28	{0.84}	20.0		22.5		25.0				
		55	279	265	251		7.53	{0.77}	22.0		24.8		27.5				
		60	289	275	260		6.90	{0.70}	24.0		27.0		30.0				
		65	299	284	269		6.37	{0.65}	26.0		29.3		32.5				
		70	309	294	278		5.91	{0.60}	28.0		31.5		35.0				
		75	319	303	287		5.52	{0.56}	30.0		33.8		37.5				
		80	329	313	296		5.18	{0.53}	32.0		36.0		40.0				
		90	349	332	314		4.60	{0.47}	36.0		40.5		45.0				
		100	379	360	341		4.14	{0.42}	40.0		45.0		50.0				
		125	439	417	395		3.31	{0.34}	50.0		56.3		62.5				
		18	25	209	199		189	9	20.09		{2.05}		10.0	206 {21.0}	11.3	226 {23.0}	12.5
			30	219	208		198		16.74		{1.71}		12.0		13.5		15.0
			35	229	218		206		14.35		{1.46}		14.0		15.8		17.5
	40		249	237	224	12.56	{1.28}		16.0	18.0	20.0						
	45		259	246	233	11.16	{1.14}		18.0	20.3	22.5						
	50		264	251	238	10.04	{1.02}		20.0	22.5	25.0						
	55		279	265	251	9.13	{0.93}		22.0	24.8	27.5						
	60		289	275	260	8.37	{0.85}		24.0	27.0	30.0						
	65		299	284	269	7.73	{0.79}		26.0	29.3	32.5						
	70		309	294	278	7.17	{0.73}		28.0	31.5	35.0						
	75		319	303	287	6.70	{0.68}		30.0	33.8	37.5						
80	329		313	296	6.28	{0.64}	32.0		36.0	40.0							
90	349		332	314	5.58	{0.57}	36.0		40.5	45.0							
100	384		365	346	5.02	{0.51}	40.0		45.0	50.0							
125	449		427	404	4.02	{0.41}	50.0		56.3	62.5							
20	25		209	199	189	11	25.24		{2.57}	10.0	255 {26.0}	11.3	284 {29.0}		12.5		
	30		219	208	198		21.04		{2.15}	12.0		13.5			15.0		
	35		229	218	206		18.03		{1.84}	14.0		15.8			17.5		
	40	249	237	224	15.78		{1.61}	16.0	18.0	20.0							
	45	259	246	233	14.02		{1.43}	18.0	20.3	22.5							
	50	264	251	238	12.62		{1.29}	20.0	22.5	25.0							
	55	279	265	251	11.47		{1.17}	22.0	24.8	27.5							
	60	289	275	260	10.52		{1.07}	24.0	27.0	30.0							
	65	299	284	269	9.71		{0.99}	26.0	29.3	32.5							
	70	309	294	278	9.02		{0.92}	28.0	31.5	35.0							
	75	319	303	287	8.41		{0.86}	30.0	33.8	37.5							
	80	329	313	296	7.89		{0.80}	32.0	36.0	40.0							
	90	349	332	314	7.01		{0.72}	36.0	40.5	45.0							
	100	369	351	332	6.31		{0.64}	40.0	45.0	50.0							
	125	399	379	359	5.05		{0.51}	50.0	56.3	62.5							
	150	429	407	386	4.21		{0.43}	60.0	67.5	75.0							
	Standard operation frequency (reference value)								1000,000 times			500,000 times		300,000 times			

※ Do not use the spring exceeding the deflection of $L \times 50\%$.

※ When installing a coil spring, apply an initial load.

※ Load calculation method: Load (N) = Spring constant (N/mm) × deflection (mm)

$\text{kgf} = \text{N} \times 0.101972$

Coil Springs Strong Coil TF Type

SPRINGS

Catalog No.	D	L	U/price (in yen)			d	Spring constant		F=L×40%		F=L×45%		F=L×50%	
			1-19 pcs.	20-49 pcs.	50 pcs.		N/mm	{kgf/mm}	F mm	Load N {kgf}	F mm	Load N {kgf}	F mm	Load N {kgf}
P-TF	22	25	214	204	193	11	31.38	{3.20}	10.0	314 {32.0}	11.3	353 {36.0}	12.5	392 {40.0}
		30	224	213	202		26.15	{2.67}	12.0		13.5		15.0	
		35	234	223	211		22.41	{2.29}	14.0		15.8		17.5	
		40	249	237	224		19.61	{2.00}	16.0		18.0		20.0	
		45	259	246	233		17.43	{1.78}	18.0		20.3		22.5	
		50	269	256	242		15.69	{1.60}	20.0		22.5		25.0	
		55	284	270	256		14.26	{1.45}	22.0		24.8		27.5	
		60	294	280	265		13.07	{1.33}	24.0		27.0		30.0	
		65	304	289	274		12.07	{1.23}	26.0		29.3		32.5	
		70	314	299	283		11.21	{1.14}	28.0		31.5		35.0	
		75	324	308	292		10.46	{1.07}	30.0		33.8		37.5	
		80	334	317	301		9.81	{1.00}	32.0		36.0		40.0	
		90	354	336	319		8.72	{0.89}	36.0		40.5		45.0	
		100	379	360	341		7.84	{0.80}	40.0		45.0		50.0	
		125	414	393	373		6.28	{0.64}	50.0		56.3		62.5	
		150	459	436	413		5.23	{0.53}	60.0		67.5		75.0	
	25	25	219	208	198	13.5	39.20	{4.00}	10.0	392 {40.0}	11.3	441 {45.0}	12.5	490 {50.0}
		30	224	213	202		32.67	{3.33}	12.0		13.5		15.0	
		35	239	227	215		28.00	{2.86}	14.0		15.8		17.5	
		40	249	237	224		24.50	{2.50}	16.0		18.0		20.0	
		45	259	246	233		21.78	{2.22}	18.0		20.3		22.5	
		50	269	256	242		19.60	{2.00}	20.0		22.5		25.0	
		55	289	275	260		17.82	{1.82}	22.0		24.8		27.5	
		60	299	284	269		16.33	{1.67}	24.0		27.0		30.0	
		65	309	294	278		15.08	{1.54}	26.0		29.3		32.5	
		70	319	303	287		14.00	{1.43}	28.0		31.5		35.0	
		75	329	313	296		13.07	{1.33}	30.0		33.8		37.5	
		80	339	322	305		12.25	{1.25}	32.0		36.0		40.0	
		90	359	341	323		10.89	{1.11}	36.0		40.5		45.0	
		100	389	370	350		9.80	{1.00}	40.0		45.0		50.0	
		125	429	407	386		7.84	{0.80}	50.0		56.3		62.5	
		150	494	469	444		6.53	{0.67}	60.0		67.5		75.0	
	175	549	521	494	5.60	{0.57}	70.0	78.8	87.5					
	200	604	574	544	4.90	{0.50}	80.0	90.0	100.0					
	27	25	219	208	198	13.5	47.11	{4.80}	10.0	471 {48.0}	11.3	530 {54.0}	12.5	588 {60.0}
		30	224	213	202		39.26	{4.00}	12.0		13.5		15.0	
		35	239	227	215		33.65	{3.43}	14.0		15.8		17.5	
		40	249	237	224		29.44	{3.00}	16.0		18.0		20.0	
		45	259	246	233		26.17	{2.67}	18.0		20.3		22.5	
		50	269	256	242		23.56	{2.40}	20.0		22.5		25.0	
		55	289	275	260		21.41	{2.18}	22.0		24.8		27.5	
		60	299	284	269		19.63	{2.00}	24.0		27.0		30.0	
		65	309	294	278		18.12	{1.85}	26.0		29.3		32.5	
		70	319	303	287		16.83	{1.72}	28.0		31.5		35.0	
		75	329	313	296		15.70	{1.60}	30.0		33.8		37.5	
		80	339	322	305		14.72	{1.50}	32.0		36.0		40.0	
		90	359	341	323		13.09	{1.33}	36.0		40.5		45.0	
		100	389	370	350		11.78	{1.20}	40.0		45.0		50.0	
		125	434	412	391		9.42	{0.96}	50.0		56.3		62.5	
		150	504	479	453		7.85	{0.80}	60.0		67.5		75.0	
	175	579	550	521	6.73	{0.69}	70.0	78.8	87.5					
	200	654	621	589	5.89	{0.60}	80.0	90.0	100.0					
	30	25	209	199	189	16	56.62	{5.77}	10.0	569 {58.0}	11.3	637 {65.0}	12.5	706 {72.0}
		30	219	208	198		47.19	{4.81}	12.0		13.5		15.0	
		35	224	213	202		40.44	{4.12}	14.0		15.8		17.5	
		40	229	218	206		35.39	{3.61}	16.0		18.0		20.0	
		45	249	237	224		31.46	{3.21}	18.0		20.3		22.5	
		50	259	246	233		28.31	{2.89}	20.0		22.5		25.0	
		55	279	265	251		25.74	{2.62}	22.0		24.8		27.5	
		60	289	275	260		23.59	{2.41}	24.0		27.0		30.0	
		65	299	284	269		21.78	{2.22}	26.0		29.3		32.5	
		70	309	294	278		20.22	{2.06}	28.0		31.5		35.0	
		75	319	303	287		18.87	{1.92}	30.0		33.8		37.5	
		80	329	313	296		17.69	{1.80}	32.0		36.0		40.0	
		90	349	332	314		15.73	{1.60}	36.0		40.5		45.0	
		100	379	360	341		14.16	{1.44}	40.0		45.0		50.0	
		125	439	417	395		11.32	{1.15}	50.0		56.3		62.5	
		150	509	483	458		9.44	{0.96}	60.0		67.5		75.0	
		175	584	554	525		8.09	{0.82}	70.0		78.8		87.5	
		200	638	606	575		7.08	{0.72}	80.0		90.0		100.0	
Standard operation frequency (reference value)							1000,000 times		500,000 times		300,000 times			

※ Do not use the spring exceeding the deflection of L × 50%.

※ When installing a coil spring, apply an initial load.

※ Load calculation method: Load (N) = Spring constant (N/mm) × deflection (mm)
kgf=N×0.101972

Catalog No.	D	L	U/price (in yen)			d	Spring constant N/mm {kgf/mm}		F=L×40%		F=L×45%		F=L×50%	
			1-19 pcs.	20-49 pcs.	50 pcs.				F mm	Load N {kgf}	F mm	Load N {kgf}	F mm	Load N {kgf}
P-TF	35	40	259	246	233	19	47.94	4.89	16.0	765 {78.0}	18.0	863 {88.0}	20.0	961 {98.0}
		45	269	256	242		42.62	4.35	18.0		20.3		22.5	
		50	289	275	260		38.36	3.91	20.0		22.5		25.0	
		55	299	284	269		34.87	3.56	22.0		24.8		27.5	
		60	319	303	287		31.96	3.26	24.0		27.0		30.0	
		65	334	317	301		29.50	3.01	26.0		29.3		32.5	
		70	349	332	314		27.40	2.79	28.0		31.5		35.0	
		75	369	351	332		25.57	2.61	30.0		33.8		37.5	
		80	389	370	350		23.97	2.44	32.0		36.0		40.0	
		90	429	407	386		21.31	2.17	36.0		40.5		45.0	
		100	469	445	422		19.18	1.96	40.0		45.0		50.0	
		125	569	540	512		15.34	1.56	50.0		56.3		62.5	
		150	658	625	593		12.79	1.30	60.0		67.5		75.0	
		175	758	720	682		10.96	1.12	70.0		78.8		87.5	
		200	838	796	754		9.59	0.98	80.0		90.0		100.0	
	40	40	309	294	278	22	62.67	6.39	16.0	1,000 {102.0}	18.0	1,128 {115.0}	20.0	1,255 {128.0}
		45	319	303	287		55.70	5.68	18.0		20.3		22.5	
		50	329	313	296		50.13	5.11	20.0		22.5		25.0	
		55	359	341	323		45.58	4.65	22.0		24.8		27.5	
		60	389	370	350		41.78	4.26	24.0		27.0		30.0	
		65	414	393	373		38.56	3.93	26.0		29.3		32.5	
		70	439	417	395		35.81	3.65	28.0		31.5		35.0	
		75	469	446	422		33.42	3.41	30.0		33.8		37.5	
		80	499	474	449		31.33	3.20	32.0		36.0		40.0	
		90	549	521	494		27.85	2.84	36.0		40.5		45.0	
		100	599	569	539		25.07	2.56	40.0		45.0		50.0	
		125	708	673	637		20.05	2.04	50.0		56.3		62.5	
		150	828	787	745		16.71	1.70	60.0		67.5		75.0	
		175	948	900	853		14.32	1.46	70.0		78.8		87.5	
		200	1,077	1,023	970		12.53	1.28	80.0		90.0		100.0	
	225	1,190	1,131	1,071	11.14	1.14	90.0	101.3	112.5					
	250	1,302	1,237	1,172	10.03	1.02	100.0	112.5	125.0					
	275	1,414	1,343	1,273	9.12	0.93	110.0	123.8	137.5					
	300	1,526	1,450	1,373	8.36	0.85	120.0	135.0	150.0					
	50	50	549	521	494	27.5	78.44	8.00	20.0	1,569 {160.0}	22.5	1,765 {180.0}	25.0	1,961 {200.0}
		55	567	539	510		71.31	7.27	22.0		24.8		27.5	
		60	584	554	525		65.37	6.67	24.0		27.0		30.0	
		65	621	590	559		60.34	6.15	26.0		29.3		32.5	
		70	658	625	593		56.03	5.71	28.0		31.5		35.0	
		75	703	668	633		52.30	5.33	30.0		33.8		37.5	
		80	748	711	673		49.03	5.00	32.0		36.0		40.0	
		90	808	768	727		43.58	4.44	36.0		40.5		45.0	
		100	888	843	799		39.22	4.00	40.0		45.0		50.0	
		125	1,067	1,014	961		31.38	3.20	50.0		56.3		62.5	
		150	1,237	1,175	1,113		26.15	2.67	60.0		67.5		75.0	
		175	1,406	1,336	1,266		22.41	2.29	70.0		78.8		87.5	
		200	1,571	1,493	1,414		19.61	2.00	80.0		90.0		100.0	
		225	1,738	1,651	1,564		17.43	1.78	90.0		101.3		112.5	
		250	1,905	1,810	1,715		15.69	1.60	100.0		112.5		125.0	
	275	2,085	1,981	1,877	14.26	1.45	110.0	123.8	137.5					
	300	2,264	2,151	2,038	13.07	1.33	120.0	135.0	150.0					
	350	2,643	2,511	2,379	11.21	1.14	140.0	157.5	175.0					
	400	2,993	2,843	2,693	9.81	1.00	160.0	180.0	200.0					
	450	3,342	3,175	3,007	8.72	0.89	180.0	202.5	225.0					
	500	3,691	3,506	3,322	7.84	0.80	200.0	225.0	250.0					
	60	60	918	872	826	33	94.07	9.59	24.0	2,260 {230.5}	27.0	2,540 {259.0}	30.0	2,820 {287.6}
		70	968	919	871		80.63	8.22	28.0		31.5		35.0	
		80	1,017	967	916		70.56	7.19	32.0		36.0		40.0	
		90	1,087	1,033	979		62.72	6.40	36.0		40.5		45.0	
		100	1,217	1,156	1,095		56.44	5.76	40.0		45.0		50.0	
		125	1,446	1,374	1,302		45.16	4.60	50.0		56.3		62.5	
		150	1,661	1,578	1,495		37.63	3.84	60.0		67.5		75.0	
		175	1,885	1,791	1,697		32.25	3.29	70.0		78.8		87.5	
		200	2,175	2,066	1,957		28.22	2.88	80.0		90.0		100.0	
		225	2,404	2,284	2,164		25.09	2.56	90.0		101.3		112.5	
		250	2,633	2,502	2,370		22.58	2.30	100.0		112.5		125.0	
		275	2,878	2,734	2,590		20.53	2.09	110.0		123.8		137.5	
		300	3,122	2,966	2,810		18.81	1.92	120.0		135.0		150.0	
		350	3,641	3,459	3,277		16.13	1.64	140.0		157.5		175.0	
		400	4,140	3,933	3,726		14.11	1.44	160.0		180.0		200.0	
	450	4,638	4,406	4,175	12.54	1.28	180.0	202.5	225.0					
	500	5,137	4,880	4,623	11.29	1.15	200.0	225.0	250.0					
Standard operation frequency (reference value)									1000,000 times		500,000 times		300,000 times	

※ Do not use the spring exceeding the deflection of $L \times 50\%$.

※ When installing a coil spring, apply an initial load.

※ Load calculation method: Load (N) = Spring constant (N/mm) $\times$ deflection (mm)
 $\text{kgf} = \text{N} \times 0.101972$

Heat Insulator Sheets

Heat Insulator Sheets Overview	408
Heat Insulator Sheets	
Heat Insulator Sheets Bakelite Paper	M-DNAP..... 410
Heat Insulator Sheets Bakelite Cloth	M-DNAC..... 412
Heat Insulator Sheets Basic Grade	M-DNBR..... 414
Heat Insulator Sheets Heat Resisting Grade	M-DNHR..... 416
Heat Insulator Sheets High Strength Grade	M-DNSR..... 418
Heat Insulator Sheets High Temperature Resisting Grade	M-DNLR..... 420


Heat Insulator Sheets Overview

Heat insulator sheets




Grade	Bakelite paper	Bakelite cloth
Catalog No.	M-DNAP	M-DNAC
Shipping	3 days	
Page	P.410	P.412

Shipping times are shown in business days (excluding the day of order).




Grade	Basic grade	Heat resisting grade	High strength grade	High temperature resisting grade
Catalog No.	M-DNBR	M-DNHR	M-DNSR	M-DNLR
Shipping	3 days			
Page	P.414	P.416	P.418	P.420

Heat insulator sheet physical property image diagram



Reference diagram

◆ Main plastic material and mold temperature



Notes for use

Effects of heat insulator sheets

- ◆ Reduce heat losses from molds and save energy.
- ◆ Shorten the time required for the temperature to rise at the initial stage of molding.
- ◆ Restrict heat transfer and stabilize the temperature distribution on molds.

Precautions for handling

- ◆ When installing a heat insulator sheet, do not tighten the bolts too hard. Doing so may break the sheet.
- ◆ Do not use in areas where water and other liquid may come in.
- ◆ Care should be taken during storage to prevent moisture absorption.

Precautions and conditions for machining

- ◆ When machining, dust must be suck up into a dust collector so that it may not scatter.
- ◆ If dust attaches to the machine, its accuracy may diminish.
- ◆ When drilling holes, care should be taken so as not to cause cracks upon removal of the tool.



Machining conditions

Machining	Lathe turning	Milling	Drilling
Tool material	Ultra-molecular (K10)	Ultra-molecular (K10)	Ultra-molecular (K10)
Revolutions (r/min)	Blade large ~ small 50 ~ 1000	Blade large ~ small 300 ~ 1000	$\phi 2$ gimlet 1000 ~ 1500 $\phi 5$ gimlet 500 ~ 1000
Cutting depth (mm)	0.5 ~ 3.0	0.5 ~ 2.0	—
Feed (mm/revolution)	0.1 ~ 0.2	0.1 ~ 0.2	0.1 ~ 0.5

(Note) The above values are for reference only.

Examples of use and additional processing

Example of use




Handling of products not listed in this catalog

We are also dealing with heat insulator sheets of the following specifications upon request. Please feel free to consult us.

- ◆ Products other than the grades shown in this catalog that are manufactured by domestic and overseas brands
- ◆ Products of size not listed in this catalog
- ◆ Heat insulator sheets that have a thickness with a increased tolerance accuracy
- ◆ Additional machining with tools such as drills and end-mills


Example of additional machining



Heat Insulator Sheets Bakelite Paper

HIGH TEMPERATURE INSULATOR SHEETS

Catalog No.	Main material	Main base material
M-DNAP	Phenol resin	Craft paper



Dimension of T	3	5	10	15
Limit deviations of T	±0.20	±0.30	±0.45	±0.55

※ The catalog No. of former M-DNA has been changed to M-DNAP due to a specification change.

Features

This is a low-priced standard laminated sheet used as a heat insulator sheet for resin forming molds.

Heat-proof temperature (°C)	Specific gravity	Water absorption rate (%)	Izot impact strength (parallel to layer) J/cm	Compression strength MPa	Thermal conductivity W/(m·K)	Expansion coefficient 1/°C
130	1.3 ~ 1.4	0.2 ~ 0.8	0.29 ~ 0.39	245 ~ 300	0.25	4×10^{-5}

※ The above values are only an example and not a guarantee.

The products of sizes other than those shown in the right table and additional machining with tools such as drills and end mills are also available upon request. Please feel free to consult us.

The maximum production size is 2,000 mm × 1,200 mm. In addition to the thickness options listed in the right table, 4, 6, 8, 12, 20 and 25 mm are also available. The accuracy level of thickness tolerance can be further increased by special machining.

How to order

Catalog No.


M-DNAP

A × B × T

250 × 200 × 5



Shipped in 3 business day (excl. the day of order)





Price list

Catalog No.	T	A In 1mm steps	Unit price in yen B in 1mm steps											
			20~50	51~100	101~150	151~200	201~250	251~300	301~350	351~400	401~450	451~500	501~550	551~600
M-DNAP	3	20 ~ 50	120											
		51 ~ 100	230	250										
		101 ~ 150	250	270	570									
		151 ~ 200	320	360	720	750								
		201 ~ 250	400	500	870	920	1,310							
		251 ~ 300	450	590	1,040	1,090	1,550	1,870						
		301 ~ 350	500	680	1,190	1,250	1,780	2,160	2,180					
		351 ~ 400	560	760	1,340	1,410	2,030	2,460	2,480	2,850				
		401 ~ 450	620	850	1,490	1,580	2,270	2,750	2,760	3,060	3,200			
		451 ~ 500	680	930	1,650	1,760	2,510	3,040	3,070	3,380	3,530	3,850		
		501 ~ 550	760	1,050	1,880	2,010	2,880	3,490	3,510	4,060	4,450	4,640	4,820	
		551 ~ 600	820	1,140	2,030	2,160	3,110	3,690	3,780	4,400	4,830	5,040	5,220	7,560
		601 ~ 650	870	1,220	2,200	2,330	3,350	4,080	4,100	4,750	5,220	5,400	5,640	8,150
		651 ~ 700	930	1,310	2,350	2,430	3,600	4,390	4,430	5,080	5,580	5,850	6,030	8,740
		701 ~ 750	990	1,400	2,500	2,670	3,840	4,680	4,730	5,430	5,970	6,210	6,470	9,350
		751 ~ 800	1,040	1,480	2,660	2,700	4,050	4,980	5,020	5,770	6,350	6,570	6,750	9,900
	5	20 ~ 50	170											
		51 ~ 100	320	430										
		101 ~ 150	390	540	810									
		151 ~ 200	470	720	1,040	1,260								
		201 ~ 250	550	860	1,250	1,540	1,930							
		251 ~ 300	620	1,010	1,480	1,820	2,290	2,970						
		301 ~ 350	700	1,080	1,700	2,100	2,650	3,150	3,850					
		351 ~ 400	770	1,310	1,920	2,230	3,020	4,270	4,370	5,450				
		401 ~ 450	810	1,440	1,980	2,300	3,290	4,780	4,890	6,080	6,200			
		451 ~ 500	940	1,580	2,190	2,560	3,650	5,300	5,410	6,740	6,870	7,520		
		501 ~ 550	1,050	1,810	2,690	2,970	4,260	6,070	6,200	7,750	7,870	8,620	8,690	
		551 ~ 600	1,130	1,940	2,700	3,150	4,500	6,590	6,750	8,380	8,530	9,370	9,420	10,160
		601 ~ 650	1,210	2,100	3,140	3,920	4,960	7,100	7,270	8,730	9,190	10,120	10,170	10,940
		651 ~ 700	1,280	2,240	3,350	4,050	5,330	7,590	7,650	9,000	9,890	10,440	10,800	11,700
		701 ~ 750	1,360	2,390	3,590	4,480	5,680	8,010	8,310	9,810	10,560	10,800	11,650	12,550
		751 ~ 800	1,440	2,530	3,800	4,760	6,030	8,190	8,550	10,170	10,800	11,250	11,700	12,600
	10	20 ~ 50	310											
		51 ~ 100	580	810										
		101 ~ 150	720	1,080	1,950									
		151 ~ 200	860	1,350	2,480	2,970								
		201 ~ 250	1,010	1,620	2,970	3,600	4,500							
		251 ~ 300	1,150	1,890	3,550	4,400	5,420	6,950						
		301 ~ 350	1,260	1,980	4,090	5,080	6,260	8,040	8,200					
		351 ~ 400	1,350	2,210	4,620	5,750	7,110	9,140	9,320	12,510				
		401 ~ 450	1,440	2,340	5,150	6,430	7,960	10,230	10,450	14,020	14,040			
		451 ~ 500	1,620	2,700	5,690	7,110	8,800	11,330	11,570	15,540	15,570	16,350		
		501 ~ 550	1,940	3,380	6,490	7,560	8,910	12,980	13,260	16,650	17,810	18,770	18,880	
		551 ~ 600	2,080	3,650	7,020	7,920	9,810	13,500	14,380	19,280	19,330	20,380	20,500	21,830
		601 ~ 650	2,220	3,920	7,550	8,510	10,350	14,220	14,490	20,800	20,850	21,980	22,110	23,550
		651 ~ 700	2,370	4,190	7,880	8,910	10,980	14,400	15,210	21,600	21,960	22,590	23,130	24,210
		701 ~ 750	2,510	4,460	8,010	9,000	11,700	14,850	15,930	21,960	22,230	23,220	23,400	24,660
		751 ~ 800	2,660	4,730	8,100	9,900	12,600	15,750	16,650	22,230	22,470	23,580	23,850	25,200
	15	20 ~ 50	310											
		51 ~ 100	580	1,130										
		101 ~ 150	720	1,500	2,430									
		151 ~ 200	860	1,870	3,090	3,600								
		201 ~ 250	1,010	2,250	3,750	4,410	5,850							
		251 ~ 300	1,150	2,630	4,230	5,450	6,840	8,100						
		301 ~ 350	1,290	2,700	4,410	5,850	7,200	8,460	9,000					
		351 ~ 400	1,430	3,380	5,720	7,130	10,170	12,470	12,560	17,170				
		401 ~ 450	1,580	3,510	6,390	7,970	11,410	13,950	14,070	18,000	19,220			
		451 ~ 500	1,720	3,780	7,050	8,780	12,600	15,440	15,550	20,250	21,290	22,680		
		501 ~ 550	1,940	4,710	8,050	10,070	14,430	17,710	17,830	24,210	24,430	26,070	26,910	
		551 ~ 600	2,080	5,070	8,710	10,880	15,670	19,200	19,340	25,470	26,530	28,300	29,230	30,160
		601 ~ 650	2,220	5,430	9,370	11,730	16,860	20,680	20,860	26,100	28,610	30,530	31,550	32,560
		651 ~ 700	2,370	5,820	10,030	12,570	18,090	22,180	22,370	29,700	30,680	32,750	33,300	34,940
		701 ~ 750	2,510	6,180	10,680	13,420	19,290	23,710	23,900	32,400	32,800	33,570	34,290	35,730
		751 ~ 800	2,660	6,580	11,380	14,270	20,520	25,190	25,200	33,030	33,300	34,200	35,100	36,900

Heat Insulator Sheets Bakelite Cloth

HIGH TEMPERATURE INSULATOR SHEETS

Catalog No.	Main material	Main base material
M-DNAC	Phenol resin	Cotton cloth



Dimension of T	3	5	10	15
Limit deviations of T	±0.30	±0.40	±0.65	±0.80

Features

Use this grade when more mechanical strength than bakelite paper heat insulator sheet is required.

Heat-proof temperature (°C)	Specific gravity	Water absorption rate (%)	Izot impact strength (parallel to layer) J/cm	Compression strength MPa	Thermal conductivity W/(m·K)	Expansion coefficient 1/°C
130	1.3 ~ 1.4	0.7 ~ 1.3	0.6 ~ 1.1	255 ~ 323	0.33	2×10^{-5}

※ The above values are only an example and not a guarantee.

The products of sizes other than those shown in the right table and additional machining with tools such as drills and end mills are also available upon request. Please feel free to consult us.

The maximum production size is 2,000 mm × 1,000 mm. The accuracy level of thickness tolerance can be further increased by special machining.



How to order

Catalog No.

M-DNAC


A × B × T

250 × 250 × 5



Shipping

Shipped in 3 business day (excl. the day of order)




Price list

Catalog No.	T	A In 1 mm steps	Unit price in yen											
			B In 1 mm steps											
			20~50	51~100	101~150	151~200	201~250	251~300	301~350	351~400	401~450	451~500	501~550	551~600
M-DNAC	3	20 ~ 50	180											
		51 ~ 100	340	380										
		101 ~ 150	380	410	860									
		151 ~ 200	480	540	1,080	1,130								
		201 ~ 250	590	760	1,310	1,380	1,960							
		251 ~ 300	680	890	1,560	1,640	2,320	2,810						
		301 ~ 350	760	1,020	1,780	1,880	2,670	3,240	3,270					
		351 ~ 400	840	1,130	2,020	2,120	3,040	3,690	3,720	4,280				
		401 ~ 450	940	1,270	2,240	2,380	3,400	4,130	4,150	4,590	4,800			
		451 ~ 500	1,020	1,400	2,480	2,640	3,770	4,560	4,610	5,070	5,290	5,780		
		501 ~ 550	1,130	1,580	2,830	3,020	4,320	5,240	5,270	6,090	6,670	6,960	7,230	
		551 ~ 600	1,230	1,720	3,050	3,240	4,670	5,540	5,670	6,610	7,250	7,560	7,830	11,340
		601 ~ 650	1,310	1,840	3,290	3,500	5,020	6,120	6,160	7,130	7,830	8,100	8,470	12,220
		651 ~ 700	1,400	1,960	3,530	3,650	5,400	6,590	6,640	7,610	8,370	8,780	9,050	13,110
		701 ~ 750	1,490	2,100	3,750	4,010	5,770	7,020	7,090	8,150	8,960	9,320	9,710	14,030
		751 ~ 800	1,570	2,210	3,990	4,050	6,080	7,470	7,530	8,660	9,530	9,860	10,130	14,850
	5	20 ~ 50	260											
		51 ~ 100	480	650										
		101 ~ 150	590	810	1,220									
		151 ~ 200	700	1,080	1,560	1,890								
		201 ~ 250	830	1,300	1,880	2,310	2,890							
		251 ~ 300	940	1,510	2,210	2,730	3,430	4,460						
		301 ~ 350	1,050	1,620	2,560	3,150	3,970	4,730	5,780					
		351 ~ 400	1,160	1,960	2,880	3,350	4,530	6,400	6,550	8,170				
		401 ~ 450	1,220	2,160	2,970	3,460	4,930	7,170	7,340	9,120	9,310			
		451 ~ 500	1,400	2,380	3,290	3,830	5,470	7,960	8,120	10,120	10,310	11,280		
		501 ~ 550	1,580	2,720	4,040	4,460	6,390	9,100	9,310	11,630	11,800	12,930	13,030	
		551 ~ 600	1,690	2,920	4,050	4,730	6,750	9,880	10,130	12,570	12,800	14,060	14,140	15,250
		601 ~ 650	1,810	3,150	4,720	5,880	7,440	10,660	10,910	13,100	13,790	15,170	15,260	16,420
		651 ~ 700	1,920	3,370	5,020	6,080	7,990	11,390	11,480	13,500	14,840	15,660	16,200	17,550
		701 ~ 750	2,040	3,580	5,390	6,720	8,520	12,020	12,470	14,720	15,840	16,200	17,470	18,820
		751 ~ 800	2,160	3,800	5,700	7,150	9,050	12,290	12,830	15,260	16,200	16,880	17,550	18,900
	10	20 ~ 50	460											
		51 ~ 100	860	1,220										
		101 ~ 150	1,080	1,620	2,930									
		151 ~ 200	1,300	2,030	3,730	4,460								
		201 ~ 250	1,510	2,430	4,460	5,400	6,750							
		251 ~ 300	1,730	2,840	5,320	6,610	8,130	10,420						
		301 ~ 350	1,890	2,970	6,130	7,610	9,400	12,060	12,300					
		351 ~ 400	2,030	3,310	6,930	8,630	10,670	13,710	13,990	18,770				
		401 ~ 450	2,160	3,510	7,720	9,640	11,930	15,350	15,680	21,030	21,060			
		451 ~ 500	2,430	4,050	8,530	10,670	13,200	17,000	17,360	23,320	23,360	24,530		
		501 ~ 550	2,910	5,080	9,740	11,340	13,370	19,470	19,890	24,980	26,720	28,150	28,320	
		551 ~ 600	3,120	5,480	10,530	11,880	14,720	20,250	21,570	28,920	29,000	30,560	30,750	32,740
		601 ~ 650	3,340	5,890	11,330	12,760	15,530	21,330	21,740	31,200	31,280	32,970	33,170	35,330
		651 ~ 700	3,560	6,290	11,820	13,370	16,470	21,600	22,820	32,400	33,120	33,890	34,470	36,320
		701 ~ 750	3,770	6,700	12,020	13,500	17,550	22,280	23,900	32,940	33,350	34,830	35,100	36,990
		751 ~ 800	3,990	7,100	12,150	14,850	18,900	23,630	24,980	33,350	33,710	35,370	35,780	37,800
	15	20 ~ 50	460											
		51 ~ 100	860	1,690										
		101 ~ 150	1,080	2,260	3,650									
		151 ~ 200	1,300	2,810	4,640	5,400								
		201 ~ 250	1,510	3,380	5,630	6,620	8,780							
		251 ~ 300	1,730	3,940	6,350	8,170	10,260	12,150						
		301 ~ 350	1,940	4,050	6,620	8,780	10,800	12,690	13,500					
		351 ~ 400	2,150	5,080	8,590	10,690	15,260	18,700	18,840	25,760				
		401 ~ 450	2,370	5,270	9,590	11,960	17,120	20,930	21,110	27,000	28,840			
		451 ~ 500	2,580	5,670	10,580	13,180	18,900	23,160	23,330	30,380	31,940	34,020		
		501 ~ 550	2,910	7,070	12,070	15,110	21,650	26,570	26,750	36,320	36,640	39,110	40,370	
		551 ~ 600	3,120	7,610	13,070	16,330	23,510	28,800	29,020	38,210	39,800	42,440	43,850	45,240
		601 ~ 650	3,340	8,150	14,060	17,600	25,290	31,020	31,290	39,150	42,920	45,790	47,320	48,840
		651 ~ 700	3,560	8,740	15,040	18,860	27,140	33,260	33,560	44,550	46,030	49,130	49,950	52,410
		701 ~ 750	3,770	9,280	16,030	20,130	28,940	35,560	35,850	48,600	49,190	50,360	51,440	53,600
		751 ~ 800	3,990	9,870	17,060	21,400	30,780	37,790	37,800	49,550	49,950	51,300	52,650	55,350

Heat Insulator Sheets Basic Grade

HIGH TEMPERATURE INSULATOR SHEETS

Catalog No.	Main material	Main base material
M-DNBR	Borate type binder	Glass mat



※ The catalog No. of former M-DNB has been changed to M-DNBR due to a specification change.

Features

This is a heat resisting grade heat insulator sheet for resin forming molds, which provides both benefits of heat proof property and cost economy.

Heat-proof temperature (°C)	Specific gravity	Water absorption rate (%)	Izot impact strength (parallel to layer) J/cm	Compression strength MPa	Thermal conductivity W/(m·K)	Expansion coefficient 1/°C
250	2.0 ~ 2.2	2 ~ 5	1.5	150 ~ 200	0.3	6.6×10^{-6}

※ The above values are only an example and not a guarantee.

The products of sizes other than those shown in the right table and additional machining with tools such as drills and end mills are also available upon request. Please feel free to consult us.

The maximum production size is 1,000 mm × 1,000 mm. In addition to the thickness options listed in the right table, 1, 2, 6, 8, 20, 25, 30 and 35*1 mm are also available. The accuracy level of thickness tolerance can be further increased by special machining.

*1. The maximum production size is 900 mm × 900 mm.



How to order

Catalog No.

A × B × T


M-DNBR

280 × 230 × 5



Shipping

Shipped in 3 business day (excl. the day of order)




Price list

Catalog No.	T	A In 1 mm steps	Unit price in yen												
			B in 1 mm steps												
			20~50	51~100	101~150	151~200	201~250	251~300	301~350	351~400	401~450	451~500	501~550	551~600	
M-DNBR	3	20 ~ 50	350												
		51 ~ 100	650	990											
		101 ~ 150	820	1,310	1,800										
		151 ~ 200	990	1,640	2,290	2,950									
		201 ~ 250	1,140	1,960	2,780	3,600	4,420								
		251 ~ 300	1,310	2,290	3,270	4,260	5,240	6,220							
		301 ~ 350	1,470	2,620	3,770	4,910	6,050	7,200	8,350						
		351 ~ 400	1,640	2,950	4,260	5,560	6,870	8,180	9,500	10,820					
		401 ~ 450	1,800	3,270	4,740	6,220	7,690	9,150	10,650	12,140	13,550				
		451 ~ 500	1,960	3,600	5,240	6,870	8,510	10,120	11,790	13,460	15,050	16,720			
		501 ~ 550	2,210	4,090	5,980	7,860	9,770	11,620	13,460	15,400	17,250	19,180	21,030		
		551 ~ 600	2,380	4,420	6,470	8,510	10,560	12,580	14,610	16,720	18,740	20,770	22,790	24,900	
		601 ~ 650	2,530	4,740	6,960	9,150	11,350	13,550	15,750	18,040	20,240	22,440	24,640	26,840	
		651 ~ 700	2,700	5,080	7,440	9,860	12,230	14,610	16,980	19,270	21,650	24,020	26,400	28,780	
		701 ~ 750	2,870	5,400	7,940	10,470	13,020	15,580	18,130	20,590	23,140	25,700	28,250	30,800	
		751 ~ 800	3,030	5,730	8,430	11,090	13,820	16,540	19,270	21,910	24,640	27,370	30,010	32,740	
	5	20 ~ 50	470												
		51 ~ 100	870	1,300											
		101 ~ 150	1,080	1,730	2,380										
		151 ~ 200	1,300	2,160	3,040	3,910									
		201 ~ 250	1,520	2,600	3,690	4,770	5,850								
		251 ~ 300	1,730	3,040	4,340	5,640	6,940	8,250							
		301 ~ 350	1,950	3,470	4,990	6,500	8,030	9,500	11,090						
		351 ~ 400	2,160	3,910	5,640	7,370	9,150	10,820	12,580	14,340					
		401 ~ 450	2,380	4,340	6,290	8,250	10,210	12,140	14,080	16,020	18,040				
		451 ~ 500	2,600	4,770	6,940	9,150	11,260	13,460	15,580	17,780	19,980	22,090			
		501 ~ 550	2,930	5,420	7,920	10,380	12,940	15,400	17,860	20,420	22,880	25,340	27,900		
		551 ~ 600	3,140	5,850	8,560	11,260	13,990	16,720	19,450	22,090	24,820	27,540	30,270	33,000	
		601 ~ 650	3,360	6,290	9,240	12,140	15,050	18,040	20,940	23,850	26,750	29,740	32,650	35,550	
		651 ~ 700	3,580	6,720	9,860	13,020	16,190	19,270	22,440	25,610	28,780	31,860	35,020	38,190	
		701 ~ 750	3,790	7,150	10,560	13,900	17,250	20,590	23,940	27,370	30,710	34,060	37,400	40,740	
		751 ~ 800	4,010	7,590	11,180	14,780	18,300	21,910	25,520	29,040	32,650	36,260	39,780	43,380	
	10	20 ~ 50	750												
		51 ~ 100	1,410	2,110											
		101 ~ 150	1,760	2,820	3,860										
		151 ~ 200	2,110	3,520	4,920	6,330									
		201 ~ 250	2,460	4,220	5,980	7,740	9,500								
		251 ~ 300	2,820	4,920	7,030	9,150	11,260	13,380							
		301 ~ 350	3,170	5,620	8,090	10,560	13,020	15,490	17,950						
		351 ~ 400	3,520	6,330	9,150	11,970	14,780	17,600	20,420	23,230					
		401 ~ 450	3,860	7,030	10,210	13,380	16,540	19,710	22,880	26,050	29,220				
		451 ~ 500	4,220	7,740	11,260	14,780	18,300	21,820	25,340	28,860	32,380	35,820			
		501 ~ 550	4,740	8,790	12,850	16,900	20,940	24,990	29,040	33,090	37,050	41,100	45,140		
		551 ~ 600	5,100	9,500	13,900	18,300	22,700	27,100	31,500	35,820	40,220	44,620	49,020	53,420	
		601 ~ 650	5,450	10,210	14,960	19,710	24,460	29,220	33,970	38,630	43,380	48,140	52,890	57,640	
		651 ~ 700	5,800	10,910	16,020	21,120	26,220	31,330	36,340	41,450	46,550	51,660	56,760	61,860	
		701 ~ 750	6,150	11,620	17,070	22,530	27,980	33,440	38,810	44,260	49,720	55,180	60,630	66,090	
		751 ~ 800	6,500	12,320	18,130	23,940	29,740	35,460	41,270	47,080	52,890	58,700	64,500	70,310	
	15	20 ~ 50	1,060												
		51 ~ 100	2,010	3,010											
		101 ~ 150	2,510	4,010	5,520										
		151 ~ 200	3,010	5,020	7,020	9,060									
		201 ~ 250	3,510	6,020	8,530	11,000	13,550								
		251 ~ 300	4,010	7,020	10,030	13,020	16,020	19,100							
		301 ~ 350	4,510	8,030	11,530	15,050	18,570	22,090	25,610						
		351 ~ 400	5,020	9,060	13,020	17,070	21,030	25,080	29,130	33,090					
		401 ~ 450	5,520	10,030	14,520	19,100	23,580	28,070	32,650	37,140	41,620				
		451 ~ 500	6,020	11,000	16,020	21,030	26,050	31,060	36,080	41,100	46,110	51,130			
		501 ~ 550	6,780	12,580	18,300	24,110	29,830	35,640	41,360	47,170	52,890	58,700	64,420		
		551 ~ 600	7,280	13,550	19,800	26,050	32,380	38,630	44,880	51,130	57,460	63,710	69,960	76,210	
		601 ~ 650	7,780	14,520	21,300	28,070	34,850	41,620	48,400	55,180	61,950	68,730	75,500	82,280	
		651 ~ 700	8,280	15,580	22,790	30,100	37,400	44,620	51,920	59,220	66,440	73,740	81,050	88,260	
		701 ~ 750	8,780	16,540	24,290	32,120	39,860	47,700	55,440	63,180	71,020	78,760	86,500	94,340	
		751 ~ 800	9,240	17,600	25,870	34,140	42,420	50,690	58,960	67,230	75,500	83,780	92,050	100,320	

Heat Insulator Sheets Heat Resisting Grade

HIGH TEMPERATURE INSULATOR SHEETS

Catalog No.	Main material	Main base material
M-DNHR	Phosphate type binder	Glass mat



Features

This is a heat resisting grade heat insulator sheet that can be used for the high-temperature side surface panels of IC plastic molds, etc.

Heat-proof temperature (°C)	Specific gravity	Water absorption rate (%)	Izot impact strength (parallel to layer) J/cm	Compression strength MPa	Thermal conductivity W/(m·K)	Expansion coefficient 1/°C
500	2.0 ~ 2.2	4 ~ 6	1.1	120 ~ 150	0.3	9.0×10^{-6}

※ The above values are only an example and not a guarantee.

The products of sizes other than those shown in the right table and additional machining with tools such as drills and end mills are also available upon request. Please feel free to contact us.

The maximum production size is 1,000mm × 1,000 mm. In addition to the thickness options listed in the right table, 6, 8, 12, 20, 25 and 30 mm are also available. The accuracy level of thickness tolerance can be further increased by special machining.



How to order

Catalog No.

A × B × T


M-DNHR

350 × 300 × 10



Shipping

Shipped in 3 business day (excl. the day of order)





Price list

Catalog No.	T	A In 1 mm steps	Unit price in yen B In 1 mm steps											
			20~50	51~100	101~150	151~200	201~250	251~300	301~350	351~400	401~450	451~500	501~550	551~600
M-DNHR	3	20 ~ 50	280											
		51 ~ 100	520	790										
		101 ~ 150	650	1,050	1,440									
		151 ~ 200	790	1,310	1,830	2,360								
		201 ~ 250	920	1,570	2,230	2,880	3,540							
		251 ~ 300	1,050	1,830	2,620	3,410	4,190	4,980						
		301 ~ 350	1,180	2,090	3,010	3,920	4,840	5,760	6,680					
		351 ~ 400	1,310	2,360	3,410	4,450	5,500	6,550	7,600	8,660				
		401 ~ 450	1,440	2,620	3,790	4,980	6,150	7,320	8,520	9,720	10,840			
		451 ~ 500	1,570	2,880	4,190	5,500	6,810	8,100	9,430	10,770	12,040	13,380		
		501 ~ 550	1,770	3,270	4,780	6,280	7,810	9,290	10,770	12,320	13,800	15,350	16,830	
		551 ~ 600	1,900	3,540	5,170	6,810	8,450	10,070	11,690	13,380	15,000	16,610	18,230	19,920
		601 ~ 650	2,020	3,790	5,570	7,320	9,080	10,840	12,600	14,430	16,190	17,950	19,710	21,470
		651 ~ 700	2,160	4,070	5,960	7,880	9,790	11,690	13,590	15,420	17,320	19,220	21,120	23,020
		701 ~ 750	2,300	4,320	6,350	8,380	10,420	12,460	14,500	16,470	18,520	20,560	22,600	24,640
		751 ~ 800	2,420	4,580	6,740	8,870	11,050	13,240	15,420	17,530	19,710	21,890	24,010	26,190
	5	20 ~ 50	370											
		51 ~ 100	700	1,040										
		101 ~ 150	860	1,390	1,910									
		151 ~ 200	1,040	1,730	2,430	3,120								
		201 ~ 250	1,210	2,090	2,950	3,820	4,680							
		251 ~ 300	1,390	2,430	3,470	4,510	5,550	6,600						
		301 ~ 350	1,570	2,770	4,000	5,200	6,420	7,600	8,870					
		351 ~ 400	1,730	3,120	4,510	5,900	7,320	8,660	10,070	11,480				
		401 ~ 450	1,910	3,470	5,030	6,600	8,170	9,720	11,260	12,810	14,430			
		451 ~ 500	2,090	3,820	5,550	7,320	9,010	10,770	12,460	14,220	15,980	17,670		
		501 ~ 550	2,340	4,340	6,340	8,310	10,350	12,320	14,290	16,330	18,300	20,280	22,320	
		551 ~ 600	2,520	4,680	6,850	9,010	11,190	13,380	15,560	17,670	19,850	22,040	24,220	26,400
		601 ~ 650	2,690	5,030	7,390	9,720	12,040	14,430	16,760	19,080	21,400	23,800	26,120	28,440
		651 ~ 700	2,870	5,380	7,880	10,420	12,950	15,420	17,950	20,490	23,020	25,480	28,020	30,550
		701 ~ 750	3,040	5,720	8,450	11,120	13,800	16,470	19,150	21,890	24,570	27,240	29,920	32,600
		751 ~ 800	3,210	6,070	8,940	11,830	14,640	17,530	20,420	23,230	26,120	29,000	31,820	34,710
	10	20 ~ 50	600											
		51 ~ 100	1,130	1,690										
		101 ~ 150	1,410	2,250	3,090									
		151 ~ 200	1,690	2,820	3,930	5,060								
		201 ~ 250	1,970	3,370	4,780	6,190	7,600							
		251 ~ 300	2,250	3,930	5,620	7,320	9,010	10,700						
		301 ~ 350	2,530	4,500	6,470	8,450	10,420	12,390	14,360					
		351 ~ 400	2,820	5,060	7,320	9,570	11,830	14,080	16,330	18,590				
		401 ~ 450	3,090	5,620	8,170	10,700	13,240	15,770	18,300	20,840	23,370			
		451 ~ 500	3,370	6,190	9,010	11,830	14,640	17,460	20,280	23,090	25,910	28,650		
		501 ~ 550	3,790	7,030	10,280	13,520	16,760	19,990	23,230	26,470	29,640	32,880	36,120	
		551 ~ 600	4,070	7,600	11,120	14,640	18,160	21,680	25,200	28,650	32,170	35,690	39,210	42,730
		601 ~ 650	4,360	8,170	11,970	15,770	19,570	23,370	27,170	30,910	34,710	38,510	42,310	46,110
		651 ~ 700	4,640	8,730	12,810	16,900	20,980	25,060	29,080	33,160	37,240	41,320	45,410	49,490
		701 ~ 750	4,920	9,290	13,660	18,020	22,390	26,750	31,050	35,410	39,780	44,140	48,510	52,870
		751 ~ 800	5,200	9,860	14,500	19,150	23,800	28,370	33,020	37,660	42,310	46,960	51,600	56,250
	15	20 ~ 50	840											
		51 ~ 100	1,600	2,410										
		101 ~ 150	2,010	3,210	4,420									
		151 ~ 200	2,410	4,010	5,610	7,250								
		201 ~ 250	2,810	4,810	6,820	8,800	10,840							
		251 ~ 300	3,210	5,610	8,030	10,420	12,810	15,280						
		301 ~ 350	3,610	6,420	9,220	12,040	14,850	17,670	20,490					
		351 ~ 400	4,010	7,250	10,420	13,660	16,830	20,060	23,300	26,470				
		401 ~ 450	4,420	8,030	11,620	15,280	18,870	22,460	26,120	29,710	33,300			
		451 ~ 500	4,810	8,800	12,810	16,830	20,840	24,850	28,860	32,880	36,890	40,900		
		501 ~ 550	5,420	10,070	14,640	19,290	23,870	28,510	33,090	37,730	42,310	46,960	51,530	
		551 ~ 600	5,830	10,840	15,840	20,840	25,910	30,910	35,900	40,900	45,970	50,970	55,970	60,970
		601 ~ 650	6,220	11,620	17,040	22,460	27,880	33,300	38,720	44,140	49,560	54,980	60,400	65,820
		651 ~ 700	6,630	12,460	18,230	24,080	29,920	35,690	41,540	47,380	53,150	59,000	64,840	70,610
		701 ~ 750	7,020	13,240	19,430	25,700	31,890	38,160	44,350	50,550	56,810	63,010	69,200	75,470
		751 ~ 800	7,390	14,080	20,700	27,320	33,930	40,550	47,170	53,790	60,400	67,020	73,640	80,260

Heat Insulator Sheets High Strength Grade

HIGH TEMPERATURE INSULATOR SHEETS

Catalog No.	Main material	Main base material
M-DNSR	Super heat proof epoxy resin	Glass cloth



Features

This grade has an enhanced mechanical strength and thus more resistance to the deformation due to the clamping force during molding.

Heat-proof temperature (°C)	Specific gravity	Water absorption rate (%)	Izot impact strength (parallel to layer) J/cm	Compression strength MPa	Thermal conductivity W/(m·K)	Expansion coefficient 1/°C
200	1.8 ~ 1.9	0.05	4.5	500 ~ 580	0.3	6.5×10^{-5}

※ The above values are only an example and not a guarantee.

The products of sizes other than those shown in the right table and additional machining with tools such as drills and end mills are also available upon request. Please feel free to consult us.

The maximum production size is 2,000 mm × 1,000 mm. In addition to the thickness options listed in the right table, 20 mm is also available. The accuracy level of thickness tolerance can be further increased by special machining.

* 1. The maximum production size for thickness 15 and 20 mm is 1,000 mm × 1,000 mm.

How to order

Catalog No.


A × B × T

M-DNSR

400 × 300 × 10

Shipping

Shipped in 3 business day (excl. the day of order)




Price list

Catalog No.	T	A In 1 mm steps	Unit price in yen													
			B In 1 mm steps													
			20~50	51~100	101~150	151~200	201~250	251~300	301~350	351~400	401~450	451~500	501~550	551~600		
M-DNSR	3	20 ~ 50	630													
		51 ~ 100	1,170	1,780												
		101 ~ 150	1,470	2,360	3,250											
		151 ~ 200	1,780	2,950	4,120	5,310										
		201 ~ 250	2,060	3,530	5,010	6,480	7,960									
		251 ~ 300	2,360	4,120	5,900	7,660	9,420	11,200								
		301 ~ 350	2,650	4,720	6,780	8,840	10,890	12,950	15,030							
		351 ~ 400	2,950	5,310	7,660	10,010	12,370	14,730	17,110	19,480						
		401 ~ 450	3,250	5,900	8,540	11,200	13,840	16,470	19,170	21,860	24,390					
		451 ~ 500	3,530	6,480	9,420	12,370	15,320	18,220	21,230	24,240	27,090	30,100				
		501 ~ 550	3,980	7,370	10,750	14,140	17,580	20,910	24,240	27,720	31,050	34,530	37,860			
		551 ~ 600	4,280	7,960	11,640	15,320	19,010	22,650	26,290	30,100	33,740	37,380	41,030	44,830		
		601 ~ 650	4,560	8,540	12,530	16,470	20,430	24,390	28,350	32,470	36,430	40,390	44,350	48,310		
		651 ~ 700	4,870	9,140	13,400	17,740	22,020	26,290	30,570	34,690	38,970	43,240	47,520	51,800		
		701 ~ 750	5,170	9,720	14,290	18,850	23,440	28,040	32,630	37,070	41,660	46,250	50,850	55,440		
		751 ~ 800	5,450	10,310	15,170	19,960	24,870	29,780	34,690	39,440	44,350	49,260	54,010	58,920		
	5	20 ~ 50	840													
		51 ~ 100	1,570	2,340												
		101 ~ 150	1,940	3,120	4,290											
		151 ~ 200	2,340	3,900	5,460	7,030										
		201 ~ 250	2,740	4,690	6,640	8,590	10,530									
		251 ~ 300	3,120	5,460	7,810	10,160	12,500	14,850								
		301 ~ 350	3,520	6,240	8,980	11,700	14,450	17,110	19,960							
		351 ~ 400	3,900	7,030	10,160	13,270	16,470	19,480	22,650	25,820						
		401 ~ 450	4,290	7,810	11,330	14,850	18,370	21,860	25,340	28,830	32,470					
		451 ~ 500	4,690	8,590	12,500	16,470	20,280	24,240	28,040	32,000	35,960	39,760				
		501 ~ 550	5,270	9,760	14,260	18,690	23,280	27,720	32,160	36,750	41,180	45,620	50,210			
		551 ~ 600	5,660	10,530	15,410	20,280	25,190	30,100	35,010	39,760	44,670	49,580	54,490	59,400		
		601 ~ 650	6,050	11,330	16,630	21,860	27,090	32,470	37,700	42,930	48,150	53,540	58,770	63,990		
		651 ~ 700	6,450	12,100	17,740	23,440	29,150	34,690	40,390	46,090	51,800	57,340	63,040	68,750		
		701 ~ 750	6,830	12,870	19,010	25,030	31,050	37,070	43,080	49,260	55,280	61,300	67,320	73,340		
		751 ~ 800	7,220	13,670	20,120	26,610	32,950	39,440	45,940	52,270	58,770	65,260	71,600	78,090		
	10	20 ~ 50	1,350													
		51 ~ 100	2,530	3,800												
		101 ~ 150	3,170	5,070	6,950											
		151 ~ 200	3,800	6,340	8,850	11,390										
		201 ~ 250	4,440	7,590	10,750	13,920	17,110									
		251 ~ 300	5,070	8,850	12,650	16,470	20,280	24,080								
		301 ~ 350	5,700	10,120	14,560	19,010	23,440	27,880	32,310							
		351 ~ 400	6,340	11,390	16,470	21,540	26,610	31,680	36,750	41,820						
		401 ~ 450	6,950	12,650	18,370	24,080	29,780	35,480	41,180	46,890	52,590					
		451 ~ 500	7,590	13,920	20,280	26,610	32,950	39,280	45,620	51,960	58,290	64,470				
		501 ~ 550	8,540	15,820	23,130	30,410	37,700	44,990	52,270	59,560	66,690	73,970	81,260			
		551 ~ 600	9,170	17,110	25,030	32,950	40,870	48,790	56,710	64,470	72,390	80,310	88,230	96,150		
		601 ~ 650	9,800	18,370	26,930	35,480	44,040	52,590	61,140	69,540	78,090	86,640	95,200	103,750		
		651 ~ 700	10,440	19,640	28,830	38,020	47,200	56,390	65,420	74,610	83,790	92,980	102,170	111,360		
		701 ~ 750	11,070	20,910	30,730	40,550	50,370	60,190	69,850	79,680	89,500	99,320	109,140	118,960		
		751 ~ 800	11,700	22,180	32,630	43,080	53,540	63,840	74,290	84,740	95,200	105,650	116,110	126,560		
	15	20 ~ 50	1,900													
		51 ~ 100	3,610	5,420												
		101 ~ 150	4,510	7,220	9,940											
		151 ~ 200	5,420	9,030	12,640	16,320										
		201 ~ 250	6,320	10,830	15,350	19,800	24,390									
		251 ~ 300	7,220	12,640	18,060	23,440	28,830	34,370								
		301 ~ 350	8,120	14,450	20,750	27,090	33,420	39,760	46,090							
		351 ~ 400	9,030	16,320	23,440	30,730	37,860	45,140	52,430	59,560						
		401 ~ 450	9,940	18,060	26,140	34,370	42,450	50,530	58,770	66,840	74,920					
		451 ~ 500	10,830	19,800	28,830	37,860	46,890	55,920	64,940	73,970	83,000	92,030				
		501 ~ 550	12,200	22,650	32,950	43,400	53,700	64,150	74,450	84,900	95,200	105,650	115,950			
		551 ~ 600	13,100	24,390	35,640	46,890	58,290	69,540	80,780	92,030	103,440	114,680	125,930	137,170		
		601 ~ 650	14,000	26,140	38,330	50,530	62,730	74,920	87,120	99,320	111,510	123,710	135,910	148,100		
		651 ~ 700	14,910	28,040	41,030	54,170	67,320	80,310	93,460	106,600	119,590	132,740	145,890	158,880		
		701 ~ 750	15,800	29,780	43,720	57,820	71,760	85,850	99,790	113,730	127,830	141,770	155,710	169,800		
		751 ~ 800	16,630	31,680	46,570	61,460	76,350	91,240	106,130	121,020	135,910	150,800	165,690	180,580		

Heat Insulator Sheets High Temperature Resisting Grade

HIGH TEMPERATURE INSULATOR SHEETS

Catalog No.	Main material	Main base material
M-DNLR	Silicic acid base binder	Glass cloth



Features

This is a reliable grade that has the highest heat proof property, mechanical strength and dimensional stability among the series.

Heat-proof temperature (°C)	Specific gravity	Water absorption rate (%)	Izot impact strength (parallel to layer) J/cm	Compression strength MPa	Thermal conductivity W/(m·K)	Expansion coefficient 1/°C
400	2.0 ~ 2.1	0.1	2.5	420 ~ 480	0.3	2.3×10^{-5}

※ The above values are only an example and not a guarantee.

The products of sizes other than those shown in the right table and additional machining with tools such as drills and end mills are also available upon request. Please feel free to consult us.
The maximum production size is 1,000 mm × 1,000 mm.
The accuracy level of thickness tolerance can be further increased by special machining.

How to order

Catalog No.


M-DNLR

A × B × T

230 × 200 × 5



Shipped in 3 business day (excl. the day of order)




Price list

Catalog No.	T	A In 1mm steps	Unit price in yen												
			B In 1mm steps												
			20~50	51~100	101~150	151~200	201~250	251~300	301~350	351~400	401~450	451~500	501~550	551~600	
M-DNLR	3	20 ~ 50	840												
		51 ~ 100	1,570	2,370											
		101 ~ 150	1,960	3,150	4,330										
		151 ~ 200	2,370	3,920	5,490	7,080									
		201 ~ 250	2,750	4,710	6,670	8,640	10,600								
		251 ~ 300	3,150	5,490	7,860	10,230	12,570	14,930							
		301 ~ 350	3,530	5,530	8,280	11,780	14,530	17,270	20,050						
		351 ~ 400	3,920	5,800	10,230	13,350	16,490	19,640	22,810	25,980					
		401 ~ 450	4,330	6,060	11,040	14,930	18,460	21,960	25,560	29,150	32,520				
		451 ~ 500	4,710	6,890	12,570	16,490	20,420	24,290	28,300	32,310	36,120	40,130			
		501 ~ 550	5,300	9,820	14,340	18,860	23,440	27,880	32,310	36,960	41,400	46,040	50,480		
		551 ~ 600	5,700	10,600	15,520	20,420	25,340	30,200	35,060	40,130	44,990	49,840	54,700	59,770	
		601 ~ 650	6,080	11,390	16,700	21,960	27,240	32,520	37,800	43,300	48,580	53,860	59,140	64,420	
		651 ~ 700	6,490	12,190	17,860	23,650	29,360	35,060	40,760	46,250	51,960	57,660	63,360	69,060	
		701 ~ 750	6,880	12,970	19,050	25,130	31,260	37,380	43,510	49,420	55,550	61,670	67,800	73,920	
		751 ~ 800	7,270	13,750	20,230	26,610	33,160	39,710	46,250	52,590	59,140	65,680	72,020	78,570	
	5	20 ~ 50	1,120												
		51 ~ 100	2,090	3,120											
		101 ~ 150	2,600	4,160	5,720										
		151 ~ 200	3,120	5,190	7,290	9,380									
		201 ~ 250	3,650	6,250	8,850	11,450	14,040								
		251 ~ 300	4,160	6,910	10,410	13,530	16,670	19,790							
		301 ~ 350	4,690	7,170	11,980	15,610	19,260	22,810	26,610						
		351 ~ 400	5,190	7,840	13,530	17,700	21,960	25,980	30,200	34,430					
		401 ~ 450	5,720	8,280	15,100	19,790	24,500	29,150	33,790	38,440	43,300				
		451 ~ 500	6,250	9,640	16,670	21,960	27,030	32,310	37,380	42,660	47,940	53,010			
		501 ~ 550	7,030	13,010	19,010	24,920	31,050	36,960	42,870	49,000	54,910	60,830	66,950		
		551 ~ 600	7,540	14,040	20,550	27,030	33,580	40,130	46,680	53,010	59,560	66,110	72,650	79,200	
		601 ~ 650	8,070	15,100	22,180	29,150	36,120	43,300	50,270	57,240	64,200	71,390	78,360	85,320	
		651 ~ 700	8,600	16,140	23,650	31,260	38,860	46,250	53,860	61,460	69,060	76,450	84,060	91,660	
		701 ~ 750	9,100	17,170	25,340	33,370	41,400	49,420	57,450	65,680	73,710	81,730	89,760	97,790	
		751 ~ 800	9,630	18,220	26,820	35,480	43,930	52,590	61,250	69,700	78,360	87,010	95,460	104,120	
	10	20 ~ 50	1,800												
		51 ~ 100	3,380	5,070											
		101 ~ 150	4,220	6,760	9,280										
		151 ~ 200	5,070	7,440	11,040	15,190									
		201 ~ 250	5,910	9,640	13,790	18,570	22,810								
		251 ~ 300	6,760	10,510	15,680	21,960	27,030	32,100							
		301 ~ 350	7,440	11,040	16,560	24,820	31,260	37,170	43,080						
		351 ~ 400	7,840	11,800	19,360	28,720	35,480	42,240	49,000	55,760					
		401 ~ 450	8,280	12,420	20,680	31,770	39,710	47,310	54,910	62,520	70,120				
		451 ~ 500	9,640	13,790	24,820	35,480	43,930	52,380	60,830	69,270	77,720	85,960			
		501 ~ 550	11,390	21,100	30,840	40,550	50,270	59,980	69,700	79,410	88,920	98,630	108,350		
		551 ~ 600	12,230	22,810	33,370	43,930	54,490	65,050	75,610	85,960	96,520	107,080	117,640	128,200	
		601 ~ 650	13,080	24,500	35,900	47,310	58,710	70,120	81,520	92,720	104,120	115,530	126,930	138,340	
		651 ~ 700	13,920	26,190	38,440	50,690	62,940	75,190	87,230	99,480	111,720	123,970	136,220	148,470	
		701 ~ 750	14,770	27,880	40,970	54,070	67,160	80,260	93,140	106,230	119,330	132,420	145,520	158,610	
		751 ~ 800	15,610	29,570	43,510	57,450	71,390	85,110	99,050	112,990	126,930	140,870	154,810	168,750	
	15	20 ~ 50	3,190												
		51 ~ 100	5,760	8,710											
		101 ~ 150	7,370	11,670	15,950										
		151 ~ 200	8,710	12,870	18,970	26,000									
		201 ~ 250	10,260	16,420	23,590	31,770	39,000								
		251 ~ 300	11,670	18,030	26,670	37,400	46,110	54,680							
		301 ~ 350	12,870	19,030	28,280	42,490	53,350	63,400	73,450						
		351 ~ 400	13,680	20,370	33,110	49,060	60,450	72,110	83,500	95,030					
		401 ~ 450	14,340	21,310	35,380	54,290	67,820	80,560	93,420	106,420	119,420				
		451 ~ 500	16,490	23,460	42,490	60,450	74,790	89,130	95,430	117,810	132,150	146,360			
		501 ~ 550	19,440	36,050	52,680	69,160	85,780	102,130	118,750	135,240	151,320	167,800	184,420		
		551 ~ 600	21,050	39,000	56,830	74,790	92,750	110,840	128,810	146,360	164,310	182,140	200,100	218,060	
		601 ~ 650	22,390	41,820	61,120	80,560	100,120	119,420	138,860	157,750	177,050	196,490	216,050	235,490	
		651 ~ 700	23,720	44,770	65,410	86,450	107,090	127,860	148,370	169,410	190,050	211,090	231,730	252,510	
		701 ~ 750	25,340	47,710	69,830	92,070	114,460	136,580	158,420	180,800	202,650	225,430	247,540	269,790	
		751 ~ 800	26,670	50,400	74,120	97,840	121,560	145,020	168,610	192,330	216,050	239,910	263,230	287,080	

Product Data / Technical Data

- Mold Base Structure and Component Name 424
- Precision of Mold Base Plates 436
- Hole Dimensions of Parts Installed in Mold Bases 437
- Threaded Holes for Eye Bolts on Mold Bases..... 438
- Length of Guide Pins for Mold Bases 439
- Specification of Pipe Threads..... 440
- Hexagon Socket Head Cap Screws 442
- Calculation of Gravity Center of a Mold Base 443
- Calculation of the Deflection of Cavity Plate (Moving Half) 444
- Calculation of the Deflection of Support Pin..... 445
- Mold Steel Brands Comparison Table..... 446
- Material Property Data List..... 448
- Frequently Used Limit Deviations for Fits (Holes)..... 450
- Frequently Used Limit Deviations for Fits (Shaft)..... 452
- Hardness Conversion Table..... 454
- SI Unit Conversion Table/Weight and Measure Conversion Table..... 455

Mold Base Structure and Component Name S Series



This diagram shows **SB** type as a representative example.


The following mold base specifications are not shown in the Bluebook Plastic Mold Component Vol 1, but can be made to order in the same way as standard products. Please advise us on your specification requirements as follows:

Type name	Specification	Order example
SE type Option #S	A specification option defined by eliminating the stripper plate from SE type	MDC SE 2025 40 30 50 S V - N / #S*1
SF type Option #S	A specification option defined by eliminating the stripper plate from SF type	MDC SF 2025 40 60 50 S - - N / #S*1

*1. When specifying these specifications, please add **#S** to the respective order codes of SE and SF types.


SA Type

Ejector pin ejection type




SB Type

Stripper plate ejection type




SC Type

Ejector pin ejection type without backing plate




SD Type

Stripper plate ejection type without backing plate




SE Type

Stripper plate ejection type, which is actuated by mold opening behavior




SE Type Option #S

An option defined by eliminating stripper plate from SE type




SF Type

Stripper plate ejection type, which is actuated by mold opening behaviour, without backing plate




SF Type Option #S

An option defined by eliminating stripper plate from SF type



Mold Base Structure and Component Name D Series



This diagram shows **DB** type as a representative example.


The following mold base specifications are not shown in the Bluebook Plastic Mold Component Vol 1, but can be made to order in the same way as standard products. Please advise us on your specification requirements as follows:

Type name	Specification	Order example
DE type Option #S	A specification option defined by eliminating the stripper plate from DE type	MDC DE 2025 40 30 50 S V - N OH 180 / #S *1
DF type Option #S	A specification option defined by eliminating the stripper plate from DF type	MDC DF 2025 40 60 50 S - - N OH 180 / #S *1

*1. When specifying these specifications, please add #S to the respective order codes of DE and DF types.


DA Type

Ejector pin ejection type




DB Type

Stripper plate ejection type




DC Type

Ejector pin ejection type without Backing plate




DD Type

Stripper plate ejection type without Backing plate




DE Type

Stripper plate ejection type, which is actuated by mold opening behavior




DE Type Option #S

An option defined by eliminating stripper plate from DE type




DF Type

Stripper plate ejection type, which is actuated by mold opening behaviour, without Backing plate




DF Type Option #S

An option defined by eliminating stripper plate from DF type



Mold Base Structure and Component Name E Series



This diagram shows **EB** type as a representative example.

The following mold base specifications are not shown in the Bluebook Plastic Mold Component Vol 1, but can be made to order in the same way as standard products. Please advise us on your specification requirements as follows:


Type name	Specification	Order example
EE type	A specification defined by eliminating the runner stripper plate from DE type	MDC EE 2025 40 30 50 S V - N OH 180 ^{*1}
EF type	A specification defined by eliminating the runner stripper plate from DF type	MDC EF 2025 40 60 50 S - - N OH 180 ^{*1}
EE type Option #S	A specification option defined by eliminating the stripper plate from EE type	MDC EE 2025 40 30 50 S V - N OH 160 / #S ^{*2}
EF type Option #S	A specification option defined by eliminating the stripper plate from EF type	MDC EF 2025 40 60 50 S - - N OH 160 / #S ^{*2}

*1. The type names of these specifications change to **EE** and **EF** types respectively.

*2. When specifying these specifications, please add **#S** to the respective order codes of EE and EF types.


EA Type

Ejector pin ejection type




EB Type

Stripper plate ejection type




EC Type

Ejector pin ejection type without Backing plate




ED Type

Stripper plate ejection type without Backing plate




EE Type

Stripper plate ejection type, which is actuated by mold opening behavior




EE Type Option #S

An option defined by eliminating stripper plate from EE type




EF Type

Stripper plate ejection type, which is actuated by mold opening behavior, without Backing plate




EF Type Option #S

An option defined by eliminating stripper plate from EF type



Mold Base Structure and Component Name F Series



This diagram shows **FB** type as a representative example.

The following mold base specifications are not shown in the Bluebook Plastic Mold Component Vol 1, but can be made to order in the same way as standard products. Please advise us on your specification requirements as follows:


Type name	Specification	Order example
FB type	A specification defined by adding stripper plate to FA type	MDC FB 2025 40 30 50 S V M N OH 210 ^{*1}
FD type	A specification defined by adding stripper plate to FC type	MDC FD 2025 40 60 50 S - M N OH 210 ^{*1}
FE type Option #S	A specification option defined by eliminating the stripper plate from FE type	MDC FE 2025 40 30 50 S V - N OH 190 / #S ^{*2}
FF type Option #S	A specification option defined by eliminating the stripper plate from FF type	MDC FF 2025 40 60 50 S - - N OH 190 / #S ^{*2}

*1. The type names of these specifications change to **FB** and **FD** types respectively.

*2. When specifying these specifications, please add **#S** to the respective order codes of FE and FF types.


FA Type

Ejector pin ejection type




FB Type

A type defined by adding a Stripper plate to FA type




FC Type

Ejector pin ejection type without Backing plate




FD Type

A type defined by adding a Stripper plate to FC type




FE Type

Stripper plate ejection type, which is actuated by mold opening behavior




FE Type Option #S

An option defined by eliminating stripper plate from FE type




FF Type

Stripper plate ejection type, which is actuated by mold opening behavior, without Backing plate




FF Type Option #S

An option defined by eliminating stripper plate from FF type



Mold Base Structure and Component Name G Series



This diagram shows **GB** type as a representative example.

The following mold base specifications are not shown in the Bluebook Plastic Mold Component Vol 1, but can be made to order in the same way as standard products. Please advise us on your specification requirements as follows:


Type name	Specification	Order example
GB type	A specification defined by adding stripper plate to GA type	MDC GB 2025 40 30 50 S V M N OH 190 ^{*1}
GD type	A specification defined by adding stripper plate to GC type	MDC GD 2025 40 60 50 S - M N OH 190 ^{*1}
GE type	A specification defined by eliminating runner stripper plate from FE type	MDC GE 2025 40 30 50 S V - N OH 190 ^{*1}
GF type	A specification defined by eliminating runner stripper plate from FF type	MDC GF 2025 40 60 50 S - - N OH 190 ^{*1}
GE type Option #S	A specification option defined by eliminating the stripper plate from GE type	MDC GE 2025 40 30 50 S V - N OH 170 / #S ^{*2}
GF type Option #S	A specification option defined by eliminating the stripper plate from GF type	MDC GF 2025 40 60 50 S - - N OH 170 / #S ^{*2}

*1. The type names of these specifications change to **GB, GD, GE, GF types** respectively.

*2. When specifying these specifications, please add **#S** to the respective order codes of GE and GF types.


GA Type

Ejector pin ejection type




GB Type

A type defined by adding a Stripper plate to GA type




GC Type

Ejector pin ejection type without Backing plate




GD Type

A type defined by adding a Stripper plate to GC type




GE Type

Stripper plate ejection type, which is actuated by mold opening behavior




GE Type Option #S

An option defined by eliminating the stripper plate from GE type




GF Type

Stripper plate ejection type, which is actuated by mold opening behavior, without Backing plate





GF Type Option #S

An option defined by eliminating the stripper plate from GF type




Mold Base Structure and Component Name H Series



This diagram shows **HB** type as a representative example.


HA Type

Ejector pin ejection type




HB Type

Stripper plate ejection type




HC Type

Ejector pin ejection type without Backing plate



HD Type


Stripper plate ejection type without Backing plate



Precision of Mold Base Plates

The precision specification of standard mold bases is defined as follows:


Mold plates, ejector plates and other plates



※ The surface roughness symbols shown in the above chart are arithmetic average roughness (Ra).

Material	F-S50C (thickness 25 or less) F-S55C (thickness 30 or more)	
Limit deviations of T	L dimension	Limit deviations of T
	300 or less	+0.1 ~ +0.2
	Over 300 and 600 or less	+0.15 ~ +0.25
	Over 600 and 1150 or less	+0.2 ~ +0.3
Uniformity of thickness (T)	0.008 per 100 mm	
Flatness of both surfaces of T	L dimension \ T dimension	
	300 or less	Over 300 and 1150 or less
	Over 5 and 10 or less	0.020 0.040
	Over 10 and 20 or less	0.015 0.020
	Over 20 and 40 or less	0.010 0.015
	Over 40 and 350 or less	0.008 0.010
※ Values per 100 mm		
Squareness of reference plane	0.008 per 100 mm	

Spacer blocks




※ The surface roughness symbols shown in the above chart are arithmetic average roughness (Ra).

Material	F-SS400 or equivalent or higher
Uniformity of thickness (T)	0.008 per 100 mm
Variation of T in a pair of plates	0.02

Hole Dimensions of Parts Installed in Mold Bases

The hole dimension specifications of guide pins, support pins and other parts installed in standard mold bases are as follows:



A type of pin supplied
with a support pin collar

A type of pin not supplied
with a support pin collar

Hole dimensions of guide pins, guide bushings and support pins

Nominal dimension	Guide pin hole			Guide bushing hole				Support pin hole				
	A	B	C	D	E	F	G	H	I	J	K	L
12	12	18	5	18	23	5	M4	12	18	6	18	14
16	16	21	6	25	31	6	M5	16	21	8	22	18
20	20	26		30	36	8	M6	20	26	10	28	24
25	25	31	8	35	41		M8	25	31	12	33	29
30	30	36		42	48	10		30	36	14	40	34
35	35	41		48	55			35	41	16	45	39
40	40	46		10	55	62	12	40	46	18	50	45
50	50	57	12	70	77	M10		—	—	—	—	—
60	60	67	15	80	87		—	—	—	—	—	
70	70	77		90	97		—	—	—	—	—	

Hole dimensions of return pins

Nominal dimension	Return pin hole				
	M	N	O	P*2*3	R
10	10	11	16	35	4
12	12	13	18	50	
15	15	16	21	60	
20	20	21	26	80	
25	25	26	31	100	
30	30	31	36	120	
35	35	36	41	130	

*2. The P dimensions in the above table are minimum values. The P dimensions can be larger than these values.

*3. When thickness ≤ P, P = thickness.

Hole dimensions of hexagon socket head cap screws

Nominal dimension	Hexagon socket head cap screw		
	S	T	U
M8	M8	9	21
M10	M10	11	24
M12	M12	14	28
M14	M14	16	31
M16	M16	18	34
M20	M20	22	46
M24	M24	26	56

Hole dimensions of puller bolts

Nominal dimension	Puller bolts			
	V	W	X	Y*1
20	21	13	31	25
25	26	17	36	29


*1. These are dimensions of H series.

Threaded Holes for Eye Bolts on Mold bases

On the mold bases, threaded holes for eye bolts are provided for securing safety and convenience of persons transporting and handling them. The plates on which to create threaded holes are determined based on the size of the mold base as shown below. The thread size is determined based on the maximum weight of the mold base.

Adding threaded holes for eye bolts ➡ P.222

Plates on which to create threaded holes for eye bolts




Name of the plate on which to create threaded holes for eye bolts	Applicable mold base
Plate B	Nominal dimension 1515 to 3560

Name of the plate on which to create threaded holes for eye bolts	Applicable mold base
Plate A Plate B	Nominal dimension 4040 to 5070

Name of the plate on which to create threaded holes for eye bolts	Applicable mold base
All plates	Nominal dimension 5555 to 7080

Specification of threaded holes for eye bolts




Length of Guide Pins for Mold Bases


Length of guide pins

When setting the length of guide pins for a standard mold base, N dimension is determined by the thickness of the plate in which to install guide bushings, and the length of the guide pin is determined based on the N dimension. Depending on the thickness of plates, N dimension is provided as a range, so guide pins with a length within the range is installed in the mold base.

How to specify length of guide pins → P.44



Mold base without stripper plate



Mold base with stripper plate



N dimension

D	A										
	20 ~ 50	60	70	80	90	100	110	120	130	140	150
12	3	3 ~ 8									
16	3	3	3 ~ 8	3 ~ 8							
20	3	3	3	3 ~ 8	3 ~ 13	3 ~ 13					
25	3	3	3	3 ~ 8	3 ~ 13	3 ~ 13	3 ~ 13	3 ~ 18			
30	3	3	3	3 ~ 8	3 ~ 13	3 ~ 13	3 ~ 13	3 ~ 18	3 ~ 18		
35	3	3	3	3	3	3 ~ 13	3 ~ 13	3 ~ 18	3 ~ 18	3 ~ 18	3 ~ 23
40	3	3	3	3	3	3 ~ 13	3 ~ 13	3 ~ 18	3 ~ 18	3 ~ 18	3 ~ 23

D	A						
	50 ~ 130	150	160	180	200	220	250
50	3	3 ~ 23	3 ~ 23	3 ~ 33	3 ~ 43	3 ~ 53	3 ~ 63
60	3	3 ~ 23	3 ~ 23	3 ~ 33	3 ~ 43	3 ~ 53	3 ~ 63






How to differentiate the use of guide bushing M-GBA and M-GBB

If the plate in which to install guide bushing is thin, use M-GBA and if it is thick, use M-GBB. For details on the classification of length of guide bushings and thickness of plates, see page 27.



Specification of Pipe Threads

Type of pipe thread (abstract of JIS B 0202, 0203 : 1999)

Thread name		Taper pipe thread		Parallel pipe thread
External thread	Name of external thread	Taper external pipe thread		Parallel external pipe thread
	Nominal code	R (former nominal code PT)		G (former nominal code PF)
	Appearance of external thread			
Internal thread	Name of internal thread	Taper Internal pipe thread	Parallel internal pipe thread (Parallel internal thread that fits taper external pipe thread)	Parallel internal pipe thread (Parallel internal thread that fits parallel external pipe thread)
	Nominal code	Rc (former nominal code: PT)	Rp (former nominal code: PS)	G (former nominal code: PF)
	Appearance of internal thread			
Scope		Applicable to threads used mainly for <u>pressure-tight</u> joints on the threads for joining pipes, pipefittings, fluid machinery, etc.		Applicable to threads used mainly for <u>mechanical joints</u> for joining pipes, pipefittings, fluid machinery, etc.
Remarks		① In addition to the former PT, PS and PF pipe threads, Rc, Rp and G pipe threads, which are based on ISO Standard, are now prescribed in the JIS Standard. Rc, Rp and G are in the main body of the standard. PT, PS and PF are in the Annex, and are planned to be abolished in the future. ② For the 1/16 to 1 pipe threads that are mainly used for molds, "Rc and PT", "Rp and PS" and "G and PF" are equivalent pipe threads respectively. For 1/16, however, PT, PS, and PF pipe threads are not available		

Thread codes used additional processing specifications

In general, taper pipe threads are used for water and oil channels on molds. Although PT and PS codes are conventionally used for the nominal dimensions of pipe threads, we use codes defined based on JIS Rc and Rp for our additional processing specification. The relation of our thread codes for additional processing specifications, JIS standard nominal codes and conventional nominal size code are as follows:


Type of pipe thread	Our thread codes for additional machining spec.	JIS standard nominal codes	Conventional nominal codes
Taper internal pipe thread	RC	Rc	PT
Parallel internal pipe thread (parallel internal thread for taper external pipe thread)	RP	Rp	PS

Definitions of technical terms used in taper pipe threads (JIS B 0203 : 1999)

Technical term	Definition
gauge diameter	Measure diameter of the thread, whether external or internal, at the gauge plane.
major cone	Imaginary cone which just touches the crests a taper external thread or the roots of a taper internal thread.
gauge plane	Plane perpendicular to the axis of the taper thread, at which the major cone has the gauge diameter. Remarks: For external threads the gauge plane is located at a distance equal to the nominal gauge length from the small end of the thread. For internal threads the gauge plane is located at the end face of the threaded part.
gauge length	The distance from the gauge plane of an external thread to the small end of the thread.
reference plane	Visible surface of each of the internally and externally threaded parts, which facilitates the reading of the gauge when the thread is inspected.
complete thread	The part of thread which is fully formed at both crest and root. Remarks: When there is a chamfer at the start of the thread not exceeding one pitch in length, this is included in the length of complete thread.
incompleted thread	The part of the thread which is fully formed at the root, but truncated at the crest by its intersection with cylindrical surface of the product
washout thread; vanish thread	That part of the thread which is not fully formed at the root. Remarks: The washout thread is produced by the bevel at the start of the threading tool.
useful thread	The distance from the gauge plane of an external thread to the small end of the thread.
fitting allowance	Length of useful thread beyond the gauge plane of an external thread required to provide for assembly with an internal thread at the upper limit of the tolerance. Remarks: Internally threaded parts will have a sufficient length to accommodate the fitting allowance, except when they have a free run-out.
Wrenching allowance	Length of useful thread which is provided to accommodate the relative movement between the end of the externally threaded part and the internally threaded part required for wrenching beyond the position of hand-tight engagement.

Taps for taper internal pipe threads (abstract of JIS B 4446: 1998)

For taps used for machining internal pipe threads, following three types are currently commercially available. Since the taper pipe threads are tapered shape, it is important to manage the position of the gauge diameter to ensure the proper fitting of external and internal pipe threads. As the position of gauge diameter differs depending on the type of tap, be sure to check the tap to use when machining internal threads.



Nominal of thread	Rc			PT short thread				PT long thread			
	L1		K1	L2		K2		L3		K3	
	Gauge length	Limit deviations	Max. DIMM	Gauge length	Limit deviations	Gauge length	Limit deviations	Gauge length	Limit deviations	Gauge length	Limit deviations
1/16	14	+2 -1	10.1	—	—	—	—	—	—	—	—
1/8	15		10.1	16.5	±1	10.5	+0.5 -1.0	19	±1	13	±0.91
1/4	19		15.0	19.5		12.5	+0.5 -1.5	28	±1.5	21	±1.34
3/8	21		15.4	21		14		28		21	
1/2	26		20.5	27	±1.5	17		35		25	±1.81
3/4	28		21.8	29		19		35		25	
1	33		26.0	35		22		45	±2	32	±2.31

※ Rc denotes a tap that is prescribed in the main body of JIS B 4446: 1998. For Rc1/16, the dimensions of commercially available taps may slightly differ depending on tool manufacturers.
 ※ PT short thread and PT long thread denote the taps that are prescribed in the annex of JIS B 4446: 1998.
 ※ Shown on the left are schematic views of 1/4 taps.

Specification of internal pipe thread

The table below shows our standard for machining internal threads.

The "position of gauge diameter" and the "length of thread" of our nipples and plugs for coupler with a taper pipe thread vary depending on production companies. Also, the depth of screwing external thread can change depending on the thickness of applying seal agent and length of winding sealing materials.

Taper internal pipe thread
Nominal code Rc (PT)

Parallel internal pipe thread
Nominal code Rp (PS)

Nominal of thread Rc (PT)	Z1 (Approx.)	L2	K2
1/16	12.5	16.5	10.5
1/8	12.5	16.5	10.5
1/4	15	19.5	12.5
3/8	17	21	14
1/2	20	27	17
3/4	22	29	19
1	25	35	22

※ We use taps that meet PT short thread prescribed in the annex of JIS B 4446: 1998. For 1/16 tap, we use taps that meet Rc specified in the main body of JIS B 4446 1998


Nominal size Rp (PS)	Z2 (Approx.)	L4	
1/16	12.5	19	
1/8	12.5	19	
1/4	15	28	
3/8	17	28	
1/2	20	35	
3/4	22	35	
1	25	45	

※ We use taps that meet PS prescribed in the annex of JIS B 4446: 1998. For 1/16 tap, we use taps that meet Rp specified in the main body of JIS B 4446 1998

Hexagon Socket Head Cap Screws


[Excerpt from JIS B 1176 (2000)]
[Excerpt from JIS B 1176 (1974)]

Dimension of counterbore and bolt holes for hexagon socket head cap screws (reference)



Nominal of thread (d)	M3	M4	M5	M6	M8	M10	M12	M14	M16	M20	M24	M30
ds	3	4	5	6	8	10	12	14	16	20	24	30
ds'	3.4	4.5	5.5	6.6	9	11	14	16	18	22	26	33
dk	5.5	7	8.5	10	13	16	18	21	24	30	36	45
dk'	6.5	8	9.5	11	14	17.5	20	23	26	32	39	48
k	3	4	5	6	8	10	12	14	16	20	24	30
k'	2.7	3.6	4.6	5.5	7.4	9.2	11	12.8	14.5	18.5	22.5	28
k''	3.3	4.4	5.4	6.5	8.6	10.8	13	15.2	17.5	21.5	25.5	32

Dimension of hexagon socket head cap screws



Nominal of thread (d)		M3	M4	M5	M6	M8	M10	M12	(M14)	M16	M20	M24	M30
Pitch of thread (P)		0.5	0.7	0.8	1	1.25	1.5	1.75	2	2	2.5	3	3.5
b	Reference	18	20	22	24	28	32	36	40	44	52	60	72
dk	Max. ^{*1}	5.50	7.00	8.50	10.00	13.00	16.00	18.00	21.00	24.00	30.00	36.00	45.00
	Max. ^{*2}	5.68	7.22	8.72	10.22	13.27	16.27	18.27	21.33	24.33	30.33	36.39	45.39
	Min.	5.32	6.78	8.28	9.78	12.73	15.73	17.73	20.67	23.67	29.67	35.61	44.61
da	Max.	3.6	4.7	5.7	6.8	9.2	11.2	13.7	15.7	17.7	22.4	26.4	33.4
ds	Max.	3.00	4.00	5.00	6.00	8.00	10.00	12.00	14.00	16.00	20.00	24.00	30.00
	Min.	2.86	3.82	4.82	5.82	7.78	9.78	11.73	13.73	15.73	19.67	23.67	29.67
k	Max.	3.00	4.00	5.00	6.00	8.00	10.00	12.00	14.00	16.00	20.00	24.00	30.00
	Min.	2.86	3.82	4.82	5.7	7.64	9.64	11.57	13.57	15.57	19.48	23.48	29.48
r	Min.	0.1	0.2	0.2	0.25	0.4	0.4	0.6	0.6	0.6	0.8	0.8	1
s	Nominal	2.5	3	4	5	6	8	10	12	14	17	19	22
	Max ^{*3}	2.56	3.071	4.084	5.084	6.095	8.115	10.115	12.142	14.142	17.23	19.275	22.275
	Max ^{*4}	2.58	3.080	4.095	5.140	6.140	8.175	10.175	12.212	14.212			
	Min.	2.52	3.020	4.020	5.020	6.020	8.025	10.025	12.032	14.032	17.05	19.065	22.065
t	Min.	1.3	2	2.5	3	4	5	6	7	8	10	12	15.5

※ The above table shows main dimensions excerpt from JIS B1176: 2000. For details, refer to the standard.

*1. This should be applied to the heads without no knurled pattern.



*2. This should be applied to the heads with no knurled pattern.

*3. This should be applied to strength class 12.9.

*4. This should be applied to other strength classes.

Calculation of Gravity Center of a Mold Base

Calculating the center of gravity of a mold base is not an easy task because various parts are installed on a mold base and different alternatives are made to it. Shown below is a simple formula for calculating center of gravity of a mold base with plates assembled.



$$\begin{aligned}
 M_c &= \frac{\text{Sum of the moment of each plate}}{\text{Weight of mold base}} \\
 &= \frac{(T_m + R_m + A_m + S_m + B_m + U_m + C_m + E_m + F_m + L_m)}{(T_w + R_w + A_w + S_w + B_w + U_w + C_w + E_w + F_w + L_w)}
 \end{aligned}$$

M_c : Center of gravity position from the top surface of Plate T

$T_m \sim L_m$: moment of each plate with the top surface of clamping plate as a reference (omit if there is no plate)

$T_w \sim L_w$: weight of each plate (omit if there is no plate)

※ Protrusion amount of the clamping plate is assumed to be even.


※ The width of the right and left side spacer blocks is assumed to be the same.

Plate code	Calculation of weight of each plate	Calculation of moment of each plate
Plate T	$T_w = TW \times TL \times T_t \times \text{specific weight}$	$T_m = T_w \times T_t / 2$
Plate R	$R_w = KW \times KL \times R_t \times \text{specific weight}$	$R_m = R_w \times (T_t + R_t) / 2$
Plate A	$A_w = KW \times KL \times A_t \times \text{specific weight}$	$A_m = A_w \times (T_t + R_t + A_t) / 2$
Plate S	$S_w = KW \times KL \times S_t \times \text{specific weight}$	$S_m = S_w \times (T_t + R_t + A_t + S_t) / 2$
Plate B	$B_w = KW \times KL \times B_t \times \text{specific weight}$	$B_m = B_w \times (T_t + R_t + A_t + S_t + B_t) / 2$
Plate U	$U_w = KW \times KL \times U_t \times \text{specific weight}$	$U_m = U_w \times (T_t + R_t + A_t + S_t + B_t + U_t) / 2$
Plate C	$C_w = CW \times KL \times C_t \times 2 \times \text{specific weight}$	$C_m = C_w \times (T_t + R_t + A_t + S_t + B_t + U_t + C_t) / 2$
Plate E	$E_w = EFW \times KL \times E_t \times \text{specific weight}$	$E_m = E_w \times \{T_t + R_t + A_t + S_t + B_t + U_t + C_t - F_t - (4^{*1}) - E_t\} / 2$
Plate F	$F_w = EFW \times KL \times F_t \times \text{specific weight}$	$F_m = F_w \times (T_t + R_t + A_t + S_t + B_t + U_t + C_t - F_t) / 2$
Plate L	$L_w = TW \times TL \times L_t \times \text{specific weight}$	$L_m = L_w \times (T_t + R_t + A_t + S_t + B_t + U_t + C_t + L_t) / 2$

*1. Applied if the specification of the ejector plates is spacer type. No need if it is counterbore type.

Calculation of the Deflection of Cavity Plate (Moving Half)

The injection pressure applied by the injection molding machine acts on the projection plane inside the cavity and causes a deflection of the cavity plate (moving half). If the deflection is large, it may result in a change in thickness or flash on the molded products or other problems. Therefore, it is necessary to check possible deflection by using a formula for cantilever. As shown in the formula below, the deflection increases in proportion to the cube of thickness of backing plate (h) and to the fourth power of the spacing on the inside of the spacer block. Thus, it is more effective in decreasing the deflection to narrow the spacing on the inside of the spacer block. Increasing the thickness of the backing plate or width of the spacer block has a limit due to the restrictions on the height of the mold and effective space of the ejector plate. Reinforcement with support pillars, etc. is also another option that can be used to reduce deflection.



- B : Width of cavity plate (mm)
- L : Spacing (mm) on the inside of the spacer block
- h : Thickness of backing plate (mm)
- W : Length (mm) of the part receiving the cavity internal injection pressure P
- b : Width (mm) of the part receiving the cavity internal injection pressure P
- p : Cavity internal injection pressure (kgf/cm²)
- E : modules of longitudinal elasticity (Young's modules) of the material (kgf/cm²)
- $\delta_{\max}$: maximum deflection of the backing plate (mm)

[When assuming $W=L$ for simplifying the calculation]

$$\delta_{\max} = \frac{5 \cdot p \cdot b \cdot L^4}{32 \cdot E \cdot B \cdot h^3}$$

$$h = \sqrt[3]{\frac{5 \cdot p \cdot b \cdot L^4}{32 \cdot E \cdot B \cdot \delta_{\max}}}$$

E values

Material	E (kgf/cm ²)
Soft steel	210×10^4
Pre-hardened steel (SCM440 series)	203×10^4
Cast iron	$(75 \sim 105) \times 10^4$
Ultra duralumin ALQUEEN 300	73×10^4

Rough guides of cavity internal injection pressure P (ref. value)

Molding condition	p (kgf/cm ²)
Lower injection pressure	200 ~ 400
Higher injection pressure	400 ~ 600
(Note) In practice, it is desirable to measure the actual values using a pressure sensor → (P 458)	


Rough guides of maximum allowable deflection that takes parting line flash into account (reference value)

Molding material, etc.	Maximum allowable deflection $\delta_{\max}$ (mm)
Materials with high flow (PA, PP, etc.)	0.025 or less
Materials with regular flow	0.03 ~ 0.05
Molded product that allows flash	0.1 ~ 0.2

Reference: Michio Komatsu, "Plastic Injection Molding Design Manual" Nikkan Kogyo Shinbunsha

Calculation of the Deflection of Support Pin

In addition to the parting line for taking out molded products, three-plate mold has one more parting line for taking runner out. Therefore, three-plate mold makes a larger mold opening stroke to take out runner, and thus the support pin that guides and supports the opening and closing of cavity plate (fixed half) is subject to a bending moment that is a product of weight of cavity plate (fixed half) and distance to the fully open position resulting in a deflection. It is necessary to check possible deflection by using a formula for cantilever.



W : Load applied per support pin (kgf)

E : modules of longitudinal elasticity (Young's modules) 21,000kgf/mm²

I : Cross sectional secondary moment $I = \pi (D-1)^4 / 64$

※ Oil groove is assumed here and (D-1) is used as diameter.

Deflection Y in L area

$$Y = \frac{W \cdot M^3}{3 \cdot E \cdot I} \left(1 + \frac{3 \cdot N}{2 \cdot M} \right)$$

As shown in the above, the deflection increases in proportion to the load applied to the support pin (W) and to the cube of mold opening distance (M). Therefore, it significantly changes depending on the mold base used and the mold opening distance required. If the deflection becomes larger than the clearance of the pin and bushing, they will slide with interference, making a squeak noise, which will cause binding, etc.

In reality, however, the clearance between the pin and bushing is only 0.03 mm, and keeping all the molds smaller than this value requires the use of pins with a larger diameter, and is thus difficult from the perspective of effective space and costs.

It would be better to use such a measure when necessary for quality reason, etc.

For allowable deflection, 0.3 to 0.4 mm or less values are used in many applications, but the values are generally determined on a case by case basis as they change according to the level of precision required for the molded products, appearance and mold. Calculating deflection is suggested to evaluate the precision of the molds that have been produced in the past to evaluate their level of precision, including potential of binding and other troubles in planning a new design, or establish and maintain an internal design standard.

Mold Steel Brands Comparison Table

Plastic Mold Steel Brands Comparison Table

Classification	Hardness for use (HRC)	Applicable standards				Futaba standard product	Material manufacturer									
		JIS	AISI	DIN			Kobe Steel	Hitachi Metals	Daido Steel	Bohla Uddeholm	Aichi Steel	Nihon Kosyuha Steel	Nippon steel & sumitomo metal	Sanyo special steel	Nachi -Fujikoshi	
				Name	Material No.											
As rolled steel	13	SC Series	1055 1050	CK55 C55	1.1203 1.0535	F-S55C F-S50C	S55C S50C									
	13						KTSM21 KTSM2A KTSM22				AUK1	KPM1 KPMAX	SD17 SD18T	PC55		
Pre hardened steel	28	SCM Series	4140	42CrMo4	1.7225		KTSM31		PDS3		AUK11		SD61			
	33	SCM (Improved)	P20	<Supeior weldability>		HPM7 PXA30		HPM7	PXA30			KPM30				
	33	SCM (Improved)	P20	35CrMo4	1.2330		KTSM3M			PLAMAX M238 IMPAX HH (35 ~ 40HRC)			SD70 SD100			
	40	SCM (Improved)	P20Ni Series			HPM-MAGIC		HPM-MAGIC		NIMAX						
		pre-cipitation hardening	P21	<Free-machining>		HPM1 NAK55		HPM1	NAK55			KAP65		PCM40		
				<Mirror finishing property>		NAK80 HPM-PRO		HPM-PRO	NAK80			KAP88		PCM40S		
			P21	<Rust - prevention property>		CENA1		CENA1								
			SKD61 (Improved)	(H13)	(X40CrMoV51)	(1.2344)	FDAC DH2F		FDAC	DH2F			KAP90F			
	Quenched and tempered steel	50	SKD61 Series	H13	X40CrMoV51	1.2344	F-SKD61		DAC	DHA DHA1	ORVAR-2M W302	SKD61	KDA		QD61	
56 ~ 62		SKD11	(D2)	(X155CrVmo121)	(1.2379)	F-SKD11		SLD	DC11		SKD11	KD11		QC11	CDS11	
		SKD11 (Improved)				HPM31 PD613		HPM31	PD613 DC53	CALDIE	AUD11	KD21		QCM8		
		SKD12	A2			RIGOR			DC12	RIGOR		KD12				
Stainless steel	Pre hardened	33	SUS Series 420J2	420	(X38Cr13)	(1.4031)	HPM38 STAVAX		HPM38	S-STAR	STAVAX M303	420M			PROVA-400	
			SUS Series (free-machining)						HPM77	G-STAR	RoyAlloy					
		35	SUS Series 630	S17400					PSL	NAK101			U630		QSH6	
		40	SUS Series								EDRO400 M303-HH					
	52	SUS Series 420J2	420	(X38Cr13)	(1.4031)	HPM38 STAVAX		HPM38 HPM38S	S-STAR D-STAR	STAVAX M333					PROVA-400	
	57	SUS Series 440C	440C	X105CrMo17	1.4125			SUS440C	SUS440C	M340 ELMAX (Power metall)				QPD5 SPC5 (Power metall)	440C PROVA-500 (Power metall)	
Age hardened steel	50 or more	Maraging steel						YAG	MAS1C			KMS18-20			EXEO-M21	
	40	Non-magunetic steel						HPM75				NMS1				
Copper Alloy steel								(HIT71) (HIT72) (HIT75)		MOLDMAX HH/LH/XL/V						

Stamping Die Steel Brands Comparison Table

Classification	Hardness for use (HRC)	Applicable standards				Futaba standard product	Material manufacturer									
		equivalent JIS	equivalent AISI	DIN			Hitachi Metals	Daido Steel	Bohla Uddeholm	Nihon Kosyuha Steel	Sanyo special steel	Aichi Steel	Nachi -Fujikoshi			
				Name	Material No.											
Carbon tool steel	53 ~ 61	SK105	W1-10	C105W1	1.1645			YK3			QK3	SK3				
	Alloy tool steel	56 ~ 62	SKS93	(W5)			F-SK3	YCS3	YK30		K3M	QK3M	SK301			
			SKS3	(O1)	100MnCrW4	1.2510	F-SKS3	SGT	GOA		KS3	QKS3	SKS3			
			SKD1	D3	X210Cr12	1.2080		CRD	DC1		KD1	QC1	SKD1			
			SKD11	(D2)	(X155CrVMo121)	(1.2379)	F-SKD11	SLD	DC11	K110	KD11	QC11	SKD11	CDS11		
			SKD 11 (Improved)	High hardness	For 8% or high temp. tempering			SLD8	DC53	K340	KD21	QCM7 QCM8	AUD15 AUD11	MDS9		
					Free machining & low quenching strain & coated long life		SLD-MAGIC	SLD-MAGIC								
			Free-machining		Middle Cr SKD	ARK1	ARK1			DCMX	CALDIE					
																Matrix Series
			Others						NOGA		SXACE AUD11X					
			Powder dies steel									VANADIS4E				
			Nitriding power steel									VANCRON40				
			SKD12	A2	X100CrMoV51	1.2363	RIGOR		DC12	RIGOR	KD12					
			Flame hardening steel						HMD5	GO5		FH5 KRCX	QF3	SX105V SX4		
			Low temperature air-cooled quenching					ACD37	ACD37	GO4		KSM				
High impact steel						YSM	GS5		KTV5	QF1	AKS4					
Pre hardened steel	33	SCM (Improved)	P20	<Superior weldability>		HPM7 PXA30	HPM7	PXA30		KPM30						
	37	SCM (Improved)	P20	35CrMo4	1.2330				IMPAX HH (35 ~ 40HRC)							
	40	SCM (Improved)	P20	<Free-machining>				GO40F								
		Precipitation hardening	P21	<Free-machining>		HPM1 NAK55	HPM1	NAK55		KAP65	PCM40					
				<Mirror finishing property>		NAK80 HPM-PRO	HPM-PRO	NAK80		KAP88	PCM40S					
	P21	<Rust - prevention property>		CENA1	CENA1											
High-speed tool steel	55 ~ 68	SKH51	M2	S6-5-2	1.3343		YXM1	MH51	S600	H51	QH51		SKH9			
		SKH55 Series	M35	S6-2-5	1.3243		YXM4	MH55	S705	HM35			HM35 HS53M			
		SKH57 Series		S10-4-3-10	1.3207		XVC5	MH8		MV10			HS93R DURO-SP			
		Matrix Series High-speed					YXR3 YXR33 YXR7	DRM1 DRM2 DRM3	W360	KMX1 KMX2 KMX3	QHZ		DURO-F1, F3, F7 DURO-V2, V5 FAX38			
Powder metal high-speed tool steel	58 ~ 70	SKH40			1.3244		HAP40	DEX40	VANADIS30				FAX38			
			M3:2			ASP23	HAP10	DEX20	VANADIS23		ASP23		FAX31			
							HAP50 HAP72	DEX60	VANADIS60 Super Clean		ASP30 ASP60 SPMR8		FAX55 FAXG2			
		Matrix Series powder metal high-speed					HAP5R	DEX-M1 DEX-M3								

Reference: Special Steel Vol.56 No.6 2007

Material Property Data List

The table below shows main material properties of the plates shown in the RED BOOK.

For detailed information on each property, see the RED BOOK (RED BOOK is a name of our plate general catalog).

Property values shown in International system of unit (SI unit)

Classification	Material	Hardness for use		Tensile property		Physical property	
		HRC	HB	0.2% proof stress N/mm ²	Tensile strength N/mm ²	Thermal expansion coefficient × 10 ⁻⁶ /°C [20 ~ 200°C]	Thermal conductivity coefficient W/(m·°C) [20°C]
Carbon tool steel	F-SS400	—	116 ~ 150	275 (Yield point)	450	13.1 [0 ~ 300°C]	58.6 [0°C]
	F-S55C	6 ~ 22	170 ~ 240	366	749	12.6 [25 ~ 200°C]	46.0 [50°C]
Pre hardened steel	HPM7	29 ~ 33	279 ~ 311	853	973	12.2	34.3
	PXA30	30 ~ 33	286 ~ 311	845	980	12.7 [30 ~ 200°C]	34.7
	HPM-MAGIC	37 ~ 41	344 ~ 381	1,020	1,200	12.3 [30 ~ 200°C]	31.4
	HPM1	37 ~ 41	344 ~ 381	1,010	1,216	11.8	32.7
	NAK55	37 ~ 43	344 ~ 400	981	1,255	12.5	38.9
	NAK80	37 ~ 43	344 ~ 400	981	1,255		
	HPM-PRO	37 ~ 41	344 ~ 381	1,020	1,200	13.0 [30 ~ 200°C]	28.3
	CENA1	37 ~ 42	344 ~ 390	1,150	1,225	11.4	28.1
	DH2F	38 ~ 42	353 ~ 390	1,100	1,330	10.8	25.5
	FDAC	38 ~ 42	353 ~ 390	1,060	1,240	11.7 [20 ~ 100°C]	30.5
	Stainless	HPM38	50 ~ 55 29 ~ 33HRC (pre-hardened state)	1,618	1,912	11.9	25.1
		STAVAX ESR	50 ~ 55 27 ~ 35HRC (pre-hardened state)	1,610	2,050	11.0	16.0
Quenched and tempered steel	※1 F-SKD61	53 or less	—	1,070 〈40HRC〉	1,250	12.5 〈45HRC〉	30.5
	※2	HPM31	55 ~ 60	1,490 〈61HRC〉	2,120	12.3 〈60HRC〉	28.5
		PD613	56 ~ 61	1,815 〈59HRC〉	2,280	11.7 [30 ~ 200°C] 〈60HRC〉	28.5
		RIGOR	54 ~ 59	—	—	11.6 〈62HRC〉	26.0
	Cold work tool steel	F-SK3	58 ~ 63	— 〈60HRC〉	1,670	11.3 〈197HB: annealed state〉	45.2
		F-SKS3	60 ~ 62	— 〈60HRC〉	1,370	12.4 〈62HRC〉	34.7
		F-SKD11	58 ~ 63	1,570 〈60HRC〉	1,810	12.5 〈60HRC〉	29.3
		SLD-MAGIC	60 ~ 62	1,780 〈60HRC〉	1,890	12.3	28.9
		ARK1	58 ~ 62	— 〈60HRC〉	1,690	12.4 〈59HRC〉	29.5
		ACD37	58 ~ 62	—	—	13.1 〈60HRC〉	46.0 [100°C]
		ASP23	56 ~ 65	—	—	11.7 〈62HRC〉	23.9
Alluminium alloy	AAG	—	59	100	200	23.8	138
	AAS	—	150	420	520	23.6	130

※ 1. Hot work tool steel ※ 2. Die steel for plastic mold

Property values shown in traditional unit systems (CGS and MKS units)

Classification	Material	Hardness for use		Tensile property		Physical property	
		HRC	HB	0.2% proof stress kgf/mm ²	Tensile strength kgf/mm ²	Thermal expansion coefficient × 10 ⁻⁶ /°C [20 ~ 200°C]	Thermal conductivity coefficient cal/(cm·s·°C) [20°C]
Carbon tool steel	F-SS400	—	116 ~ 150	28 (Yield point)	46	13.1 [0 ~ 300°C]	0.14 [0°C]
	F-S55C	6 ~ 22	170 ~ 240	37.3	76.4	12.6 [25 ~ 200°C]	0.110 [50°C]
Pre hardened steel	HPM7	29 ~ 33	279 ~ 311	87.0	99.2	12.2	0.082
	PXA30	30 ~ 33	286 ~ 311	86	100	12.7 [30 ~ 200°C]	0.083
	HPM-MAGIC	37 ~ 41	344 ~ 381	104	122	12.3 [30 ~ 200°C]	0.075
	HPM1	37 ~ 41	344 ~ 381	103	124	11.8	0.078
	NAK55	37 ~ 43	344 ~ 400	100	128	12.5	0.093
	NAK80	37 ~ 43	344 ~ 400	100	128		
	HPM-PRO	37 ~ 41	344 ~ 381	104	122	13.0 [30 ~ 200°C]	0.068
	CENA1	37 ~ 42	344 ~ 390	117	125	11.4	0.067
	DH2F	38 ~ 42	353 ~ 390	112	136	10.8	0.061
	FDAC	38 ~ 42	353 ~ 390	108	126	11.7 [20 ~ 100°C]	0.073
	Stainless	HPM38	50 ~ 55 29 ~ 33HRC (pre-hardened state)	165	195	11.9	0.060
		STAVAX ESR	50 ~ 55 27 ~ 35HRC (pre-hardened stae)	164	209	11.0	0.038
Quenched and tempered steel	※1 F-SKD61	53 or less	—	109 〈40HRC〉	127	12.5 〈45HRC〉	0.073
	※2 HPM31	55 ~ 60	—	152 〈61HRC〉	216	12.3 〈60HRC〉	0.068
	PD613	56 ~ 61	—	185 〈59HRC〉	233	11.7 [30 ~ 200°C] 〈60HRC〉	0.068
	RIGOR	54 ~ 59	—	—	—	11.6 〈62HRC〉	0.062
	Cold work tool steel	F-SK3	58 ~ 63	— 〈60HRC〉	170	11.3 〈197HB: annealed state〉	0.108
		F-SKS3	60 ~ 62	— 〈60HRC〉	140	12.4 〈62HRC〉	0.083
		F-SKD11	58 ~ 63	160 〈60HRC〉	185	12.5 〈60HRC〉	0.070
		SLD-MAGIC	60 ~ 62	182 〈60HRC〉	193	12.3	0.069
		ARK1	58 ~ 62	— 〈60HRC〉	172	12.4 〈59HRC〉	0.070
		ACD37	58 ~ 62	—	—	13.1 〈60HRC〉	0.11 [100°C]
		ASP23	56 ~ 65	—	—	11.7 〈62HRC〉	0.057
Alluminium alloy	AAG	—	59	10	20	23.8	0.33
	AAS	—	150	43	53	23.6	0.31

※ 1. Hot work tool steel ※ 2. Die steel for plastic mold

Limit Deviations for Fits Used Frequently (Holes)

Limit deviations for frequently used fits of holes

Classification of basic size (mm)		Tolerance class of hole																
Over	Or less	B10	C9	C10	D8	D9	D10	E7	E8	E9	F6	F7	F8	G6	G7	H6	H7	H8
—	3	+180 +140	+85 +60	+100 +60	+34 +20	+45 +20	+60 +20	+24 +14	+28 +14	+39 +14	+12 +6	+16 +6	+20 +6	+8 +2	+12 +2	+6 0	+10 0	+14 0
3	6	+188 +140	+100 +70	+118 +70	+48 +30	+60 +30	+78 +30	+32 +20	+38 +20	+50 +20	+18 +10	+22 +10	+28 +10	+12 +4	+16 +4	+8 0	+12 0	+18 0
6	10	+208 +150	+116 +80	+138 +80	+62 +40	+76 +40	+98 +40	+40 +25	+47 +25	+61 +25	+22 +13	+28 +13	+35 +13	+14 +5	+20 +5	+9 0	+15 0	+22 0
10	14	+220 +150	+138 +95	+165 +95	+77 +50	+93 +50	+120 +50	+50 +32	+59 +32	+75 +32	+27 +16	+34 +16	+43 +16	+17 +6	+24 +6	+11 0	+18 0	+27 0
14	18																	
18	24	+244 +160	+162 +110	+194 +110	+98 +65	+117 +65	+149 +65	+61 +40	+73 +40	+92 +40	+33 +20	+41 +20	+53 +20	+20 +7	+28 +7	+13 0	+21 0	+33 0
24	30																	
30	40	+270 +170	+182 +120	+220 +120	+119 +80	+142 +80	+180 +80	+75 +50	+89 +50	+112 +50	+41 +25	+50 +25	+64 +25	+25 +9	+34 +9	+16 0	+25 0	+39 0
40	50	+280 +180	+192 +130	+230 +130														
50	65	+310 +190	+214 +140	+260 +140	+146 +100	+174 +100	+220 +100	+90 +60	+106 +60	+134 +60	+49 +30	+60 +30	+76 +30	+29 +10	+40 +10	+19 0	+30 0	+46 0
65	80	+320 +200	+224 +150	+270 +150														
80	100	+360 +220	+257 +170	+310 +170	+174 +120	+207 +120	+260 +120	+107 +72	+126 +72	+159 +72	+58 +36	+71 +36	+90 +36	+34 +12	+47 +12	+22 0	+35 0	+54 0
100	120	+380 +240	+267 +180	+320 +180														
120	140	+420 +260	+300 +200	+360 +200	+208 +145	+245 +145	+305 +145	+125 +85	+148 +85	+185 +85	+68 +43	+83 +43	+106 +43	+39 +14	+54 +14	+25 0	+40 0	+63 0
140	160	+440 +280	+310 +210	+370 +210														
160	180	+470 +310	+330 +230	+390 +230	+242 +170	+285 +170	+355 +170	+146 +100	+172 +100	+215 +100	+79 +50	+96 +50	+122 +50	+44 +15	+61 +15	+29 0	+46 0	+72 0
180	200	+525 +340	+355 +240	+425 +240														
200	225	+565 +380	+375 +260	+445 +260	+242 +170	+285 +170	+355 +170	+146 +100	+172 +100	+215 +100	+79 +50	+96 +50	+122 +50	+44 +15	+61 +15	+29 0	+46 0	+72 0
225	250	+605 +420	+395 +280	+465 +280														
250	280	+690 +480	+430 +300	+510 +300	+271 +190	+320 +190	+400 +190	+162 +110	+191 +110	+240 +110	+88 +56	+108 +56	+137 +56	+49 +17	+69 +17	+32 0	+52 0	+81 0
280	315	+750 +540	+460 +330	+540 +330														
315	355	+830 +600	+500 +360	+590 +360	+299 +210	+350 +210	+440 +210	+182 +125	+214 +125	+265 +125	+98 +62	+119 +62	+151 +62	+54 +18	+75 +18	+36 0	+57 0	+89 0
355	400	+910 +680	+540 +400	+630 +400														
400	450	+1010 +760	+595 +440	+690 +440	+327 +230	+385 +230	+480 +230	+198 +135	+232 +135	+290 +135	+108 +68	+131 +68	+165 +68	+60 +20	+83 +20	+40 0	+63 0	+97 0
450	500	+1090 +840	+635 +480	+730 +480														

Remarks: In each row of the above table, upper values represent upper deviations and lower values represent lower deviations.

[Excerpt from JIS B 0401-2 (1998)]

Unit: μm

Range of basic size (mm)		Tolerance class of hole																
Over	Or less	H9	H10	JS6	JS7	K6	K7	M6	M7	N6	N7	P6	P7	R7	S7	T7	U7	X7
—	3	+25 0	+40 0	±3	±5	0 −6	0 −10	−2 −8	−2 −12	−4 −10	−4 −14	−6 −12	−6 −16	−10 −20	−14 −24	—	−18 −28	−20 −30
3	6	+30 0	+48 0	±4	±6	+2 −6	+3 −9	−1 −9	0 −12	−5 −13	−4 −16	−9 −17	−8 −20	−11 −23	−15 −27	—	−19 −31	−24 −36
6	10	+36 0	+58 0	±4.5	±7.5	+2 −7	+5 −10	−3 −12	0 −15	−7 −16	−4 −19	−12 −21	−9 −24	−13 −28	−17 −32	—	−22 −37	−28 −43
10	14	+43 0	+70 0	±5.5	±9	+2 −9	+6 −12	−4 −15	0 −18	−9 −20	−5 −23	−15 −26	−11 −29	−16 −34	−21 −39	—	−26 −44	−33 −51
14	18																	−38 −56
18	24	+52 0	+84 0	±6.5	±10.5	+2 −11	+6 −15	−4 −17	0 −21	−11 −24	−7 −28	−18 −31	−14 −35	−20 −41	−27 −48	—	−33 −54	−46 −67
24	30																	−54 −61
30	40	+62 0	+100 0	±8	±12.5	+3 −13	+7 −18	−4 −20	0 −25	−12 −28	−8 −33	−21 −37	−17 −42	−25 −50	−34 −59	—	−45 −70	−51 −71
40	50																	−64 −76
50	65	+74 0	+120 0	±9.5	±15	+4 −15	+9 −21	−5 −24	0 −30	−14 −33	−9 −39	−26 −45	−21 −51	−30 −60	−42 −72	−55 −85	−76 −106	−111 −141
65	80													−32 −62	−48 −78	−64 −94	−91 −121	−135 −165
80	100	+87 0	+140 0	±11	±17.5	+4 −18	+10 −25	−6 −28	0 −35	−16 −38	−10 −45	−30 −52	−24 −59	−38 −73	−58 −93	−78 −113	−111 −146	−165 −200
100	120													−76 −101	−126 −166	−232 −273		
120	140	+100 0	+160 0	±12.5	±20	+4 −21	+12 −28	−8 −33	0 −40	−20 −45	−12 −52	−36 −61	−28 −68	−48 −88	−77 −117	−107 −147	−155 −195	−233 −273
140	160													−50 −90	−85 −125	−119 −159	−175 −215	−265 −305
160	180													−53 −93	−93 −133	−131 −171	−195 −235	−295 −335
														−197 −232				
180	200	+115 0	+185 0	±14.5	±23	+5 −24	+13 −33	−8 −37	0 −46	−22 −51	−14 −60	−41 −70	−33 −79	−60 −106	−105 −151	−149 −195	−219 −265	−333 −379
200	225													−63 −109	−113 −159	−163 −209	−241 −287	−368 −414
225	250													−67 −113	−123 −169	−179 −225	−267 −313	−408 −454
														−408 −454				
250	280	+130 0	+210 0	±16	±26	+5 −27	+16 −36	−9 −41	0 −52	−25 −57	−14 −66	−47 −79	−36 −88	−74 −126	−138 −190	−198 −250	−295 −347	−455 −507
280	315													−78 −130	−150 −202	−220 −272	−330 −382	−505 −557
315	355													−87 −144	−169 −226	−247 −304	−369 −426	−569 −626
														−93 −150	−187 −244	−273 −330	−414 −471	−639 −696
400	450	+155 0	+250 0	±20	±31.5	+8 −32	+18 −45	−10 −50	0 −63	−27 −67	−17 −80	−55 −95	−45 −108	−103 −166	−209 −272	−307 −370	−467 −530	−717 −780
450	500													−109 −172	−229 −292	−337 −400	−517 −580	−797 −860

Product Data /
Technical Data

Limit Deviations for Fits Used Frequently (Holes)

Limit Deviations for Fits Used Frequently (Shaft)

Limit deviations for frequently used fits of shafts

Range of basic size (mm)		Tolerance class of shaft														
Over	Or less	b9	c9	d8	d9	e7	e8	e9	f6	f7	f8	g5	g6	h5	h6	h7
—	3	−140	−60	−20	−20	−14	−14	−14	−6	−6	−6	−2	−2	0	0	0
		−165	−85	−34	−45	−24	−28	−39	−12	−16	−20	−6	−8	−4	−6	−10
3	6	−140	−70	−30	−30	−20	−20	−20	−10	−10	−10	−4	−4	0	0	0
		−170	−100	−48	−60	−32	−38	−50	−18	−22	−28	−9	−12	−5	−8	−12
6	10	−150	−80	−40	−40	−25	−25	−25	−13	−13	−13	−5	−5	0	0	0
		−186	−116	−62	−76	−40	−47	−61	−22	−28	−35	−11	−14	−6	−9	−15
10	14	−150	−95	−50	−50	−32	−32	−32	−16	−16	−16	−6	−6	0	0	0
		−193	−138	−77	−93	−50	−59	−75	−27	−34	−43	−14	−17	−8	−11	−18
18	24	−160	−110	−65	−65	−40	−40	−40	−20	−20	−20	−7	−7	0	0	0
		−212	−162	−98	−117	−61	−73	−92	−33	−41	−53	−16	−20	−9	−13	−21
24	30	−170	−120	−80	−80	−50	−50	−50	−25	−25	−25	−9	−9	0	0	0
		−232	−182	−119	−142	−75	−89	−112	−41	−50	−64	−20	−25	−11	−16	−25
30	40	−180	−130	−100	−100	−60	−60	−60	−30	−30	−30	−10	−10	0	0	0
		−242	−192	−146	−174	−90	−106	−134	−49	−60	−76	−23	−29	−13	−19	−30
40	50	−190	−140	−120	−120	−72	−72	−72	−36	−36	−36	−12	−12	0	0	0
		−264	−214	−174	−207	−107	−126	−159	−58	−71	−90	−27	−34	−15	−22	−35
50	65	−200	−150	−145	−145	−85	−85	−85	−43	−43	−43	−14	−14	0	0	0
		−274	−224	−208	−245	−125	−148	−185	−68	−83	−106	−32	−39	−18	−25	−40
65	80	−220	−170	−170	−170	−100	−100	−100	−50	−50	−50	−15	−15	0	0	0
		−307	−257	−242	−285	−146	−172	−215	−79	−96	−122	−35	−44	−20	−29	−46
80	100	−240	−180	−190	−190	−110	−110	−110	−56	−56	−56	−17	−17	0	0	0
		−327	−267	−271	−320	−162	−191	−240	−88	−108	−137	−40	−49	−23	−32	−52
100	120	−260	−200	−210	−210	−125	−125	−125	−62	−62	−62	−18	−18	0	0	0
		−360	−300	−299	−350	−182	−214	−265	−98	−119	−151	−43	−54	−25	−36	−57
120	140	−280	−210	−220	−220	−135	−135	−135	−68	−68	−68	−20	−20	0	0	0
		−380	−310	−310	−350	−198	−232	−290	−108	−131	−165	−47	−60	−27	−40	−63
140	160	−310	−230	−240	−240	−145	−145	−145	−72	−72	−72	−20	−20	0	0	0
		−410	−330	−340	−355	−170	−170	−170	−88	−108	−137	−40	−49	−23	−32	−52
160	180	−340	−240	−260	−260	−150	−150	−150	−75	−96	−122	−35	−44	−20	−29	−46
		−455	−355	−375	−395	−182	−214	−265	−98	−119	−151	−43	−54	−25	−36	−57
180	200	−380	−260	−280	−280	−162	−191	−240	−88	−108	−137	−40	−49	−23	−32	−52
		−495	−375	−420	−395	−198	−232	−290	−108	−131	−165	−47	−60	−27	−40	−63
200	225	−420	−280	−300	−300	−170	−170	−170	−88	−108	−137	−40	−49	−23	−32	−52
		−535	−395	−440	−440	−198	−232	−290	−108	−131	−165	−47	−60	−27	−40	−63
225	250	−480	−300	−320	−320	−198	−232	−290	−108	−131	−165	−47	−60	−27	−40	−63
		−610	−430	−440	−440	−210	−210	−210	−108	−131	−165	−47	−60	−27	−40	−63
250	280	−540	−330	−350	−350	−210	−210	−210	−108	−131	−165	−47	−60	−27	−40	−63
		−670	−460	−480	−480	−232	−232	−232	−108	−131	−165	−47	−60	−27	−40	−63
280	315	−600	−360	−380	−380	−225	−225	−225	−112	−112	−112	−49	−49	−28	−38	−66
		−740	−500	−520	−520	−250	−250	−250	−125	−125	−125	−56	−56	−32	−44	−76
315	355	−680	−400	−420	−420	−240	−240	−240	−120	−120	−120	−56	−56	−32	−44	−76
		−820	−540	−560	−560	−270	−270	−270	−135	−135	−135	−64	−64	−36	−50	−84
355	400	−760	−440	−460	−460	−250	−250	−250	−125	−125	−125	−56	−56	−32	−44	−76
		−915	−595	−610	−610	−280	−280	−280	−140	−140	−140	−64	−64	−36	−50	−84
400	450	−840	−480	−500	−500	−270	−270	−270	−135	−135	−135	−64	−64	−36	−50	−84
		−995	−635	−650	−650	−300	−300	−300	−150	−150	−150	−72	−72	−40	−56	−96
450	500	−840	−480	−500	−500	−270	−270	−270	−135	−135	−135	−64	−64	−36	−50	−84
		−995	−635	−650	−650	−300	−300	−300	−150	−150	−150	−72	−72	−40	−56	−96

Remarks: In each row of the above table, upper values represent upper deviations and lower values represent lower deviations.

[Excerpt from JIS B 0401-2 (1998)]

Unit: μm

Range of basic size (mm)		Tolerance class of shaft															
Over	Or less	h8	h9	js5	js6	js7	k5	k6	m5	m6	n6	p6	r6	s6	t6	u6	x6
—	3	0 -14	0 -25	± 2	± 3	± 5	+4 0	+6 0	+6 +2	+8 +2	+10 +4	+12 +6	+16 +10	+20 +14	—	+24 +18	+26 +20
3	6	0 -18	0 -30	± 2.5	± 4	± 6	+6 +1	+9 +1	+9 +4	+12 +4	+16 +8	+20 +12	+23 +15	+27 +19	—	+31 +23	+36 +28
6	10	0 -22	0 -36	± 3	± 4.5	± 7.5	+7 +1	+10 +1	+12 +6	+15 +6	+19 +10	+24 +15	+28 +19	+32 +23	—	+37 +28	+43 +34
10	14	0 -27	0 -43	± 4	± 5.5	± 9	+9 +1	+12 +1	+15 +7	+18 +7	+23 +12	+29 +18	+34 +23	+39 +28	—	+44 +33	+51 +40
14	18																+56 +45
18	24	0 -33	0 -52	± 4.5	± 6.5	± 10.5	+11 +2	+15 +2	+17 +8	+21 +8	+28 +15	+35 +22	+41 +28	+48 +35	—	+54 +41	+67 +54
24	30														+54 +41	+61 +48	+77 +64
30	40	0 -39	0 -62	± 5.5	± 8	± 12.5	+13 +2	+18 +2	+20 +9	+25 +9	+33 +17	+42 +26	+50 +34	+59 +43	+64 +48	+76 +60	+96 +80
40	50														+70 +54	+86 +70	+113 +97
50	65	0 -46	0 -74	± 6.5	± 9.5	± 15	+15 +2	+21 +2	+24 +11	+30 +11	+39 +20	+51 +32	+60 +41	+72 +53	+85 +66	+106 +87	+141 +122
65	80												+62 +43	+78 +59	+94 +75	+121 +102	+165 +146
80	100	0 -54	0 -87	± 7.5	± 11	± 17.5	+18 +3	+25 +3	+28 +13	+35 +13	+45 +23	+59 +37	+73 +51	+93 +71	+113 +91	+146 +124	+200 +178
100	120												+76 +54	+101 +79	+126 +104	+166 +144	+232 +210
120	140												+88 +63	+117 +92	+147 +122	+195 +170	+273 +248
140	160	0 -63	0 -100	± 9	± 12.5	± 20	+21 +3	+28 +3	+33 +15	+40 +15	+52 +27	+68 +43	+90 +65	+125 +100	+159 +134	+215 +190	+305 +280
160	180												+93 +68	+133 +108	+171 +146	+235 +210	+335 +310
180	200												+106 +77	+151 +122	+195 +166	+265 +236	+379 +350
200	225	0 -72	0 -115	± 10	± 14.5	± 23	+24 +4	+33 +4	+37 +17	+46 +17	+60 +31	+79 +50	+109 +80	+159 +130	+209 +180	+287 +258	+414 +385
225	250												+113 +84	+169 +140	+225 +196	+313 +284	+454 +425
250	280	0 -81	0 -130	± 11.5	± 16	± 26	+27 +4	+36 +4	+43 +20	+52 +20	+66 +34	+88 +56	+126 +94	+190 +158	+250 +218	+347 +315	+507 +475
280	315												+130 +98	+202 +170	+272 +240	+382 +350	+557 +525
315	355	0 -89	0 -140	± 12.5	± 18	± 28.5	+29 +4	+40 +4	+46 +21	+57 +21	+73 +37	+98 +62	+144 +108	+226 +190	+304 +268	+426 +390	+626 +590
355	400												+150 +114	+244 +208	+330 +294	+471 +435	+696 +660
400	450	0 -97	0 -155	± 13.5	± 20	± 31.5	+32 +5	+45 +5	+50 +23	+63 +23	+80 +40	+108 +68	+166 +126	+272 +232	+370 +330	+530 +490	+780 +740
450	500												+172 +132	+292 +252	+400 +360	+580 +540	+860 +820

Product Data /
Technical Data

Limit Deviations for Fits Used Frequently (Shaft)

Hardness Conversion Table [SAE J 417] Revised in 1983

Approximate Conversion Values for Rockwell C Hardness Values of Steel ⁽¹⁾

Rockwell C scale Hardness ⁽²⁾	Vickers hardness	Brinnell hardness 10 mm ball Load 3000 kgf		Rockwell hardness ⁽³⁾			Rockwell superficial hardness Diamond conical indenter			Shore hardness	Tensile strength (approximate value) Mpa {kgf/mm ² } ⁽²⁾	Rockwell C scale Hardness ⁽³⁾
		Standard ball	Tungsten carbide ball	A scale Load 60 kgf Diamond conical indenter	B scale Load 100 kgf Dia. 1.6 mm (1/16 in.) ball	D scale Load 100 kgf Diamond conical indenter	15-N scale Load 15 kgf	30-N scale Load 30 kgf	45-N scale Load 45 kgf			
HRC	HV	HBS	HBW	HRA	HRB	HRD	HR15N	HR30N	HR45N	HS	—	HRC
68	940	—	—	85.6	—	76.9	93.2	84.4	75.4	97	—	68
67	900	—	—	85.0	—	76.1	92.9	83.6	74.2	95	—	67
66	865	—	—	84.5	—	75.4	92.5	82.8	73.3	92	—	66
65	832	—	(739)	83.9	—	74.5	92.2	81.9	72.0	91	—	65
64	800	—	(722)	83.4	—	73.8	91.8	81.1	71.0	88	—	64
63	772	—	(705)	82.8	—	73.0	91.4	80.1	69.9	87	—	63
62	746	—	(688)	82.3	—	72.2	91.1	79.3	68.8	85	—	62
61	720	—	(670)	81.8	—	71.5	90.7	78.4	67.7	83	—	61
60	697	—	(654)	81.2	—	70.7	90.2	77.5	66.6	81	—	60
59	674	—	(634)	80.7	—	69.9	89.8	76.6	65.5	80	—	59
58	653	—	615	80.1	—	69.2	89.3	75.7	64.3	78	—	58
57	633	—	595	79.6	—	68.5	88.9	74.8	63.2	76	—	57
56	613	—	577	79.0	—	67.7	88.3	73.9	62.0	75	—	56
55	595	—	560	78.5	—	66.9	87.9	73.0	60.9	74	2075 {212}	55
54	577	—	543	78.0	—	66.1	87.4	72.0	59.8	72	2015 {205}	54
53	560	—	525	77.4	—	65.4	86.9	71.2	58.6	71	1950 {199}	53
52	544	(500)	512	76.8	—	64.6	86.4	70.2	57.4	69	1880 {192}	52
51	528	(487)	496	76.3	—	63.8	85.9	69.4	56.1	68	1820 {186}	51
50	513	(475)	481	75.9	—	63.1	85.5	68.5	55.0	67	1760 {179}	50
49	498	(464)	469	75.2	—	62.1	85.0	67.6	53.8	66	1695 {173}	49
48	484	451	455	74.7	—	61.4	84.5	66.7	52.5	64	1635 {167}	48
47	471	442	443	74.1	—	60.8	83.9	65.8	51.4	63	1580 {161}	47
46	458	432	432	73.6	—	60.0	83.5	64.8	50.3	62	1530 {156}	46
45	446	421	421	73.1	—	59.2	83.0	64.0	49.0	60	1480 {151}	45
44	434	409	409	72.5	—	58.5	82.5	63.1	47.8	58	1435 {146}	44
43	423	400	400	72.0	—	57.7	82.0	62.2	46.7	57	1385 {141}	43
42	412	390	390	71.5	—	56.9	81.5	61.3	45.5	56	1340 {136}	42
41	402	381	381	70.9	—	56.2	80.9	60.4	44.3	55	1295 {132}	41
40	392	371	371	70.4	—	55.4	80.4	59.5	43.1	54	1250 {127}	40
39	382	362	362	69.9	—	54.6	79.9	58.6	41.9	52	1215 {124}	39
38	372	353	353	69.4	—	53.8	79.4	57.7	40.8	51	1180 {120}	38
37	363	344	344	68.9	—	53.1	78.8	56.8	39.6	50	1160 {118}	37
36	354	336	336	68.4	(109.0)	52.3	78.3	55.9	38.4	49	1115 {114}	36
35	345	327	327	67.9	(108.5)	51.5	77.7	55.0	37.2	48	1080 {110}	35
34	336	319	319	67.4	(108.0)	50.8	77.2	54.2	36.1	47	1055 {108}	34
33	327	311	311	66.8	(107.5)	50.0	76.6	53.3	34.9	46	1025 {105}	33
32	318	301	301	66.3	(107.0)	49.2	76.1	52.1	33.7	44	1000 {102}	32
31	310	294	294	65.8	(106.0)	48.4	75.6	51.3	32.5	43	980 {100}	31
30	302	286	286	65.3	(105.5)	47.7	75.0	50.4	31.3	42	950 {97}	30
29	294	279	279	64.7	(104.5)	47.0	74.5	49.5	30.1	41	930 {95}	29
28	286	271	271	64.3	(104.0)	46.1	73.9	48.6	28.9	41	910 {93}	28
27	279	264	264	63.8	(103.0)	45.2	73.3	47.7	27.8	40	880 {90}	27
26	272	258	258	63.3	(102.5)	44.6	72.8	46.8	26.7	38	860 {88}	26
25	266	253	253	62.8	(101.5)	43.8	72.2	45.9	25.5	38	840 {86}	25
24	260	247	247	62.4	(101.0)	43.1	71.6	45.0	24.3	37	825 {84}	24
23	254	243	243	62.0	100.0	42.1	71.0	44.0	23.1	36	805 {82}	23
22	248	237	237	61.5	99.0	41.6	70.5	43.2	22.0	35	785 {80}	22
21	243	231	231	61.0	98.5	40.9	69.9	42.3	20.7	35	770 {79}	21
20	238	226	226	60.5	97.8	40.1	69.4	41.5	19.6	34	760 {77}	20
(18)	230	219	219	—	96.7	—	—	—	—	33	730 {75}	(18)
(16)	222	212	212	—	95.5	—	—	—	—	32	705 {72}	(16)
(14)	213	203	203	—	93.9	—	—	—	—	31	675 {69}	(14)
(12)	204	194	194	—	92.3	—	—	—	—	29	650 {66}	(12)
(10)	196	187	187	—	90.7	—	—	—	—	28	620 {63}	(10)
(8)	188	179	179	—	89.5	—	—	—	—	27	600 {61}	(8)
(6)	180	171	171	—	87.1	—	—	—	—	26	580 {59}	(6)
(4)	173	165	165	—	85.5	—	—	—	—	25	550 {56}	(4)
(2)	166	158	158	—	83.5	—	—	—	—	24	530 {54}	(2)
(0)	160	152	152	—	81.7	—	—	—	—	24	515 {53}	(0)

Note (1) Figures in blue are based on ASTM E 140, Table 1 (jointly prepared by SAE, ASM and ASTM).

(2) The units and figures shown in parentheses { } following the listed values are the results of conversion from psi figures by reference to JIS Z 8413 and Z8438 conversion tables. For your reference, 1MPa=1N/mm²

(3) The figures in parentheses () are in ranges not frequently used. They are given as reference data.

SI Unit Conversion Table / Weight & Measure Conversion table [Excerpt from JIS Handbook]

Conversion rate of JIS units upon switchover to SI units (units in red are SI Units)

Pressure

Pa	bar	kgf/cm ²	atm	mmH ₂ O	mmHg 又は Torr
1	1×10^{-5}	$1.019\,72 \times 10^{-5}$	$9.869\,23 \times 10^{-6}$	$1.019\,72 \times 10^{-1}$	$7.500\,62 \times 10^{-3}$
1×10^5	1	1.019 72	$9.869\,23 \times 10^{-1}$	$1.019\,72 \times 10^4$	$7.500\,62 \times 10^2$
$9.806\,65 \times 10^4$	$9.806\,65 \times 10^{-1}$	1	$9.678\,41 \times 10^{-1}$	1×10^4	$7.355\,59 \times 10^2$
$1.013\,25 \times 10^5$	1.013 25	1.033 23	1	$1.033\,23 \times 10^4$	$7.600\,00 \times 10^2$
9.806 65	$9.806\,65 \times 10^{-5}$	1×10^{-4}	$9.678\,41 \times 10^{-5}$	1	$7.355\,59 \times 10^{-2}$
$1.333\,22 \times 10^2$	$1.333\,22 \times 10^{-3}$	$1.359\,51 \times 10^{-3}$	$1.315\,79 \times 10^{-3}$	$1.359\,51 \times 10$	1

Note: $1\text{Pa} = 1\text{N/m}^2$

Specific heat

J/(kg·K)	kcal/(kg·°C), cal/(g·°C)
1	$2.388\,89 \times 10^{-4}$
$4.186\,05 \times 10^3$	1

Note: $1\text{cal} = 4.186\,05\text{J}$ (by Measurement Act)

Coefficient of heat transfer

W/(m ² ·K)	kcal/(h·m ² ·°C)
1	$8.600\,0 \times 10^{-1}$
1.162 79	1

Note: $1\text{cal} = 4.186\,05\text{J}$ (by Measurement Act)

Power (process rate, power), heat flow rate

kW	kgf·m/s	PS	kcal/h	Note: $1\text{W} = 1\text{J/s}$, PS: French horse power $1\text{PS} = 0.735\,5\text{kW}$ (by Act for Enforcement of Measurement Act) $1\text{cal} = 4.186\,05\text{J}$ (in accordance with Measurement Act)
1	$1.019\,72 \times 10^2$	1.359 62	$8.600\,0 \times 10^2$	
$9.806\,65 \times 10^{-3}$	1	$1.333\,33 \times 10^{-2}$	8.433 71	
7.355×10^{-1}	7.5×10	1	$6.325\,29 \times 10^2$	
$1.162\,79 \times 10^{-3}$	$1.185\,72 \times 10^{-1}$	$1.580\,95 \times 10^{-3}$	1	

Stress

Pa	MPa 又は N/mm ²	kgf/mm ²	kgf/cm ²
1	1×10^{-6}	$1.019\,72 \times 10^{-7}$	$1.019\,72 \times 10^{-5}$
1×10^6	1	$1.019\,72 \times 10^{-1}$	$1.019\,72 \times 10$
$9.806\,65 \times 10^6$	9.806 65	1	1×10^2
$9.806\,65 \times 10^4$	$9.806\,65 \times 10^{-2}$	1×10^{-2}	1

Work, energy & quantity of heat

J	kW·h	kgf·m	kcal
1	$2.777\,78 \times 10^{-7}$	$1.019\,72 \times 10^{-1}$	$2.388\,89 \times 10^{-4}$
3.600×10^6	1	$3.670\,98 \times 10^5$	$8.600\,0 \times 10^2$
9.806 65	$2.724\,07 \times 10^{-6}$	1	$2.342\,70 \times 10^{-3}$
$4.186\,05 \times 10^3$	$1.162\,79 \times 10^{-3}$	$4.268\,58 \times 10^2$	1

Note: $1\text{J} = 1\text{W} \cdot \text{s}$, $1\text{J} = 1\text{N} \cdot \text{m}$

$1\text{cal} = 4.186\,05\text{J}$ (by Measurement Act)

Weight & Measure Conversion Table

Measure comparison table

Shaku	Kan	Meter	Inch	Feet	Yard
1	0.166667	0.30303	11.9303	0.994194	0.33140
6	1	1.81818	71.5819	5.96516	1.98839
3.3	0.55	1	39.3701	3.28084	1.09361
0.08382	0.01397	0.0254	1	0.08333	0.02778
1.00584	0.16764	0.3048	12	1	0.33333
3.01752	0.50292	0.9144	36	3	1

Volume comparison table

Go	Cubic centimeter	Liter	Gallon (UK)	Gallon (US)	Cubic inch
1	180.39	0.18039	0.03968	0.04765	11.01
0.00554	1	0.001	0.00022	0.00026	0.06102
5.5435	1000	1	0.21997	0.26417	61.024
25.2	4546.09	4.54609	1	1.20095	277.42
20.98	3785.41	3.78541	0.833	1	231
0.0908	16.3871	0.01639	0.0036	0.0043	1

Weight comparison table

Kan	Kin	Gram	Ton (UK)	Ton (US)	Ounce	Pound
1	6.25	3750	0.003691	0.004134	132.277	8.26733
0.16	1	600	0.000591	0.000661	21.1644	1.32277
0.000267	0.001667	1	0.00000098	0.0000011	0.035274	0.0022046
262.4543	1640.339	1016050	1	1.12	35840	2240
241.916	1511.975	907185	0.892857	1	32000	2000
0.007569	0.047249	28.3495	0.000028	0.000031	1	0.0625
0.120958	0.755987	453.5924	0.000446	0.0005	16	1


Customer Guide

New Proposition for In-Mold Resin Pressure

Measurement, MOLD MARSHALLING SYSTEM.....	458
Company Profile.....	460
Catalog Request.....	462

Mold Marshalling System

What is Mold Marshalling System?



Mold marshalling system is a measuring system for injection molding that visualizes resin behavior inside the mold, which has been a black box so far.

It uses a sensor mounted inside the mold and a special amplifier installed outside to measure in-mold resin temperature and pressure, convert them into electrical signals or voltages and output the data on the PC or various measuring devices. Qualified data can be used for various purposes such as automated selection of defective products, quality control, evaluation of molds, etc.

Features

A variety of measurement & monitoring functions


Low cost

Easy to use


Functional

Compact


Ejector pin shaped pin sensor that can be easily mounted in the mold.




Visualize the in-mold resin temperature and pressure with waveforms.



An example of measurement screen



Examples of molding defects that can be determined from in-mold pressure values.



A New Proposal for In-Mold Resin Pressure / Temperature Measurement

Benefits of in-mold resin pressure measurements

Detection of defective products

- Alarm signals triggered by fluctuations in waveform with respect to a reference waveform notify the occurrence of molding defects such as short shots and over packing, etc.

Setting of molding conditions according to changes in molding machine or environment

- By saving a waveform when a good product has been produced and performing molding operations with the waveform, the same quality of molded products can be produced.

Analysis of mold structure and resin flow

- By analysing the time required until the resin reaches the sensor and the pressure during the period, products of uniform quality can be achieved at the time of multi-cavity molding.

Identification of relations of in-mold pressure and molding defects

- The type of potential defects can be projected by checking the pressure waveform against the good product waveform (reference waveform).

Benefits of in-mold resin temperature measurement

Actual measurement of resin temperature

- Accurate grasp of in-mold temperature is now possible.
Fast 8 ms response time for high-speed actual measurement. Contactless temperature measurement system (optical fiber infrared system)

Detection of defective products

- Alarm signals triggered by fluctuations in waveform with respect to a reference waveform notify the occurrence of molding defects such as short shots, sink marks, and gas burning, etc.

Optimization of molding conditions

- Molding conditions can be optimized through resin temperature controls

Comparison with CAE Analysis

- By comparing the CAE comparison results with the actual measurement, the data can be effectively utilized to improve the accuracy of CAE analysis.

Company Profile


Futaba's high technology connects dreams and future of people and society

Modern society is progressing rapidly and its needs becoming increasingly diversified. To respond to these needs, and helps the society develop further and achieve more in the future, advanced technologies are required. By utilizing its accumulated advanced technologies and experiences, Futaba is dedicated to developing new products that are needed and useful in every aspect of life, thereby contributing to dreams and future of people and society.

“Supports Manufacturing”

Machinery & tooling Division



Provides a wide variety of components and equipments that realize streamlining production of molds, which become the source of every product



“Eye Communication”

Electronic Components Division

Fluorescent display tubes boasting superior performance and reliability. We respond to needs flexibly with our advanced technology and a strong product development capability.



Electronic Systems Division

Radio control systems with overwhelming popularity appeals Futaba's advanced technology to the world.

Nurturing dreams

Radio control devices for hobby



Propositions to industries

Radio control devices for commercial use



Catalog Request

Please use our catalogs as an aid while designing prastic molding line or developing tools.

For prastic molds



BLUE BOOK Plastic Mold Components



BLUE BOOK Additional Mold Base Processing & Mold Parts Edition

For molds & Equipment




RED BOOK Plate general catalog



Red Book Plate general catalog for Equipment

For in-mold resin pressure & temp. measuring system



Mold Marshalling Sysmtem

For press die sets



Green Book press die sets Components

For Stamping & Plastic Molding Lines



Equipment For Automation General Catalog

Index

Catalog No. Code Index

Code	Name of Additional Processing, Component or Part	Page
C		
CGPGB1	Change Type and Length of Guide Pins ①	44
CGPGB2	Change Type and Length of Guide Pins ②	46
CGPGBS	Change Precision Guide Pins and Guide Bushings	42
CGPH	Change Specification of Guide Pin Holes	55
CIHRPN	Added Return Pin Holes and/or Change Return Pin Hole Diameter	68
CIHSPN	Change Clearance Holes for Support Pin	62
CILI	Change Tolerance of Plate Thickness	30
CIMA	Change Plate Materials	29
CIS1	Change Dimension and/or Installation Method of Clamping Plate -No Protrusion	22
CIS2	Change Dimension and/or Installation Method of Clamping Plate -2-Direction Protrusion	22
CIS3	Change Dimension and/or Installation Method of Clamping Plate -2-Direction Protrusion	22
CIS4	Change Dimension and/or Installation Method of Clamping Plate -3-Direction Protrusion	22
CIS5	Change Dimension and/or Installation Method of Clamping Plate -3-Direction Protrusion	22
CIS6	Change Dimension and/or Installation Method of Clamping Plate -3-Direction Protrusion	22
CIS7	Change Dimension and/or Installation Method of Clamping Plate -3-Direction Protrusion	22
CIS8	Change Dimension and/or Installation Method of Clamping Plate -4-Direction Protrusion	22
CISCEF	Change Width of Spacer Blocks and Ejector Plates	28
CISG	Surface Grind	31
CIT	Change Plate Thickness	24
CPD	Change Parts Diameter	40
CPHGBN	Change Installation of Guide Bushings and/or Added Guide Bushings Specification	48
CPHRP8	Change Return Pin Collars Thickness to 8 mm	66
CPHSP	Addition of H Series Support Pin Collars	60
CPL	Change Length of Return Pins, Assembly Screws, Puller Bolts	64
CPNP	Changing Position and the Number of Assembly Screws	74
CPP	Change Position of Parts	72
CPPZ	Added Counterbore for Puller Bolts (H Series)	80
CPRPT	Change Return Pin with Thread Holes ①	70
CPSPD	Change Support Pin Collars (Type M-SPD)	60
CPZL	Change Counterbore Depth of Puller Bolts (H Series)	81
CSET	Change Nominal Base Size	34
CSPGB	Change Type and Length of Support Pins	58
E		
ESI	Omit Standard Plates	36
ESM	Omit Threaded Holes for Standard Eyebolt	232
	Omit Standard Ejector Rod Holes	236
ESP	Omit Support Pin Collars	61
	Omit Standard Parts	82
ESH	Omit Installation Holes for Standard Parts	82
ESPH	Omit Standard Parts and Installation Holes	82
H		
HF	High-Precision Plates -High-Precision Milling Finish	262
HG	High-Precision Plates -High-Precision Grinding Finish	264
H-H		
H-HSB	Miniature Hot Sprue Bushings	358
H-HSB-TB1G	Terminal mounting box	360
H-HSB-CTA	Temperature controller	360

Code	Name of Additional Processing, Component or Part	Page
M		
MCH	Added Clamping Holes	240
MCM	Added Clamp Slot (For A-Plate or B-Plate)	241
MEH1	Added Ejector Rod Holes	236
MEH2	Added Ejector Rod Holes	236
MEH3	Added Ejector Rod Holes	236
MEH4A	Added Ejector Rod Holes	236
MEH4B	Added Ejector Rod Holes	236
MEH5A	Added Ejector Rod Holes	236
MEH5B	Added Ejector Rod Holes	236
MEH7	Added Ejector Rod Holes	236
MEH9	Added Ejector Rod Holes	236
MFG	Added Clamp Slot (For Clamping Plate)	238
MFK1A	Added Threaded Holes for Eyebolt (Side Surface Threaded Holes) -1 Hole	224
MFK1AL	Added Threaded Holes for Eyebolt (Side Surface Threaded Holes) -1 Hole	224
MFK1AR	Added Threaded Holes for Eyebolt (Side Surface Threaded Holes) -1 Hole	224
MFK1B	Added Threaded Holes for Eyebolt (Side Surface Threaded Holes) -1 Hole	224
MFK1BL	Added Threaded Holes for Eyebolt (Side Surface Threaded Holes) -1 Hole	224
MFK1BR	Added Threaded Holes for Eyebolt (Side Surface Threaded Holes) -1 Hole	224
MFK1C	Added Threaded Holes for Eyebolt (Side Surface Threaded Holes) -1 Hole	224
MFK1CL	Added Threaded Holes for Eyebolt (Side Surface Threaded Holes) -1 Hole	224
MFK1CR	Added Threaded Holes for Eyebolt (Side Surface Threaded Holes) -1 Hole	224
MFK1D	Added Threaded Holes for Eyebolt (Side Surface Threaded Holes) -1 Hole	224
MFK1DL	Added Threaded Holes for Eyebolt (Side Surface Threaded Holes) -1 Hole	224
MFK1DR	Added Threaded Holes for Eyebolt (Side Surface Threaded Holes) -1 Hole	224
MFK1H	Added Threaded Holes for Eyebolt (Side Surface Threaded Holes) (For C-Plate)	228
MFK1HL	Added Threaded Holes for Eyebolt (Side Surface Threaded Holes) (For C-Plate)	228
MFK1HR	Added Threaded Holes for Eyebolt (Side Surface Threaded Holes) (For C-Plate)	228
MFK1M	Added Threaded Holes for Eyebolt (Side Surface Threaded Holes) (For C-Plate)	228
MFK1ML	Added Threaded Holes for Eyebolt (Side Surface Threaded Holes) (For C-Plate)	228
MFK1MR	Added Threaded Holes for Eyebolt (Side Surface Threaded Holes) (For C-Plate)	228
MFK2AC	Added Threaded Holes for Eyebolt (Side Surface Threaded Holes) -2 Holes	226
MFK2ACL	Added Threaded Holes for Eyebolt (Side Surface Threaded Holes) -2 Holes	226
MFK2ACR	Added Threaded Holes for Eyebolt (Side Surface Threaded Holes) -2 Holes	226
MFK2AP	Added Threaded Holes for Eyebolt (Side Surface Threaded Holes) -2 Holes	226
MFK2BD	Added Threaded Holes for Eyebolt (Side Surface Threaded Holes) -2 Holes	226
MFK2BDL	Added Threaded Holes for Eyebolt (Side Surface Threaded Holes) -2 Holes	226
MFK2BDR	Added Threaded Holes for Eyebolt (Side Surface Threaded Holes) -2 Holes	226
MFK2BP	Added Threaded Holes for Eyebolt (Side Surface Threaded Holes) -2 Holes	226
MFK2CP	Added Threaded Holes for Eyebolt (Side Surface Threaded Holes) -2 Holes	226
MFK2DP	Added Threaded Holes for Eyebolt (Side Surface Threaded Holes) -2 Holes	226
MFK4	Added Threaded Holes for Eyebolt (Side Surface Threaded Holes) -4 Holes	226
MFK4ACP	Added Threaded Holes for Eyebolt (Side Surface Threaded Holes) -4 Holes	226
MFK4BDP	Added Threaded Holes for Eyebolt (Side Surface Threaded Holes) -4 Holes	226
MGK1A	Added Threaded Holes for Eyebolt (Side Surface Threaded Holes) (Thread Depth Designation) -1 Hole	224
MGK1AL	Added Threaded Holes for Eyebolt (Side Surface Threaded Holes) (Thread Depth Designation) -1 Hole	224
MGK1AR	Added Threaded Holes for Eyebolt (Side Surface Threaded Holes) (Thread Depth Designation) -1 Hole	224
MGK1B	Added Threaded Holes for Eyebolt (Side Surface Threaded Holes) (Thread Depth Designation) -1 Hole	224
MGK1BL	Added Threaded Holes for Eyebolt (Side Surface Threaded Holes) (Thread Depth Designation) -1 Hole	224
MGK1BR	Added Threaded Holes for Eyebolt (Side Surface Threaded Holes) (Thread Depth Designation) -1 Hole	224
MGK1C	Added Threaded Holes for Eyebolt (Side Surface Threaded Holes) (Thread Depth Designation) -1 Hole	224
MGK1CL	Added Threaded Holes for Eyebolt (Side Surface Threaded Holes) (Thread Depth Designation) -1 Hole	224
MGK1CR	Added Threaded Holes for Eyebolt (Side Surface Threaded Holes) (Thread Depth Designation) -1 Hole	224

Catalog No. Code Index

Code	Name of Additional Processing, Component or Part	Page
MGK1D	Added Threaded Holes for Eyebolt (Side Surface Threaded Holes) (Thread Depth Designation) -1 Hole	224
MGK1DL	Added Threaded Holes for Eyebolt (Side Surface Threaded Holes) (Thread Depth Designation) -1 Hole	224
MGK1H	Added Threaded Holes for Eyebolt (Side Surface Threaded Holes) (Thread Depth Designation) (For C Plate)	228
MGK1HL	Added Threaded Holes for Eyebolt (Side Surface Threaded Holes) (Thread Depth Designation) (For C Plate)	228
MGK1HR	Added Threaded Holes for Eyebolt (Side Surface Threaded Holes) (Thread Depth Designation) (For C Plate)	228
MGK1M	Added Threaded Holes for Eyebolt (Side Surface Threaded Holes) (Thread Depth Designation) (For C Plate)	228
MGK1ML	Added Threaded Holes for Eyebolt (Side Surface Threaded Holes) (Thread Depth Designation) (For C Plate)	228
MGK1MR	Added Threaded Holes for Eyebolt (Side Surface Threaded Holes) (Thread Depth Designation) (For C Plate)	228
MGK1DR	Added Threaded Holes for Eyebolt (Side Surface Threaded Holes) (Thread Depth Designation) -1 Hole	224
MGK2AC	Added Threaded Holes for Eyebolt (Side Surface Threaded Holes) (Thread Depth Designation) -2 Holes	226
MGK2ACL	Added Threaded Holes for Eyebolt (Side Surface Threaded Holes) (Thread Depth Designation) -2 Holes	226
MGK2ACR	Added Threaded Holes for Eyebolt (Side Surface Threaded Holes) (Thread Depth Designation) -2 Holes	226
MGK2AP	Added Threaded Holes for Eyebolt (Side Surface Threaded Holes) (Thread Depth Designation) -2 Holes	226
MGK2BD	Added Threaded Holes for Eyebolt (Side Surface Threaded Holes) (Thread Depth Designation) -2 Holes	226
MGK2BDL	Added Threaded Holes for Eyebolt (Side Surface Threaded Holes) (Thread Depth Designation) -2 Holes	226
MGK2BDR	Added Threaded Holes for Eyebolt (Side Surface Threaded Holes) (Thread Depth Designation) -2 Holes	226
MGK2BP	Added Threaded Holes for Eyebolt (Side Surface Threaded Holes) (Thread Depth Designation) -2 Holes	226
MGK2CP	Added Threaded Holes for Eyebolt (Side Surface Threaded Holes) (Thread Depth Designation) -2 Holes	226
MGK2DP	Added Threaded Holes for Eyebolt (Side Surface Threaded Holes) (Thread Depth Designation) -2 Holes	226
MGK4	Added Threaded Holes for Eyebolt (Side Surface Threaded Holes) (Thread Depth Designation) -4 Holes	226
MGK4ACP	Added Threaded Holes for Eyebolt (Side Surface Threaded Holes) (Thread Depth Designation) -4 Holes	226
MGK4BDP	Added Threaded Holes for Eyebolt (Side Surface Threaded Holes) (Thread Depth Designation) -4 Holes	226
MGPHN	Added Clearance Holes for Guide Pin	54
MHH1AKL	Channels for Water, Oil and Heater -1 Hole	194
MHH1AKR	Channels for Water, Oil and Heater -1 Hole	194
MHH1ATL	Channels for Water, Oil and Heater -1 Hole	194
MHH1ATR	Channels for Water, Oil and Heater -1 Hole	194
MHH1BKL	Channels for Water, Oil and Heater -1 Hole	194
MHH1BKR	Channels for Water, Oil and Heater -1 Hole	194
MHH1BTL	Channels for Water, Oil and Heater -1 Hole	194
MHH1BTR	Channels for Water, Oil and Heater -1 Hole	194
MHH1CTL	Channels for Water, Oil and Heater -1 Hole	194
MHH1CTR	Channels for Water, Oil and Heater -1 Hole	194
MHH1DTL	Channels for Water, Oil and Heater -1 Hole	194
MHH1DTR	Channels for Water, Oil and Heater -1 Hole	194
MHH2AKP	Channels for Water, Oil and Heater -2 Holes	196
MHH2AKZ	Channels for Water, Oil and Heater -2 Holes	196
MHH2ATP	Channels for Water, Oil and Heater -2 Holes	196
MHH2ATZ	Channels for Water, Oil and Heater -2 Holes	196
MHH2BKP	Channels for Water, Oil and Heater -2 Holes	196
MHH2BKZ	Channels for Water, Oil and Heater -2 Holes	196
MHH2BTP	Channels for Water, Oil and Heater -2 Holes	196
MHH2BTZ	Channels for Water, Oil and Heater -2 Holes	196
MHH2CTP	Channels for Water, Oil and Heater -2 Holes	196
MHH2CTZ	Channels for Water, Oil and Heater -2 Holes	196
MHH2DTP	Channels for Water, Oil and Heater -2 Holes	196
MHH2DTZ	Channels for Water, Oil and Heater -2 Holes	196
MHH3AZP	Channels for Water & Oil -Circulation Type	198
MHH3AZZ	Channels for Water & Oil -Circulation Type	198
MHH3BZP	Channels for Water & Oil -Circulation Type	198
MHH3BZZ	Channels for Water & Oil -Circulation Type	198
MHH3CZP	Channels for Water & Oil -Circulation Type	198
MHH3CZZ	Channels for Water & Oil -Circulation Type	198
MHH3DZP	Channels for Water & Oil -Circulation Type	198

Code	Name of Additional Processing, Component or Part	Page
MHH3DZZ	Channels for Water & Oil -Circulation Type	198
MHK1A	Added Threaded Holes for Eyebolt (Side Surface Threaded Holes) (Prepared Hole Depth Designation) -1 Hole	224
MHK1AL	Added Threaded Holes for Eyebolt (Side Surface Threaded Holes) (Prepared Hole Depth Designation) -1 Hole	224
MHK1AR	Added Threaded Holes for Eyebolt (Side Surface Threaded Holes) (Prepared Hole Depth Designation) -1 Hole	224
MHK1B	Added Threaded Holes for Eyebolt (Side Surface Threaded Holes) (Prepared Hole Depth Designation) -1 Hole	224
MHK1BL	Added Threaded Holes for Eyebolt (Side Surface Threaded Holes) (Prepared Hole Depth Designation) -1 Hole	224
MHK1BR	Added Threaded Holes for Eyebolt (Side Surface Threaded Holes) (Prepared Hole Depth Designation) -1 Hole	224
MHK1C	Added Threaded Holes for Eyebolt (Side Surface Threaded Holes) (Prepared Hole Depth Designation) -1 Hole	224
MHK1CL	Added Threaded Holes for Eyebolt (Side Surface Threaded Holes) (Prepared Hole Depth Designation) -1 Hole	224
MHK1CR	Added Threaded Holes for Eyebolt (Side Surface Threaded Holes) (Prepared Hole Depth Designation) -1 Hole	224
MHK1D	Added Threaded Holes for Eyebolt (Side Surface Threaded Holes) (Prepared Hole Depth Designation) -1 Hole	224
MHK1DL	Added Threaded Holes for Eyebolt (Side Surface Threaded Holes) (Prepared Hole Depth Designation) -1 Hole	224
MHK1DR	Added Threaded Holes for Eyebolt (Side Surface Threaded Holes) (Prepared Hole Depth Designation) -1 Hole	224
MHK1H	Added Threaded Holes for Eyebolt (Side Surface Threaded Holes) (Prepared Hole Depth Designation) (For C Plate)	228
MHK1HL	Added Threaded Holes for Eyebolt (Side Surface Threaded Holes) (Prepared Hole Depth Designation) (For C Plate)	228
MHK1HR	Added Threaded Holes for Eyebolt (Side Surface Threaded Holes) (Prepared Hole Depth Designation) (For C Plate)	228
MHK1M	Added Threaded Holes for Eyebolt (Side Surface Threaded Holes) (Prepared Hole Depth Designation) (For C Plate)	228
MHK1ML	Added Threaded Holes for Eyebolt (Side Surface Threaded Holes) (Prepared Hole Depth Designation) (For C Plate)	228
MHK1MR	Added Threaded Holes for Eyebolt (Side Surface Threaded Holes) (Prepared Hole Depth Designation) (For C Plate)	228
MHK2AC	Added Threaded Holes for Eyebolt (Side Surface Threaded Holes) (Prepared Hole Depth Designation) -2 Holes	226
MHK2ACL	Added Threaded Holes for Eyebolt (Side Surface Threaded Holes) (Prepared Hole Depth Designation) -2 Holes	226
MHK2ACR	Added Threaded Holes for Eyebolt (Side Surface Threaded Holes) (Prepared Hole Depth Designation) -2 Holes	226
MHK2AP	Added Threaded Holes for Eyebolt (Side Surface Threaded Holes) (Prepared Hole Depth Designation) -2 Holes	226
MHK2BD	Added Threaded Holes for Eyebolt (Side Surface Threaded Holes) (Prepared Hole Depth Designation) -2 Holes	226
MHK2BDL	Added Threaded Holes for Eyebolt (Side Surface Threaded Holes) (Prepared Hole Depth Designation) -2 Holes	226
MHK2BDR	Added Threaded Holes for Eyebolt (Side Surface Threaded Holes) (Prepared Hole Depth Designation) -2 Holes	226
MHK2BP	Added Threaded Holes for Eyebolt (Side Surface Threaded Holes) (Prepared Hole Depth Designation) -2 Holes	226
MHK2CP	Added Threaded Holes for Eyebolt (Side Surface Threaded Holes) (Prepared Hole Depth Designation) -2 Holes	226
MHK2DP	Added Threaded Holes for Eyebolt (Side Surface Threaded Holes) (Prepared Hole Depth Designation) -2 Holes	226
MHK4	Added Threaded Holes for Eyebolt (Side Surface Threaded Holes) (Prepared Hole Depth Designation) -4 Holes	226
MHK4ACP	Added Threaded Holes for Eyebolt (Side Surface Threaded Holes) (Prepared Hole Depth Designation) -4 Holes	226
MHK4BDP	Added Threaded Holes for Eyebolt (Side Surface Threaded Holes) (Prepared Hole Depth Designation) -4 Holes	226
MKKB1/PL	Rough Pockets Machining -Rectangle with Rounded Corners (Inside Corner R) (Blind Pocket)	206
MKKB1/UR	Rough Pockets Machining -Rectangle with Rounded Corners (Inside Corner R) (Blind Pocket)	206
MKKB2/PL	Rough Pockets Machining -Rectangle with Rounded Corners (Outside Corner R) (Blind Pocket)	208
MKKB2/UR	Rough Pockets Machining -Rectangle with Rounded Corners (Outside Corner R) (Blind Pocket)	208
MKKC1/PL	Rough Pockets Machining -Circular Pocket (1 Hole) (Blind Pocket)	210
MKKC1/UR	Rough Pockets Machining -Circular Pocket (1 Hole) (Blind Pocket)	210
MKKC2/PL	Rough Pockets Machining -Circular Pocket (2 Holes) (Blind Pocket)	210
MKKC2/UR	Rough Pockets Machining -Circular Pocket (2 Holes) (Blind Pocket)	210
MKKC4/PL	Rough Pockets Machining -Circular Pocket (4 Holes) (Blind Pocket)	210
MKKC4/UR	Rough Pockets Machining -Circular Pocket (4 Holes) (Blind Pocket)	210
MKKJA/PL	Rough Pockets Machining -Blind Groove (Outside Corner R)	220
MKKJB/PL	Rough Pockets Machining -Blind Groove (Outside Corner R)	220
MKKJC/PL	Rough Pockets Machining -Blind Groove (Outside Corner R)	220
MKKJD/PL	Rough Pockets Machining -Blind Groove (Outside Corner R)	220
MKKMA/PL	Rough Pockets Machining -Slide Core Groove	216
MKKMB/PL	Rough Pockets Machining -Slide Core Groove	216
MKKMC/PL	Rough Pockets Machining -Slide Core Groove	216
MKKMD/PL	Rough Pockets Machining -Slide Core Groove	216
MKKRA/PL	Rough Pockets Machining -Blind Groove (Inside Corner R)	218
MKKRB/PL	Rough Pockets Machining -Blind Groove (Inside Corner R)	218
MKKRC/PL	Rough Pockets Machining -Blind Groove (Inside Corner R)	218
MKKRD/PL	Rough Pockets Machining -Blind Groove (Inside Corner R)	218

Catalog No. Code Index

Code	Name of Additional Processing, Component or Part	Page
MKKS1/PL	Rough Pockets Machining -Through Groove	214
MKKS1/UR	Rough Pockets Machining -Through Groove	214
MKKS2/PL	Rough Pockets Machining -Through Groove	214
MKKS2/UR	Rough Pockets Machining -Through Groove	214
MOKB1/PL	Rough Pockets Machining -Rectangular with Rounded Corners (Inside Corner R) (Through Pocket)	206
MOKB2/PL	Rough Pockets Machining -Rectangular with Rounded Corners (Outside Corner R) (Through Pocket)	208
MOKC1/PL	Rough Pockets Machining -Circular Pocket (1 Hole) (Through Pocket)	210
MOKC2/PL	Rough Pockets Machining -Circular Pocket (2 Holes) (Through Pocket)	210
MOKC4/PL	Rough Pockets Machining -Circular Pocket (4 Holes) (Through Pocket)	210
MRPTZ	Change Return Pin with Thread Holes ②	71
MSH1	Machining Holes for Coil Springs ①	136
MSH2	Machining Holes for Coil Springs ①	136
MSH3	Machining Holes for Coil Springs ①	136
MSH4	Machining Holes for Coil Springs ①	136
MSH5	Machining Holes for Coil Springs ①	136
MSHF	Machining Holes for Coil Springs ②	138
MUM1	Added U Ditch for Clamping	240
MUM2	Added U Ditch for Clamping	240
MYKB1/PL	Pocket Gas Cutting -Rectangular Pocket	212
MYKC1/PL	Pocket Gas Cutting -Circular Pocket (1 Hole)	212
MYKC2/PL	Pocket Gas Cutting -Circular Pocket (2 Holes)	212
MYKC4/PL	Pocket Gas Cutting -Circular Pocket (4 Holes)	212
MZT2AC	Added Side Surface Threaded Holes with Counterbore -2 Holes	234
MZT2ACL	Added Side Surface Threaded Holes with Counterbore -2 Holes	234
MZT2ACR	Added Side Surface Threaded Holes with Counterbore -2 Holes	234
MZT2BD	Added Side Surface Threaded Holes with Counterbore -2 Holes	234
MZT2BDL	Added Side Surface Threaded Holes with Counterbore -2 Holes	234
MZT2BDR	Added Side Surface Threaded Holes with Counterbore -2 Holes	234
MZT4ACP	Added Side Surface Threaded Holes with Counterbore -4 Holes	234
MZT4BDP	Added Side Surface Threaded Holes with Counterbore -4 Holes	234

M-A

M-AGA	Angular Pins	303
--------------	--------------	------------

M-B

M-BSA	Base Spacers	394
--------------	--------------	------------

M-D

M-DNAC	Heat Insulator Sheets Bakelite Cloth	412
M-DNAP	Heat Insulator Sheets Bakelite Paper	410
M-DNBR	Heat Insulator Sheets Basic Grade	414
M-DNHR	Heat Insulator Sheets Het Resisting Grade	416
M-DNLR	Heat Insulator Sheets High Temperature Resisting Grade	420
M-DNSR	Heat Insulator Sheets High Strength Grade	418
M-DSA	Disc Spacer for M-TLBS	301
M-DSB	Disc Spacer for M-TLBS	301
M-DSC	Disc Spacer for M-TLBS	301
M-DSD	Disc Spacers for M-TLCS, M-TLDS, M-TLGS and M-TLHS	302
M-DSE	Disc Spacers for M-TLCS, M-TLDS, M-TLGS and M-TLHS	302
M-DSF	Disc Spacers for M-TLCS, M-TLDS, M-TLGS and M-TLHS	302

M-E

M-EBB	Ejector Guide Bushings -JIS Type	330
M-EBBM	Ejector Guide Bushings - 5 μm Range Type	336

Code	Name of Additional Processing, Component or Part	Page
M-EBC	Ejector Guide Bushings –Self Lubricating, Heat Resisting Type	333
M-EBD	Ejector Guide Bushings -Linear Motion Bearing Type	331
M-EBG	Ejector Guide Bushings –Self Lubricating, Copper Alloy Type	332
M-EBS	Spacers for Ejector Guide Bushing	331
M-EGA	Ejector Guide Pins -Retaining Ring Type	326
M-EGB	Ejector Guide Pins -JIS Centering Location Type	327
M-EGBM	Ejector Guide Pins - Centering Location Type (in 5 μ m Range)	334
M-EGC	Ejector Guide Pin -JIS Stuck-Out Type	328
M-EGCM	Ejector Guide Pin - Stuck-Out Type (in 5 μ m Range)	335
M-ERA	Ejector Rods	346

M-F

M-FSB	Coil Springs	396
--------------	--------------	------------

M-G

M-GBA	Guide Bushings -Shoulder Type (No Oil Groove)	286
M-GBB	Guide Bushings -Straight Type (No Oil Groove)	287
M-GBGDF	Guide Bushings -Shoulder, Self Lubricating, Copper Alloy Type	292
M-GBGF	Guide Bushings -Shoulder Type (With Oil Groove)	290
M-GBHF	Precision Guide Bushings -Shoulder Type (With Oil Groove)	288
M-GBRDF	Guide Bushings -Straight, Self Lubricating, Copper Alloy Type	293
M-GBRF	Guide Bushings -Straight Type (With Oil Groove)	291
M-GBSF	Precision Guide Bushings -Straight Type (With Oil Groove)	289
M-GPA	Guide Pins -Head Type (with Oil Groove)	274
M-GPH	Precision Guide Pins -Head Type (No Oil Groove)	278
M-GPHF	Precision Guide Pins -Head, Press-Fit Length Designation Type (No Oil Groove)	279
M-GPHFS	Precision Guide Pins -Head, Press-Fit Length Designation Type (With Spiral Oil Groove)	280
M-GPSF	Precision Guide Pins -Straight, Press-Fit Length Designation Type (No Oil Groove)	282
M-GPSFR	Precision Guide Pins -Straight, Press-Fit Length Designation Type (With Oil Groove)	283
M-GPSFS	Precision Guide Pins -Straight, Press-Fit Length Designation Type (With Spiral Oil Groove)	284

M-H

M-HLA	Tension Links	316
M-HLB	Tension Links	317
M-HRA	Retainers for Tension Link	318
M-HRB	Retainers for Tension Link	318

M-I

M-IBM	Eye Bolts	395
--------------	-----------	------------

M-L

M-LRA	Locating Rings	352
M-LRB	Locating Rings	354
M-LRC	Locating Rings	352
M-LRD	Locating Rings	356
M-LRE	Locating Rings	356
M-LRF	Locating Rings	356
M-LRG	Locating Rings	354
M-LRH	Locating Rings	352
M-LRJ	Locating Rings	354

M-O

M-OPB	Mold Opening Prevention Plate (Color Red, Yellow and Black)	321
M-OPC	Mold Opening Prevention Plate (Color Red, Yellow and Black)	321

Catalog No. Code Index

Code	Name of Additional Processing, Component or Part	Page
M-P		
M-PBA	Puller Bolts	313
M-PBAH	Ground Puller Bolts	310
M-PBB	Puller Bolts	314
	Bolts for Tension Link	318
M-PBC	Puller Bolts	312
M-PBCH	Ground Puller Bolts	308
M-PCA	Puller Bolt Collars	315
M-PCB	Puller Bolt Collars	315
M-PGBA	Pin-Point Gate Bushings	388
M-PGBB	Pin-Point Gate Bushings	388
M-PLLA	PL Pullers (Sets)	320
M-PLLM	PL Pullers (Tapered Bolt)	320
M-PLLS	PL Pullers (Plastic Sleeve)	320
M-R		
M-RLA	Runner Lock Pins	387
M-RP8B	Return Pins -Head Thick 8mm Type	337
M-RP8L	Return Pins -Head Thick 8 mm, L Dimension Designation Type- (Unit: 0.1 mm)	340
M-RP8M	Return Pins -Head Thick 8 mm, L Dimension Designation Type- (Unit: 0.01mm)	340
M-RP8N	Return Pins -Head Thick 8 mm, L Dimension Designation Type- (Unit: 1 mm)	338
M-RPL	Return Pins -Head Thick 4 mm, L Dimension Designation Type- (Unit: 0.1 mm)	341
M-RPM	Return Pins -Head Thick 4 mm, L Dimension Designation Type- (Unit: 0.01mm)	341
M-RPN	Return Pins -Head Thick 4 mm, L Dimension Designation Type- (Unit: 1 mm)	338
M-S		
M-SAGD	Sprue Bushings -Bolt Hole Type	378
M-SAGF	Sprue Bushings -Bolt Hole Type	378
M-SAGS	Sprue Bushings -Bolt Hole Type	378
M-SBA	Sprue Bushings -Bolt Hole, Straight Type (Futaba Original)	372
M-SBB	Sprue Bushings -Shoulder, Straight Type (Futaba Original)	373
M-SBC	Sprue Bushings -Bolt Hole, Straight Type (Futaba Original)	372
M-SBD	Sprue Bushings -Shoulder, Straight Type (Futaba Original)	373
M-SBED	Sprue Bushings -Shoulder, Straight Type	384
M-SBEF	Sprue Bushings -Shoulder, Straight Type	384
M-SBES	Sprue Bushings -Shoulder, Straight Type	384
M-SBFD	Sprue Bushings -Shoulder, Tapered Type	384
M-SBFF	Sprue Bushings -Shoulder, Tapered Type	384
M-SBFS	Sprue Bushings -Shoulder, Tapered Type	384
M-SBGD	Sprue Bushings -Bolt Hole, Straight, Head Thick 10 mm Type	380
M-SBGF	Sprue Bushings -Bolt Hole, Straight, Head Thick 10 mm Type	380
M-SBGS	Sprue Bushings -Bolt Hole, Straight, Head Thick 10 mm Type	380
M-SBHD	Sprue Bushings -Bolt Hole, Tapered, Head Thick 10 mm Type	380
M-SBHF	Sprue Bushings -Bolt Hole, Tapered, Head Thick 10 mm Type	380
M-SBHS	Sprue Bushings -Bolt Hole, Tapered, Head Thick 10 mm Type	380
M-SBID	Sprue Bushings -Bolt Hole, Straight, Head Thick 15 mm Type	382
M-SBIF	Sprue Bushings -Bolt Hole, Straight, Head Thick 15 mm Type	382
M-SBJD	Sprue Bushings -Bolt Hole, Tapered, Head Thick 15 mm Type	382
M-SBJF	Sprue Bushings -Bolt Hole, Tapered, Head Thick 15 mm Type	382
M-SBLH	Sprue Bushings -Cooling Channel Type	362
M-SJAC	Sprue Bushings -Bolt Hole, Straight Type (JIS)	374
M-SJAD	Sprue Bushings -Bolt Hole, Straight Type (JIS)	374
M-SJAF	Sprue Bushings -Bolt Hole, Straight Type (JIS)	374

Code	Name of Additional Processing, Component or Part	Page
M-SJBD	Sprue Bushings -Bolt Hole, Tapered Type (JIS)	374
M-SJBF	Sprue Bushings -Bolt Hole, Tapered Type (JIS)	374
M-SJCC	Sprue Bushings -Shoulder, Straight Type (JIS)	376
M-SJCD	Sprue Bushings -Shoulder, Straight Type (JIS)	376
M-SJCF	Sprue Bushings -Shoulder, Straight Type (JIS)	376
M-SJDD	Sprue Bushings -Shoulder, Tapered Type (JIS)	376
M-SJDF	Sprue Bushings -Shoulder, Tapered Type (JIS)	376
M-SPC	Support Pin Collars	297
M-SPD	Support Pin Collars	297
M-SPHF	Precision Support Pins -Head, Press-Fit Length Designation Type (No Oil Groove)	295
M-SPHFS	Precision Support Pins -Head, Press-Fit Length Designation Type (with Spiral Oil Groove)	296
M-SPN	Support Pin -Head Type (With Oil Groove)	294
M-SPR	Spacer Rings -D-Cut Type	345
M-SPR5B	Spacer Rings -Circle Type	345
M-SPR6B	Spacer Rings -Circle Type	345
M-SPR8B	Spacer Rings -Circle Type	345
M-SPR10B	Spacer Rings -Circle Type	345
M-SPR12B	Spacer Rings -Circle Type	345
M-SRC	Support Pillars -Dowel Type	343
M-SRD	Support Pillars -Screw Hole Type	342
M-SRE	Support Pillars -Bolt Hole Type	344
M-STP	Stop Pins	345
M-STPH	Stop Pins	345
M-STR	Stop Rings	345

M-T

M-TLBB	Taper Guide Pin Sets -JIS Type (Precision) (Bushings)	300
M-TLBP	Taper Guide Pin Sets -JIS Type (Precision) (Pins)	300
M-TLBS	Taper Guide Pin Sets -JIS Type (Precision) (Sets)	300
M-TLCB	Taper Guide Pin Sets -Bolt PL Installation Type (Precision) (Bushings)	298
M-TLCP	Taper Guide Pin Sets -Bolt PL Installation Type (Precision) (Pins)	298
M-TLCS	Taper Guide Pin Sets -Bolt PL Installation Type (Precision) (Sets)	298
M-TLDB	Taper Guide Pin Sets -Bolt PL Installation Type (Super Precision) (Bushings)	298
M-TLDP	Taper Guide Pin Sets -Bolt PL Installation Type (Super Precision) (Pins)	298
M-TLDS	Taper Guide Pin Sets -Bolt PL Installation Type (Super Precision) (Sets)	298
M-TLGB	Taper Guide Pin Sets -Basic Type (Precision) (Bushings)	299
M-TLGP	Taper Guide Pin Sets -Basic Type (Precision) (Pins)	299
M-TLGS	Taper Guide Pin Sets -Basic Type (Precision) (Sets)	299
M-TLHB	Taper Guide Pin Sets -Basic Type (Super Precision) (Bushings)	299
M-TLHP	Taper Guide Pin Sets -Basic Type (Super Precision) (Pins)	299
M-TLHS	Taper Guide Pin Sets -Basic Type (Super Precision) (Sets)	299
M-TR	Coil Springs	400
M-TY	Coil Springs	398

P

P-TF	Coil Springs	402
PBSA	Added Base Spacers	188
PCSMS	Added Assembly Screws	76
PCSMU	Added Assembly Screws	76
PEGA	Added Ejector Guide Pin M-EGA	120
PEGAS	Added Ejector Guide Pin M-EGA (Standard Position)	132
PEGB	Added Ejector Guide Pin M-EGB	122
PEGBM	Added Ejector Guide Pin M-EGBM	126
PEGBMS	Added Ejector Guide Pin M-EGBM (Standard Position)	132

Catalog No. Code Index

Code	Name of Additional Processing, Component or Part	Page
PEGBMT	Added Ejector Guide Pin M-EGBM (Stuck-Out Specification)	126
PEGBMTS	Added Ejector Guide Pin M-EGBM (Stuck-Out Specification, Standard Position)	132
PEGBS	Added Ejector Guide Pin M-EGB (Standard Position)	132
PEGBT	Added Ejector Guide Pin M-EGB (Stuck-Out Specification) (Standard Position)	122
PEGBTS	Added Ejector Guide Pin M-EGB (Stuck-Out Specification) (Standard Position)	132
PEGC	Added Ejector Guide Pin M-EGC	124
PEGCM	Added Ejector Guide Pin M-EGCM	128
PEGPA	Added Ejector Guide Pin M-GPA	130
PEGPHF	Added Ejector Guide Pin M-GPHF	130
PERA1	Added Ejector Rod M-ERA	146
PERA2	Added Ejector Rod M-ERA	146
PERA3	Added Ejector Rod M-ERA	146
PERA4A	Added Ejector Rod M-ERA	146
PERA4B	Added Ejector Rod M-ERA	146
PERA5A	Added Ejector Rod M-ERA	146
PERA5B	Added Ejector Rod M-ERA	146
PERA7	Added Ejector Rod M-ERA	146
PERA9	Added Ejector Rod M-ERA	146
PHLA	Added Tension Link M-HLA	176
PHLB	Added Tension Link M-HLB	178
PIBM	Added Eye Bolts	231
PLRA	Added Locating Ring M-LRA	88
PLRB	Added Locating Ring M-LRB	88
PLRC	Added Locating Ring M-LRC	88
PLRD	Added Locating Ring M-LRD	88
PLRE	Added Locating Ring M-LRE	88
PLRF	Added Locating Ring M-LRF	90
PLRG	Added Locating Ring M-LRG	90
PLRH	Added Locating Ring M-LRH	88
PLRJ	Added Locating Ring M-LRJ	88
POPB	Added Mold Opening Prevention Plate M-OPB	184
POPC	Added Mold Opening Prevention Plate M-OPC	184
PPBA1	Added Puller Bolts -A1	166
PPBA2	Added Puller Bolts -A2	168
PPBAH1	Added Puller Bolts -AH1	164
PPBAH2	Added Puller Bolts -AH 2	168
PPBAHS	Added Puller Bolts -Standard Position	170
PPBAS	Added Puller Bolts -Standard Position	170
PPBB1	Added Puller Bolts -B1	154
PPBB2	Added Puller Bolts -B2	156
PPBB3	Added Puller Bolts -B3	158
PPBB4	Added Puller Bolts -B4	160
PPBB5	Added Puller Bolts -B5	162
PPLLA1	Added PL Pullers M-PLLA	180
PPLLA2	Added PL Pullers M-PLLA	180
PPLLA3	Added PL Pullers M-PLLA	180
PPLLA4	Added PL Pullers M-PLLA	180
PSB1N	Added Sprue Bushings -Bolt Hole Type	94
PSB1Z	Added Sprue Bushings -Bolt Hole Type	94
PSB2N	Added Sprue Bushings -Shoulder Type	96
PSB2Z	Added Sprue Bushings -Shoulder Type	96
PSH1N	Added Coil Springs ①	136
PSH2N	Added Coil Springs ①	136
PSH3N	Added Coil Springs ①	136

Code	Name of Additional Processing, Component or Part	Page
PSH4N	Added Coil Springs ①	136
PSH5N	Added Coil Springs ①	136
PSHF	Added Coil Springs ②	138
PSRC1	Added Support Pillar M-SRC	144
PSRC2	Added Support Pillar M-SRC	144
PSRD1	Added Support Pillar M-SRD	144
PSRE1	Added Support Pillar M-SRE	144
PSTP	Added Stop Pin M-STP	140
PSTPH	Added Stop Pin M-STPH	140
PSTR	Added Stop Ring M-STR	140
PTLB1	Added Taper Guide Pin Set M-TLBS	108
PTLB2	Added Taper Guide Pin Set M-TLBS	108
PTLC1	Added Taper Guide Pin Set M-TLCS	104
PTLC2	Added Taper Guide Pin Set M-TLCS	104
PTLD1	Added Taper Guide Pin Set M-TLDS	104
PTLD2	Added Taper Guide Pin Set M-TLDS	104
PTLG1	Added Taper Guide Pin Set M-TLGS	106
PTLG2	Added Taper Guide Pin Set M-TLGS	106
PTLH1	Added Taper Guide Pin Set M-TLHS	106
PTLH2	Added Taper Guide Pin Set M-TLHS	106

S

SADDP	Added Plates	38
SGPT1	Install Guide Pins on T-Plate	57
SGPT2	Install Guide Pins on T-Plate	57
SGPT3	Install Guide Pins on T-Plate	57
SGPU1	Install Guide Pins on U-Plate	56
SGPU2	Install Guide Pins on U-Plate	56
SGPU3	Install Guide Pins on U-Plate	56
SGPU4	Install Guide Pins on U-Plate	56
SIMB	Mold Base for Insert Molding	32
SRPS	Added Machining Return Pin Holes on S-Plate	67

Marketing & Sales Group

Chosei Machinery & Tooling Technology Center, 1080 Yabutsuka, Chosei-mura, Chosei-gun, Chiba Prefecture, 299-4395, Japan

TEL.0475-30-0809

FAX.0475-30-0818

URL <http://www.futaba.co.jp/>

- About inquiry: If you have any inquiries about this catalog, contact your nearest Futaba office or sales office.
The contents of this catalog is as of January, 2014. Specifications and dimensions herein are subject to change without notice due to design improvement.
- Consumption tax: The prices shown in this catalog do not include consumption tax. The tax will be added to the price.
- Shipping fee: Shipping fee will be separately charged.
- Export Control: If you export MOLDZUKAN overseas, the export might be regulated under the Foreign Exchange and Foreign Trade Act, depending on the use of the software (is or is likely to be used or diverted for developing weapons). Before exporting MOLDZUKAN, you should make sure whether or not the export is subject to regulations in accordance with the act and take necessary procedures such as obtaining a license, etc. The products listed in other catalogs do not fall under the paragraph 1 to 15, Appended Table 1 of Foreign Exchange Table, however, they fall under the paragraph 16 of Catch-All Controls that has been introduced in April 2002. Also, please note that if they are exported, combined with other devices, they may be subject to the Foreign Exchange Law or Foreign Trade Law.

Futaba

Plastic Mold Components Additional
Mold Base Processing & Mold Parts
Edition VOL.1

Published February, 2014 Initial Edition

Futaba Corporation

629 Oshiba, Mobara, Chiba Prefecture 297- 8588, Japan


URL <http://www.futaba.co.jp/>

copyright©2010 by FUTABA CORPORATION

All right Reserved.

1402ABE

Machinery & Tooling Division Overseas Sales Offices



KISHIN CORPORATION

TEL.82-32-815-0222 ~ 8
FAX.82-32-814-7188
URL <http://www.kishin.com>



KISHIN PRECISION DIE AND MOLD MACHINERY (TIANJIN) CO.,LTD.

TEL.86-22-8396-8801
FAX.86-22-8396-8802



FUTABA PRECISION DIE AND MOLD MACHINERY (CHINA) CO.,LTD.

TEL.86-512-57035900
FAX.86-512-57035840



FUTABA PRECISION MOULD (SHENZHEN) CORP., LTD.

TEL.86-755-84736190
FAX.86-755-84736197



FUTABA (Hong Kong) CO.,LTD.

TEL.852-2563-6141
FAX.852-2811-0802
URL <http://www.futabahk.com.hk/>



FUTABA International Trading (Shanghai) CO.,LTD.

TEL.86-21-50366399
FAX.86-21-50366386



FUTABA JTW (THAILAND) LTD.

TEL.66-38-522-270 ~ 4
FAX.66-38-522-275
URL <http://www.fjthai.com>



FUTABA (VIETNAM) CO., LTD.

TEL.84-8-3-7700-551 ~ 5
FAX.84-8-3-7700-550



PT.FutabaDenshi Indonesia

TEL.62-21-292-88616
FAX.62-21-292-88617

Futaba Group Overseas Sales Offices

«Futaba Corporation (in Japan)»

Headquarters

629 Oshiba, Mobara, Chiba Prefecture 297-8588, Japan
TEL: 81-475-24-1111 FAX: 81-475-23-1346


Marketing & Sales Office

- **Makuhari Marketing & Sales Center (Electronic Components)**
Makuhari Techno-garden B6, 1-3 Nakase, Mihama-ku, Chiba, 261-8555, Japan
TEL: 81-43-296-5111 FAX: 81-43-296-5121
- **Machinery & Tooling Division**
1080-Yabutsuka, Chosei-mura, Chosei, Chiba Prefecture 299-4395, Japan
TEL: 81-475-30-0809 FAX: 81-475-30-0818

«Overseas Affiliates»

Asia

- **FUTABA (Hong Kong) Corporation, Ltd.**
18F, The Cameron, 33 Cameron Road, Tsim Sha Tsui, Kowloon, Hong Kong
TEL: 852-2563-6141 FAX: 852-2811-0802
- **FUTABA Precision Mould (Shenzhen) Corp., Ltd.**
No.1 Futaba Road, Danzhotou Industrial Estate, Nanwan Street, Longgang, Shenzhen, Guangdong, China
TEL: 86-755-84736190 FAX: 86-755-84736197
- **FUTABA International Trading (Shanghai) Co., Ltd.**
Unit F, 8/F, International Ocean Shipping & Finance Center, No.720 Pudong Avenue, Pudong New District, Shanghai, China
TEL: 86-21-50366399 FAX: 86-21-50366386
- **Shenzhen Office**
Room07, 13F, Office Tower, Shun Hing Square, Di Wang Commercial Centre, 5002 Shen Nan Dong Road, Luohu, Shenzhen, Guangdong, China
TEL: 86-755-8207-0299 FAX: 86-755-2583-0083
- **FUTABA Precision Die and Mold Machinery (China) Co., Ltd.**
1098 Fuchunjiang Road, Kunshan, Jiangsu, 215300, China
TEL: 86-512-57035900 FAX: 86-512-57035840
- **FUTABA Corporation of Huizhou**
16 Zhongkai Hi-Tech Industrial Development Zone, Huizhou, Guangdong, China
TEL: 86-752-2627111 FAX: 86-752-2627118
- **Kishin Precision Die and Mold Machinery (Tianjin) Co., Ltd.**
No.3 4th Branch Road, 2nd Saida Avenue, Xiqing Economic Development Area, Tianjin, China
TEL: 86-22-8396-8801 FAX: 86-22-8396-8802
- **FUTABA Electronics (Beijing) Co., Ltd.**
101, A-14, Tiantan Dongli Zhongqu, Dongcheng District, Beijing, 100061, China
TEL: 86-10-67050717 FAX: 86-10-67050576
- **FUTABA DENSHI Corp. (S) Pte. Ltd.**
152 Beach Road, The Gateway East, #23-08, Singapore 189721
TEL: 65-6291-9882 FAX: 65-6291-7391
- **Taiwan FUTABA Electronics Corporation**
No.1 Shing Kai Fa Road, Nan Tze Export Processing Zone, Kaohsiung, Taiwan
TEL: 886-7-3646516-7 FAX: 886-7-3642876
- **Taipei Office**
Room 3G03, No.5, Hsin-Yi Road, Sec.5, Taipei 11011, Taiwan, R.O.C
TEL: 886-2-8789-5068 FAX: 886-2-8789-5069
- **Kishin Corporation**
111 Eunbong-ro, Namdong-gu, Incheon, 405-849 Korea
TEL: 82-32-815-0222-8 FAX: 82-32-814-7188
- **SAMILMEGATEC Co., Ltd.**
466-7 Hyundai-Kia St, Hwaseong-si, Gyeonggi-do, 445-020 Korea
TEL: 82-31-355-9811 FAX: 82-31-355-9820
- **Futaba Electronics Components Korea Co., Ltd.**
A-1410, Woolim Lions Valley, Gasan digital 1-ro 168, Gasan-dong, Geumcheon-gu, Seoul, Korea
TEL: 82-2-2026-2512 FAX: 82-2-2026-2514
- **FUTABA Corporation of The Philippines**
120 North Science Avenue, Laguna Technopark-SEPZ, Binan, Laguna, Philippines
TEL: 63-2-843-2866 FAX: 63-2-843-2898
- **FUTABA JTW (Thailand) Ltd.**
78 Moo 2 Wellgrow Industrial Estate, Bangna-Trad Road, Tambon Pimpa, A.Bangpakong, Chachoengsao 24180, Thailand
TEL: 66-38-522270-4 FAX: 66-38-522275
- **FUTABA(Vietnam)CO.,LTD.**
Road 12 Tan Thuan E.P.Z. Tan Thuan Dong Ward, District 7 Ho Chi Minh City, Vietnam
TEL: 84-8-3-7700-551-5 FAX: 84-8-3-7700-550
- **PT.FutabaDenshi Indonesia**
Jl. Trembesi Blok F19 No. 1A, Delta Silicon 3 Industrial Park, Desa Cicau, Kec. Cikarang Pusat, Lippo Cikarang, Kab. Bekasi, Provinsi Jawa Barat, Indonesia
TEL: 62-21-292-88616 FAX: 62-21-292-88617



North America

- **FUTABA Corporation of America**
Chicago Office
711 E. State Parkway Schaumburg, Illinois 60173, U.S.A.
TEL: 1-847-884-1444 FAX: 1-847-884-1635
- **Detroit Office**
14492 Sheldon Road, Suite #370, Plymouth, Michigan 48170, U.S.A.
TEL: 1-734-459-1177 FAX: 1-734-459-1268
- **Huntsville Office**
101 Electronics Boulevard, Huntsville, Alabama 35824, U.S.A.
TEL: 1-256-461-9399 FAX: 1-256-461-1059
- **El Paso (Distribution Center)**
24 Spur Dr, El Paso, TX, United States
TEL: 1-915-771-7858
- **FUTABA (Europe) GmbH**
Halskestrasse 9, D-47877 Willich, Germany
TEL: 49-2154-943-0 FAX: 49-2154-943-200
- **«Affiliates in Japan»**
- **FUTABA Industry Co., Ltd.**
Miyakawa Bldg., 2-9 Kanda Suda-cho, Chiyoda-ku, Tokyo 101-0041, Japan
TEL: 81-3-3255-9984 FAX: 81-3-3251-9984
- **FUTABA Business System Co., Ltd.**
599 Oshiba, Mobara, Chiba Prefecture 297-0033, Japan
TEL: 81-475-26-0192
- **O.S.ENGINES Mfg. Co., Ltd.**
6-15 Imagawa 3-Chome, Higashi-Sumiyoshi-ku, Osaka Prefecture 546-0003, Japan
TEL: 81-6-6702-0225 FAX: 81-6-6704-2722
- **Futaba Precision Co., Ltd.**
10-159-2 Kasshi-cho, Kamaishi, Iwate Prefecture 026-0055, Japan
TEL: 81-193-23-0241 FAX: 81-193-25-1706
- **SATSUKI KIZAI CO., LTD.**
598-1 Monoi, Yotsukaido, Chiba Prefecture 284-0012, Japan
TEL: 81-43-422-1447 FAX: 81-43-422-1435
- **Futaba Mobile Display Corporation.**
644-55, Hitana, Nakago-cho, Kitaibaraki, Ibaraki, 319-1556, Japan
TEL: 81-293-43-6788 FAX: 81-293-43-6722

